

Cinnaminson Groundwater Contamination

New Jersey

EPA ID#: NJD980785638

EPA REGION 2

Congressional District(s): 03

Burlington

Cinnaminson Township

NPL LISTING HISTORY

Proposed Date: 10/1/1984

Final Date: 6/1/1986

Site Description

The Cinnaminson Groundwater Contamination site is an area-wide site that covers approximately 400 acres in Cinnaminson and Delran Townships in Burlington County, New Jersey. The site includes properties bounded by Union Landing Road, U.S. Route 130, River Road, and Taylors Lane. The Delaware River is located approximately 5,000 feet to the northwest, and U.S. Route 130 passes about 2,000 feet southwest of the site. The site consists of a landfill, residential properties, and light to heavy industrial properties. A number of the industrial facilities have petroleum underground storage tanks. Unlined slurry pits and cooling ponds are located on one industrial property. The landfill portion of the site originally began as a sand and gravel mining pit. During the late 1950s, municipal solid wastes were deposited in the completed unlined mining pits, while mining operations continued in other parts of the property until the late 1960s. After the mines were closed, large amounts of refuse and solid waste were deposited in the pits. Municipal and institutional wastes, bulky wastes, vegetable and food processing wastes, and industrial wastes, including hazardous substances, were deposited in two areas of the landfill. In 1980, operations ceased. A clay cap was installed over the landfill to restrict rain and surface water from infiltrating into the wastes, thus reducing the amount of contaminated liquid flowing from the site from entering the groundwater. The underlying aquifer is a source of drinking water for people living around the site. There are both public and private water supply wells within one mile of the site; however, the private wells are not being used for drinking water. Approximately 55,000 people live within a 3 mile radius of the site.

Site Responsibility: This site is being addressed through Federal and responsible party actions.

Threat and Contaminants

Arsenic and volatile organic compounds, including chloroform, benzene, tetrachloroethylene, and vinyl chloride, have been detected in the groundwater. Ingestion of contaminated groundwater poses the greatest potential risk to residents .

Cleanup Approach

Remediation of the site is being addressed in three stages, known as operable units. The first operable unit is directed at the cleanup of the groundwater contamination from the landfills at the site. The second operable unit will address the effectiveness of the clay cap in reducing the generation of leachate, the contaminated liquid flowing from the site that is carrying with it many of the landfill's pollutants. The third operable unit is directed at other industrial facilities located at the north-western part of the site.

Response Action Status

Remedial Investigation/Feasibility Study: EPA completed an investigation of the ground-water contamination at the site in 1989. The investigation included the installation of monitoring wells and sampling of the groundwater around the site to locate the areas of greatest contamination. The hydrogeology at the site is complicated by the presence of discontinuous clay layers, called "lenses", beneath the site. These clay lenses tend to create a shallow aquifer above the deep aquifer. Both the shallow and the deep aquifers were found to be contaminated. In 1990, EPA completed its feasibility study to develop and evaluate the alternatives for the remediation of groundwater contamination at the site.

Record of Decision: On September 28, 1990, EPA selected a remedy for the first operable unit, which includes pumping ground water from both the deep and shallow aquifers, treating it to remove the contamination, and reinjecting the treated ground water into the deep aquifer.

Remedial Design: Field work for the remedial design began in June 1993. The design of the ground-water remediation

system for the deep aquifer was completed in August 1996. However, the potentially responsible party suggested modifications to the design to make it more efficient. The modifications along with the final design were approved in January 1999.

Clay Cap: An evaluation of the effectiveness of the clay cap is underway.

Remedial Action : Ground-water cleanup is ongoing. Construction of the ground-water remediation system began in summer 1999 and was completed in January 2000. The plant began operation in April 2000.

Ongoing Investigations: A work plan is being developed to conduct additional investigations related to the third operable unit.

Site Facts: The design and implementation of the selected remedy was undertaken by a potentially responsible party under a unilateral administrative order.

Cleanup Progress

A groundwater pump and treat system was designed by a potentially responsible party and approved by EPA in January 1999. Construction of the pump and treat system began in summer 1999 and was completed in January 2000. The plant began operation in April 2000. Between June 2003 and June 2004, approximately 18.39 kilograms of contaminants were removed. The groundwater pump and treat system continues to operate and remove contaminants.

Site Repositories

USEPA Records Center 290 Broadway, 18th floor New York, NY 10007 (212) 637-4308

Cinnaminson Public Library 1609 Riverton Road Cinnaminson Township, NJ 08077