Groundwater Cleanups: Optimization and New Solutions

September 20, 2001
Region 3 RCRA Corrective Action Meeting
Philadelphia, PA

Walter Kovalick Jr., Ph.D.

Director
Technology Innovation Office
US Environmental Protection Agency

Technology Innovation Office

Clients for Information on Technology Innovations

Technology Vendor

Responsible
Party/
Owner
Operator

Federal/ State Project Manager

Consulting Engineer

International Markets

Investor Community

Technology Vendors

TIO's Mission

- Advocates "smarter" technologies for the characterization and cleanup of contaminated sites
- Works with clients to identify and understand better, faster, and cheaper options
- Seeks to identify and reduce barriers to the use of innovative technologies

Technology Deployment and Cost


- EPA information
- Multi-agency data
- New reports




http://cluin.org/asr

Superfund Remedial Actions: Groundwater Remedies (FY 1982 - FY 1999)


Total Sites With Pump-and-Treat, Monitored Natural Attenuation (MNA) and In Situ Groundwater Treatment Remedies = 749




Superfund Remedial Actions: Summary of Source Control Treatment Technologies (FY 1982 - FY 1999)




Superfund Remedial Actions: Trends in Types of Source Control RODs (FY 1982 - FY 1999)



Superfund Remedial Actions: In Situ Technologies for Source Control (FY 1985 - FY 1999)






http://cluin.org/products/nairt/overview.htm

North American Innovative Technology Demonstration Projects Report

- Matrix summarizing 601 government-sponsored demonstrations (1985-present)
- Sponsoring government agencies (North America)
 - Canadian Government
 - U.S. Environmental Protection Agency
 - U.S. Military Services (Army, Navy, Air Force)
 - U.S. Department of Energy
 - California Environmental Protection Agency

North American Innovative Technology Demonstration Projects In Situ Technologies 383 Projects











Federal Remediation Technologies Roundtable









FRTR Remediation Case Studies

- Document cost/performance of clean-up technologies
- Includes full-scale cleanup and large-scale demonstrations
- 274 EPA, DoD, DoE cases
- Searchable by technology, contaminant, media (www.frtr.gov)
- Superfund, RCRA, State sites


FRTR Cost and Performance Guide

In Situ Groundwater Remediation Technologies with Recommended Reporting Elements

- Air Sparging
- Bioremediation
- Bioslurping
- Circulating wells (UVB)
- Cosolvents/surfactants
- Dual-phase extraction
- Dynamic underground stripping
- In situ oxidation (Fenton's Reagent)

- Natural attenuation of nonchlorinated compounds
- Natural attenuation of nonchlorinated hydrocarbons
- Permeable Reactive Barriers
- Pump and Treat
- Phytoremediation
- Steam flushing
- Vertical barrier walls

FRTR Case Studies: Summary of Contaminants and Media




Contaminant Types

http://www.frtr.gov

Remediation Technology Cost Compendium – Year 2000

- Historical cost data compilation for 6 cleanup technologies: bioremediation, thermal desorption, SVE, on-site incineration, pump-and-treat, and PRBs
- Focus on unit cost for quantity treated and contaminant mass removed
- "Fully defined" cost data
 - Based on actual applications from federal agency sources
 - Directly linked to technology application
- Cost curves developed
- Findings reconfirm factors driving remediation technology costs
- Available September 2001


Bioventing Cost/Volume Curve Remediation Technology Cost Compendium




Use of Bioremediation at Superfund Sites

- Recent report on status-48 pages
- Describes site-specific applications of ex situ
 and in situ bioremediation at 104 Superfund sites
- Summarizes contaminants and media treated
- Provides available cost and performance data
- Analyzes trends over time
- http://cluin.org/techpubs.htm

Superfund Site Types Most Commonly Treated by Bioremediation (FY 1982 – FY 1999)¹ Part 1 of 2



Superfund Site Types Most Commonly Treated by Bioremediation (FY 1982 – FY 1999)¹ Part 2 of 2



Contaminant Groups Treated by Bioremediation Technologies at Superfund Sites (FY 1982 – FY 1999)

In Situ Treatment

Techno-	Total No. of Projects	PAHs	Other Non- Chlori- nated SVOCs	втех	Other Non- Chlori- nated VOCs	Pesti- cides And Herbi- cides	Other Chlori- nated SVOCs	Chlori- nated VOCs	Explo- sives/ Propel- lants
Source Control									
Bioventing	24	•	•	•	•	•	•	•	
Slurry Phas	se 2	•			•	•	•	•	
Other	9	•	•	•		•		•	
Groundwat	er								
Biospargin	g 3	•	•	•	•			•	
Injection/ Recirculation	17 on	•	•	•	•	•		•	
									9/20/01



EPA's Environmental Technology Verification Program

ETV Site Characterization and Monitoring Technologies Pilot Technologies

Categories	Verified	Report Status
Cone penetrometer/laser-induced fluorescence	2	Completed
Field-portable XRF (SITE)	7	Completed
Field portable GC/MS	2	Completed
Soil/soil gas sampling (SITE)	6	Completed
Well-head monitoring of VOCs	5	Completed
PCB analysis	9	Completed
Decision-support software	6	Completed
Ground water sampling	6	Completed
Explosives test kits	4	Completed
TPH test kits (SITE)	5	In Peer review
Sediments sampling (SITE)	2	Completed
Lead-in-dust detection	8	New Project

EPA REACH IT System

- Free information service, searchable on-line
- Vendor information on 371 treatment and 160 characterization technologies
- Detailed site information on 900 EPA Superfund remediation projects
- Flexible search options including by technology, contaminant, media, and sites
- Will be updated continuously by EPA and vendors (Fall 2001)

Looking Down the Road


- "Smarter" site monitoring will save money before, during, and after cleanup
- Post construction activities gaining in importance
- Economics and feasibility of groundwater DNAPL source control in transition

Monitoring: Saving Throughout the Process

"Let's get through characterization and on to cleanup"

The Triad Approach

Systematic Planning



Dynamic Workplanning

On-Site Measurement Technologies

Characteristics of the "Triad"

- Fully maximizing capabilities of <u>field analytical</u> <u>instruments</u> and rapid sampling tools
- Systematic planning
 - Meeting site or project-specific goals vs. prescriptive methods "checklists"
 - Relying on thorough advance planning/upfront understanding of the site
 - Global view of project, ultimate goals
- Dynamic or adaptive decision making
- Bringing together the right <u>team</u>
- Changing perception
 - Requirements for accurate, protective, and defensible decisions
 - Time, money, and quality

Wenatchee Tree Fruit Facility: Remediate Pesticide "Disposal" Plot

- Initial EPA estimate: excavate, transport and incinerate 708 tons of soil = \$1M (not including closure testing)
- USACE plan: Pesticide immunoassay kits guided sampling, removal, and disposal decisions in 1 mobilization using dynamic work plan
- Outcome: 334 tons landfilled; 56 tons incinerated
 - Total Cost of Project at Closeout (including COE oversight fees of \$100K) = \$589K
 - Project Lifetime = 6 months

Cost Comparison (per USACE)

	Traditional	DWP
1. Review Existing Data	\$7,150	\$11,000
2. Design Site Characterization	\$0	\$17,640
3. Implement Site Characterization	\$0	\$84,134
4. Review Char. data	\$0	\$10,000
5. Design Remedy	\$16,500	\$26,460
6. Implement Remedy (- Disposal)	\$168,094	\$271,116
7. Waste Disposal	\$910,000	\$153,570
8. Closure report	\$20,305	\$20,305
TOTAL	\$1,122,049	\$594,225

This traditional cost estimate assumes no characterization, only removal and incineration of the entire plot volume

New Emphasis on Improved O&M and "Close Out"

"We're done when construction is complete"

Future Obligations are Significant

- Optimization of pump and treat
- Improving efficiencies of groundwater monitoring
- Rethinking source term vs. plume management

Superfund Reform Initiative: Pump and Treat Optimization

- July 7, 2000 Superfund Program included pump and treat (P&T) optimization in Superfund Reform Initiative
- Collaborative effort between TIO/OERR/Regions to showcase Remedial System Evaluation (RSE) process at Fund-lead P&T systems
- Project Goals
 - Perform RSEs at 20 Fund-lead P&T systems (out of 88)
 - Increase awareness of need and benefit of optimization
 - Provide assistance to RPMs in evaluating results and implementing recommendations
 - Incorporate optimization into overall clean-up process

Overview of Results from 16 RSEs

- Cost reductions identified at 13 of 16 sites
- Improvements in remedy effectiveness identified at 12 out of 16 sites
- Significant cost savings opportunities found at 10 out of 16 sites: 15-73% reduction in annual O&M costs)

Summary of Estimated Cost Savings

	Potential Changes in Annual and Capital Costs					
	RSE of P8	RT System 1	RSE of P&T System 2			
Region	Annual cost savings	Capital investments	Annual cost savings	Capital investments		
1	(\$149K/yr)	\$117K	(\$2.1M/yr)	\$133K		
2	(\$570K/yr)	\$827K	Draft not finalized			
3	(\$40K)	\$175K	\$42K	\$120K		
4	(\$35K/yr)	\$99K	(\$62K/yr)	\$225K		
5	(\$113K/yr)	\$40K	(\$203K/yr)	\$233K		
6	(\$25K/yr)	\$105K	(\$58K/yr)	\$81K		
7	(\$22K/yr)	\$59K				

Total Potential Cost Savings = \$3.3M/yr for 12 sites
Estimated Capital Investments = \$2.2M for 12 sites (one-time cost)

Common Themes Regarding Cost Reduction

- Over design of aboveground treatment systems
 - Many aboveground treatment systems designed to treat max. concentrations and flow rates found during the RI
 - Because actual operational parameters lower than anticipated, many can be downsized to more efficient units
- Costly on-site analytical work and excessive process monitoring
 - Several sites had on-site labs and high frequency of process monitoring
 - RSE team found on-site labs not cost effective and high-frequency process monitoring unnecessary - led to increased labor costs

Common Themes Regarding Cost Reduction, cont.

- Alternate discharge options
 - Several sites had very low POTW discharge limits that should be revisited to determine if higher limits possible
 - Operators and site personnel not aware that POTW limits uncommonly low
- Potential use of alternative technologies
 - Permeable reactive barriers, in situ chemical oxidation, and other innovative in situ treatment technologies recommended at some sites
- Some O&M contracts were inefficient

Common Themes Regarding Remedy Effectiveness

- Remedy effectiveness needs to be more closely monitored
 - Most sites did not adequately evaluate whether P&T system captures the plume (1 out of 16 sites had adequately evaluated capture zone)
 - Most sites did not carefully evaluate O&M reports
 - Most O&M reports did not provide adequate interpretation of data, for example:
 - Mass removal over time
 - LTM data against clean-up goals
 - Influent and effluent data against design specifications
- Site close out needs to be better defined
 - Many sites do not have agreed upon exit strategies
 - Systems continue to operate without being required by the ROD

Key Message from Reviews to Date

GROUNDWATER REMEDIATION SYSTEMS REQUIRE ACTIVE MANAGEMENT

- Revisit system objectives
- Evaluate subsurface performance
- Evaluate aboveground performance
- Evaluate potential cost reductions
- Develop exit strategy
- Evaluate contract efficiency

Next Steps

- Next FY:
 - Complete 10 additional RSEs
 - Complete fact sheet on "Important
 Components to Effective Pump and Treat
 System Operation, Maintenance, and
 Monitoring"
 - Complete guide to evaluating groundwater capture zones

Improving Efficiencies of GW Monitoring Systems

- EPA demonstration project to evaluate effectiveness of geostatistical approaches for GW monitoring optimization
- Approach: 4 sites with existing GW monitoring plans being evaluated with geostatistical approaches
- Benefit: Geostatistics can provide more quantitative approach to determine if spatial (in space) and/or temporal (in time) redundancies or deficiencies exist
- Schedule: 4 case studies and white paper on geostatistics to be completed by Winter 2001

Ranking Criteria for Difficulty in Remediating Ground Water

National Research Council, 1997

Hydrogeology	Mobile Dissolved (Degrades/V olatilizes)	Mobile Dissolved	Strongly Sorbed, Dissolved	Strongly Sorbed, Dissolved (Degrades/V olatilizes)	Separate Phase LNAPL	Separate Phase DNAPL
Homogeneous, Single Layer	1	1-2	2	2-3	2-3	3
Homogeneous, Multiple Layers	1	1-2	2	2-3	2-3	3
Heterogenous, Single Layer	2	2	3	3	3	4
Heterogenous, Multiple Layers	2	2	3	3	3	4
Fractured Bedrock	3	3	3	3	4	4

least difficult = 1 / most difficult = 4

Rethinking Source Term vs. Plume Management

- Potential source term control solutions
 - Chemical oxidation
 - Surfactant-cosolvent flushing
 - Steam/heat
- Outstanding issues
 - Science
 - Policy
 - Other

Dynamic Underground (Steam) Stripping

- Visalia Pole Yard NPL Site in S. California
- Former wood (pole) treatment facility
- Creosote, PCP
- Pump and treat started in 1976, 10lbs/week
- Began steam stripping (dynamic underground stripping-DUS) 3 years ago
- 100,000 lbs removed in first 6 weeks
- >1,300,000 lbs removed to date
- Goal to meet MCLs
- More work needed to reduce costs

Visalia Steam Remediation Project

- Total project cost: \$21.5 M 1996 through 2000
- Unit cost per cubic yard of soil treated
 - Actual cost \$57
 - With lessons learned \$38
 - Solvent and fuels \$25
- Comparative cost per gallon of creosote removed
 - P&T \$26,000
 - DUS \$ 130
- Estimated time to remove 1.3 M pounds of creosote
 - P&T3250 years
 - DUS3 years

Small Site: Soil Treatment Technologies Six-Phase Heating

- Heats soils to remove organics in soil in situ (in place)
- Costs: \$30-60/CY, \$20-45/ton (electric 10-15% of costs or \$3-9/ton)
- Ideal for "tight" soils problematic condition for standard soil vapor extraction (SVE)
- Example: former dry cleaner in active retail center
 - Solvent (PCE) contamination: 2,000 ppb in soil,3,600 ppb in groundwater
 - Guaranteed cleanup to drinking water standards (MCLs) in 4 months (500 ppb in soil, 5 ppb in groundwater)



Six-Phase Heating Seattle Dry Cleaning Site

- Fast-track property transfer
- PCE in soil and groundwater
- Cleanup within 4 months
- To MCLs (5 ppb in water)
- Continued property use



In Situ Thermal Clean-up Projects http://clu-in.org/products/thermal

Organization	# of Projects		
Navy	9		
Air Force	5		
Army	4		
DOE	5		
Private	37		

Technologies Included:

- Conductive Heating
- ERH- Electrical Resistance Heating
- Hot Air Injection
- RF- Radio Frequency Heating
- SEE- Steam Enhanced Extraction

"Take Home" Messages

- Technology cost and performance information IS available
- Saving money on the "grey panthers" is likely
- "Smarter" measurement and monitoring throughout the site "life cycle"
- New approaches to groundwater DNAPL's are "with us"

CLU-IN World Wide Web Site http://clu-in.org





Technology Innovation Office

Search

Comments

Site Man

EPA Home

Main Menu

Hazardous Waste

Clean-Up Information

Publications & Software

Remediation

Site Characterization

Partnerships & Consortia

International Updates

Vendor Support

TechDirect

YZK

- Site Remediation Technologies
- Site Characterization Technologies
- Technology Partnerships, Roundtables, and Consortia
- Updates on International Clean-Up Activities
- Vendor Support
- Publications for Downloading
- Free E-mail Updates via TechDirect
- Regulatory Information and Technology Policy
- Links to Other Internet and Online Resources

Highlights

- Broadcasts periodic e-mail messages to list of over 11,000 subscribers
- Highlights events of interest to site remediation and site assessment professionals
- Describes new products and provides instructions on how to obtain them

Top 10 Websites For Hazardous Waste Management

- 1. http://clu-in.org (or http://www.epa.gov/tio)
- 2. http://www.epareachit.org
- 3. http://www.frtr.gov
- 4. http://www.gwrtac.org
- 5. http://www.rtdf.org
- 6. http://www.epa.gov/ORD/SITE
- 7. http://em-50.em.doe.gov
- 8. http://www.itrcweb.org/
- 9. http://www.serdp.org/research/research.html
- 10. http://www.epa.gov/etv/