United States
Environmental Protection
Agency

Development Document for Final Action for Effluent Guidelines and Standards for the Construction and Development Category

March 2004

U.S. Environmental Protection Agency
Office of Water (4303T)
1200 Pennsylvania Avenue, NW
Washington, DC 20460

EPA-821-B-04-001

Disclaimer

Neither the United States government nor any of its employees, contractors, subcontractors, or other employees makes any warranty, expressed or implied, or assumes any legal liability or responsibility for any third party's use of, or the results of such use of, any information, apparatus, product, or process discussed in this report, or represents that its use by such a third party would not infringe on privately owned rights. References to proprietary technologies are not intended to be an endorsement by the Agency.

Questions or comments regarding this technical document should be addressed to:

Mr. Jesse W. Pritts, P.E.
Engineering and Analysis Division
U.S. Environmental Protection Agency
1200 Pennsylvania Avenue, N.W. (4303T)
Washington, DC 20460
(202) 566 - 1038
pritts.jesse@epa.gov

Contents

SECTION 1: SUMMARY AND SCOPE 1-1
1.1 INTRODUCTION 1-1

SECTION 2: BACKGROUND 2-1
2.1 LEGAL AUTHORITY 2-1
2.2 CLEAN WATER ACT 2-1
2.2.1 BEST PRACTICABLE CONTROL TECHNOLOGY CURRENTLY AVAILABLE 2-1
2.2.2 BEST CONVENTIONAL POLLUTANT CONTROL TECHNOLOGY 2-2
2.2.3 BEST AVAILABLE TECHNOLOGY ECONOMICALLY ACHIEVABLE 2-3
2.2.4 NEW SOURCE PERFORMANCE STANDARDS 2-3
2.2.5 PRETREATMENT STANDARDS FOR EXISTING SOURCES AND PRETREATMENT STANDARDS FOR NEW SOURCES 2-3
2.2.6 EFFLUENT GUIDELINES SCHEDULE 2-3
2.2.7 NPDES PHASE I AND II STORM WATER RULES 2-4
2.3 POLLUTION PREVENTION ACT OF 1990 2-5
2.4 STATE REGULATIONS 2-5

SECTION 3: DATA COLLECTION 3-1
3.1 INTRODUCTION 3-1
3.2 LITERATURE SEARCH 3-1
3.3 COMPILATION OF STATE CONTROL STRATEGIES, CRITERIA, AND STANDARDS 3-1
3.4 OTHER DATA SOURCES 3-2
3.4.1 PHASE II STORM WATER RULE ECONOMIC ANALYSIS 3-2
3.4.2 USDA NATIONAL RESOURCES INVENTORY 3-3
3.4.3 CENSUS OF CONSTRUCTION 3-3
3.4.4 SOILS DATABASES, REVISED UNIVERSAL SOIL LOSS EQUATION AND SEDCAD 3-3
3.5 REFERENCES 3-4

SECTION 4: INDUSTRY PROFILE 4-1
4.1 INTRODUCTION 4-1
4.2 INDUSTRY PRACTICES AND TRENDS 4-1
4.2.1 OVERVIEW OF CONSTRUCTION LAND-DISTURBING ACTIVITIES 4-1
4.2.2 CONSTRUCTION SITE SIZE CATEGORIES AND ESTIMATES OF AMOUNT OF DISTURBED LAND 4-4
4.2.2.1 National Estimates of Disturbed Acreage 4-4
4.2.2.2 Distribution of Acreage by Project Type 4-7
4.2.2.3 Distribution of Developed Acreage by Project Size 4-13
4.2.2.4 State-Level Estimation of Developed Acreage and Sites 4-15

4.2.2.5 Estimates of Number of Sites and Acreage Covered by Regulatory Options 4-16
4.3 REFERENCES 4-17

SECTION 5: TECHNOLOGY ASSESSMENT 5-1
5.1 CONSTRUCTION EROSION AND SEDIMENT CONTROLS 5-1
5.1.1 INTRODUCTION 5-1
5.1.2 PROCEDURE FOR TECHNOLOGY ASSESSMENT 5-2
5.1.2.1 Identification of Performance Goals 5-2
5.1.2.2 Goals, Environmental Impact Areas, And Assessment Scales 5-3
5.1.2.3 Qualitative Versus Quantitative Assessment 5-4
5.1.3 REVIEW OF HISTORICAL APPROACHES TO EROSION AND SEDIMENT CONTROL 5-5
5.1.4 GOALS, CONTROL STRATEGIES, CRITERIA, AND STANDARDS 5-7
5.1.4.1 Goals, Control Strategies, Criteria, And Standards: How They Relate 5-7
5.1.4.2 Levels of Performance or "How Well Do The Strategies Work?" 5-10
5.1.4.3 Strategies, Criteria, Standards, And Enforcement 5-10
5.1.5 CONTROL TECHNIQUES, BMP SYSTEMS 5-14
5.1.5.1 Erosion Control and Prevention 5-14
5.1.5.1.1 Planning, Staging, Scheduling 5-14
5.1.5.1.2 Vegetative Stabilization 5-16
5.1.5.2 Water Handling Practices 5-40
5.1.5.2.1 Earth Dike 5-40
5.1.5.2.2 Temporary Swale 5-43
5.1.5.2.3 Temporary Storm Drain Diversion 5-50
5.1.5.2.4 Pipe Slope Drain 5-52
5.1.5.2.5 Stone Check Dam 5-56
5.1.5.2.6 Lined Waterways 5-58
5.1.5.3 Sediment Trapping Devices 5-62
5.1.5.3.1 Silt Fence 5-63
5.1.5.3.2 Super Silt Fence 5-69
5.1.5.3.3 Straw Bale Dike 5-71
5.1.5.3.4 Sediment Trap 5-74
5.1.5.3.5 Sediment Basin 5-79
5.1.5.4 Other Control Practices 5-86
5.1.5.4.1 Stone Outlet Structure 5-86
5.1.5.4.2 Rock Outlet Protection 5-88
5.1.5.4.3 Sump Pit 5-91
5.1.5.4.4 Sediment Tank 5-93
5.1.5.4.5 Stabilized Construction Entrance 5-94
5.1.5.4.6 Land Grading 5-96
5.1.5.4.7 Temporary Access Waterway Crossing 5-97
5.1.5.4.8 Dust Control 5-100
5.1.5.4.9 Storm Drain Inlet Protection 5-103

5.1.5.4.10 Polyacrylamide (PAM) 5-105
5.1.6 SUMMARY 5-107
5.2 REFERENCES 5-119

SECTION 6: REGULATORY DEVELOPMENT AND RATIONALE 6-1
6.1 REGULATORY OPTIONS FOR FINAL ACTION 6-1
6.1.1 OPTION 1 - INSPECTION AND CERTIFICATION 6-1
6.1.2 OPTION 2 - CODIFY PROVISIONS OF THE EPA CONSTRUCTION GENERAL PERMIT WITH INSPECTION AND CERTIFICATION 6-5
6.1.3 OPTION 3 - NO REGULATION 6-14
6.1.4 OPTION 4 - CODIFY PROVISIONS OF THE EPA CONSTRUCTION GENERAL PERMIT 6-14

SECTION 7: APPROACH TO ESTIMATING COSTS 7-1
7.1 OVERVIEW 7-1
7.2 ANALYSIS OF STATE EQUIVALENCY 7-2
7.3 DEVELOPMENT OF MODEL CONSTRUCTION SITES AND ESTIMATES OF BMP QUANTITIES 7-6
7.4 ESTIMATION OF BMP COSTS 7-11
7.5 REFERENCES 7-14

SECTION 8: APPROACH TO ESTIMATING POLLUTANT LOAD REDUCTIONS AND ENVIRONMENTAL BENEFITS 8-1
8.1 OVERVIEW 8-1
8.2. CATEGORIES OF REPORTED IMPACTS AND POLLUTANTS 8-5
8.2.1 INTRODUCTION 8-5
8.2.2 POLLUTANTS ASSOCIATED WITH CONSTRUCTION AND LAND DEVELOPMENT STORM WATER RUNOFF 8-6
8.2.2.1 Sediment 8-6
8.2.2.2 Metals 8-13
8.2.2.3 PAHs, and Oil and Grease 8-17
8.2.2.4 Pathogens 8-18
8.2.3 PHYSICAL IMPACTS OF CONSTRUCTION AND LAND DEVELOPMENT ACTIVITIES 8-21
8.2.3.1 Hydrologic Impacts of Construction and Land Development Activities . . . 8-23
8.2.3.2 Impacts on Geomorphology/Sediment Transport 8-27
8.2.3.3 Changes in Habitat Structure 8-30
8.2.3.4 Thermal Impacts 8-31
8.2.3.5 Direct Channel Impacts 8-31
8.2.3.6 Site Differences in Physical Impacts 8-34
8.3 ANALYSIS OF SOIL TEXTURE BY REGION 8-35
8.4 ESTIMATION OF SOIL EROSION RATES 8-35
8.5 ESTIMATION OF BMP REMOVAL EFFICIENCIES 8-40
8.5.1 APPLICATION OF SEDCAD 8-40

8.5.2 CUSTOMIZING BMP REMOVALS FOR STATE-ECOREGIONS 8-42
8.6 CALCULATION OF NATIONAL LOADINGS AND REMOVALS BY REGULATORY OPTION 8-46
8.7 INTEGRATION OF NATIONAL LOADINGS INTO NWPCAM 8-49
8.8 NWPCAM ASSESSMENT OF IN-STREAM SEDIMENT CONCENTRATIONS . . 8-49
8.8.1 NWPCAM SYSTEM OVERVIEW 8-49
8.8.2 CONSTRUCTION AND LAND DEVELOPMENT MODELING PROCESS . . 8-50
8.8.2.1 Construction and Development Loads 8-50
8.8.2.2 Distribution of Construction Sites and Loads 8-50
8.8.2.3 Removal of Background NPS TSS Loads 8-52
8.8.2.4 Routing Construction and Development Loads to the RF3Lite Network . . . 8-53
8.8.2.5 Water Quality Modeling and Economic Benefits Analysis 8-54
8.9 RESULTS OF CONSTRUCTION AND DEVELOPMENT MODELING ANALYSIS 8-54
8.10 REFERENCES 8-56

Figures

Figure 5-1. Flow Diagram Showing Relationship Among Goals, Strategies, Criteria and Standards 5-9
Figure 8-1a. State-Ecoregions in the Western United States 8-3
Figure 8-1b. State-Ecoregions in the Eastern United States 8-4
Figure 8-2. Stream Channel Enlargement as a Function of Watershed Imperviousness 8-23
Figure 8-3. Runoff Coefficient as a Function of Impervious Cover 8-25
Figure 8-4. Sediment Production from Construction Sites 8-29

Tables

Table 3-1. State Requirements for Construction Site Erosion and Sediment Control 3-2
Table 4-1. Acres Converted from Undeveloped to Developed State, 1992-1997 4-5
Table 4-2. State Rankings by Rate of Non-Federal Land Developed, 1992 - 1997 4-6
Table 4-3. New Single-Family and Multifamily Housing Units Authorized, 1995-1997 4-7
Table 4-4. Average and Median Lot Size for New Single-Family Housing Units Sold, 1995-1997 4-8
Table 4-5. Average Building Square Footage 4-10
Table 4-6. Typical Building Sizes and Size Ranges by Type of Building 4-11
Table 4-7. National Estimates of Land Area Developed Per Year, Based on Building Permit Data 4-12
Table 4-8. National Estimates of Land Area Developed Per Year, Based on National Resources Inventory Totals 4-13
Table 4-9. Distribution of 14 Community Survey Permits by Site Size 4-14
Table 4-10. Distribution of National Construction by Site Size and Development Type 4-15
Table 4-11. National Construction Acreage Subject to Effluent Guidelines Requirements 4-16
Table 4-12. Acreage Incurring Costs Under Options Considered 4-17

Table 5-1. Description of Levels of Performance of Three Control Strategies 5-10
Table 5-2. Descriptions of Levels of Difficulty in Enforcement 5-11
Table 5-3. Scheduling Considerations for Construction Activities 5-15
Table 5-4. Conditions Where Vegetative Streambank Stabilization Is Acceptable 5-19
Table 5-5. Maximum Permissible Velocities for Individual Site Conditions for Grass Swales . 5-21
Table 5-6. Typical Mulching Materials and Application Rates 5-30
Table 5-7. Measured Reductions in Soil Loss for Different Mulch Treatments 5-31
Table 5-8. Cubic Yards of Topsoil Required for Application to Various Depths 5-39
Table 5-9. Grassed Swale Pollutant Removal Efficiency Data 5-48
Table 5-10. Average Annual Operation and Maintenance Costs for a Grass Swale 5-50
Table 5-11. Recommended Pipe/Tubing Sizes for Slope Drains 5-53
Table 5-12. Slope Drain Characteristics 5-54
Table 5-13. Maximum Slope Lengths for Silt Fences 5-64
Table 5-14. Typical Requirements for Silt Fence Fabric 5-66
Table 5-15. Slope Lengths for Super Silt Fences 5-70
Table 5-16. Minimum Requirements for Super Silt Fence Geotextile Class F Fabric 5-71
Table 5-17. Maximum Land Slope and Distances Above a Straw Bale Dike 5-72
Table 5-18. Weir Length for Sediment Traps 5-76
Table 5-19. Range of Measured Pollutant Removal for Sediment Detention Basins 5-77
Table 5-20. Common Concerns Associated with Sediment Traps 5-78
Table 5-21. Common Concerns Associated with Sediment Basins 5-84
Table 5-22. Riprap Sizes and Thicknesses (SHA Specifications) 5-89
Table 5-23. Application Rates for Spray-On Adhesives 5-102
Table 5-24. Turbidity Reduction Values from PAM 5-106
Table 5-25. Summary of Information on Erosion Control and Prevention BMPs (Sub-section 5.1.5.1) 5-108
Table 5-26. Summary of Information on Erosion Control and Prevention BMPs (Sub-section 5.1.5.2) 5-111
Table 5-27. Summary of Information on Erosion Control and Prevention BMPs (Sub-section 5.1.5.3) 5-113
Table 5-28. Summary of Information on Erosion Control and Prevention BMPs (Sub-section 5.1.5.4) 5-117
Table 7-1. Total Costs of Options 7-2
Table 7-2. State Equivalency with EPA CGP Requirements 7-4
Table 7-3. Land Use-Specific Impervious Cover Factors 7-7
Table 7-4. Percentage of Construction Site in Each of Three Flow Pathways 7-8
Table 7-5. BMP Quantities Required by EPA CGP for Model Construction Sites 7-10
Table 7-6. Unit Cost Factors For BMPs 7-12
Table 7-7. State Cost Adjustment Factors 7-13
Table 7-8. Design and O & M Costs as a Percentage of Installation Costs 7-14
Table 8-1. Loading Reductions and Benefits of Regulatory Options 8-2
Table 8-2. Studies of Uncontrolled Soil Erosion as TSS From Construction Sites 8-7
Table 8-3. Sources of Sediment in Urban Areas 8-8
Table 8-4. Source Area Concentrations for TSS in Urban Areas 8-8

Table 8-5. Sediment Impacts on Receiving Waters 8-10
Table 8-6. Metal Sources and Hot Spots in Urban Areas 8-15
Table 8-7. Metal Source Area Concentrations in Urban Areas (in ug/L) 8-16
Table 8-8. Metals Impacts on Receiving Waters 8-17
Table 8-9. Effects of PAHs and Oil and Grease on Receiving Waters 8-18
Table 8-10. Percentage Detection of *Giardia* Cysts and *Cryptosporidium* Oocysts in Subwatersheds and Wastewater Treatment Plant Effluent in the New York City Water Supply Watersheds 8-20
Table 8-11. Effects of Bacteria on Receiving Waters 8-21
Table 8-12. Physical Impacts of Urbanization on Streams 8-22
Table 8-13. Hydrologic Differences Between a Parking Lot and a Meadow 8-24
Table 8-14. Comparison of Bulk Density for Undisturbed Soils and Common Urban Conditions 8-26
Table 8-15. Ecoregion Surface Soil Texture Characterization 8-36
Table 8-16. Range of Annual Erosion Estimates by Dominant Soil Type in Each Ecoregion (tons/acre/year) 8-38
Table 8-17. Estimated Soil Grain Size Distribution 8-40
Table 8-18. Description of EPA Construction Site Analysis for BMP Removal Estimation . . . 8-41
Table 8-19. Methodology for Estimating BMP Removal Rates 8-44
Table 8-20. Range of BMP Percent Removals (Weighted by Grain Size Distribution) 8-46
Table 8-21. National Annual Construction Load Estimates 8-47
Table 8-22. State Annual Construction Load Estimates (Tons) 8-48
Table 8-23. Summary of Construction and Development Loadings 8-51
Table 8-24. Example of Output from Site and Load Distribution Process 8-52
Table 8-25. NPS TSS Loads Modified for Construction and Development Analysis 8-53
Table 8-26. Summary of Construction and Development TSS Loads 8-54
Table 8-27. Summary of Waters Affected (Option 2/4) 8-54
Table 8-28. Economic Benefits Using the WQL Approach (Option 2/4) 8-55
Table 8-29. Economic Benefits Using the WQI Approach (Option 2/4) 8-55

Appendices

Appendix A: Model Construction Site Geometry
Appendix B: Supporting Cost Data
Appendix C: RUSLE Evaluation Information
Appendix D: State Erosion and Sediment Control Requirements
Appendix E: State Distribution of Construction Sites by Site Size, Land Use and Erosive Risk
Appendix F: Supporting Loads Data