



Commissioning Security Systems for Drinking Water Utilities

Office of Water (4608-T)
EPA 817-R-12-002
February 2012
www.epa.gov/watersecurity

Disclaimer

This document was developed by the U.S. Environmental Protection Agency (EPA) Division of Ground Water and Drinking Water's Water Security Initiative. The information presented in this document is intended to provide guidance and to assist drinking water utilities in the commissioning of security equipment. The EPA does not provide any guarantees for actions taken by any persons in response to this guidance. The use of the word "should" in this guidance is intended solely to recommend or suggest and does not connote a requirement.

Executive Summary

This report discusses commissioning of security systems and provides a step-wise commissioning process and commissioning forms for use by drinking water utilities. Commissioning is the testing of both new and upgraded systems to verify that the operation and performance meet contract document requirements. Increasingly, water utilities are installing sophisticated security systems at their facilities, yet utility management often finds that these systems do not operate at the expected level of performance. Even worse, some security systems are abandoned because the systems have never worked as the owner intended. Proper commissioning of equipment ensures that installed security systems will operate at the expected level of performance and decreases the likelihood that this equipment will be abandoned soon after installation.

The objectives of commissioning are to ensure security systems perform as designed, meet the owner's needs, and minimize nuisance alarms that can reduce operator confidence in the systems. Benefits of commissioning include increased operator and management confidence in the security systems, validated system documentation, and reinforced owner training. Additional benefits include increased system effectiveness and improved system maintenance by having a baseline of expected system performance. Failure to adequately commission a security system can result in the delay of system startup, owner dissatisfaction, increased maintenance, professional liability claims, warranty issues, and placing utility assets at risk.

The commissioning process begins with a plan that establishes and identifies the major elements of commissioning: systems and components to be commissioned, participants in commissioning, and participant roles. Commissioning forms are developed and incorporated into the contract documents. Pre-startup testing ensures that the system equipment is ready to be started, and functional testing provides the formal commissioning of the system (ensuring correct system operation and performance). Retesting occurs when a system does not pass functional testing, after a repair to a system, or on a periodic basis. After completion of functional testing and any re-tests of failed functional tests, a testing report, along with the system operation and maintenance manuals, is submitted to the owner. The owner then assumes responsibility for operating and maintaining the system, including retesting.

This report includes eight example forms for commissioning security equipment, including access-controlled doors, perimeter detection systems, camera systems, and video recording systems. The forms can be edited to meet individual owner needs and included in contract documents.

Table of Contents

DISCLAIMER	I
EXECUTIVE SUMMARY	III
TABLE OF CONTENTS	V
LIST OF ACRONYMS	VI
SECTION 1.0: INTRODUCTION	1
1.1 COMMISSIONING OBJECTIVES	1
1.2 BENEFITS OF COMMISSIONING	2
SECTION 2.0: THE COMMISSIONING PROCESS	4
2.1 STEP 1: SPECIFY OVERALL PLAN AND PROCESSES	4
2.2 STEP 2: IDENTIFY SYSTEMS, EQUIPMENT, AND COMPONENTS.....	4
2.3 STEP 3: DEVELOP FUNCTIONAL TEST PROCEDURES	4
2.4 STEP 4: INCORPORATE FORMS AND CHECKLISTS INTO CONTRACT DOCUMENTS	4
2.5 STEP 5: INSTALL EQUIPMENT	5
2.6 STEP 6: PERFORM PRE-STARTUP TESTS	5
2.7 STEP 7: PERFORM FUNCTIONAL TESTS	5
2.8 STEP 8: RETEST AS NECESSARY	5
2.9 STEP 9: TURN OVER	6
SECTION 3.0: COMMISSIONING FORMS	8
3.1 FUNCTIONAL TEST FORMS	8
3.1.1 Access Control Systems	8
3.1.2 Intrusion Detection Systems.....	8
3.1.3 Video Surveillance Systems.....	8
3.2 OTHER COMMISSIONING FORMS	8
SECTION 4.0: REFERENCES	9
APPENDIX A. EXAMPLE COMMISSIONING FORMS	10
A.1 SECURITY ACCESS SYSTEM – ACCESS-CONTROLLED DOOR EXAMPLE FORM	10
A.2 INTRUSION SYSTEM EXAMPLE FORM.....	12
A.3 PERIMETER DETECTION SYSTEM EXAMPLE FORM	14
A.4 CCTV FIXED POSITION CAMERA EXAMPLE FORM	16
A.5 CCTV PTZ CAMERA EXAMPLE FORM.....	18
A.6 DVR OR NVR EXAMPLE FORM	20
A.7 CLIENT WORKSTATION EXAMPLE FORM	22

List of Acronyms

The list below includes acronyms approved for use in this document. Acronyms are defined at first use in the document.

ANSI	American National Standards Institute
AWWA	American Water Works Association
BCA	Building Commissioning Association
CCTV	Closed-Circuit Television
DVR	Digital Video Recorder
EPA	U.S. Environmental Protection Agency
HVAC	Heating, Ventilation, and Air Conditioning
NVR	Network Video Recorder
PTZ	Pan-Tilt-Zoom
REX	Request to Exit

Section 1.0: Introduction

An increasing number of water utilities are installing sophisticated security systems at their facilities, yet utility management often finds that these systems do not operate at a level of performance that is expected. Even worse, some security systems are abandoned because the systems have never worked as the owner intended. Proper commissioning of equipment ensures that installed security systems will operate at an expected level of performance and decreases the likelihood that this equipment will be abandoned soon after installation. Properly designed and maintained security systems are a vital component of protective security programs for drinking water utilities, as stated in the American Water Works Association (AWWA) standard *ANSI/AWWA G430-09: Security Practices for Operation and Management*, 2009.

Commissioning is the testing of systems to verify that the operation and performance of both new and upgraded systems meet contract document requirements. A system consists of equipment, and equipment consists of components. Commissioning a system begins with commissioning components, followed by commissioning equipment, and then commissioning the entire system.

Federal and state agencies have not developed or adopted commissioning standards for security systems. The Building Commissioning Association (BCA), an industry trade group, develops standard commissioning documents. The documents consist of commonly used administrative and technical forms, training templates, and checklists¹. BCA has yet to develop security system commissioning documents, but may do so in the future. The authors of this report are not aware of other trade groups that have developed commissioning documents, but new and existing trade groups could develop these documents in the future. This report documents a commissioning process and provides forms developed by the authors based on professional experience in the commissioning of security systems on numerous projects. Commissioning of data management and communication systems is not addressed.

1.1 Commissioning Objectives

Commissioning objectives include:

- **Perform as Designed.** The systems and equipment should perform in accordance with the contract documents (i.e., drawings and specifications). The contract documents may include a commissioning or functional test form that contains a checklist for the commissioning process. This form provides documentation that the system is installed in accordance with the system specifications and indicates whether the standard of workmanship is acceptable. (Examples are included in the appendix of this report.)
- **Meet Owners' Needs.** The systems should perform in accordance with owners' needs. The owner requirements must be clearly stated in the contract documents. Commissioning involves owners and their end users at the onset of the project to help identify expectations.
- **Minimize Nuisance Alarms.** Nuisance alarms are caused by an external source such as animals, wind, rain, etc, whereas a false alarm is generated solely by the internal electronic elements of a sensor, such as a faulty circuit. The frequency of nuisance alarms should be low. Recurring nuisance alarms lead to a reduction in operator confidence in the system. Operators may start ignoring alarms that they perceive as nuisance alarms without thoroughly investigating the alarms. Recurring nuisance alarms can also unnecessarily burden emergency response services.

¹ For closed-circuit television (CCTV), BCA has developed a *Security CCTV System Construction Checklist* (BCA, 2006) to verify that a CCTV system is ready for commissioning, but has yet to develop a CCTV system commissioning document.

1.2 Benefits of Commissioning

Utility managers are increasingly commissioning equipment systems and buildings to verify that the system has been installed as designed and to improve the likelihood that the system equipment will maintain a specified level of performance throughout its life. Benefits of commissioning new systems include:

- **Increased Confidence and Satisfaction.** Utility operators and management gain confidence in the system by knowing proper system operation and that the system is functioning properly through systematic testing. Performance or achieving lifecycle and maintenance requirements can result in owner satisfaction.
- **Validated System Documentation.** Contract documents require the completion of commissioning forms that provide complete and accurate documentation of each system.
- **Improved System Maintenance.** Commissioning establishes a baseline of expected system performance for comparison purposes when maintaining the system. Operators and maintenance staff (the “end users”) learn how the system is expected to operate through the commissioning process.
- **Reinforced Owner Training.** Owner participation in startup commissioning reinforces the system training that is typically required in the contract documents. The owner also becomes more familiar with expected system performance and how to troubleshoot aspects of the system. Owner participation promotes a more effective and sustainable security culture.
- **Increased System Effectiveness.** Commissioning identifies and tests as many single points of failure as possible, thereby improving system effectiveness before the system becomes operational. Commissioning avoids delays in system startup by eliminating unexpected issues or system faults, which could require the utility to hire or assign security guards, or even cease operations, until the security system is online.
- **Less Risk.** Commissioning reduces the likelihood a faulty or ineffective security system will place staff and key utility assets at potential health and safety risks that could be caused by theft, vandalism or terrorist attack. A faulty system could put the utility at financial risk to professional liability claims.
- **Fewer Warranty Claims.** Continual callbacks with the vendor to solve system problems and settle warranty claims may arise when working with a noncommissioned system. The start date of a warranty is vague without commissioning. The contract documents should state that the manufacturer’s warranty starts after successful commissioning. Without commissioning, a manufacturer could claim that the warranty began upon delivery of the equipment which can occur months before the system begins operation.

Section 2.0: The Commissioning Process

The commissioning process consists of the following steps:

1. Specify overall plan and process
2. Identify systems, equipment, and components
3. Develop functional test procedures
4. Incorporate forms and checklists into contract documents
5. Install equipment
6. Perform pre-startup tests
7. Perform functional tests
8. Retest as necessary
9. Turn over

A plan is essential to commissioning a system as the plan establishes and identifies the major elements of commissioning: systems and components to be commissioned, participants in commissioning, and participant roles. Commissioning forms are developed and incorporated into the contract documents. Pre-start-up testing ensures that the system equipment is ready to be started, and functional testing provides the formal commissioning of the system (ensuring correct system operation and performance). Retesting occurs when a system does not pass functional testing, after a repair to a system, or on a periodic basis. After completion of functional testing and any re-tests of failed functional tests, a testing report along with the system operation and maintenance manuals are submitted to the owner. The owner then assumes responsibility for operating and maintaining the system, including retesting.

2.1 Step 1: Specify Overall Plan and Processes

A commissioning team typically consists of representatives of the contractor, owner, engineer, and end user. The team meets to decide on team member roles and responsibilities, and the associated tasks for all project phases and activities. Review and acceptance procedures, documentation requirements, and the development and approval of related commissioning checklists and forms are also decided by the team. The contractor is often not selected until after the preparation of contract documents. In these instances, the contractor joins the commissioning team once the contract is awarded.

2.2 Step 2: Identify Systems, Equipment, and Components

The commissioning team develops a list of all of the system elements to be commissioned. This list provides a complete and thorough investigation of the security system's components and equipment.

2.3 Step 3: Develop Functional Test Procedures

The functional tests are the main elements of commissioning. The commissioning team develops functional test forms and checklists for the equipment inspections or component tests that verify proper installation and performance (e.g., camera positioning, sensor calibration, etc.). Forms are discussed in more depth in Section 3. The completed forms and checklists should be reviewed by the engineer or owner's representative prior to approval of the equipment or system for initial operation.

2.4 Step 4: Incorporate Forms and Checklists into Contract Documents

The forms, checklists, and procedures to be used during commissioning are included in the contract documents (i.e., specifications and drawings).

2.5 Step 5: Install Equipment

Installation of the equipment is expected to meet or exceed all applicable federal, state, and local requirements. Installation is also expected to conform to codes (e.g., National Electrical Code, National Fire Protection Association) and ordinances of authorities that have jurisdiction in accordance with the contract documents. Equipment is installed in accordance with the manufacturers' published recommendations.

2.6 Step 6: Perform Pre-startup Tests

Pre-startup tests are the initial testing and procedures that occur in advance of the formal functional testing. The contractor performs the pre-startup tests to verify the equipment is powered, calibrated, operational, and ready for functional testing. Pre-startup tests can include verifying initial settings such as camera focus, system communication, video recording settings, system calibration, and tuning. During this stage, the contractor may find faults in the installation, hardware, or software settings, which must be corrected prior to functional testing. Even common components such as video cameras will benefit from a quick pre-startup bench test prior to installation to ensure correct focus, field of view, and backlight compensation settings. Pre-startup testing allows components damaged in shipment to be replaced and systems that require calibration or adjustment to be more efficiently serviced. The owner and engineer are typically not present during pre-startup tests.

2.7 Step 7: Perform Functional Tests

Functional testing is the formal testing of the entire security system under full operation. Successful completion of functional testing commissions the system. The purpose of functional testing is to thoroughly review and document the equipment and installation to verify that functional and performance requirements in the contract documents are met. The functional performance test consists of individual component testing and progresses to the testing of entire systems as an integrated security platform. The system is operated through all the modes of operation and under varying conditions, and each component verified to be responding during the process is documented.

During functional testing, temporary modifications may be necessary as the test proceeds. The specific tests required and the order of tests will vary depending on the type and size of systems, number of systems, sequence of installation, and relationship with the building elements (e.g., heating, ventilation, and air conditioning; building doors). Testing of systems may occur in stages depending on the progress of work or as proposed by the contractor. For example, an internet connection may not be available until after completion of building construction. Commissioning of portions of the system can occur prior to the internet connection, but the portions that require an interconnect connection are commissioned at a later date. The commissioning team uses the functional test forms developed in Step 3 and contained with the contract documents to coordinate and document the testing. The tests are typically performed by the installing contractor or vendor, and witnessed by the engineer and owner's representative.

2.8 Step 8: Retest as Necessary

Retesting may occur for three separate reasons: First, retesting may be necessary for systems that do not pass the functional test. Second, re-testing may occur after repairs are made to a system to reconfirm system performance. Third, periodic retesting of commissioned systems is recommended to ensure that system performance continues to meet contract document requirements and system performance is satisfactory. Periodic retesting occurs on a regular basis and is typically performed semi-annually or annually. Periodic retests incorporate monitoring, review, and analysis of system performance data provided by the users as well as low-level functional testing of the system by the utility. Retesting after repairs or on a periodic basis is most effective for systems that have been properly commissioned and have an established baseline performance measurement from the initial commissioning process (i.e., when

the systems are fine tuned and operating as efficiently as possible). Retesting is an essential element in security system maintenance and should be incorporated within the initial planning of the commissioning program. A schedule of required periodic testing could be a contract deliverable for the owner. The schedule could specify retesting by component, equipment, or system wide.

2.9 Step 9: Turn Over

The installing contractor prepares a functional performance test report covering all measured data, data sheets, and a comprehensive summary describing system operation at the time of the functional performance tests. The test report is submitted along with system operation and maintenance manuals to the owner. The owner accepts responsibility for operating and maintaining the security system.

Section 3.0: Commissioning Forms

During the commissioning process, the commissioning team develops functional testing forms to verify that the test results and system performance are consistent with the criteria established in the contract documents. These forms consist of project-specific tests and checklists.

3.1 Functional Test Forms

Several example security functional test forms are provided in Appendix A. These forms are provided to point out some of the more critical testing elements that are important when commissioning security systems.

3.1.1 Access Control Systems

Access control systems electronically control entry into buildings or facilities. These systems consist of door readers, access badges, computer servers, wiring, and communication protocols for allowing or denying entry to areas within a facility based on predetermined employee authorizations. The functional test form included for commissioning access control systems is the Access-controlled Door Example Form. This form can be found in Appendix A.1.

3.1.2 Intrusion Detection Systems

Intrusion detection systems provide a means for detecting unauthorized entry within a protected area by monitoring doors, hatches, fences, and perimeter boundaries. The functional test forms for commissioning intrusion detection systems include the Intrusion System Example Form and Perimeter-Detection System Example Form and can be found in Appendix A.2 and A.3.

3.1.3 Video Surveillance Systems

A video surveillance system consists of video cameras transmitting a signal to a monitoring station or recording device. There are several elements that can make up the video system, including cameras, digital or network recording systems, and system software. The functional test forms for commissioning video surveillance systems include the CCTV Fixed Position Camera, Pan-Tilt-Zoom (PTZ) Camera, Digital Video Recorder (DVR), Network Video Recorder (NVR), and Security Client Workstation Software Example Forms. These example forms can be found in Appendix A.4 through A.7.

3.2 Other Commissioning Forms

The following types of commissioning forms may be useful in addition to the included functional testing forms:

- Progress Check Forms. These forms track the progress of systems and equipment from submittal phase through installation, pre-startup testing, functional testing, and retesting.
- Pre-Startup Testing Check Forms. These forms document that the systems and equipment are powered, calibrated, operational, and ready for functional tests.

Section 4.0: References

American National Standards Institute/American Water Works Association. 2009. *AWWA Standard for Security Practices for Operation and Management*, G430-09.

Building Commissioning Association. 2006. *Security CCTV System Construction Checklist*.
<<http://www.bcx.org/resources/templates/templates.htm>>.

Appendix A. Example Commissioning Forms

A.1 Security Access System – Access-controlled Door Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

SECURITY ACCESS SYSTEM – ACCESS CONTROLLED DOOR

Panel #: _____ Port #: _____ Address #: _____

Unique Identifier: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

Access-Controlled Door: New Upgrade

A. General Notes:

1. The following procedure is to confirm the installation and operation of the Security Access System for compliance with the Contract Documents and its intended operation.

B. Checklist:

- | | | |
|--|-----------------------------|------------------------------|
| 1. Door unlock time, entry reader (<i>present card and doesn't open door</i>) | _____ | Seconds |
| 2. Valid entry – No alarms? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 3. Forced door alarms? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 4. Held door alarm after valid card read? (<i>present card and hold door open</i>) | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 5. Held door alarm after Request to Exit (REX)? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 6. Local noise operates when door held too long? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 7. Door relocks upon? (<i>opening, closing or other – specify</i>) | _____ | |
| 8. Valid card read while REX active? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 9. REX shunts alarm functions on exit? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 10. REX operates when approached from all directions? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 11. Does REX <u>NOT</u> unlock the door? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 12. “No Special Knowledge” required to exit?
<i>(If NO, write explanation under “Comments”)</i> | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 13. Door unlock time, exit reader? (<i>present card and doesn't open door</i>) | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 14. Local noise operates when card not used? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 15. Does door close and lock securely? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 16. Theft-resistant screws installed? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 17. Invalid card detected? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 18. Workmanship clean and neat? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 19. Wire tagging and panel label per specifications? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |

Comments:

A.2 Intrusion System Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

INTRUSION SYSTEM

System Type: _____ Account number: _____

Location: _____

Primary phone number: _____ Secondary phone number: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

Intrusion System: New Upgrade

A. General Notes:

1. The following procedure is to confirm the installation and operation of the Intrusion System for compliance with the Contract Documents and its intended operation.

B. Checklist:

1. Put system in test!
2. Workmanship clean and neat. No Yes
3. Wire tagging and panel label(s) per specifications. No Yes
4. Battery installed? N/A No Yes Date: _____
5. Panel communicates with Central Station? N/A No Yes
6. All zones verified with Central Station? N/A No Yes
7. Panel communicates with keyboard? N/A No Yes
8. User codes tested? N/A No Yes
9. System arms? No Yes
10. System disarms locally? No Yes
11. System disarms remotely? No Yes
12. Zone boundaries conform? No Yes
13. Local sounder activates upon alarm? No Yes
14. Sequence of operations written? No Yes
15. Sequence of operations programmed? No Yes
16. User group trained on normal system operation? No Yes
17. User group trained to verify and respond to alarm condition? No Yes
18. Central station has current list of contacts and call order? No Yes
19. Test autodialer system. Are phone numbers correct? No Yes

ZONE LIST:

AREA	ZONE / POINT	DESCRIPTION

Comments:

A.3 Perimeter Detection System Example Form

JOB #: _____ FUNCTIONAL TEST FORM

PROJECT: _____ BUILDING: _____

PERIMETER DETECTION SYSTEM

System Type: _____ Panel type: _____

Location: _____

Com Port: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

Perimeter Detection System: New Upgrade

A. General Notes:

1. The following procedure is to confirm the installation and operation of the Intrusion System for compliance with the Contract Documents and its intended operation.

B. Checklist:

1. Check if panel is communicating. No Yes
2. Check signal strength per manufacturer's instructions. N/A No Yes
3. Fence in good repair? No Yes
4. Test zones walked? No Yes
5. Complimentary sensors alarm in margins of perimeter detection system? No Yes
6. Valid alarms simulated?
 - a. Climb attempts detected? No Yes
 - b. Cut attempts detected? No Yes
 - c. Crawl attempts detected? No Yes
7. Valid intrusion detected along entire detection zone? No Yes
8. Alarm thresholds tuned?
 - a. Alarm on shadows? No Yes
 - b. Alarm due to headlights? No Yes
9. System distinguishes between valid and false alarms appropriately? No Yes
10. Video records on alarm? N/A No Yes
11. Correct camera or camera view called up? N/A No Yes
12. Cameras views line up with zone requirements? N/A No Yes

A.4 CCTV Fixed Position Camera Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

VIDEO SURVEILLANCE SYSTEM (CCTV) – FIXED POSITION CAMERA

Point Identification: _____ Location: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

CCTV – Fixed Position Camera: New Upgrade

A. General Notes:

1. The following procedure is to confirm the installation and operation of the Video Surveillance System for compliance with the Contract Documents, the National Electrical Code, and industry-accepted standards.

B. Checklist:

1. Transformer location: _____
2. Workmanship clean and neat? No Yes
3. Back-focus adjustment appropriate? No Yes
4. Lens adjustment appropriate? No Yes
5. Auto Iris lens functioning correctly? No Yes
6. Wire tagging per specifications? No Yes
7. Proper device per specifications and drawings? No Yes
8. Housing property installed? No Yes
9. Housing and mount stout enough for expected conditions? No Yes
10. Blower working? No Yes
11. Heater working? No Yes
12. Fiber transmitter functional? No Yes
13. Video synchronization adjusted? No Yes
14. Theft resistant screws installed? No Yes
15. Field of view _____
16. Changes from day to night view successfully? No Yes
17. Low light vision tested? No Yes
18. Backlight compensation tested? No Yes
19. System acts as required on power loss? No Yes

Comments:

A.5 CCTV PTZ Camera Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

VIDEO SURVEILLANCE SYSTEM (CCTV) – PAN, TILT, AND ZOOM CAMERA

Point Identification: _____ Location: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

CCTV: New Upgrade

A. General Notes:

1. The following procedure is to confirm the installation and operation of the Video Surveillance System for compliance with the Contract Documents, the National Electrical Code, and industry-accepted standards.

B. Checklist:

1. Transformer location: _____
2. Workmanship clean and neat? No Yes
3. Wire tagging per specifications? No Yes
4. Housing properly installed? No Yes
5. Blower working? No Yes
6. Heater working? No Yes
7. Fiber transmitter functional? No Yes
8. Pan left and right? No Yes
9. Theft resistant screws installed? No Yes
10. Tilt up and down? No Yes
11. Mechanical stops set? No Yes
12. Electronic stops set? No Yes
13. Limit stops on pan-tilt motor functional? N/A No Yes
14. Receiver drive test modes all functional? No Yes
15. Receiver drive address _____
16. Power source Emergency Utility UPS
17. Panelboard and circuit number _____
18. Video synchronization adjusted? No Yes
19. Field of view _____

Comments:

A.6 DVR or NVR Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

DIGITAL or NETWORK VIDEO RECORDER (DVR or NVR)

Panel type: _____ Software Version: _____

Serial Number: _____ IP Address: _____

Subnet Mask: _____ Gateway: _____

Panel location: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

DVR/NVR: New Upgrade

Location: _____ Bldg.: _____ Floor: _____

Unit Designation: _____

A. Checklist:

- | | | |
|--|------------------------------|--|
| 1. Workmanship clean and neat? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 2. Wire tagging per specifications? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 3. Proper device per specifications and drawings? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 4. Server software restarts when system rebooted? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 5. Recognizes and communicates with all cameras? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 6. Alarm generated on loss of video? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 7. Recordings schedules set? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 8. Camera views set to client requirements? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 9. Motion detection or analytics programmed for each camera? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 10. Nuisance alarm issues? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 11. Integration with access control server programmed? | <input type="checkbox"/> N/A | <input type="checkbox"/> No <input type="checkbox"/> Yes |
| 12. Spot monitor or camera pop up upon alarm? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 13. Connects with remote view software? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 14. Video recording functional? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 15. Successfully find motion event. | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 16. Successfully search for video? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 17. Successfully export video clip? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 18. Client trained on system administration? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 19. Secured logon in place? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |

Comments:

A.7 Client Workstation Example Form

JOB #: _____ **FUNCTIONAL TEST FORM**
PROJECT: _____ **BUILDING:** _____

CLIENT WORKSTATION

Client Software: _____ Software Version: _____

Serial Number: _____ IP Address: _____

Subnet Mask: _____ Gateway: _____

Performed by: _____ Date: _____

Witnessed by: _____ Date: _____

Client Workstation: New Upgrade

Location: _____ Bldg.: _____ Floor: _____

Unit Designation: _____

A. Checklist:

- | | | |
|--|--|------------------------------|
| 1. Proper device per specifications and drawings? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 2. Client software restarts when system rebooted? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 3. Monitors positioned for ease of viewing? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 4. Cables coiled and tied neatly? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 5. Recognizes and communicates with network and cameras? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 6. Alarm list view set to client requirements? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 7. Camera views set to client requirements? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 8. Alarm notification at sufficient volume to notify system users? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 9. Integration with access control server programmed? | <input type="checkbox"/> N/A <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 10. Spot monitor or camera pop up upon alarm? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 11. Successfully find motion event. | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 12. Successfully search for video? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 13. Successfully export video clip? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 14. Client trained on system monitoring? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 15. Client can connect to all sites? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 16. Client can display cameras on all monitors? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 17. Client can control PTZ cameras? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 18. Secured logon hierarchy in place? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |
| 19. Third party software enabled? | <input type="checkbox"/> No | <input type="checkbox"/> Yes |

Comments:
