

Beazer

BEAZER EAST, INC. C/O THREE RIVERS MANAGEMENT, INC.
MANOR OAK ONE, SUITE 200, 1910 COCHRAN ROAD, PITTSBURGH, PA 15220

November 6, 2015

Ms. Carolyn Bury
U.S. Environmental Protection Agency, Region V
77 West Jackson Boulevard
Mail Code DE-9J
Chicago, IL 60604-3590

Re: Former Koppers Wood-Treating Site – Carbondale, Illinois
Final Human Health Risk Assessment and Responses to USEPA’s 10/6/15 Comments

Dear Ms. Bury:

Enclosed please find the final Human Health Risk Assessment (HHRA) for the Former Koppers Wood-Treating Site in Carbondale, Illinois (the Site) prepared by Arcadis U.S., Inc. (Arcadis) on behalf of Beazer East, Inc. (Beazer). The HHRA evaluates potential adverse human health effects attributable to potential exposures to Site-related constituents, and was prepared in accordance with the Human Health Risk Assessment Work Plan (Arcadis, 2014), which was approved by USEPA in a letter to Beazer dated September 25, 2014. The attached version reflects USEPA’s October 6, 2015 comments regarding a redline version of the HHRA that was provided by Arcadis to the USEPA on April 27, 2015, subsequent edits to the draft Conceptual Site Model (CSM) figure submitted by Arcadis on October 22, 2015, and discussions during a conference call on October 28, 2015. USEPA’s approval to finalize the document to reflect the agreed-upon modifications was provided via email on October 29, 2015.

In addition to the enclosed document, provided below is a summary of USEPA’s comments from the October 6, 2015 letter to Beazer, along with a summary of how each comment was addressed. USEPA’s comments are presented below in bold font followed by our responses in italicized font.

Figure 2. Conceptual Site Model

- 1. Add a column for "Primary Constituents of Concern" after "Potential Sources" and list the Site COCs, including creosote as a DNAPL.**

Figure 2, Conceptual Site Model was revised to specify the primary constituents of concern associated with each potential source as a combined column.

- 2. The CSM does not include DNAPL and its migration pathway to receptors; the constituent and its pathway must be added.**

Figure 2, Conceptual Site Model has been revised as requested.

- 3. Change "Potential Sources" to "Sources."**

Figure 2, Conceptual Site Model has been revised as requested.

4. Under "Potential Sources," the word "possible" must be struck from the text in the box that states "possible releases during historic operations as a wood-treating facility." Releases have been documented and described in Beazer documents. Therefore, the word "possible" is inaccurate.

Figure 2, Conceptual Site Model has been revised as requested.

5. Under "Primary Media," change the box with the words "onsite soil" to "on-site surface and subsurface soil."

Figure 2, Conceptual Site Model has been revised as requested.

6. Add "gravity" under Potential Transport Mechanisms to account for DNAPL migration around the Site in the subsurface and on the surface, including into the waterways.

Figure 2, Conceptual Site Model has been revised as requested, and flow lines were adjusted to reflect this added transport mechanism.

7. For off-site soil south of the site, the current/future adult and child resident exposure pathway status should be changed from "incomplete" to "complete but insignificant." EPA's analysis of neighborhood soil concluded that exposure to contaminants of interest is complete but insignificant based on the COC concentrations observed in off-site soil. A footnote could be added in the CSM figure explaining the rationale.

As discussed with USEPA during a conference call on October 28, 2015, this proposed change would conflict with previous communications from USEPA; specifically, USEPA's March 14, 2014 letter to Beazer and the HHRA Work Plan approved by USEPA on September 25, 2014. USEPA subsequently withdrew this comment via email on October 29, 2015; therefore, no change has been made to Figure 2, Conceptual Site Model regarding this withdrawn comment.

8. For off-site soil west, north, and east of the site, the current/future adult and child resident exposure pathway status should be changed from "incomplete" to "complete but insignificant." Land-use in these areas includes farms, light commercial/industrial and undeveloped areas.

Figure 2, Conceptual Site Model has been revised as requested.

9. There should be a way to capture off-site surface water and sediment west, north, and east of the site for the current/future adult and child resident exposure pathway status. Land use in these areas includes farms, light commercial/industrial and undeveloped areas. For example, exposures to Smith Ditch, which runs from the Site to private property (farmland) to the north, were evaluated in the HHRA. Exposures to Smith Ditch water and sediment would be "complete" and presumably "insignificant."

Figure 2, Conceptual Site Model has been revised as requested. The "NA" symbols for the "Current/Future Adult and Child Resident" for "OFF-SITE SOIL WEST, NORTH, AND EAST OF THE SITE" and for "SURFACE WATER" and "SEDIMENT" have been changed to open circles noting that those exposure pathways are "Potentially Complete but Insignificant."

Other than a typo on page 6, second paragraph which states, "of the on-Site of off-Site" EPA has no further requests for revisions.

The report has been revised to address this typo.

Addressing Uncertainty Regarding Fish Ingestion

USEPA's October 6, 2015 letter also stated that "significant uncertainty" was associated with the evaluation of potential risks related to consumption of fish from Crab Orchard Creek (COC). USEPA attributed this uncertainty to a small sample set of fish that were caught close to the Site and the absence of fish samples from more distant downstream locations. USEPA believes that uncertainty is somewhat offset by the fact that a fish consumption advisory has been established for Crab Orchard Creek in Jackson County, but, in consultation with Illinois EPA, believes additional fish sampling is appropriate before eliminating the consumption advisory. Accordingly, USEPA is requiring that Beazer include fish tissue monitoring as a component of the Monitored Natural Recovery (MNR) program to be implemented for COC, and as a means for ultimately developing an "exit strategy" for the consumption advisory. This culminated in the following excerpt from the USEPA's October 6, 2015 letter:

"The EPA will approve the revised HHRA with the caveat that, because the current fish consumption exposure analysis is encumbered with uncertainty, and given the importance of human health protection, Beazer must include an analysis of Site contaminant fish body-burden in its MNR remedy. We anticipate that the MNR remedy plan will include an exit strategy based on a determination to be made by the IFCMP that will allow Beazer to discontinue monitoring fish body burden."

Beazer disagrees with USEPA's characterization of the uncertainty associated with potential COC fish consumption risks as "significant." To the contrary, Beazer believes the available data are sufficient to demonstrate that potential risks associated with the presence of Site-related constituents in COC fish are within or below USEPA's allowable risk range. Several conversations and two evaluations, in addition to the HHRA, have documented that finding.

In an Arcadis memo dated October 18, 2012¹, a conservative estimate of productivity for the portion of COC from the Site to the most downstream sediment sampling location (COC-BC-14, which is approximately 3.5 miles downstream from the confluence of Piles Fork and COC and only approximately 1.1 miles upstream of the Dillinger Road bridge) yields an upper bound estimate of 30 kg of edible size whole fish per year. This translates into one meal produced every 9.2 days (about 25 grams/day) and eaten by a single person throughout the year. This production rate is below the ingestion rate of one meal per week (about 32 grams/day) assumed by IEPA when setting the fish advisory. Though this difference in rates may not appear very large, keep in mind that the productivity-based fish consumption rate assumes all the fish produced by this portion of COC are eaten by a *single* person. If this portion of COC were fished by 10 people, only about 2.5 grams/day could be produced for each person.

Additionally, an Arcadis April 18, 2013 letter to Dr. Thomas Hornshaw of IEPA employed a spatial weighting approach to estimate exposure point concentrations for the entire length of COC (i.e., from Crab Orchard Lake downstream to the Big Muddy River) given that the fish consumption advisory is applicable to all of COC, not just the portion immediately downstream of the Site. The risk assessments conducted by USEPA assumed that this entire length of COC has a concentration equal to that observed near the Site. The

¹ The Arcadis memo dated October 18, 2012 was included as an attachment to a February 18, 2013 letter from Beazer to IEPA regarding the Fish Consumption Advisory Assessment.

spatial weighting approach accounts for observed changes in the concentration of dioxin in sediments and fish with distance from the Site. When these differences in dioxin concentration with distance from the Site are accounted for, potential risks associated with dioxin in edible fish fall within USEPA's acceptable risk range and meet IEPA's target risk for both adult and child consumers even assuming an unrestricted consumption rate (225 meals per year, 140 grams/day). Using a still conservative but more representative consumption rate of one meal per week (32 grams/day) potential risks are well below the IEPA target risk of 1×10^{-5} and are in the low-end of USEPA's acceptable risk range.

The findings about potential risk summarized above indicate that a very large margin of safety exists between any risk that may be associated with consumption of COC fish, IEPA target risk levels, and especially USEPA's allowable risk range. Beazer believes these findings indicate that when conservative but reasonable and representative assumptions are used to estimate potential risks associated with dioxins that may be present in COC fish, little uncertainty surrounds the conclusions that such potential risks are within or below USEPA's allowable risk range.

Notwithstanding Beazer's disagreement with USEPA's position that substantial uncertainty exists in the estimation of potential risk from consumption of COC fish, Beazer is amenable to working in good faith with the USEPA toward developing a reasonable fish tissue monitoring component of the MNR Plan, including an attainable exit strategy for such component. In the meantime, pending its final review of the enclosed HHRA, we understand that USEPA will issue a written approval of the HHRA under the condition that we collectively work toward the development of a fish tissue sampling component of the MNR Plan. It is Beazer's understanding that such written approval will be provided by USEPA within the next several weeks.

Please feel free to contact me at 412-208-8867 if you have any questions or require additional information regarding this submittal, and to discuss potential dates for a meeting or conference call to continue prior discussions concerning an MNR Plan, including fish tissue monitoring components.

Sincerely,



Michael Slenska, P.E.
Senior Environmental Manager

Enclosure

cc: Tammy Moore, USEPA
Jose Cisneros, USEPA
Chip McChesney, Beazer
Jeffrey Holden, Arcadis
Paul Anderson, Arcadis
Marjorie Buckholtz, Brightfields
Pete Pedersen, Brightfields

Beazer East, Inc.

**Human Health Risk Assessment for the
Former Koppers Wood-Treating Site**

Carbondale, Illinois

November 6, 2015



**Human Health Risk
Assessment for the Former
Koppers Wood-Treating Site**

Carbondale, Illinois

Prepared for:
Beazer East, Inc.

Prepared by:
ARCADIS U.S., Inc.
1 Executive Drive
Suite 303
Chelmsford
Massachusetts 01824
Tel 978 937 9999
Fax 978 937 7555

Our Ref.:
B0039313.0000

Date:
November 6, 2015

1. Introduction	1
1.1 Site Description and Setting	1
1.2 Summary of Operational History	2
1.3 Prior Remedial Activities	2
1.4 Document Organization	4
2. Hazard Identification	5
2.1 On-Site Data	6
2.1.1 Soil	6
2.1.2 Sediment	7
2.2 Off-Site Data	7
2.2.1 Railroad Property	7
2.2.2 35' Swath	7
2.2.3 Soil North and West of the Site	7
2.2.4 Sediment North and West of the Site	7
2.2.5 Soil East of the Site	8
2.2.6 Crab Orchard Creek and Piles Fork Sediment	8
2.2.7 Crab Orchard Creek and Piles Fork Surface Water	8
2.2.8 Catfish	8
2.3 Screening of Compounds of Potential Concern	9
3. Exposure Assessment	11
3.1 Current and Future Site Conditions	11
3.2 Exposure Areas	12
3.3 Potential Exposure Pathways and Receptor Populations	13
3.4 Exposure Estimates	15
3.4.1 Soil and Sediment	16
3.4.2 Surface Water	18
3.4.3 Fish and Deer	19

3.4.3.1	Deer Meat EPCs	20
3.4.4	Potential Human Receptors and Exposure Assumptions	21
3.4.4.1	Current/Future On-Site Adult Maintenance Worker/Caretaker	21
3.4.4.2	Current/Future On-site Adult Deer Hunter and Adolescent and Child Deer Consumer	22
3.4.4.3	Current/Future On-site or Off-Site Adolescent Trespasser	22
3.4.4.4	Future On-site or Off-Site Adult and Adolescent Hikers/Bicycle Trail Users	23
3.4.4.5	Future On-site Solar Farm Redevelopment Worker	23
3.4.4.6	Future On-site Solar Farm Maintenance Worker	24
3.4.4.7	Current/Future Off-site Adult and Adolescent Kayaker/Canoeist	24
3.4.4.8	Current/Future Off-site Adult and Adolescent Recreational Angler and Child Fish Consumer	25
3.4.5	Exposure Point Concentrations	25
4.	Toxicity Assessment	30
4.1	Non-Carcinogenic Toxicity Values	30
4.2	Carcinogenic Toxicity Values	31
5.	Risk Characterization	33
5.1	Non-Carcinogenic Risk Characterization	33
5.2	Potential Carcinogenic Risk Characterization	35
6.	Uncertainty Analysis	38
6.1	Hazard Identification	38
6.2	Exposure Assessment	38
6.3	Toxicity Assessment	39
6.4	Risk Characterization	40
7.	Summary and Conclusion	42
8.	References	44

Tables

Table 1	On-Site Soil COPC Screening
Table 2	On-Site Sediment COPC Screening
Table 3	Off-Site Railroad Property Soil COPC Screening
Table 4	Off-Site 35' Swath Property Soil COPC Screening
Table 5	Off-Site North & West of the Site Soil COPC Screening
Table 6	Off-Site North & West of the Site Sediment COPC Screening
Table 7	Off-Site East of the Site Soil COPC Screening
Table 8	Off-Site East of the Site Sediment COPC Screening
Table 9	Off-Site Surface Water COPC Screening
Table 10	Off-Site Fish COPC Screening
Table 11	Benzo(a)pyrene Toxic Equivalency Factors
Table 12	2,3,7,8-Tetrachlorodibenzo-p-dioxin Toxic Equivalency Factors
Table 13	Summary of Exposure Pathways
Table 14	Human Health Exposure Assumptions
Table 15	Exposure Point Concentration Summary – Site Soil
Table 16	Exposure Point Concentration Summary – Proposed Solar Use Area Soil
Table 17	Exposure Point Concentration Summary – Future Proposed Solar Use Area Soil
Table 18	Exposure Point Concentration Summary – Southern Conservation Exposure Area Soil
Table 19	Exposure Point Concentration Summary – Railroad Property Soil
Table 20	Exposure Point Concentration Summary – 35' Swath Property Soil
Table 21	Exposure Point Concentration Summary – Soil North & West of the Site
Table 22	Exposure Point Concentration Summary – Soil East of the Site
Table 23	Exposure Point Concentration Summary – Sediment North & West of the Site
Table 24	Exposure Point Concentration Summary – Sediment East of the Site
Table 25	Exposure Point Concentration Summary – Off-Site Surface Water

Table 26	Exposure Point Concentration Summary – Off-Site Fish
Table 27	Exposure Point Concentration Summary – Deer
Table 28	Non-Cancer Toxicity Data – Oral/Dermal
Table 29	Non-Cancer Toxicity Data – Inhalation
Table 30	Cancer Toxicity Data – Oral/Dermal
Table 31	Cancer Toxicity Data – Inhalation
Table 32	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adult Maintenance Worker/Caretaker
Table 33	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adult Deer Hunter and Consumer
Table 34	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adolescent Deer Consumer
Table 35	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Child Deer Consumer
Table 36	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adolescent Trespasser
Table 37	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adult Hikers/Bicycle Trail Users
Table 38	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future On-Site Adolescent Hikers/Bicycle Trail Users
Table 39	Calculation of Cancer Risks and Non-Cancer Hazards – Future On-Site Solar Farm Redevelopment Worker
Table 40	Calculation of Cancer Risks and Non-Cancer Hazards – Future On-Site Solar Farm Maintenance Worker
Table 41	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adult Kayaker/Canoeist
Table 42	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Kayaker/Canoeist
Table 43	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adult Recreational Angler
Table 44	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Recreational Angler
Table 45	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Child Fish Consumer

Table 46	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Trespasser – Railroad Property
Table 47	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Trespasser – 35' Swath Property
Table 48	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Trespasser – Soil North & West of the Site
Table 49	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Trespasser – Soil East of the Site
Table 50	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adolescent Trespasser – Sediment North & West of the Site
Table 51	Calculation of Cancer Risks and Non-Cancer Hazards – Current/Future Off-Site Adult Hiker/Bicycle Trail Users – Railroad Property
Table 52	Calculation of Cancer Risks and Non-Cancer Hazards – Current/ Future Off-Site Adolescent Hiker/Bicycle Trail Users – Railroad Property
Table 53	Summary of Estimated Potential Human Health Risks and Hazards

Figures

Figure 1	Sample Locations and Exposure Areas
Figure 2	HHRA Conceptual Site Model for Potential Exposure
Figure 3	Flouranthene Thiessen Polygon Map
Figure 4	Naphthalene Thiessen Polygon Map
Figure 5	Pentachlorophenol Thiessen Polygon Map
Figure 6	Pyrene Thiessen Polygon Map
Figure 7	BaP-TE Thiessen Polygon Map
Figure 8	Arsenic Thiessen Polygon Map
Figure 9	Chromium Thiessen Polygon Map
Figure 10	Dioxin/Furan Thiessen Polygon Map

Appendices

A	Data by Medium
B	USEPA March 14, 2014 Letter, Work Plans and Characterization Data for the Neighborhood South of the Site
C	ProUCL Output

Acronyms and Abbreviations

95 th UCL	95 th percentil upper confidence limit
ABS _d	dermal absorption factor
ABS _{GI}	gastrointestinal absorption factor
ABS _o	oral absorption fraction
ADD	average daily dose
ADE	average daily exposure
ASL	above screening level
AT	averaging time
Ba _{deer}	biotransfer factor for deer
BaP	benzo(a)pyrene
BaP-TE	benzo(a)pyrene toxic equivalents
bgs	below ground surface
Br	plant-soil bioconcentration factor
BSL	below screening level
B _{soil}	soil bioavailability factor
BW	body weight
C	concentration
Cal EPA	California Environmental Protection Agency
CAMU	corrective action management unit
C _{deer}	constituent concentration in deer meat
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CF	conversion factor
cm ²	square centimeters
cm ³ /d	cubic centimeters per day
COC	Crab Orchard Creek
COPC	constituent of potential concern

C_{plant}	constituent concentration in plant tissue
CS	constituent concentration in soil
C_{sw}	constituent concentration in surface water
CSF	cancer slope factor
DA_{event}	absorbed dose
days/yr	days per year
DL	detection limit
DNAPL	dense non-aqueous phase liquid
ED	exposure duration
EF	exposure frequency
EFH	Exposure Factors Handbook
EPC	exposure point concentration
ET	exposure time
EV	event frequency
events/day	events per day
FA	fraction absorbed of water
FI	fraction ingestion
ft	feet
g/day	grams per day
GI	gastro-intestinal
g/kg-day	gram per kilogram per day
HASP	health and safety plan
HEAST	Health Effects Assessment Summary Tables
HHRA	human health risk assessment
HI	hazard index
HQ	hazard quotient
hr/day	hour per day
hr/event	hour per event

IEPA	Illinois Environmental Protection Agency
IR	ingestion rate
IRIS	Integrated Risk Information System
IUR	inhalation unit risk
kg	kilograms
kg/day	kilogram per day
Kp	dermal permeability constant
L	liter
LADD	lifetime average daily dose
LADE	lifetime average daily exposure
L/day	liters per day
LOAEL	lowest observed adverse effects level
m ³	cubic meter
m ³ /kg	cubic meter per kilogram
mg	milligram
mg/cm ²	milligrams per square centimeter
mg/cm ² -event	milligram per square centimeter per event
mg/day	milligrams per day
mg/kg	milligram per kilogram
mg/kg-day	milligram per kilogram per day
(mg/kg-day) ⁻¹	per milligram per kilogram per day
mg/kg ww	milligram per kilogram in wet weight
mg/m ³	milligram per cubic meter
m ³ /kg	cubic meter per kilogram
MW	mega watt
NA	not available
NAS	National Academy of Sciences
ND	non-detect

NOAEL	no observed adverse effects level
NSL	no screening level
NTX	no toxicity data available
PAHs	polynuclear aromatic hydrocarbons
PEF	particulate emission factor
PELCR	potential excess lifetime cancer risk
POTW	publicly owned treatment works
PPE	personal protection equipment
PPRTV	provisional peer reviewed toxicity values
PRG	preliminary remediation goal
Q_{plant}	quantity of plants ingested
Q_{soil}	quantity of soil ingested
RAGS	Risk Assessment Guidance for Superfund
RCRA	Resource Conservation and Recovery Act
RfC	reference concentration
RfD	reference dose
RME	reasonable maximum exposure
RSL	regional screening levels
SA	surface area
SVOCs	semivolatile organic compounds
TCDD	2,3,7,8-tetrachlorodibenzo-p-dioxin
TCDD-TEQ	2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
TEF	toxic equivalency factors
T_{event}	lag time per event
t_{event}	event duration
UCL	upper confidence limit
ug/kg	microgram per kilogram
ug/L	micrograms per liter

ug/m ³	microgram per cubic meter
(ug/m ³) ⁻¹	per microgram per cubic meter
UR	unit risk
USEPA	United States Environmental Protection Agency
VOCs	volatile organic compounds
yrs	years

1. Introduction

On behalf of Beazer East, Inc. (Beazer), ARCADIS has developed this human health risk assessment (HHRA) for the Former Koppers Wood-Treating Site (Site) in Carbondale, Illinois. The objective of the HHRA is to evaluate potential adverse human health effects attributable to potential exposures to Site-related constituents. To achieve this purpose, this HHRA is structured to estimate the potential health risk associated with potential exposures to the constituents at this Site, which are then compared to a risk limit that is defined as a matter of United States Environmental Protection Agency (USEPA) policy as being “acceptable”. If the estimated potential risk is less than the policy-based risk limit, the concentrations at a site are characterized as being below a level of concern for human health risk and there is no need to take further action to reduce either the media-specific concentrations or the potential for contact by people. If the estimated potential risk exceeds the acceptable theoretical risk limit, actions may be evaluated to reduce those potential risks, including limiting the potential for exposure and reducing the concentrations of constituents in the media of concern. The risk estimates provided in this HHRA are likely to overestimate actual risks, if any, to provide a conservative basis for future risk management decisions. The conclusions of the HHRA, along with the ecological risk assessment, will be used by risk managers to determine whether any further remedial actions need to be implemented at the Site and, as necessary, to potentially assist in the development of cleanup levels or establishment of additional institutional controls protective of human health.

This HHRA is prepared in accordance with the USEPA-approved work plan (ARCADIS 2014) and current USEPA human health risk assessment approaches defined under the CERCLA regulatory framework (USEPA 1988) including USEPA Risk Assessment Guidance for Superfund (RAGS) Volume I, Human Health Evaluation Manuals (Part A [1989], Part D [2001], Part E [2004], Part F [2009]), USEPA Supplemental Guidance for Developing Soil Screening Levels for Superfund Sites (USEPA 2002) ; and other recent USEPA risk assessment guidance. This HHRA supersedes a November 2014 version of the document, and incorporates revisions to address USEPA comments dated March 5, 2015 and October 6, 2015.

1.1 Site Description and Setting

The Site is located in the northeastern portion of the City of Carbondale in Jackson County, Illinois (Figure 1). Land use surrounding the Site is a mixture of residential, agricultural, and commercial/industrial. The southern edge of the Site is bordered by a former railroad property owned by Illinois Central Gulf Railroad. A residential portion of the City of Carbondale lies south of the railroad property adjacent to the western part of the Site; open and wooded areas are present to the south adjacent to the central and eastern parts of the Site. North Marion Street cuts through the western end of the Site. To the west of North Marion Street lies some wooded property, a former railroad property, and a

commercial/industrial area. The land to the north and east of the Site consists of cultivated, vacant, and wooded areas. A few residences are also located to the north of the property. The property itself (approximately 218 acres) consists of mainly grassy and wooded areas, with several gravel access roads. A garage, office building and waste- water treatment system are located in the west-central portion of the Site. Glade Creek flows to the northwest across the Site's southwestern corner, wraps around to the north of the Site, and then flows to the southeast across the eastern portion of the Site. Various surface water drainage ditches and wetlands areas are present on the Site. All of these features eventually drain to Glade Creek to the west, north, or east of the Site.

1.2 Summary of Operational History

Ayer & Lord Tie Company began producing pressure-treated railroad crossties, utility poles, and other wood products at the Site in approximately 1905. In 1940, Koppers Company purchased the facility. The facility changed ownership (largely through corporate mergers, acquisitions and reconfigurations) numerous times between 1988 and 1992, when the Site was conveyed to Beazer. Wood-treating operations at the Site ceased in 1991.

During the years of operation, a variety of chemicals were used at one time or another, including creosote, pentachlorophenol, fluoro-chrome-arsenate phenol, chromated zinc chloride, and non-combustible fire retardant. The treatment process generally involved pressurized impregnation of wood-treating compounds into the wood products, after which time the wood was staged in designated areas to "drip dry" and await shipment from the facility. Liquids generated by the process were subject to various methods of treatment and discharge over the operational history of the Site. Historical treatment methods included use of lagoons, impoundments, and spray fields. Beginning in the 1970s, more advanced treatment methods were employed, providing for on-Site treatment followed by discharge to the Carbondale Publicly Owned Treatment Works (POTW) for additional treatment under a discharge permit.

1.3 Prior Remedial Activities

Numerous remediation activities have occurred at the Site over the years, including actions that were taken while the facility was operating, as part of facility decommissioning, and following facility decommissioning. A summary of the completed remediation activities conducted while the facility was operating and during facility decommissioning is provided below.

- Between 1981 and 1983, soil containing creosote was excavated from the area between the former lagoon area, Glade Creek, and the north drainage ditch. The soil was stockpiled on top of plastic. In 2005, these waste piles were removed and placed into an on-Site containment cell (further discussed below).

- Between 1988 and 1991 the former surface impoundments (part of the facility's waste water treatment system during operation) were closed. A total of 5,794 tons of sludge and underlying soil was removed from the bottom of the impoundments, stabilized, and sent off-Site for disposal. Following sludge removal, an engineered cover was constructed over the impoundments.
- In 1990, a "grout blanket" was installed in a portion of Glade Creek in the eastern end of the Site as an Interim Remedial Measure. The purpose of the grout blanket was to inhibit the possible discharge of creosote into the creek from underlying soils. The grout blanket was decommissioned in 2004 as part of the Glade Creek channel relocation efforts (further discussed below).
- Between 1991 and 1992, the wood-treating facility was decommissioned. During this time, the majority of the former treatment process buildings and equipment were demolished and storage tanks were dismantled and removed from the Site. The remainder of the buildings and structures were demolished in 2005 prior to installing the former process area surface cover (further discussed below).

In 2004, USEPA issued a *RCRA Corrective Action Final Decision and Response to Comments* document that outlined additional corrective actions to be implemented at the Site. These corrective actions were conducted between 2004 and 2010, and included the following:

- In 2004, a Corrective Action Management Unit (CAMU) containment cell was constructed to provide for long-term consolidation and containment of remediation waste generated from various areas of the Site. A total of approximately 31,200 cubic yards of materials were placed in the containment cell. An engineered cover system was installed over the cell in 2010.
- Between 2004 and 2005, an approximately 1,500-foot section of Glade Creek in the eastern portion of the Site was relocated east of its previous location to circumvent a zone of subsurface DNAPL. Soils excavated to construct the new channel were used to backfill the old channel. In addition, a 35-foot deep barrier trench was constructed along the former channel alignment to collect subsurface DNAPL and minimize the potential for DNAPL to migrate toward and discharge to the relocated channel. Trench spoils were placed in the CAMU containment cell.
- In 2005, a DNAPL recovery system was installed in an existing recovery well located in the former process area.
- In 2005, various waste piles, soil/debris piles, and coal tar/asphalt materials were excavated and placed in the CAMU containment cell.

- Between 2005 and 2006, a 27.4-acre surface cover was installed over the former process area of the Site to mitigate direct contact with impacted surface soils. Portions of the cover also included a synthetic liner to minimize rainwater infiltration to groundwater.
- Between 2005 and 2006, visibly impacted sediments were excavated from Glade Creek (from the relocated section downstream to Piles Fork). Excavated sediments were placed in the CAMU containment cell.
- In 2008 a culvert was installed in an on-Site drainage ditch.
- In 2010, a 7.9-acre surface cover was installed in the former lagoon area, and soils were removed from various areas of the Site, including the North Drainage Ditch and portions of the railroad property south of the Site. Excavated soils were placed in the CAMU containment cell and the final cover was installed on the cell.

1.4 Document Organization

The remaining sections of this report describe the methodology and results of the HHRA. This HHRA was conducted in accordance with the USEPA-approved work plan (ARCADIS 2014) and follows the four-step process of hazard identification (Section 2), exposure assessment (Section 3), toxicity assessment (Section 4), and risk characterization (Section 5) as defined by the National Academy of Sciences (NAS 1983) and USEPA (2000). A qualitative uncertainty assessment is also included (Section 6) followed by a summary section (Section 7).

2. Hazard Identification

In the Hazard Identification step, analytical data are evaluated and constituents of potential concern (COPCs) are identified in each environmental medium for evaluation in the quantitative risk assessment.

Multiple remedial activities have occurred at the Site. As a result some of the historical soil and sediment data do not reflect current conditions at the Site. Consequently, to characterize current conditions at the Site, the data supporting the HHRA include soil, sediment, surface water, and fish data collected in 2005 or later.

Most of the data collected after 2005 and used in this HHRA were collected in accordance with the following USEPA-approved work plans (each specific work plan provides details regarding the rationale for specific sample locations and sampling methodologies):

- April 22, 2005 Revised Supplemental Soil Sampling Work Plan (BBL 2005)
- February 21, 2006 Sampling and Analysis Plan for Southern Drainage Ditches (BBL 2006), as revised to address USEPA comments dated March 2, 2006
- December 18, 2007 Baseline Characterization Work Plan (BCWP; ARCADIS 2007)
- January 4, 2008 Addendum to June 15, 2006 Southern Drainage Ditches Report/Work Plan (ARCADIS 2008)
- October 26, 2009 Work Plan for Additional Investigations (Beazer 2009)
- March 25, 2010 Additional Sampling Locations email (ARCADIS 2010)
- January 24, 2011 Work Plan for Additional PCDD/PCDF Sampling (ARCADIS 2011)
- November 19, 2012 Work Plan for Additional Soil Sampling and PCDD/PCDF Analysis (ARCADIS 2012)

Each of these work plans was reviewed and approved by USEPA before sample collection occurred. Each of these sampling efforts was also conducted in accordance with the Quality Assurance Project Plan (QAPP) (ARCADIS 2008c) to ensure proper collection and analysis procedures were followed.

Groundwater data were not evaluated in the screening because exposure to COPCs in groundwater is not anticipated under any of the on-Site or off-Site receptor scenarios. Under current conditions, on-Site groundwater is not used as a potable water supply. During routine maintenance activities, it is possible for maintenance personnel to contact groundwater while monitoring groundwater wells, but health and safety rules governing such monitoring require use of personal protective equipment that prevents dermal exposures to constituents in groundwater. Anticipated future solar development at the Site will also not result in exposure to constituents in groundwater because no groundwater

wells will need to be drilled as part of the solar development nor will excavation need to occur below the groundwater table. Further, the facility is served by a public water supply, and City ordinance precludes potable well installations in areas served by public water. Finally, future use of onsite groundwater is expected to be precluded by deed restrictions to be imposed for the property. Thus, under current and future conditions on-Site exposure to constituents in groundwater is not expected to occur.

Current and future off-Site exposure to constituents in groundwater is also not expected to occur. Such exposure is possible via two pathways: potable use of groundwater, and migration of constituents in shallow groundwater and direct contact with groundwater in basements of nearby homes. Exposure to constituents in groundwater through potable use is not occurring and is not expected to occur because a public water supply exists for all nearby homes and City ordinance precludes potable wells in areas served by public water. In addition, extensive groundwater monitoring data indicate that constituents in shallow groundwater are not currently migrating off-Site. Future offsite migration in shallow groundwater is also not anticipated, and this will continue to be evaluated through ongoing implementation of the Site's groundwater monitoring program. Thus, under current and future conditions, off-Site exposure to constituents in groundwater is not expected to occur.

All constituents that are detected in at least one sample collected at the Site were included in the COPC screening. The screening process and results are summarized below for each medium retained for evaluation.

2.1 On-Site Data

2.1.1 Soil

A total of 210 surface soil samples collected from the Site were evaluated, but not all samples were analyzed for all constituents. One hundred and sixty-three surface soil samples were analyzed for semi-volatile organic compounds (SVOCs) including polycyclic aromatic hydrocarbons (PAHs). One hundred and nine samples were sampled for pentachlorophenol. One hundred and forty-two samples were sampled for arsenic. Fifty-five samples were analyzed for chromium and copper. One hundred and three samples were analyzed for dioxins/furans. Surface soil samples were defined as any soil sample collected from the ground surface. The depth of the surface soils varied, however the majority of the surface soils were sampled to a depth of six inches. Table 1 summarizes constituents that were detected in at least one soil sample collected at the Site. Analytical results are presented in Appendix A.

2.1.2 Sediment

A total of 17 sediment samples were collected from the Site, including wetland areas, Smith Ditch, and the Large Pond. Fifteen sediment samples were analyzed for SVOCs including PAHs and pentachlorophenol, arsenic, chromium, and copper. Six sediment samples were analyzed for dioxins/furans. Table 2 summarizes constituents that were detected in at least one sediment sample collected at the Site. Analytical results are presented in Appendix A.

2.2 Off-Site Data

2.2.1 Railroad Property

Thirty-eight surface soil samples were collected from the railroad property to the south of the Site. Thirty-two samples were analyzed for SVOCs including PAHs. Twenty-seven samples were sampled for pentachlorophenol. Twenty-two samples were analyzed for arsenic. Twelve samples were sampled for chromium and copper. Twenty-four samples were analyzed for dioxins/furans. Table 3 summarizes constituents that were detected in at least one soil sample collected from the railroad property. Analytical results are presented in Appendix A.

2.2.2 35' Swath

Nine surface soil samples were collected from the 35-foot swath of Beazer-owned property to the south of the railroad property. Eight samples were analyzed for PAHs and pentachlorophenol. Five samples were analyzed for arsenic. Four samples were sampled for chromium and copper. Six samples were analyzed for dioxins/furans. Table 4 summarizes constituents that were detected in at least one soil sample collected from the 35-foot swath property. Analytical results are presented in Appendix A.

2.2.3 Soil North and West of the Site

Thirteen surface soil samples were collected from the agricultural area to the north and west of the Site. Eleven samples were analyzed for PAHs, pentachlorophenol, arsenic, chromium and copper. Thirteen samples were analyzed for dioxins/furans. Table 5 summarizes constituents that were detected in at least one soil sample collected from the area to the north and west of the Site. Analytical results are presented in Appendix A.

2.2.4 Sediment North and West of the Site

Fourteen sediment samples were collected from Glade Creek and Smith Ditch to the north and west of the Site. Fourteen samples were analyzed for PAHs, pentachlorophenol, arsenic, chromium and copper. Nine samples were analyzed for dioxins/furans. Table 6 summarizes constituents that were detected in at least one sediment sample collected from

Glade Creek and Smith Ditch to the north and west of the Site. Analytical results are presented in Appendix A.

2.2.5 Soil East of the Site

Eight surface soil samples were collected from the floodplain to the east of the Site. Eight samples were analyzed for PAHs, pentachlorophenol, arsenic, chromium and copper. Four samples were analyzed for dioxins/furans. Table 7 summarizes constituents that were detected in at least one soil sample collected from the floodplain to the east of the Site. Analytical results are presented in Appendix A.

2.2.6 Crab Orchard Creek and Piles Fork Sediment

Sediment samples were collected from Crab Orchard Creek and Piles Fork, where recreational activities may occur. Twenty-two sediment samples were collected but not all samples were analyzed for all constituents. Four samples were analyzed for SVOCs, including pentachlorophenol. An additional fifteen samples were analyzed for just PAHs and pentachlorophenol. Nineteen sediment samples were analyzed for arsenic, chromium, and copper. Sixteen sediment samples were analyzed for dioxins/furans. Table 8 summarizes constituents that were detected in at least one sediment sample collected from the Crab Orchard Creek and Piles Fork. Analytical results are presented in Appendix A.

2.2.7 Crab Orchard Creek and Piles Fork Surface Water

Surface water samples were not collected from Crab Orchard Creek or Piles Fork, where recreational activities may occur. Therefore, surface water samples collected from Glade Creek closer to the Site, were used to conservatively estimate potential exposures to constituents in surface water in Crab Orchard Creek and Piles Fork. Four surface water samples were collected from Glade Creek and analyzed for PAHs, pentachlorophenol, arsenic, chromium, and copper. Table 9 summarizes constituents that were detected in at least one surface water sample and used to conservatively represent potential concentrations in Crab Orchard Creek and Piles Fork. Analytical results are presented in Appendix A.

2.2.8 Catfish

Edible-sized catfish were collected from three Crab Orchard Creek locations. Fillet samples were analyzed for PAHs, pentachlorophenol, arsenic, chromium, copper, and dioxins/furans. Table 10 summarizes constituents that were detected in at least one catfish sample. Analytical results are presented in Appendix A.

2.3 Screening of Compounds of Potential Concern

Maximum detected soil and sediment concentrations were conservatively screened against the regional screening levels (RSLs) (USEPA 2014a) or against USEPA's dioxin PRGs (<http://www.epa.gov/superfund/health/contaminants/dioxin/dioxinsoil.html>) for 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents (TCDD-TEQ). For potential on-Site soil exposures commercial/industrial RSLs/PRGs were used (Table 1). For potential on-Site sediment exposures commercial/industrial RSLs/PRGs were adjusted for an exposure frequency of 16 days per year, which is a conservative estimate of potential exposure to sediments that recognizes the small size and limited extent of ditches on-Site and that most of the ditches are in areas of the Site that are difficult to access. The 16 days per year assumes a commercial/industrial worker may contact on-Site sediments twice per month during the warmer months of the year (March through October) (Table 2).

For all off-Site soils, residential RSLs/PRGs were used for screening (Tables 3, 4, 5, and 7). Off-Site sediments along Smith Ditch and Glade Creek to the west and north of the Site were screened separately from off-Site sediments along Piles Fork and Crab Orchard Creek to the east of the Site because land use differs and associated receptors differ. The HHRA assumes Piles Fork and Crab Orchard Creek can support fishing and kayaking. To the west and north the creeks are too small to support such recreational activity but do pass near residential properties and, thus, direct contact exposures are possible. For off-Site sediments, residential RSLs/PRGs were modified to reflect a 16 day per year exposure frequency and used for COPC screening (Tables 6 and 8). This exposure frequency assumes exposure to sediment twice a month during the warmer months of the year (March through October, i.e., the times of year when recreational activities are likely to be greatest).

If maximum concentrations of a constituent are below the RSLs/PRGs, that constituent was not included as a COPC and was not retained in the HHRA. Screening COPCs against RSLs/PRGs results in the exclusion of some compounds that were detected relatively often (i.e., greater than 5% frequency of detection). However, the screening levels are developed to intentionally be conservative. Further, screening the maximum concentration against such conservative screening levels means that while these compounds may have been detected relatively frequently all the detected concentrations were below the conservative screening level and, therefore, are not expected to pose an unacceptable risk and will not change the results of the overall evaluation of potential risk presented in this risk assessment

For surface water and fish concentrations, which do not have RSLs, all detected constituents were retained as COPCs in the HHRA.

In accordance with USEPA guidance (1993), potentially carcinogenic polycyclic aromatic hydrocarbons (PAHs) are assumed to have analogous modes of action to benzo(a)pyrene (BaP). BaP, benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene,

dibenz(a,h)anthracene, and indeno(1,2,3-cd)pyrene, are considered by USEPA to be potentially carcinogenic PAHs. However, USEPA has developed carcinogenic toxicity factors only for benzo(a)pyrene, generally assumed to be one of the most potent carcinogenic members of the PAH class of constituents. Therefore, the toxic equivalence of BaP is a quantitative indicator of the comparative carcinogenic potency of a PAH constituent compared to the potency of BaP. Toxic equivalency factors (TEFs) have been developed to relate the carcinogenic potency of all other potentially carcinogenic PAHs to the potency of BaP. These TEFs were applied to concentrations of individual carcinogenic PAHs in each sample and the total BaP-TE was calculated for each sample. If one of the potentially carcinogenic PAHs was not detected in any particular sample, half of the detection limit for that potentially carcinogenic PAH was used in the calculation of BaP-TE for that sample. Table 11 presents the BaP TEFs used in the BaP-TE calculations.

Similar to potentially carcinogenic PAHs, dioxin and furan congeners are conservatively assumed to have analogous modes of action in their carcinogenic toxicity (van den Berg et al., 2006). TEFs have been developed to relate the carcinogenic potency of certain other congeners to the potency of 2,3,7,8-TCDD (van den Berg et al., 2006). Again, these TEFs were applied to concentrations of individual dioxin and furan congeners in each sample and the total TCDD-TEQ was calculated for each sample. If one of the congeners was not detected in any particular sample, half of the detection limit for that congener was used in the calculation of TCDD-TEQ for that sample. For the 17 congeners with TEFs, Table 12 presents the TCDD TEFs used in the TCDD-TEQ calculations.

Tables 1 through 10 present the COPC screening results for on-Site soil, on-Site sediment, off-Site soil, off-Site sediment, surface water, and fish, respectively. In doing so, they identify the media-specific COPCs evaluated in the remainder of this HHRA.

3. Exposure Assessment

The risk assessment process requires the identification of exposure scenarios to assess the potential for current and potential future adverse health effects from COPCs at or near the Site. While these scenarios represent hypothetical people and activities, they reflect the physical description of the Site and the surrounding areas, as well as the activities that may potentially occur in these areas.

For exposure and potential risks to occur, a complete exposure pathway must exist. A complete pathway requires the following elements (USEPA, 1989):

- a source and mechanism for release of constituents;
- a transport or retention medium;
- a point of potential human contact (exposure point) with the affected medium; and
- an exposure route (i.e., ingestion, dermal contact, or inhalation) at the exposure point.

If any one of these elements is missing, the pathway is not considered complete. For example, if human activity patterns and/or the location of potentially exposed individuals relative to the location of an affected exposure medium prevent human contact, then that exposure pathway is not complete.

The exposure assessment is presented in the following four subsections and is consistent with the USEPA-approved work plan (ARCADIS 2014). Section 3.1 presents the current and future Site conditions for the purpose of identifying potential receptor groups. Section 3.2 contains a pathways analysis and identifies all complete and potentially complete exposure scenarios selected for evaluation in the HHRA. Section 3.3 provides the algorithms, receptor-specific exposure assumptions and parameters used to estimate potential exposure (daily intakes) to the COPCs. Section 3.4 describes the methods used to estimate media-specific exposure point concentrations (EPCs) for the identified COPCs and used to estimate potential daily exposures.

3.1 Current and Future Site Conditions

The Site is not currently used for commercial purposes, and activities are primarily limited to operation and maintenance of the previously completed remedy components, such as mowing, maintenance of the CAMU containment cell, recovery of DNAPL at collection points, and periodic groundwater monitoring. Portions along the southern and western property boundaries are fenced to deter access to the Site.

Anticipated future plans include development of a solar energy farm on a portion of the Site (shown as the proposed non-gravel and gravel solar use areas on Figure 1). Future development may also include construction of a bike path along or near the southern boundary of the Site to connect separate bike paths being planned by the City of Carbondale and to potentially provide access to the Green Earth, Inc. Pyles Fork Preserve to the south of the Site. Alternatively, pending further coordination with the City of Carbondale and the Illinois Central Gulf Railroad, the bike path may be constructed on the railroad property that abuts the southern property boundary of the Site.

Additionally, it is currently anticipated that the City of Carbondale will hold a conservation easement for the majority of the Site not planned for solar development. Thus, future exposure is assumed to be associated with recreational use for portions of the Site on which a bike path may be constructed and potential trespassers on portions of the Site outside the solar development area.

3.2 Exposure Areas

For the purposes of the HHRA, the Site is divided into multiple “Exposure Areas” (Figure 1). These exposure areas were developed during prior investigations and evaluations for the Site, and generally divide the Site into areas of current/future use. The various on-Site and off-Site exposure areas and bases for them are summarized below.

Eastern Conservation Exposure Area – Represents the eastern portion of the Site, including floodplain areas, that is primarily undeveloped, wooded, and/or overgrown, and where conservation land use is anticipated.

Southern Conservation Exposure Area – Represents the semi-wooded portion of the Site between the proposed solar area and the residential area located to the south of the Site. This is also potentially representative of where a bike path may be constructed as part of the redevelopment activities.

Proposed Solar Use Area – Represents the portion of the Site where solar panels are currently envisioned in support of a 20 MW solar array. This is the area where solar-related construction and operational activities would occur, and that would be fenced to preclude access.

Central Conservation Exposure Area – Represents the central portion of the Site where conservation land use is anticipated outside the portion of the Site where solar use is proposed.

Western Conservation Exposure Area – Represents the portion of the Site property located west of North Marion Street; which was not part of historical wood-treating operations and where future conservation land use is anticipated.

Off-Site areas were defined where potential risks will be evaluated for one or more receptor scenarios and are summarized below.

North and West of the Site – Includes the areas of Glade Creek and Smith Ditch, and floodplain soils in the immediate vicinity of the creeks that are located to the north and west of the Site. This area extends upstream to the point where Glade Creek crosses the railroad tracks immediately west of the Site and downstream to the point where Glade Creek reaches the Site property.

East of the Site – Represents the small portion of Glade Creek and its floodplain that lays beyond the property boundary to the east of the Site, as well as the downstream portions of Piles Fork and Crab Orchard Creek.

Railroad Property – Represents the area immediately to the south of the Site that includes the former railroad bed (Figure 1).

35' Swath – Includes a thirty-five foot swath of land, owned by Beazer East, Inc., to the south of the railroad property (Figure 1).

3.3 Potential Exposure Pathways and Receptor Populations

Potential exposure pathways are the ways by which potential receptors may be exposed to COPCs. This subsection identifies the complete or potentially complete exposure pathways for each of the identified current and future receptors at this Site, consistent with the USEPA-approved work plan (ARCADIS 2014). Table 13 summarizes the exposure scenarios (receptors and pathways) considered for evaluation in this HHRA.

As presented above (Section 1.2.1), historical wood-treatment methods were associated with releases of wood-treating-related constituents. As discussed in Section 1.3, multiple remedial actions have occurred at the Site to remove and reduce the concentration of constituents both on the Site as well as those that may be transported off the Site via surface water runoff. Residual constituent concentrations have been detected in soil on the Site.

In a letter dated March 14, 2014, USEPA (USEPA 2014b; Appendix B hereto) concludes that exposure pathways for the neighborhood to the south of the Site are incomplete. USEPA cited multiple lines of evidence in supporting this conclusion as quoted below:

The following surface soil sampling events in the neighborhood supported [US]EPA's analysis:

- 1) a soil sampling event that USEPA and IEPA completed in 2005*
- 2) a soil sampling event that the City of Carbondale completed in 2006, and*

- 3) *soil sampling events completed by Beazer East, Inc. in 2012.*

[US]EPA also considered these other available lines of evidence:

- 1) *the concentrations and distribution of analytes in the soil did not indicate airborne migration under current conditions;*
- 2) *physical barriers present in the land surface between the Site and the neighborhood would likely prevent overland flow of chemical migration from the Koppers Site to the neighborhood during precipitation events (berm and drainage ditches);*
- 3) *the contaminant concentrations north of the property line (on the Koppers side) were orders of magnitude higher than concentrations found in the neighborhood to the south (supporting the conclusion that physical barriers prevent overland flow/surface migration to the south);*
- 4) *the detected chemical concentrations in the neighborhood were generally in the range of urban area background concentrations; and*
- 5) *the containment remedies and their maintenance within the facility prevent chemicals being released off-site in the future.*

Therefore, the HHRA does not evaluate potential exposure in the neighborhood to the south of the Site. Copies of available work plans (summarizing the sampling scope and rationale) and data reports (summarizing sampling results) for the 2005 USEPA/IEPA, 2006 City of Carbondale, and 2012 Beazer sampling events are included in Appendix B.

On-Site receptors considered to have potentially complete pathways include:

- a current/future on-site adult maintenance worker/caretaker;
- a current/future on-Site adult deer hunter and adolescent and child deer consumer;
- a current/future on-Site adolescent trespasser;
- a future on-Site adult and adolescent hikers/bicycle users;
- a future on-Site solar farm redevelopment worker; and,
- a future on-Site solar farm maintenance worker.

Off-Site receptors considered to have potentially complete pathways include:

- a current/future off-Site adult and adolescent kayaker/canoer;
- a current/future off-Site adult and adolescent recreational angler and child fish consumer;
- a current/future adolescent trespasser; and,

- hypothetical future adult and adolescent hikers/bicycle users in railroad property.

The current/future on-Site adult maintenance worker/caretaker represents the current Site worker who maintains the Site and performs routine sampling at the Site. This worker is assumed to be exposed to the entire on-Site portion of the Site (Eastern Conservation Exposure Area, Southern Conservation Exposure Area, Proposed Solar Use Exposure Area, Central Conservation Exposure Area, and Western Conservation Exposure Area shown on Figure 1). This individual is assumed to be exposed to surface soil on-Site. The exposure point concentration was estimated to be the spatially-weighted 95th upper confidence limit on the mean of all surface soil data on-Site, as discussed in Section 3.4.5.

The potentially complete pathways to be considered in the HHRA, as well as others determined in coordination with USEPA to be either incomplete or insignificant, are demonstrated in the conceptual site model (Figure 2) and presented in Table 13. The conceptual site model identifies each of the exposure pathways, including the potential primary sources, potentially impacted media (including release and transport mechanisms), potential human receptors that could come into contact with those media, and complete exposure routes for each of those receptor groups.

3.4 Exposure Estimates

The HHRA assumes potential receptors may be exposed to constituents in soil, air sediments and other environmental media while working or recreating on or near the Site. To estimate potential risk to constituents, the potential dose for non-cancer effects is estimated by averaging the dose over the amount of time each receptor may be exposed to constituents at the Site and is referred to as the average daily dose (ADD). The potential dose for potential cancer health effects is estimated by averaging the dose over the life of the receptor and is referred to as the lifetime average daily dose (LADD). The ADD and LADD are combined with toxicity benchmarks to estimate the potential for adverse health effects to occur. To develop the potential dose estimate, conservative assumptions are made about how often and to what extent each receptor is potentially exposed to constituents. Section 4 further discusses the differences between non-cancer and cancer health effects.

The ADD is an estimate of a receptor's potential daily intake from oral and dermal exposure to COPCs with potential non-carcinogenic effects. According to USEPA (1989), the exposure dose should be calculated by averaging over the period of time for which the receptor is assumed to be exposed. For potential exposures that occur over a period that is greater than 10% of a lifetime (or more than 7 years in duration), a chronic ADD is estimated. For potential exposures that are less than 10% of a lifetime (or less than 7 years in duration), a subchronic ADD is estimated. The future on-Site solar farm redevelopment worker scenario, current/future on-Site child deer consumer scenario, and current/future off-Site child recreational angler scenario are assumed to be subchronic exposures, while the

estimated exposures for all other receptor groups are considered chronic. The chronic and subchronic ADD for each COPC via each route of exposure is compared to the chronic or subchronic toxicity value (e.g. the reference dose [RfD]; see Section 4.1) for that COPC to estimate the potential hazard index associated with exposure to that COPC via that route of exposure. Hazard indices are presented and discussed in Section 5.1.

For COPCs associated with potentially carcinogenic effects in humans, the LADD is an estimate of potential daily intake over the course of a lifetime. In accordance with USEPA (1989), the LADD is calculated by averaging the assumed exposure over the receptor's entire lifetime (assumed to be 70 years). The LADD for each COPC via each route of exposure is combined with the cancer slope factor (CSF; see Section 4.2) for that COPC in order to estimate the excess lifetime cancer risk due to exposure to that COPC via that route of exposure. Excess lifetime cancer risks are presented and discussed in Section 5.2.

Consistent with USEPA guidance (USEPA, 2009), inhalation exposures were evaluated in a different manner. Instead of estimating doses, an average daily exposure (ADE) concentration (can be either chronic or subchronic) and a lifetime average daily exposure (LADE) concentration were estimated for non-carcinogens and carcinogens, respectively.

3.4.1 Soil and Sediment

The HHRA assumes potential exposure to soil occurs via incidental ingestion, dermal contact, and inhalation of dust. Because of its high moisture content sediment is not likely to be entrained in the air as dust. Additionally, because sediment is typically removed from hands by movement through the surface water, incidental ingestion of sediment becomes insignificant and the ingestion pathway was considered negligible. Thus, only the potential dermal contact pathway was evaluated for sediment. ADDs and LADDs for soil ingestion were calculated as follows:

$$(L)ADD = \frac{CS \times IR \times ABS_o \times FI \times EF \times ED \times CF}{AT \times BW}$$

where:

- (L)ADD = (Lifetime) Average Daily Dose Due to Ingestion (mg/kg-day);
- CS = Constituent Concentration in Soil (mg/kg);
- IR = Ingestion Rate of Soil or Sediment (mg/day);
- ABS_o = Oral Absorption Factor (unitless);
- FI = Fraction Ingested (unitless);
- EF = Exposure Frequency (days/year);
- ED = Exposure Duration (years);

- CF = Conversion Factor (10^{-6} kg/mg);
 AT = Averaging time (days); and
 BW = Body weight (kg).

ADDs and LADDs for dermal absorption of soil and sediment were calculated as follows:

$$(L)ADD = \frac{CS \times CF \times AF \times ABS_d \times EF \times ED \times SA}{AT \times BW}$$

where:

- (L)ADD = (Lifetime) Average Daily Dose Due to Dermal Contact (mg/kg-day);
 CS = Constituent Concentration in Soil and Sediment (mg/kg);
 CF = Conversion Factor (10^{-6} kg/mg);
 AF = Soil-to-Skin Adherence Factor (mg/cm²);
 ABS_d = Dermal Absorption Factor (unitless);
 EF = Exposure Frequency (days/year);
 ED = Exposure Duration (years);
 SA = Skin Surface Area Available for Contact (cm²/day);
 BW = Body weight (kg); and
 AT = Averaging time (days).

ADEs and LADEs for the inhalation of dust from soil were calculated as follows:

$$(L)ADE = \frac{CS \times (1|PEF) \times CF \times ET \times EF \times ED}{AT}$$

where:

- (L)ADE = (Lifetime) Average Daily Exposure due to Dust Inhalation (ug/m³);
 CS = Constituent Concentration in Soil (mg/kg);
 PEF = Particulate Emissions Factor (m³/kg);
 CF = Conversion factor (10^3 ug/mg);
 ET = Exposure time (hours/day);
 EF = Exposure frequency (days/year);
 ED = Exposure duration (years); and
 AT = Averaging time (hours).

3.4.2 Surface Water

The HHRA assumes potential exposure to surface water occurs via incidental ingestion and dermal contact. ADDs and LADDs for surface water ingestion were calculated as follows:

$$(L)ADD = \frac{C_{sw} \times IR \times CF \times ET \times EF \times ED}{AT \times BW}$$

where:

- (L)ADD = (Lifetime) Average Daily Dose Due to Ingestion (mg/kg-day);
- C_{sw} = Constituent Concentration in Surface Water (ug/L);
- IR = Ingestion Rate of Surface Water (L/hour);
- CF = Conversion Factor (10⁻³ mg/ug);
- ET = Exposure Time (hours/day);
- EF = Exposure Frequency (days/year);
- ED = Exposure Duration (years);
- BW = Body Weight (kg); and
- AT = Averaging Time (days).

ADDs and LADDs for dermal absorption of surface water were calculated as follows:

$$(L)ADD = \frac{DA_{event} \times EV \times EF \times ED \times SA}{AT \times BW}$$

where:

- (L)ADD = (Lifetime) Average Daily Dose Due to Dermal Contact (mg/kg-day);
- DA_{event} = Absorbed Dose (mg/cm²-event);
- EV = Event Frequency (events/day);
- EF = Exposure Frequency (days/year);
- ED = Exposure Duration (years);
- SA = Skin Surface Area Available for Contact (cm²);
- BW = Body weight (kg); and
- AT = Averaging time (days).

DA_{event} water will be calculated as follows:

If t_{event} ≤ t*, then:

$$DA_{\text{event}} = 2FA \times K_p \times C_{\text{sw}} \times CF \times \sqrt{\frac{6\tau \times t_{\text{event}}}{\pi}}$$

If $t_{\text{event}} > t^*$, then:

$$DA_{\text{event}} = FA \times K_p \times C_{\text{sw}} \times CF \times \left[\frac{t_{\text{event}}}{1+B} + 2T_{\text{event}} \left(\frac{1+3B+3B^2}{(1+B)^2} \right) \right]$$

where:

- DA_{event} = Absorbed Dose (mg/cm²-event);
- FA = Fraction Absorbed of Water (unitless);
- K_p = Dermal Permeability Coefficient of Compound in Water (cm/hour);
- C_{sw} = Constituent Concentration in Surface Water (ug/L);
- CF = Conversion Factor (10³ cm³/L x 10⁻³ mg/ug);
- T_{event} = Lag Time per Event (hours/event);
- t_{event} = Event Duration (hours/event);
- t^* = Time to Reach Steady-State (hours) = 2.4 T_{event} ; and
- B = Dimensionless Ratio of the Permeability Coefficient of a Constituent through the Stratum Corneum Relative to its Permeability Coefficient across the Epidermis (unitless).

3.4.3 Fish and Deer

The HHRA assumes potential exposure to fish and deer tissue occurs via consumption of tissue. ADDs and LADDs for fish and deer ingestion were calculated as follows:

$$(L)ADD = \frac{C \times IR \times EF \times ED \times CF}{AT \times BW}$$

where:

- (L)ADD = (Lifetime) Average Daily Dose Due to Ingestion (mg/kg-day);
- C = Constituent Concentration in Fish or Deer (mg/kg dry weight);
- IR = Consumption Rate of Fish or Deer (mg/day wet weight);
- EF = Exposure Frequency (days/year);
- ED = Exposure Duration (years);
- CF = Conversion Factor (10⁻⁶ kg/mg);

AT = Averaging Time (days); and

BW = Body Weight (kg).

3.4.3.1 Deer Meat EPCs

Concentrations of COPCs in deer meat were estimated using uptake equations found in USEPA's Human Health Risk Assessment Protocol for Hazardous Waste Combustion Facilities (USEPA 2005). Equations used to model uptake from soil to beef were used to model deer meat concentrations. COPCs in soil were assumed to be consumed by the deer both through the plants that make up their diet and through direct ingestion of soil that may be on the plants they ingest.

COPC concentrations in the plants in a deer's diet were calculated using the following equation:

$$C_{\text{plant}} = C_{\text{soil}} \times Br$$

where:

C_{plant} = Constituent Concentration in Plants Due to Root Uptake (mg/kg dry weight);

C_{soil} = Constituent Concentration in Soil (mg/kg); and

Br = Plant-Soil Bioconcentration Factor (unitless).

COPC concentrations in deer meat were calculated using the following equation:

$$C_{\text{deer}} = \left((F \times Q_{\text{plant}} \times C_{\text{plant}}) + Q_{\text{soil}} \times C_{\text{soil}} \times B_{\text{soil}} \right) \times Ba_{\text{deer}}$$

where:

C_{deer} = Constituent Concentration in Deer Meat (mg/kg dry weight);

F = Fraction of Plants Grown on Site Soil and Ingested by the Deer (unitless);

Q_{plant} = Quantity of Plants Ingested by the Deer per Day (kg dry weight/day);

C_{plant} = Constituent Concentration in Plants (mg/kg dry weight);

Q_{soil} = Quantity of Soil Ingested by the Deer per Day (kg/day);

C_{soil} = Constituent Concentration in Soil (mg/kg);

B_{soil} = Soil Bioavailability Factor (unitless); and

B_{deer} = Biotransfer Factor for Deer (beef used as a surrogate) (day/kg fresh weight).

The HHRA assumes deer have a food ingestion rate of 1.74 kg wet weight per day (Sample, 1994) and a soil ingestion rate of 2% of the food ingestion (Sample, 1994). Table 27 presents EPCs for deer meat.

A discussion of the exposure parameters used to estimate potential exposure for the identified receptors is presented in the following sections.

3.4.4 Potential Human Receptors and Exposure Assumptions

Exposure assumptions for on-Site and off-Site receptors considered to have potentially complete pathways are presented in Table 14. These assumptions are consistent with estimating a reasonable maximum exposure (RME) that is representative of a high-end exposures. RME assumptions are not always the maximum exposure possible; rather, they represent a combination of assumptions some of which may be representative of the central tendency for a particular exposure parameter (e.g., bodyweight, exposure frequency) and others that represent the upper end of the likely range of values for an exposure parameter (e.g., soil ingestion rate, exposure duration). Some of the assumptions may be taken from USEPA guidance (e.g., bodyweight, exposure duration, soil ingestion rate) and others may be based on site-specific information (e.g., exposure frequency). When combined, they represent and a high-end (or RME) exposure even when some Site-specific assumptions are employed.

3.4.4.1 *Current/Future On-Site Adult Maintenance Worker/Caretaker*

The HHRA assumes on-Site adult maintenance workers/caretakers are potentially exposed to surface soils via incidental ingestion, dermal contact and inhalation of dust while mowing the CAMU area and performing other activities related to maintaining the Site. Maintenance workers/caretakers are assumed to be exposed to surface soils at the Site 2½ days/week for 50 weeks/year. Such contact is assumed to occur for 25 years (USEPA 2002).

Because mowing may result in generation of dust from soil, an upper-bound soil ingestion rate of 100 mg/day is assumed, representing twice the typical daily soil ingestion rate (50 mg/day) for adults recommended by USEPA (1997). To be conservative, the HHRA assumes that 100 percent of the soil ingested by the worker for the day is from the Site.

Given the nature of the work, it is most likely that long sleeves and long pants are worn to protect the arms and legs. The HHRA assumes that the head, hands, and forearms have contact with soil. The HHRA also assumes that maintenance workers/caretakers are present on-Site 8 hours/day on each day of exposure.

The exposure assumptions used to evaluate the current/future on-Site adult maintenance worker/caretaker are presented in Table 14.

3.4.4.2 Current/Future On-site Adult Deer Hunter and Adolescent and Child Deer Consumer

A hypothetical scenario was also included under which a family harvests and consumes deer that have foraged at the Site and have potentially been exposed to constituents while foraging. Ingestion rates for wild caught meat are not available from the USEPA's Exposure Factors Handbook (USEPA 2011). Therefore, deer ingestion rates were derived using the methodology described below.

First, the number of deer potentially harvested from the Site was estimated based on data presented in the Summary of 2012-2013 Illinois Deer Seasons (IDNR 2013). Dividing the number of deer harvested in Jackson County, which includes Carbondale, by the number of acres of Jackson County produces a rate of 0.0082 deer harvested per acre. This correlates to an estimated potential average harvest of 1.5 deer per year from the 187-acre Site.

Second, using a mean deer weight of 56.5 kilograms from Sample (1994) and a meat yield from a buck of 40% (http://www.butcher-packer.com/index.php?main_page=document_general_info&products_id=331), the Site could potentially yield 34.8 kg of edible meat per year or 95.5 grams per day.

Third, the hypothetical total of 95.5 grams per day was conservatively distributed among a single family of four people representing three different age groups; two adults, one adolescent, and one child, by assuming the same distribution of ingestion rates for the each age group (adult, adolescent, and child) as is presented for total meat ingestion in the 2011 Exposure Factors Handbook (USEPA 2011). The resulting deer ingestion rates are 28.1, 25.0 and 14.2 grams per day, for adults, adolescents and children, respectively.

The exposure assumptions used to evaluate the /future on-Site adult deer hunter and adolescent and child deer consumer are presented in Table 14.

3.4.4.3 Current/Future On-site or Off-Site Adolescent Trespasser

The HHRA assumes that an adolescent (age 6 through 16) could go around or over the fence and potentially be exposed to Site surface soils via incidental ingestion, dermal contact and inhalation of dust. Additionally, the HHRA assumes that an adolescent trespasser may also potentially be exposed to off-Site surface soils via incidental ingestion, dermal contact and inhalation of dust and may potentially be exposed to sediment via dermal contact to the north and west of the Site. The trespasser is assumed to be exposed to surface soils at the Site one day per week for the four warm months of the year. The HHRA assumes the contact occurs for 10 years.

The trespasser is assumed to ingest soil at a rate of 100 mg/day (1997). The HHRA assumes that a trespasser's lower legs, feet, forearms and hands are exposed and potentially have contact with soil. The HHRA assumes that a trespasser contacts on-Site or off-Site soil for two 2 hours per day on each day of exposure.

The exposure assumptions used to evaluate the current/future on-Site or off-Site adolescent trespasser are presented in Table 14.

3.4.4.4 Future On-site or Off-Site Adult and Adolescent Hikers/Bicycle Trail Users

The HHRA assumes that adult and adolescent hikers/bicycle trail users are potentially exposed to surface soils via incidental ingestion, dermal contact and inhalation of dust while walking on or riding on the future bike trail. That trail could be on the Site or possibly on the railroad property to the south of the Site. The hiker/bicycle trail user is assumed to potentially be exposed to surface soils once per week for 52 weeks per year. The HHRA assumes adults will use the bicycle trail for 20 years and that adolescents will use the trail for 10 years.

The HHRA assumes the soil ingestion rate is 100 mg/day for the adult and 200 mg/day for the adolescent. The HHRA conservatively assumes that 10 percent of the soil potentially ingested by the hiker/bicycle trail user for the day is from the Site.

The HHRA assumes adults potentially have their head, hands, forearms and lower legs exposed and that adolescents potentially have their lower legs, forearms, and hands exposed. The HHRA assumes that hiker/bicycle trail users are present on the trail for one hour on each of the 52 days per year of assumed exposure.

The exposure assumptions used to evaluate the future on-Site or off-Site adult and adolescent hikers/bicycle trail users are presented in Table 14.

3.4.4.5 Future On-site Solar Farm Redevelopment Worker

The HHRA assumes that on-Site solar farm redevelopment workers are potentially exposed to surface soils via incidental ingestion, dermal contact and inhalation of dust while installing the solar farm at the Site. The solar farm redevelopment worker is assumed to potentially be exposed to surface soils at the Site five days per week for two months per year. The HHRA assumes this contact occurs for 1 year.

Because installation of solar panels may cause redevelopment workers to come into close contact with soil, an upper-bound soil ingestion rate of 330 mg/day is assumed (USEPA 2002). To be conservative, the HHRA assumes that 100 percent of the soil ingested by the solar farm redevelopment worker for the day is from the Site.

Given the nature of the work, it is most likely that long sleeves and long pants are worn to protect the arms and legs. Thus, the HHRA assumes that the head, hands, and forearms have contact with soil. The HHRA also assumes that solar farm redevelopment workers are present on-Site 8 hours/day on each day of exposure.

The exposure assumptions used to evaluate the solar farm redevelopment worker are presented in Table 14.

3.4.4.6 Future On-site Solar Farm Maintenance Worker

The HHRA assumes that on-Site solar farm maintenance workers are exposed to surface soils via incidental ingestion, dermal contact and inhalation of dust while performing maintenance activities at the solar farm on the Site. Based on communications with Brightfields (the proposed solar developer) the worker is assumed to be exposed to surface soils at the Site 1 ½ days/week for 50 weeks/year, as representative of the high-end of the likely amount of time a maintenance worker regularly spends at a solar facility. This contact will be assumed to occur for 25 years (USEPA 2002).

Because mowing may result in the generation of dust from soil, an upper-bound soil ingestion rate of 100 mg/day is assumed, representing twice the typical daily soil ingestion rate (50 mg/day) for adults recommended by USEPA (1997). To be conservative, the HHRA assumes that 100 percent of the soil ingested by the solar farm maintenance worker for the day is from the Site.

Given the nature of the work, it is most likely that long sleeves and long pants are worn to protect the arms and legs. Thus, the HHRA assumes that the head, hands, and forearms have contact with soil. The HHRA also assumes that solar farm maintenance workers are present on-Site 8 hours/day on each day of exposure.

The exposure assumptions used to evaluate the on-Site solar farm maintenance workers are presented in Table 14.

3.4.4.7 Current/Future Off-site Adult and Adolescent Kayaker/Canoeist

The HHRA assumes that off-Site adult and adolescent kayakers/canoeists are exposed to sediments and surface water via dermal contact while kayaking/canoeing on Crab Orchard Creek or Piles Fork. Although the banks of Crab Orchard Creek and Piles Fork are extremely steep in the vicinity of the Site and the water level is often not deep enough for a kayak or canoe, the recreator is conservatively assumed to be exposed to sediments and surface water once/year. This contact will be assumed to occur for 30 years for the adult and 10 years for the adolescent.

The adult is assumed to have their head, hands, forearms and lower legs exposed to the surface water. However, sediment exposure is only likely to occur to hands and feet. Similarly, the adolescent is assumed to have their head, hands, forearms, lower legs, and feet exposed to the surface water. Again, sediment exposure is only likely to occur to hands and feet. The HHRA assumes that the recreator is present 0.5 hours/day on each day of exposure.

The exposure assumptions used to evaluate the off-Site adult and adolescent kayaker/canoist are presented in Table 14.

3.4.4.8 Current/Future Off-site Adult and Adolescent Recreational Angler and Child Fish Consumer

Although it was difficult to catch enough fish for environmental sampling, the HHRA conservatively assumes that the current/future off-Site adult and adolescent recreational angler are exposed to sediment and surface soils dermal contact and fish tissue via ingestion. The HHRA assumes that the current/future off-Site child fish consumer (ages 1-6) is potentially exposed to COPCs via consumption of fish but not via contact with surface water and sediments given the nature of Crab Orchard Creek or Piles Fork near the Site. The adult and adolescent anglers are assumed to be exposed to sediments and surface water once/year. The HHRA assumes potential exposure to surface water, sediments and fish occurs for 30 years for the adult and 10 years for the adolescent. Children between the ages of 1 and 6 are assumed to consume fish for 5 years.

The adult is assumed to have their head, hands, forearms and lower legs exposed to the surface water. However, sediment exposure is only likely to occur to hands and feet. Similarly, the adolescent is assumed to have their head, hands, forearms, lower legs, and feet exposed to the surface water. Again, sediment exposure is only likely to occur to hands and feet. The HHRA assumes the recreator is present 0.5 hours/day on each day of exposure.

The fish is assumed to be conservatively distributed among a single family of four people representing three different age groups; two adults, one adolescent, and one child, by assuming the same distribution of ingestion rates for the each age group (adult, adolescent, and child) of 8.1 g/day.

The exposure assumptions used to evaluate the off-Site adult and adolescent recreational angler and child fish consumer are presented in Table 14.

3.4.5 Exposure Point Concentrations

Exposure Point Concentrations (EPCs) for COPCs in on-Site surface soil and off-Site surface soil in the railroad property and the 35' swath of Beazer-owned property to the south were estimated using spatially-weighted 95th percentile upper confidence limits

(UCLs) on the mean to account for the varying densities of sampling locations on different parts of the Site. Spatially-weighted 95th UCLs for each exposure area were calculated using Thiessen polygons, which are a common geostatistical approach for representing the data points of non-equal portions of an area. Geostatistical methods have been researched, used, and endorsed by USEPA for approximately the past two decades. The usefulness of geostatistical tools to help overcome variation in sampling distribution is described in several USEPA documents published over the past twenty years (Breckenridge et al 1991; USEPA 2001). USEPA began research into geostatistical methods around 1985, and has developed its own geostatistical software tools including GEO-PACK and GEO-EAS, which became available in 1990 and 1991, respectively (USEPA 1990; USEPA 1991a). Perhaps most notably, risk assessment guidance published by USEPA includes use of geostatistical methods to improve data analysis and to help determine the EPC.

The Thiessen polygon technique was selected as the most appropriate spatial tool because it captures the representativeness of the sampling locations across the evaluated area without any biases that may be introduced by more complex interpolative geospatial tools such as Kriging or splining.

The Thiessen polygon geostatistical approach involves using software (for example, ArcGIS) to draw polygons within an overall area of interest (e.g., the Site) so that each polygon contains one sample point, and the area within that polygon is closer to that point than it is to any other sample location. All soil within a polygon is then assumed to have the same concentration as that polygon's sample point. This approach reflects the underlying assumption that the concentration of a COPC in soil can be represented by the sample point closest to that location. However, in certain instances, hard boundaries are used to constrain polygon boundaries when a site feature precludes the expectation that soil in a given area is represented by the closest sample point. For example, the following constraints were used when developing polygon boundaries for the Site:

1. North Marion Street was established as a hard boundary between polygons associated with samples to the west of the road and those to the east of the road. This is based on the expectation that the road is a physical boundary that would preclude the expectation that sample points on one side of the road would be representative of soils on the other side of the road given the road's physical features and the differing nature of historical operations on one side versus the other;
2. The former North Drainage Ditch was established as a hard boundary for polygons associated with sample points collected from the former lagoon area. This is based on the North Drainage Ditch being a highly incised drainage feature in this area. The presence of this feature, combined with the substantially different use histories between the areas south (former lagoon) and north (farm field and borrow pit) of the channel, precludes the expectation that samples from the former lagoon would be representative of soil in the farm field and borrow pit; and


3. The boundaries between the railroad property exposure area to the south of the Site and the southern property lines of the Site were established as a hard boundary. This is based on the Site's southern property boundary having been defined as the southern limit of potential ecological exposures associated with the Southern Exposure area at the direction of the USEPA. However, potential human exposures were identified for the railroad property and the 35' swath of Beazer-owned property to the south. A separate set of polygons was established to support the human health risk assessment for the railroad and Beazer-owned properties to the south. Use of the southern property line as a hard boundary is not intended to imply that a physical barrier exists at the property line. Rather, it simply precluded the need for two sets of varying polygons in the Southern Exposure area (i.e., one set supporting the human health risk assessment that includes the railroad property and a second supporting the ecological risk assessment only for the Southern Exposure Area).

A spatially weighted 95th UCL EPC for any given exposure area was calculated by considering the fraction of the total exposure area that each individual polygon represents. This spatially weighted 95th UCL concentration represents a central tendency estimate of the exposure point concentration in the exposure area.

Not all COPCs were analyzed in every sample; therefore, Thiessen polygons were drawn for each COPC. Accordingly, the polygons and calculations differ slightly between COPCs depending on the dataset.

Exposure area boundaries were then overlaid on the Thiessen polygons. This overlaying of the exposure area boundaries on the existing polygons resulted in some polygons being divided between two exposure areas. In other words, a portion of some polygons falls within one exposure area and the remainder falls within another exposure area. In such cases, each portion of the polygon was treated as any other polygon in the respective exposure areas and was assumed to have a concentration equal to that of the original polygon when estimating the spatially weighted EPC for that exposure area (i.e., the upper 95th percentile of the distribution of spatially weighted arithmetic means). This process is illustrated below for the dioxin data at the polygon associated with sample location A1-24 that is located in the former process area east-southeast of the CAMU, as shown on attached Figure 1.

Sample location A1-24 has an associated TCDD-TEQ concentration of 906 ppt. The polygon associated with this sample point includes portions that fall within the existing surface cover of the Proposed Solar Use Area, uncovered portions of the Proposed Solar Use Area, and the Southern Exposure Area. The area and boundaries associated with each portion of the polygon are shown in the following excerpts:



For the portion of this polygon that falls within the surface cover (33,350 ft²), the process assumes a concentration of “0” because a clean soil cover presently exists in this area. When evaluating this polygon’s contribution to the overall Site-wide concentration, the remaining area of the polygon (103,242 ft²) was assigned a TCDD-TEQ of 906 ppt.

Figures 3 through 10 present the polygons for fluoranthene, naphthalene, pentachlorophenol, pyrene, BaP-TE, arsenic, chromium, and TCDD-TEQ, respectively.

For several other on-Site and off-Site media and exposure areas (i.e., on-Site sediment, off-Site soil to the north & west and east, off-Site sediments, off-Site surface water, and fish tissue), spatially defining the extent of the Thiessen polygons would require the establishment of boundaries for the polygons, some of which might be viewed as arbitrary. For example, for the floodplain soils to the north and west of the Site, any influence of constituents in Glade Creek would be expected to decrease rapidly with distance away from the creek. Thus, floodplain samples were collected close to the creek to maximize finding the highest potential constituent concentrations. How rapidly concentrations decline is not known making the establishment of the outer boundary of a polygon for such a sample arbitrary. Alternatively, establishing boundaries for sediment and fish samples, which are confined to the banks for either Glade Creek, Piles Fork or Crab Orchard Creek, would be possible as is spatially weighting such concentrations (as was done during the evaluation of potential fish consumption risks associated with Crab Orchard Creek [ARCADIS 2013]). However, to be conservative, USEPA’s ProUCL software (USEPA 2013) was used to derive the 95% UCL of the arithmetic mean concentration for on-Site and off-Site sediments, off-Site surface water and fish in Crab Orchard Creek. Appendix C presents the results from ProUCL. Tables 15 through 26 present the EPCs for:

- Site surface soil (Table 15);
- current proposed solar use area surface soil (includes both non-gravel and gravel areas shown on Figure 1) (Table 16);

- future proposed solar use area surface soil (which assumes that the portion of the solar use area covered by gravel has non-detectable COPC concentrations; shown as gravel area on Figure 1) (Table 17);
- southern conservation exposure area surface soil (Table 18);
- railroad property surface soil (Table 19);
- 35-foot swath surface soil (Table 20);
- north and west of the Site surface soil (Table 21);
- east of the Site surface soil (Table 22);
- north and west of the Site sediment (Table 23);
- Crab Orchard Creek and Piles Fork sediment (Table 24);
- Crab Orchard Creek and Piles Fork surface water (Table 25); and
- catfish (Table 26).

4. Toxicity Assessment

The purpose of the Toxicity Assessment is to identify the types of adverse health effects a COPC may potentially cause, as well as the relationship between the amount of COPC to which receptors may be exposed (i.e., the dose) and the likelihood of an adverse health effect (i.e., response). Adverse health effects are characterized by USEPA as carcinogenic or non-carcinogenic. Dose-response relationships are defined by USEPA for oral and inhalation routes of exposure. The results of the toxicity assessment, when combined with the results of the exposure assessment (Section 3), are then used to estimate potential risk (Section 5).

This section provides dose-response information for COPCs evaluated in the HHRA. Section 4.1 describes the USEPA approach for developing non-carcinogenic dose-response values. The carcinogenic dose-response relationships developed by USEPA are discussed in Section 4.2. Non-carcinogenic and carcinogenic dose-response values used in this risk assessment are presented in Tables 28, 29, 30 and 31. Dose-response information used in this risk assessment was obtained from the following sources, in order of priority in accordance with USEPA guidance (USEPA 2003b):

- USEPA's IRIS (USEPA, 2014c);
- Provisional Peer Reviewed Toxicity Values (PPRTVs) (USEPA, 2014d); and
- Other sources, such as California EPA and USEPA's Health Effects Assessment Summary Tables (HEAST).

4.1 Non-Carcinogenic Toxicity Values

Constituents with known or potential non-carcinogenic effects are assumed to have a dose below which no adverse effect occurs, or conversely, above which an effect may be seen. This dose is called the threshold dose (or threshold exposure for inhalation pathways). In laboratory experiments, this dose is known as the no observed adverse effect level (NOAEL). The lowest dose at which an adverse effect is seen is called the lowest observed adverse effect level (LOAEL). By applying uncertainty factors to the NOAEL or the LOAEL, the USEPA has developed reference doses (RfDs) for chronic oral and dermal exposures and reference concentrations (RfCs) for chronic inhalation exposures to constituents with potential non-carcinogenic effects (USEPA 2000).

The uncertainty factors account for uncertainties associated with the dose-response value, such as the effect of using an animal study to derive a human dose-response value, extrapolating from the high doses used in the laboratory experiment to the low doses typically encountered in environmental settings, and evaluating sensitive subpopulations. For constituents with potential non-carcinogenic effects, the RfD and RfC provide

reasonable certainty that if the specified exposure dose is below the RfD or the exposure concentration is below the RfC, then no potential non-carcinogenic health effects are expected to occur even if daily exposure were to occur for a lifetime. RfDs are expressed in terms of milligrams of constituent per kilogram of body weight per day (mg/kg-day). RfCs are expressed as milligrams per cubic meter (mg/m³).

Oral, dermal, and inhalation routes of exposure were evaluated in this risk assessment. Because dermal toxicity values are not generally available, oral dose-response information is used to estimate the potential risk associated with both oral and dermal exposures. In the absence of dermal RfDs, the oral RfD was multiplied by an appropriate gastrointestinal absorption factor (ABS_{GI}) (USEPA 2004) for use in estimating potential non-cancer hazards from dermal exposures. The ABS_{GI} is also known as the oral-to-dermal adjustment factor. The ABS_{GI} factor adjusts the orally-administered dose for the amount absorbed because dermal exposure doses are expressed as “absorbed” doses (note that oral and inhalation doses are usually expressed as “administered” doses). Constituent-specific ABS_{GI}s were obtained from USEPA RAGS Part E (2004) where they exist. A default ABS_{GI} factor of 100% was used where no ABS_{GI} value is recommended by USEPA.

Potential exposures that occur over a period that is greater than 10% of a lifetime (or more than 7 years in duration) are considered chronic exposures and are compared with chronic toxicity values. Potential exposures that are less than 10% of a lifetime (or less than 7 years in duration) are considered subchronic exposures and are compared with subchronic toxicity values, where available. The future on-Site solar farm redevelopment worker scenario, current/future on-Site child deer consumer scenario, and current/future off-Site child recreational angler scenario are assumed to be subchronic exposures and, thus, used the subchronic non-cancer toxicity values. All other scenarios were assumed to potentially be chronic exposures. Toxicity values used in the evaluation of non-carcinogenic effects are presented in Table 28 (oral and dermal) and in Table 29 (inhalation).

4.2 Carcinogenic Toxicity Values

Constituents with known or potential carcinogenic effects are conservatively assumed to have some probability of causing an adverse health response (cancer) at any dose. That is, the threshold dose for the cancer endpoint is assumed to be zero. The cancer-causing potency of known or potential carcinogens is estimated based on laboratory animal toxicological data and human epidemiological data. There is uncertainty in extrapolating observed responses from high doses in laboratory experiments or occupational settings, to the expected responses from low doses typically encountered in environmental settings. USEPA therefore conservatively assumes that the dose-response curve for carcinogens is linear at low doses, i.e., every unit increase of constituent dose corresponds to the same unit increase in the lifetime probability of cancer. The numerical estimate of the cancer-causing potency of a constituent for dermal and oral exposures is referred to by the USEPA as the Cancer Slope Factor (CSF). A CSF is expressed in terms of the inverse of a

milligram of constituent per kilogram body weight per day $[(\text{mg}/\text{kg}\cdot\text{day})^{-1}]$. For inhalation exposures, the numerical estimate is expressed as an inhalation unit risk (IUR) factor. The IUR is expressed in terms of micrograms of a constituent per cubic meter $(\mu\text{g}/\text{m}^3)^{-1}$ and represents the upper-bound excess lifetime cancer risk estimated to result from continuous exposure to a constituent at a concentration of $1 \mu\text{g}/\text{m}^3$ in air. CSFs and IURs are presented in Table 30 and 31, respectively.

CSFs have not been developed for the dermal exposure route. In the absence of dermal slope factors, the oral slope factor was divided by an appropriate ABS_{GI} (USEPA 2004) for use in estimating potential cancer risk from dermal exposures. Constituent-specific ABS_{GI} s were obtained from USEPA RAGS Part E (2004) where they exist. A default ABS_{GI} factor of 100% was used where no ABS_{GI} value is recommended by USEPA.

5. Risk Characterization

The Risk Characterization combines the results of the Exposure Assessment with the results of the Toxicity Assessment to derive quantitative estimates of the potential for adverse health effects to occur as a result of potential exposure to Site-related constituents. Non-carcinogenic and carcinogenic risk characterizations are described separately below.

5.1 Non-Carcinogenic Risk Characterization

The potential for exposures to COPCs in soil at the Site to result in potential adverse non-carcinogenic health effects is estimated by comparing the ADD for each COPC (as discussed in Section 4.1) with the RfD for that COPC, or in the case of the inhalation pathway, comparing the ADE for each COPC with the RfC for that COPC. The resulting ratio, which is unitless, is known as the hazard quotient (HQ) for that COPC. The summation of all individual COPC HQs is the hazard index (HI). The HI is calculated using the following formula:

$$HI = E_1/RfD_1 + E_2/RfD_2 + \dots + E_i/RfD_i.$$

where:

- HI = Hazard Index;
- E/RfD = Hazard Quotient;
- E_i = exposure intake for the ith COPC (mg/kg-day); and
- RfD_i = Reference Dose (mg/kg-day) or Reference Concentration (mg/m³) for the ith COPC.

When the HQ for a given COPC and pathway does not exceed 1, the RfD has not been exceeded, and potential adverse non-carcinogenic health effects are not expected to occur as a result of exposure to that COPC via that pathway. The HQs for each COPC are summed to yield the Hazard Index (HI) for that pathway. A total HI is then calculated for each exposure medium by summing the pathway-specific HIs. A total HI that does not exceed 1 indicates that potential adverse non-carcinogenic health effects are not expected to occur as a result of that receptor's potential exposure to COPCs in the environmental medium evaluated (USEPA 2000). This approach assumes that sub-threshold chronic exposures to multiple constituents are additive (similarly for subchronic exposures by the future on-site solar farm redevelopment worker, current/future on-Site child deer consumer, and current/future off-Site child recreational angler receptors). However, HIs should only be summed for constituents with the same target organ or endpoint. Therefore, where the Total HI across all media exceeds 1, endpoint-specific HIs are estimated and compared to the HI limit of 1. An endpoint-specific total HI that does not exceed 1 indicates that no potential adverse non-carcinogenic health effects are expected to occur as a result of that

receptor's potential exposure to COPCs in the environmental medium evaluated. An endpoint-specific total HI of greater than 1 indicates a potential for adverse effects to that endpoint.

The estimated hazards from all pathways and COPCs for all on-Site and off-Site exposure areas for each receptor group within each of those areas are summarized below. Each bullet identifies an exposure area and receptor group, presents the HI for that exposure area and receptor group, and refers to the table in which more details (e.g. the HQs associated with specific exposure pathways and COPCs) can be found.

- Current/Future on-Site Adult Maintenance Worker/Caretaker: 2 (with all target organ HIs less than or equal to 1) (Table 32);
- Current/Future On-site Adult Deer Hunter and Consumer: 0.1 (Table 33);
- Current/Future On-site Adolescent Deer Consumer: 0.2 (Table 34);
- Current/Future On-site Child Deer Consumer: 0.3 (Table 35);
- Current/Future On-site Adolescent Trespasser: 0.3 (Table 36);
- Future On-site Adult Hikers/Bicycle Trail Users: 0.3 (Table 37);
- Future On-site Adolescent Hikers/Bicycle Users: 0.8 (Table 38);
- Future On-site Solar Farm Redevelopment Worker: 0.5 (Table 39);
- Future On-site Solar Farm Maintenance Worker: 0.2 (Table 40);
- Current/Future Off-site Adult Kayaker/Canoeist: 0.0001 (Table 41);
- Current/Future Off-site Adolescent Kayaker/Canoeist: 0.0002 (Table 42);
- Current/Future Off-site Adult Recreational Angler: 0.1 (Table 43);
- Current/Future Off-site Adolescent Recreational Angler: 0.1 (Table 44);
- Current/Future Off-site Child Fish Consumer: 0.4 (Table 45);
- Current/Future Off-site Adolescent Trespasser on the Railroad Property: 0.2 (Table 46);
- Current/Future Off-site Adolescent Trespasser on the 35' Swath Property: 0.3 (Table 47);
- Current/Future Off-site Adolescent Trespasser to Soil North and West of the Site: 0.005 (Table 48);
- Current/Future Off-site Adolescent Trespasser to Soil East of the Site: 0.3 (Table 49);
- Current/Future Off-site Adolescent Trespasser to Sediment North and West of the Site: 0.007 (Table 50);
- Hypothetical Future Off-Site Adult Hikers/Bicycle Trail Users on the Railroad Property: 0.04 (Table 51); and,

- Hypothetical Future Off-Site Adolescent Hikers/Bicycle Trail Users on the Railroad Property: 0.01 (Table 52).

As evident from the summary presented above, all exposure areas and receptors evaluated within those areas in this HHRA have total HIs that are at or below USEPA's limit of 1 indicating that potential non-cancer hazards for all receptor groups are acceptable. Table 53 summarizes HIs for all receptors.

5.2 Potential Carcinogenic Risk Characterization

The purpose of carcinogenic risk characterization is to estimate the potential likelihood, over and above the background cancer rate, that a receptor will develop cancer in his or her lifetime as a result of potential Site-related exposures to COPCs in various environmental media. This likelihood is a function of the dose of a COPC and the CSF for that COPC or, in the case of the inhalation pathway, a function of the exposure to the COPC and the IUR. The relationship between the Potential Excess Lifetime Cancer Risk (PELCR) and the estimated LADD or the LADE of a COPC may be expressed as an exponential equation:

$$A = 1 - e^{-(B \times C)}$$

where:

- A = Potential Excess Lifetime Cancer Risk (PELCR) (unitless);
- B = Cancer Slope Factor (mg/kg-day)⁻¹ or Unit Risk (mg/m³)⁻¹; and
- C = Lifetime Average Daily Dose (mg/kg-day) or Lifetime Average Daily Exposure (mg/m³).

This is the general form of the equation, and may be used in all cases to estimate potential excess lifetime cancer risk, regardless of the magnitude of the potential estimated risk.

The exponential equation can be simplified to a linear equation, which closely approximates the results of the exponential equation when the product of the dose and cancer slope factor is less than 0.01. The simplified linear form of the equation is expressed as:

$$A = B \times C$$

where:

- A = Potential Excess Lifetime Cancer Risk (PELCR) (unitless);
- B = Cancer Slope Factor (mg/kg-day)⁻¹ or Unit Risk (mg/m³)⁻¹; and
- C = Lifetime Average Daily Dose (mg/kg-day) or Lifetime Average Daily Exposure (mg/m³).

The exponential equation should be used when the product of the dose and cancer slope factor is greater than 0.01. This practice of using the general equation prevents calculation of potential risks that are greater than one.

The product of the CSF and the LADD or the UR and the LADE is unitless, and provides an estimate of the potential carcinogenic risk associated with a receptor's exposure to that COPC via that pathway. Pathway PELCRs are calculated for each COPC the USEPA assumes may potentially cause cancer. The PELCRs for each pathway by which the receptor is assumed to be exposed are calculated by summing the potential risks derived for each COPC. A Total PELCR is then calculated for each exposure medium by summing the pathway-specific PELCRs.

In general, the USEPA considers PELCRs that are below 1 chance in 1,000,000 (1×10^{-6} or $1E-06$) to be so small as to be negligible, and PELCRs above $1E-04$ to be sufficiently large they warrant further evaluation and possible mitigation. Potential excess lifetime cancer risk estimates that range between $1E-06$ and $1E-04$ are generally considered to be acceptable (USEPA 1991b).

The total potential excess lifetime cancer risks from all pathways and COPCs for all on-Site and off-Site exposure areas for each receptor group within each of those areas are summarized below. Each bullet identifies an exposure area and receptor group, presents the PELCR for that exposure area and receptor group, and refers to the table in which more details (e.g. the PELCRs associated with specific exposure pathways and COPCs) can be found.

- Current/Future on-Site Adult Maintenance Worker/Caretaker: $8E-05$ (Table 32);
- Current/Future On-site Adult Deer Hunter and Consumer: $1E-05$ (Table 33);
- Current/Future On-site Adolescent Deer Consumer: $5E-06$ (Table 34);
- Current/Future On-site Child Deer Consumer: $4E-06$ (Table 35);
- Current/Future On-site Adolescent Trespasser: $7E-06$ (Table 36);
- Future On-site Adult Hiker/Bicycle Trail Users: $9E-06$ (Table 37);
- Future On-site Adolescent Hiker/Bicycle Trail Users: $1E-05$ (Table 38);
- Future On-site Solar Farm Redevelopment Worker: $2E-06$ (Table 39);
- Future On-site Solar Farm Maintenance Worker: $2E-05$ (Table 40);
- Current/Future Off-site Adult Kayaker/Canoeist: $4E-05$ (Table 41);
- Current/Future Off-site Adolescent Kayaker/Canoeist: $4E-05$ (Table 42);
- Current/Future Off-site Adult Recreational Angler: $6E-05$ (Table 43);
- Current/Future Off-site Adolescent Recreational Angler: $5E-05$ (Table 44);

- Current/Future Off-site Child Fish Consumer: 1E-05 (Table 45);
- Current/Future Off-site Adolescent Trespasser on the Railroad Property: 1E-06 (Table 46);
- Current/Future On-site Adolescent Trespasser on the 35' Swath Property: 6E-06 (Table 47);
- Current/Future Off-site Adolescent Trespasser to Soil North and West of the Site: 7E-07 (Table 48);
- Current/Future Off-site Adolescent Trespasser to Soil East of the Site: 8E-07 (Table 49);
- Current/Future Off-site Adolescent Trespasser to Sediment North and West of the Site: 2E-06 (Table 50);
- Hypothetical Future Off-site Adult Hikers/Bicycle Trail Users on the Railroad Property: 3E-06 (Table 51); and,
- Hypothetical Future Off-site Adolescent Hikers/Bicycle Trail Users on the Railroad Property: 5E-06 (Table 52).

As evident from the summary presented above, all exposure areas and receptors evaluated within those areas in this HHRA have total PELCRs that fall within or below USEPA's acceptable risk range (1E-06 to 1E-04) indicating that potential cancer risks for all receptor groups are acceptable. Table 53 summarizes total PELCRs for all receptors.

6. Uncertainty Analysis

Within any of the four steps of the risk assessment process, assumptions must be made due to a lack of full scientific knowledge. Some of the assumptions are supported by considerable scientific evidence, while others have less support. Every assumption introduces some degree of uncertainty into the risk assessment process. As a result, conservative assumptions have been made throughout the risk assessment to ensure that public health is protected and that potential risks and hazards are not underestimated. It is likely, therefore, that when all of the assumptions are combined, potential risks, if any, are overestimated rather than underestimated.

6.1 Hazard Identification

During the Hazard Identification step, constituents are selected for inclusion in the quantitative risk assessment. All constituents in samples of the various environmental media where detected above relevant risk-based screening criteria as well as constituents without screening criteria were considered COPCs and were evaluated in the HHRA. Several rounds of sampling have been conducted at the Site and data were evaluated using acceptable analytical methodologies. Therefore, it is unlikely that constituents associated with unacceptable risk have been excluded from the risk assessment as part of the COPC selection process in the hazard identification step.

6.2 Exposure Assessment

This HHRA is conducted using RME parameters. During the exposure assessment, average daily doses of COPC to which hypothetical receptors are potentially exposed are estimated in accordance with the USEPA-approved HHRA work plan (ARCADIS 2014). This involves assumptions about how often hypothetical exposure occurs. Such assumptions include location, accessibility, and use of an area. With this in mind, the hypothetical receptor who may potentially be exposed, and the location of exposure, were both defined for this risk assessment. The locations where certain activities were assumed to take place have been purposely selected to be consistent with the use of the Site.

USEPA (2011) recommends an upper bound soil ingestion rate for young children of 200 mg/day. However, based on information provided by the authors of the study upon which that estimate is derived, it appears that a more reasonable upper bound ingestion rate for young children is 100 mg/day (Stanek and Calabrese 2000). Similarly, USEPA (2011) does not specifically recommend an upper bound estimate of soil ingestion for older children and adults, but does recommend an average ingestion rate for these age groups of 50 mg/day. Additional information provided by Stanek et al. (1997) however, indicate that 50 mg/day is a more reasonable upper bound estimate for these age groups. Thus, for the 6 to 16 year old trespasser receptor, it is likely that soil ingestion has been overestimated because a soil ingestion rate of 100 mg/day was used in the trespasser exposure scenarios.

The HHRA used soil adherence factors derived from studies that measured actual soil loading onto skin during various types of activities. The adherence factors were selected based upon similarity of the activities conducted by the study participants to the assumed activities of the hypothetical receptors evaluated in the risk assessment. It was assumed, therefore, that the soil adherence for hypothetical receptors in the risk assessment would be similar to soil adherence observed in the studies. It was also assumed that absorption of constituents from soil adhered to skin would be similar to absorption from soil observed in studies used to derive the absorption adjustment factors. However, such studies typically measure absorption by applying enough soil to the skin so that an “infinite source” of a constituent is available for absorption. This HHRA assumes that the amount of soil assumed to adhere to receptors’ skin approximates the “infinite source” amount used to estimate dermal absorption of constituents from soil. However, rates of absorption measured in studies may not be representative of absorption that occurs when lower degrees of adherence occur.

The estimated dermal exposures in this HHRA to COPCs in sediment while kayaking are likely overestimated. USEPA’s final Dermal Risk Assessment Guidance manual (USEPA 2004) notes the following with regard to sediment exposure: “For significant dermal exposure to sediments to occur, sediment samples must be located in areas in which individuals are likely to come into direct contact with the sediments. For kayaking, this includes areas which are near shore and in which sediments are exposed at some time during the year. Sediments which are consistently covered by considerable amounts of water are likely to wash off before the individual reaches the shore.” Further, for significant dermal absorption of contaminants to occur from water, contact needs to be reasonably extensive and prolonged like that associated with swimming, wading, or showering or bathing. Brief incidental contact while kayaking is unlikely to result in dermal absorption.

6.3 Toxicity Assessment

Toxicity data used for the HHRA can be limited. Much of the data used to generate human health criteria are derived from animal studies. This results in uncertainties, given the following:

Both endpoints of toxicity (effect or target organ) and the doses at which effects are observed are generally extrapolated from animals to humans;

Results of short-term exposure studies are used to predict the effects of long-term exposures;

Results of studies using high doses are used to predict effects from exposures to low doses usually expected at hazardous waste sites; and

Effects exhibited by homogeneous populations of animals (or humans) are used to predict effects in heterogeneous populations with variable sensitivities (e.g., the young, elderly, infirmed).

6.4 Risk Characterization

The risk of potential adverse human health effects depends on estimated levels of potential exposure and on dose-response relationships. Once potential exposure to, and potential risk from, each of the COPCs is estimated, the total risk posed by potential exposure to COPCs is determined by combining the health risk contributed by each COPC. Where COPCs do not interact, do not affect the same target organ or do not have the same mechanism of action, summing the risks for multiple COPCs results in an overestimate of risk posed by the Site. However, in order not to understate the potential risk, it was conservatively assumed that the potential effects of different COPCs are additive.

Potential exposures used to estimate potential risk for the various Site receptors are considered to be upper bound estimates of potential exposure. They represent a combination of assumptions; some of which represent the central tendency for a particular exposure parameter with others representing the upper end of the range of values for an exposure parameter. When combined, they represent a high-end (or RME) exposure even when some Site-specific assumptions are employed. Additional conservatism is embodied in the potential exposure estimates based on the receptor-specific factors as described below.

- **Current/future on-Site adult maintenance worker/caretaker** – In practice, and consistent with the Site's health and safety protocols, the maintenance worker/caretaker utilizes personal protective equipment (PPE) to limit exposure to COPCs at the Site when engaged in activities where the potential for significant direct exposure exists.
- **Future on-Site solar farm redevelopment and maintenance workers** – Redevelopment and future maintenance work would be directed under a health and safety plan which would include the use of PPE to limit exposure to COPCs at the Site.
- **Current/future on-Site adolescent trespasser** – The HHRA assumes trespassing occurs on a regular basis, although evidence does not support this assumption. The Site is currently fenced and trespassers are very rarely observed on the Site. Future plans include continuing to fence portions of the Site and limit potential access to the bike path.
- **Current/future on-Site deer hunter and consumers** – This scenario assumes that the deer spends 100% of its time at the Site and only consumes vegetation from the Site. This is highly unlikely based on the typical home range of deer and the abundance

of preferred forage in adjacent croplands. Therefore, the calculation of COPCs in deer tissue is a likely over-estimate of exposure to the hunter/consumer.

- **Future on-Site hikers/bicycle users** – These receptors are assumed to get 100% of their daily soil exposure from the short time they would spend on the future bike path on the days they are recreating. This scenario also assumes that soil exposure occurs during recreating, which is highly unlikely given that bike path soil will be covered (e.g., by gravel or asphalt) during the construction of the bike path.
- **Current/future off-Site kayaker/canoists** – The portions of Crab Orchard Creek that are adjacent to the Site have very steep, muddy banks that are difficult to navigate. They also include substantial woody debris and obstructions that make navigating the Creek with a kayak or canoe extremely difficult. Additionally, the water levels fluctuate dramatically throughout the year and are often too low for either a kayak or canoe during the warmer summer months.
- **Current/future off-Site recreational anglers** – As discussed above, the Creek is not very accessible. Additionally, gathering enough fish to conduct laboratory analysis was difficult and it is unlikely that substantial subsistence angling would occur in this portion of the Creek.

The risk and hazard estimates provided in the HHRA are based on RME scenarios that use numerous exposure assumptions that are known to be conservative combined with toxicity factors that are also derived to be conservative. The end result of using multiple conservative assumptions is that the risk and hazard estimates presented in this HHRA likely greatly overstate potential risk for most, if not all, receptors potentially exposed to COPCs at this Site.

7. Summary and Conclusion

This HHRA was conducted in accordance with the USEPA-approved work plan (ARCADIS 2014) and current USEPA guidance to evaluate potential adverse health effects attributable to potential exposures to Site-related constituents. The conclusions of this HHRA can be used to determine whether any further remedial actions need to be implemented at the Site and, as necessary, to potentially assist in the development of cleanup levels or establishment of additional institutional controls protective of human health.

Potential exposures to several on-Site and off-Site exposure areas were evaluated. COPCs were identified by comparing the detected concentrations in relevant environmental samples to conservative risk-based concentrations defined to be protective of the receptors representing these exposure areas. All constituents identified as COPCs were evaluated in this HHRA.

The selection of exposure pathways in this HHRA considered the physical and environmental setting of the Site, local demographics, current and reasonably anticipated future land use, and input provided by the USEPA.

Potential cancer risks and non-carcinogenic hazards were estimated for all complete or potentially complete exposure pathways. Potential exposures to COPCs in each exposure area were estimated in this HHRA using reasonably maximum exposure parameters. Receptors evaluated include:

- current/future on-site adult maintenance workers/caretakers;
- current/future on-Site adult deer hunters and adolescent and child deer consumers;
- current/future on-Site adolescent trespassers;
- future on-Site adult and adolescent hikers/bicycle trail users;
- future on-Site solar farm redevelopment workers;
- future on-Site solar farm maintenance workers;
- current/future off-Site adult and adolescent kayakers/canoists;
- current/future off-Site adult and adolescent recreational anglers and child fish consumers;
- current/future adolescent trespassers; and
- hypothetical future adult and adolescent hikers/bicycle trail users in railroad property.

For each COPC and exposure scenario, non-carcinogenic hazard indices and potential excess lifetime cancer risks were developed to estimate the potential for non-carcinogenic and carcinogenic health effects in accordance with USEPA guidelines (USEPA, 1989).



**Human Health Risk Assessment
for the Former Koppers Wood-
Treating Site**

Carbondale, Illinois

Non-cancer hazard indices for all exposure scenarios and receptors were at or below USEPA's HI limit of 1. Potential excess lifetime cancer estimates for all exposure scenarios and receptors were within or below USEPA's range of allowable risk. These findings indicate that potential cancer and non-cancer risk to all areas and receptors included in this risk assessment are acceptable.

8. References

ARCADIS 2007. Baseline Characterization Work Plan. December 18, 2007.

ARCADIS 2008. Addendum to June 15, 2006 Southern Drainage Ditches Report/Work Plan. Letter from Jeffrey Holden (ARCADIS) to Carolyn Bury (USEPA). January 4, 2008.

ARCADIS 2010. Re: Preliminary Comments, Carbondale Site – Additional Sampling Locations. Email from David Bessingpas (ARCADIS) to Carolyn Bury (USEPA). March 25, 2010.

ARCADIS 2011. Work Plan for Additional PCDD/PCDF Sampling. January 24, 2011.

ARCADIS 2012. Work Plan for Additional Soil Sampling and PCDD/PCDF Analysis. November 19, 2012.

ARCADIS 2013. Additional Information Pertinent to the Fish Consumption Advisory for Crab Orchard Creek (Jackson County, Illinois). Letter from Paul Anderson to Tom Hornshaw. April 18, 2013.

ARCADIS 2014. Former Koppers Wood-Treating Site Human Health Risk Assessment Work Plan, Carbondale, Illinois. Submitted October 1, 2014.

Beazer 2009. Work Plan for Additional Investigations. Letter from Mike Slenska (Beazer) to Carolyn Bury (USEPA). October 26, 2009.

BBL 2005. Revised Supplemental Soil Sampling Work Plan. Letter from Jeffrey Holden (BBL) to Carolyn Bury (USEPA). April 22, 2005.

BBL 2006. Sampling and Analysis Plan (SAP) for Southern Drainage Ditches. February 21, 2006.

Breckenridge, R. P., Williams, J. R., and Keck, J. F. 1991. Characterizing Soils for Hazardous Waste Site Assessments. Ground-Water Issue, EPA/540/4-91/003, Office of Research and Development, Office of Solid Waste and Emergency Response.

California Environmental Protection Agency, Office of Environmental Health Hazard Assessment Hot Spots Unit Risk and Cancer Potency Values; 2011 Update. Accessed via http://www.oehha.ca.gov/air/hot_spots/pdf/CPFs042909.pdf.

California Environmental Protection Agency, 2013. Office of Environmental Health Hazard Assessment, Inhalation Reference Exposure Levels, October 18, 2013 update.

IDNR 2013. Summary of 2012-2013 Illinois Deer Seasons. Forest Wildlife Program, Illinois Department of Natural Resources.

<http://www.dnr.illinois.gov/hunting/deer/Documents/IllinoisDeerHarvestReportFinal.2012.2013.pdf>

National Academy of Sciences (NAS). 1983. Risk Assessment in the Federal Government. Managing the Process. National Academy Press, Washington, D.C. March.

Sample 1994. Estimating Exposure of Terrestrial Wildlife to Contaminants. Environmental Sciences Division. Oak Ridge National Laboratory, Oak Ridge, Tennessee. B.E. Sample and G.W. Suter II. ES/ER/TM-125. September 1994.

Stanek III, E.J., E.J. Calabrese, R. Barnes, and P. Pekow. 1997. Soil Ingestion in Adults - Results of a Second Pilot Study. *Ecotoxicology and Environmental Safety*. 36: 249-257.

Stanek, E.J., III; Calabrese, E.J. (2000). Daily Soil Ingestion Estimates for Children at a Superfund Site. *Risk Anal* 20: 627-635. October 2000.

USEPA 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA. EPA 540 G-80 004. October.

USEPA 1989. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual (Part A). EPA/540/1-89-002. December 1989.

USEPA 1990. Geostatistics For Waste Management: User's Manual For the GEOPACK (Version 1.0), Geostatistical Software System. EPA/600/8-90/004, January, 1990. <http://www.epa.gov/ada/download/models/geopack.pdf>

USEPA. 1991a. GEO-EAS 1.2.1. Geostatistical Environmental Assessment Software. User's Guide. EPA 600/4-88/033, March, 1991. <http://www.epa.gov/ada/download/models/geoeas.pdf>

USEPA 1991b. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Supplemental Guidance "Standard Default Exposure Factors." Interim Final. OSWER Directive: 9285.6-03. Office of Solid Waste and Emergency Response, Washington, D.C., March, 28 pp

USEPA 1993. Provisional Guidance for Quantitative Risk Assessment of Polycyclic Aromatic Hydrocarbons. Office of Research and Development. EPA/600/R-93/089. July.

USEPA 1997. Exposure Factors Handbook. Exposure Assessment Group, Office of Research and Development, National Center for Environmental Assessment, Washington, DC.

USEPA 1997. Health Effects Assessment Summary Tables. July.

USEPA 2000. *Risk Characterization Handbook*. Science Policy Council, Washington, D.C.
EPA-100-B-00-002. <http://www.epa.gov/osa/spc/pdfs/rchandbk.pdf>.

USEPA 2001. Risk Assessment Guidance for Superfund: Volume III - Part A, Process for
Conducting Probabilistic Risk Assessment. EPA 540-R-02-002, OSWER 9285.7-45.
December. Office of Emergency and Remedial Response.
http://www.epa.gov/oswer/riskassessment/rags3adt/pdf/rags3adt_complete.pdf

USEPA 2002. Supplemental Guidance for Developing Soil Screening Levels of Superfund
Sites. Office of Emergency and Remedial Response, U.S. Environmental Protection
Agency, Washington, D.C. 20460. EPA/540/R/99/005. OSWER 9355.4-24. December.

USEPA 2004. Risk Assessment Guidance for Superfund (RAGS), Volume I: Human Health
Evaluation Manual, Part E, Supplemental Guidance for Dermal Risk Assessment.
EPA/540/R/99/005. U.S. Environmental Protection Agency, Office of Emergency and
Remedial Response. July.

USEPA 2005. *Human Health Risk Assessment Protocol for Hazardous Waste Combustion
Facilities*. Final. Office of Solid Waste and Emergency Response. September 2005.
EPA/530-R-05-006.

USEPA 2009. Risk Assessment Guidance for Superfund: Volume 1. Human Health
Evaluation Manual (Part F, Supplemental Guidance for Inhalation Risk Assessment - Final).
OSWER Directive 9285.7-82. Office of Superfund Remediation and Technology Innovation,
U.S. Environmental Protection Agency, Washington, D.C. January.

USEPA.2011 *Exposure Factors Handbook 2011 Edition (Final)*. U.S. Environmental
Protection Agency, Washington, DC, EPA/600/R-09/052F, 2011.

USEPA. 2013. ProUCL Version 5.0. September 2013.
<http://www.epa.gov/osp/hstl/tsc/software.htm>.

USEPA 2014a. Regional Screening Levels (RSLs). May.
http://www.epa.gov/reg3hwmd/risk/human/rb-concentration_table/index.htm

USEPA 2014b. Letter dated March 14, 2014 from Carolyn Bury, USEPA Region 5 to Mike
Slenska, Beazer East, Inc. *Re: Response to Human Health Risk Assessment Inquiry.
Former Koppers Company Wood-Treating Site, Carbondale, IL*. U.S. EPA ID No. ILD 000
819 946



USEPA 2014c. Integrated Risk Information System (IRIS) online database. Environmental Criteria and Assessment Office, Cincinnati, OH. accessed February 2014.
(<http://www.epa.gov/iris/>)

USEPA 2014d. Provisional Peer Reviewed Toxicity Values for Superfund (PPRTV). Online Assessments Electronic Library. Office of Superfund Remediation and Technology Innovation, Washington, DC 20460. (<http://hhpprtv.ornl.gov/>)

USEPA 2015a. Letter dated March 5, 2015 from Carolyn Bury, USEPA Region 5 to Mike Slenska, Beazer East, Inc. *Re: Review of November 26, 2014 Human Health Risk Assessment, Former Koppers Company Wood-Treating Site, Carbondale, IL*, U.S. EPA ID No. ILD 000 819 946

USEPA 2015b. Letter dated October 6, 2015 from Carolyn Bury, USEPA Region 5 to Mike Slenska, Beazer East, Inc. *Re: Human Health Risk Assessment, Former Koppers Company Wood-Treating Site, Carbondale, IL*, U.S. EPA ID No. ILD 000 819 946

van den Berg et al, 2006. Van den Berg, M., L.S. Birnbaum, M. Denison, M. De Vito, W. Farland, M. Feeley, H. Fiedler, H. Hakansson, A. Hanberg, L. Haws, M. Rose, S. Safe, D. Schrenk, C. Tohyama, A. Tritscher, J. Tuomisto, M. Tysklind, N. Walker, and R.E. Peterson. July 7, 2006. The 2005 World Health Organization Reevaluation of Human and Mammalian Toxic Equivalency Factors for Dioxins and Dioxin-Like Compounds. *Toxicological Sciences*. 93(2): 223–241.



Tables

**TABLE 1
ON-SITE SOIL COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
83-32-9	Acenaphthene	123/163	123	163	75.5	1.3	1100000	SDD-7-TLB	8.5	18000	9800	4500000	no	BSL
208-96-8	Acenaphthylene	154/163	154	163	94.5	3.6	81000	SDD-7-TLB	8.5	92	3640	NA	no	NTX
120-12-7	Anthracene	156/163	156	163	95.7	3.1	500000	SDD-7-TLB	8.5	9.4	9510	23000000	no	BSL
191-24-2	Benzo(ghi)perylene	154/163	154	163	94.5	3.3	220000	SDD-7-TLB	8.5	360	8380	NA	no	NTX
86-74-8	Carbazole	1/1	1	1	100	1300	1300	SDD-16			1300	NA	no	NTX
206-44-0	Fluoranthene	157/163	157	163	96.3	1.7	4900000	SDD-7-TLB	8.5	92	46500	3000000	yes	ASL
86-73-7	Fluorene	137/163	137	163	84.0	1.6	670000	SDD-7-TLB	8.7	2700	7030	3000000	no	BSL
91-20-3	Naphthalene	141/163	141	163	86.5	1.4	680000	SDD-7-TLB	8.5	1900	7340	17000	yes	ASL
87-86-5	Pentachlorophenol	84/109	84	109	77.1	10	190000	SDD-16	43	88000	15800	4000	yes	ASL
85-01-8	Phenanthrene	162/163	162	163	99.4	2.7	1800000	SDD-7-TLB	360	360	21100	NA	no	NTX
108-95-2	Phenol	1/5	1	5	20.0	46	46	GC-BC-FPT3-5R	8.8	98	25.1	25000000	no	BSL
129-00-0	Pyrene	157/163	157	163	96.3	4.4	2500000	SDD-7-TLB	8.5	9.4	28700	2300000	yes	ASL
50-32-8	BaP-TE (NDs = 1/2 DL)	163/163	163	163	100	7.37	699000	SDD-7-TLB			16700	290	yes	ASL
Metals														
7440-38-2	Arsenic	142/142	142	142	100	1100	63800	A2-15			14500	3000	yes	ASL
7440-47-3	Chromium	55/55	55	55	100	12900	155000	A2-16			30600	6300	yes	ASL
7440-50-8	Copper	55/55	55	55	100	9500	55400	A2-13(3/29/2010)			23500	4700000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	103/103	103	103	100	0.00299	35.6	A3-14			2.75	0.664	yes	ASL

Notes:

- Derivation of screening concentration is discussed in Section 2.3 of the report.
- Average calculated including non-detect concentrations at 1/2 the detection limit.
- ug/kg = microgram per kilogram
- COPC = constituent of potential concern
- SVOCs = semi-volatile organic compounds
- NDs = non-detects
- DL = detection limit
- BaP-TE = benzo(a)pyrene toxic equivalents
- TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
- NA = not available
- BSL = maximum concentration below screening level
- ASL = maximum concentration above screening level
- NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 2
ON-SITE SEDIMENT COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
83-32-9	Acenaphthene	9/15	9	15	60.0	14	2700	GC-BC-10	0.00925	71	257	7000000	no	BSL
208-96-8	Acenaphthylene	13/15	13	15	86.7	0.058	4600	A5-7	0.00925	53	1020	NA	no	NTX
120-12-7	Anthracene	13/15	13	15	86.7	0.069	5600	A5-7	0.00925	53	1310	360000000	no	BSL
191-24-2	Benzo(ghi)perylene	13/15	13	15	86.7	0.11	8600	A5-7	0.00925	53	1990	NA	no	NTX
206-44-0	Fluoranthene	13/15	13	15	86.7	0.11	22000	GC-BC-10	0.00925	53	2420	47000000	no	BSL
86-73-7	Fluorene	11/15	11	15	73.3	0.013	3100	GC-BC-10	0.00925	53	336	47000000	no	BSL
91-20-3	Naphthalene	7/15	7	15	46.7	35	680	A5-7	0.00925	72	115	270000	no	BSL
87-86-5	Pentachlorophenol	12/15	12	15	80.0	0.09	2100	A5-7	0.0455	260	513	63000	no	BSL
85-01-8	Phenanthrene	15/15	15	15	100	0.0065	16000	GC-BC-10			1410	NA	no	NTX
129-00-0	Pyrene	13/15	13	15	86.7	0.078	13000	GC-BC-10	0.00925	53	1670	36000000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	13/13	13	13	100	67.45	9480	A5-7			3250	4500	yes	ASL
Metals														
7440-38-2	Arsenic	15/15	15	15	100	5.3	71500	GC-BC-09			12300	47000	yes	ASL
7440-47-3	Chromium	15/15	15	15	100	17.95	27000	GC-BC-09			17400	98000	no	BSL
7440-50-8	Copper	15/15	15	15	100	17.7	26800	A5-7			18600	73000000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	6/6	6	6	100	0.037	0.688	SD-BC-01			0.316	13.8	no	BSL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.

Average calculated including non-detect concentrations at 1/2 the detection limit.

ug/kg = microgram per kilogram

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

NDs = non-detects

DL = detection limit

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

NA = not available

BSL = maximum concentration below screening level

ASL = maximum concentration above screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 3
OFF-SITE RAILROAD PROPERTY SOIL COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Units	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs															
83-32-9	Acenaphthene	ug/kg	22/32	22	32	68.8	2.2	300000	SB-119	0.64	19	9450	350000	no	BSL
208-96-8	Acenaphthylene	ug/kg	31/32	31	32	96.9	2.8	50000	SB-119	8.9	8.9	2420	NA	no	NTX
120-12-7	Anthracene	ug/kg	32/32	32	32	100	2.5	840000	SB-119			27300	1700000	no	BSL
191-24-2	Benzo(ghi)perylene	ug/kg	31/32	31	32	96.9	6	47000	SB-119	8.5	8.5	3330	NA	no	NTX
206-44-0	Fluoranthene	ug/kg	32/32	32	32	100	5.35	4300000	SB-119			141000	230000	yes	ASL
86-73-7	Fluorene	ug/kg	24/32	24	32	75.0	2.4	140000	SB-119	0.64	280	4450	230000	no	BSL
91-20-3	Naphthalene	ug/kg	30/32	30	32	93.8	2.5	46000	SB-119	8.5	8.8	1780	3800	yes	ASL
87-86-5	Pentachlorophenol	ug/kg	12/27	12	27	44.4	17.5	8000	A1-37	42	870000	17100	990	yes	ASL
85-01-8	Phenanthrene	ug/kg	32/32	32	32	100	6.45	2800000	SB-119			89200	NA	no	NTX
129-00-0	Pyrene	ug/kg	32/32	32	32	100	5.65	2900000	SB-119			95500	170000	yes	ASL
50-32-8	BaP-TE (NDs = 1/2 DL)	ug/kg	30/30	30	30	100	9.75	275000	SB-119			13800	15	yes	ASL
Metals															
7440-38-2	Arsenic	ug/kg	22/22	22	22	100	3400	36400	A1-11			11100	670	yes	ASL
7440-47-3	Chromium	ug/kg	12/12	12	12	100	11900	20700	A1-45			17500	300	yes	ASL
7440-50-8	Copper	ug/kg	12/12	12	12	100	12500	40100	A1-40			21000	310000	no	BSL
Dioxins/Furans															
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	ug/kg	24/24	24	24	100	0.00431	7.605	A1-1(12/9/2009)			0.962	0.06	yes	ASL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.

Average calculated including non-detect concentrations at 1/2 the detection limit.

ug/kg = microgram per kilogram

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

NDs = non-detects

DL = detection limit

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

NA = not available

BSL = maximum concentration below screening level

ASL = maximum concentration above screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 4
OFF-SITE 35' SWATH PROPERTY SOIL COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Units	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs															
83-32-9	Acenaphthene	ug/kg	5/8	5	8	62.5	5.3	900	A1-41	9.2	19	134	350000	no	BSL
208-96-8	Acenaphthylene	ug/kg	8/8	8	8	100	2.8	2600	SB-115			514	NA	no	NTX
120-12-7	Anthracene	ug/kg	8/8	8	8	100	3.4	3100	SB-115			847	1700000	no	BSL
191-24-2	Benzo(ghi)perylene	ug/kg	8/8	8	8	100	6	4800	A1-41			1550	NA	no	NTX
206-44-0	Fluoranthene	ug/kg	8/8	8	8	100	19	25000	A1-41			5590	230000	no	BSL
86-73-7	Fluorene	ug/kg	6/8	6	8	75.0	3	520	A1-41	9.2	9.4	91.6	230000	no	BSL
91-20-3	Naphthalene	ug/kg	8/8	8	8	100	2.5	3600	SB-115			544	3800	no	BSL
87-86-5	Pentachlorophenol	ug/kg	3/8	3	8	37.5	30.5	3200	SB-115	46	790	568	990	yes	ASL
85-01-8	Phenanthrene	ug/kg	8/8	8	8	100	9.7	12000	A1-41			3010	NA	no	NTX
129-00-0	Pyrene	ug/kg	8/8	8	8	100	13	13000	A1-41			3660	170000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	ug/kg	7/7	7	7	100	15.5	9860	SB-115			3480	15	yes	ASL
Metals															
7440-38-2	Arsenic	ug/kg	5/5	5	5	100	8500	12850	A1-44(3/30/2010)			10700	670	yes	ASL
7440-47-3	Chromium	ug/kg	4/4	4	4	100	16550	20700	A1-45			18500	300	yes	ASL
7440-50-8	Copper	ug/kg	4/4	4	4	100	12350	23400	A1-45			17700	310000	no	BSL
Dioxins/Furans															
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	ug/kg	6/6	6	6	100	0.00431	7.605	A1-1(12/9/2009)			1.46	0.06	yes	ASL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.
Average calculated including non-detect concentrations at 1/2 the detection limit.
ug/kg = microgram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
NDs = non-detects
DL = detection limit
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
NA = not available
BSL = maximum concentration below screening level
ASL = maximum concentration above screening level
NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 5
OFF-SITE NORTH AND WEST OF THE SITE SOIL COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
83-32-9	Acenaphthene	6/11	6	11	54.5	8.9	240	A4-5	8.4	10	33.3	350000	no	BSL
208-96-8	Acenaphthylene	9/11	9	11	81.8	3.2	580	A4-5	8.4	8.8	101	NA	no	NTX
120-12-7	Anthracene	10/11	10	11	90.9	1.3	860	A4-5	8.8	8.8	132	1700000	no	BSL
191-24-2	Benzo(ghi)perylene	9/11	9	11	81.8	12	1400	A4-5	8.4	8.8	253	NA	no	NTX
206-44-0	Fluoranthene	11/11	11	11	100	5.5	3200	A4-5			514	230000	no	BSL
86-73-7	Fluorene	5/11	5	11	45.5	6.3	230	A4-5	8.4	62	30.1	230000	no	BSL
91-20-3	Naphthalene	7/11	7	11	63.6	5.4	560	A4-5	8.4	10	86.1	3800	no	BSL
85-01-8	Phenanthrene	11/11	11	11	100	6.8	2500	A4-5			351	NA	no	NTX
129-00-0	Pyrene	11/11	11	11	100	3.8	1800	A4-5			305	170000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	11/11	11	11	100	8.38	1730	A4-5			368	15	yes	ASL
Metals														
7440-38-2	Arsenic	11/11	11	11	100	6900	13000	A4-6			10000	670	yes	ASL
7440-47-3	Chromium	11/11	11	11	100	14700	28200	A4-6			19300	300	yes	ASL
7440-50-8	Copper	11/11	11	11	100	15300	128000	A4-5			35600	310000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	13/13	13	13	100	0.00232	0.0472	A4-6			0.0149	0.06	no	BSL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.

Average calculated including non-detect concentrations at 1/2 the detection limit.

ug/kg = microgram per kilogram

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

NDs = non-detects

DL = detection limit

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

NA = not available

BSL = maximum concentration below screening level

ASL = maximum concentration above screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 6
OFF-SITE NORTH AND WEST OF THE SITE SEDIMENT COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
83-32-9	Acenaphthene	13/14	13	14	92.9	8	1200	A6-3	40	40	187	7700000	no	BSL
208-96-8	Acenaphthylene	14/14	14	14	100	11	340	A6-3			127	NA	no	NTX
120-12-7	Anthracene	14/14	14	14	100	13	460	A6-3			193	37000000	no	BSL
191-24-2	Benzo(ghi)perylene	14/14	14	14	100	39	1400	GC-BC-03			462	NA	no	NTX
206-44-0	Fluoranthene	14/14	14	14	100	87	4600	GC-BC-03			992	5000000	no	BSL
86-73-7	Fluorene	12/14	12	14	85.7	7.9	990	A6-3	40	76	158	5000000	no	BSL
91-20-3	Naphthalene	9/14	9	14	64.3	8.1	2000	A6-3	40	86	252	83000	no	BSL
87-86-5	Pentachlorophenol	4/14	4	14	28.6	82	220	SD-BC-04	50	520	146	22000	no	BSL
85-01-8	Phenanthrene	14/14	14	14	100	37	2100	A6-3			519	NA	no	NTX
129-00-0	Pyrene	14/14	14	14	100	69	2600	GC-BC-03			639	3700000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	14/14	14	14	100	74.2	2600	GC-BC-03			727	330	yes	ASL
Metals														
7440-38-2	Arsenic	14/14	14	14	100	6700	29200	GC-BC-06			11900	15000	yes	ASL
7440-47-3	Chromium	14/14	14	14	100	14600	60500	A4-1			22100	6600	yes	ASL
7440-50-8	Copper	14/14	14	14	100	12500	39200	GC-BC-04			25900	6800000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	9/9	9	9	100	0.00471	0.144	SD-BC-04			0.0358	1.46	no	BSL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.

Average calculated including non-detect concentrations at 1/2 the detection limit.

ug/kg = microgram per kilogram

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

NDs = non-detects

DL = detection limit

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

NA = not available

BSL = maximum concentration below screening level

ASL = maximum concentration above screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 7
OFF-SITE EAST OF THE SITE SOIL COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
83-32-9	Acenaphthene	6/8	6	8	75.0	3.2	7.3	GC-BC-FPT6-5R	8.7	9.1	4.47	350000	no	BSL
208-96-8	Acenaphthylene	8/8	8	8	100	10	67	GC-BC-FPT6-5L			31.4	NA	no	NTX
120-12-7	Anthracene	8/8	8	8	100	15	80	GC-BC-FPT6-5L			40.9	1700000	no	BSL
191-24-2	Benzo(ghi)perylene	8/8	8	8	100	48	200	GC-BC-FPT6-5L			115	NA	no	NTX
206-44-0	Fluoranthene	8/8	8	8	100	21	160	GC-BC-FPT6-33%R			77.6	230000	no	BSL
86-73-7	Fluorene	8/8	8	8	100	3.7	14	GC-BC-FPT6-5R			8.46	230000	no	BSL
91-20-3	Naphthalene	8/8	8	8	100	3.1	9.4	GC-BC-FPT6-5R			6.04	3800	no	BSL
87-86-5	Pentachlorophenol	4/4	4	4	100	7.2	52	GC-BC-FPT6-33%L			19.0	990	no	BSL
85-01-8	Phenanthrene	8/8	8	8	100	13	53	GC-BC-FPT6-33%R			31.6	NA	no	NTX
129-00-0	Pyrene	8/8	8	8	100	22	160	GC-BC-FPT6-33%R			80.0	170000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	8/8	8	8	100	65.6	236	GC-BC-FPT6-5L			166	15	yes	ASL
Metals														
7440-38-2	Arsenic	8/8	8	8	100	6300	9400	GC-BC-FPT6-33%L			7530	670	yes	ASL
7440-47-3	Chromium	8/8	8	8	100	15800	27400	GC-BC-FPT6-33%R			20000	300	yes	ASL
7440-50-8	Copper	8/8	8	8	100	16000	27600	GC-BC-FPT6-33%R			20500	310000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	4/4	4	4	100	0.0132	0.165	GC-BC-FPT6-5L			0.0590	0.06	yes	ASL

Notes:

- Derivation of screening concentration is discussed in Section 2.3 of the report.
- Average calculated including non-detect concentrations at 1/2 the detection limit.
- ug/kg = microgram per kilogram
- COPC = constituent of potential concern
- SVOCs = semi-volatile organic compounds
- NDs = non-detects
- DL = detection limit
- BaP-TE = benzo(a)pyrene toxic equivalents
- TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
- NA = not available
- BSL = maximum concentration below screening level
- ASL = maximum concentration above screening level
- NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 8
OFF-SITE EAST OF THE SITE SEDIMENT COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/kg	Maximum Detect ug/kg	Max Detect Location	Minimum Non-Detect ug/kg	Maximum Non-Detect ug/kg	Arithmetic Average ug/kg	Screening Concentration ug/kg	COPC?	Rationale
SVOCs														
90-12-0	1-Methylnaphthalene	4/4	4	4	100	22	1000	PF-BC-03-NAPL			288	370000	no	BSL
832-69-9	1-Methylphenanthrene	4/4	4	4	100	19	1500	PF-BC-03-NAPL			417	NA	no	NTX
2245-38-7	2,3,5-Trimethylnaphthalene	4/4	4	4	100	14	460	PF-BC-03-NAPL			132	NA	no	NTX
28804-88-8	2,6-Dimethylnaphthalene	4/4	4	4	100	13	890	PF-BC-03-NAPL			248	NA	no	NTX
91-57-6	2-Methylnaphthalene	4/4	4	4	100	14	560	PF-BC-03-NAPL			158	500000	no	BSL
83-32-9	Acenaphthene	17/19	17	19	89.5	20	79000	COC-BC-04-DEL	55.5	83	4760	7700000	no	BSL
208-96-8	Acenaphthylene	19/19	19	19	100	3.8	5700	COC-BC-04-DEL			410	NA	no	NTX
120-12-7	Anthracene	19/19	19	19	100	5.2	54000	COC-BC-04-DEL			3330	37000000	no	BSL
192-97-2	Benzo(e)pyrene	4/4	4	4	100	150	2100	PF-BC-03-NAPL			660	NA	no	NTX
191-24-2	Benzo(ghi)perylene	19/19	19	19	100	15	8100	COC-BC-04-DEL			907	NA	no	NTX
92-52-4	Biphenyl	3/4	3	4	75.0	1.4	2.35	COC-BC-04(7/15/2010)	50	50	7.59	100000	no	BSL
132-65-0	Dibenzothiophene	4/4	4	4	100	12	1000	PF-BC-03-NAPL			284	1700000	no	BSL
206-44-0	Fluoranthene	19/19	19	19	100	15	250000	COC-BC-04-DEL			16100	5000000	no	BSL
86-73-7	Fluorene	19/19	19	19	100	20	78000	COC-BC-04-DEL			4710	5000000	no	BSL
91-20-3	Naphthalene	15/19	15	19	78.9	5.4	4500	COC-BC-04-DEL	55.5	1000	327	83000	no	BSL
87-86-5	Pentachlorophenol	3/19	3	19	15.8	97	150	PF-BC-03-NAPL	47	29000	897	22000	no	BSL
198-55-0	Perylene	4/4	4	4	100	57	490	PF-BC-03-NAPL			173	NA	no	NTX
85-01-8	Phenanthrene	19/19	19	19	100	27	280000	COC-BC-04-DEL			17700	NA	no	NTX
129-00-0	Pyrene	19/19	19	19	100	21	150000	COC-BC-04-DEL			10000	3700000	no	BSL
50-32-8	BaP-TE (NDs = 1/2 DL)	13/13	13	13	100	30.4	37300	COC-BC-04-DEL			4050	330	yes	ASL
Metals														
7440-38-2	Arsenic	19/19	19	19	100	5950	16600	COC-BC-07			8900	15000	yes	ASL
7440-47-3	Chromium	19/19	19	19	100	12600	22500	COC-BC-04-DEL,GC-BC-16			15700	6600	yes	ASL
7440-50-8	Copper	19/19	19	19	100	12400	23500	GC-BC-16			15900	6800000	no	BSL
Dioxins/Furans														
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	16/16	16	16	100	0.00247	0.055	GC-BC-16			0.0177	1.46	no	BSL

Notes:

Derivation of screening concentration is discussed in Section 2.3 of the report.
Average calculated including non-detect concentrations at 1/2 the detection limit.
ug/kg = microgram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
NDs = non-detects
DL = detection limit
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
NA = not available
BSL = maximum concentration below screening level
ASL = maximum concentration above screening level
NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 9
OFF-SITE SURFACE WATER COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect ug/L	Maximum Detect ug/L	Max Detect Location	Minimum Non-Detect ug/L	Maximum Non-Detect ug/L	Arithmetic Average ug/L	COPC?	Rationale
SVOCs													
87-86-5	Pentachlorophenol	1/4	1	4	25	0.76	0.76	GC-BC-05	0.94	1.1	0.568	yes	NSL
83-32-9	Acenaphthene	3/4	3	4	75	0.18	0.24	GC-BC-10	0.2	0.2	0.185	yes	NSL
208-96-8	Acenaphthylene	1/4	1	4	25	0.15	0.15	GC-BC-05	0.19	0.21	0.113	no	NTX
120-12-7	Anthracene	4/4	4	4	100	0.22	0.27	GC-BC-05			0.235	yes	NSL
206-44-0	Fluoranthene	3/4	3	4	75	0.335	0.38	GC-BC-05	0.2	0.2	0.296	yes	NSL
86-73-7	Fluorene	2/4	2	4	50	0.365	0.44	GC-BC-05	0.2	0.21	0.253	yes	NSL
85-01-8	Phenanthrene	4/4	4	4	100	0.23	0.37	GC-BC-05			0.290	no	NTX
129-00-0	Pyrene	3/4	3	4	75	0.0675	0.074	GC-BC-05	0.2	0.2	0.0781	yes	NSL
Metals													
7440-38-2	Arsenic	4/4	4	4	100	2.6	4.1	GC-BC-05			3.09	yes	NSL
7440-47-3	Chromium	3/4	3	4	75	1.3	1.8	GC-BC-05,GC-BC-08	5	5	1.85	yes	NSL
7440-50-8	Copper	4/4	4	4	100	1.4	2.9	GC-BC-08			2.40	yes	NSL

Notes:

Average calculated including non-detect concentrations at 1/2 the detection limit.

ug/L = microgram per liter

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

NSL = no screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

**TABLE 10
OFF-SITE FISH COPC SCREENING
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Detection Frequency	Detect Count	Result Count	Detection Frequency (%)	Minimum Detect mg/kg	Maximum Detect mg/kg	Max Detect Location	Minimum Non-Detect mg/kg	Maximum Non-Detect mg/kg	Arithmetic Average mg/kg	COPC?	Rationale
SVOCs													
83-32-9	Acenaphthene	3/3	3	3	100	0.0047	0.022	COC-BC-07-EDCAT			0.0152	yes	NSL
208-96-8	Acenaphthylene	2/3	2	3	66.7	0.00092	0.0018	COC-BC-07-EDCAT	0.00069	0.00069	0.00102	no	NTX
120-12-7	Anthracene	3/3	3	3	100	0.0016	0.0077	COC-BC-07-EDCAT			0.00477	yes	NSL
191-24-2	Benzo(ghi)perylene	1/3	1	3	33.3	0.0025	0.0025	COC-BC-07-EDCAT	0.0007	0.00073	0.00107	no	NTX
206-44-0	Fluoranthene	3/3	3	3	100	0.006	0.02	COC-BC-07-EDCAT			0.015	yes	NSL
86-73-7	Fluorene	3/3	3	3	100	0.0032	0.015	COC-BC-07-EDCAT			0.00973	yes	NSL
85-01-8	Phenanthrene	3/3	3	3	100	0.0064	0.024	COC-BC-07-EDCAT			0.0155	no	NTX
108-95-2	Phenol	3/3	3	3	100	0.0019	0.0081	COC-BC-07-EDCAT			0.00543	yes	NSL
129-0-00	Pyrene	3/3	3	3	100	0.028865	0.1245	COC-BC-07-EDCAT			0.0784	yes	NSL
50-32-8	BaP-TE (NDs = 1/2 DL)	1/3	1	3	33.3	0.0053	0.0053	COC-BC-07-EDCAT	0.0015	0.0015	0.00228	yes	NSL
Metals													
7440-38-2	Arsenic	3/3	3	3	100	0.06	0.17958	COC-BC-07-EDCAT			0.139	yes	NSL
7440-47-3	Chromium	1/3	1	3	33.3	0.03	0.03	COC-BC-04-EDCAT	0.01449	0.01533	0.015	yes	NSL
7440-50-8	Copper	3/3	3	3	100	0.24	0.42924	COC-BC-07-EDCAT			0.325	yes	NSL
Dioxins/Furans													
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	3/3	3	3	100	1.60E-07	3.10E-07	COC-BC-07-EDCAT			2.11E-07	yes	NSL

Notes:

Average calculated including non-detect concentrations at 1/2 the detection limit.

mg/kg = milligram per kilogram

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

NSL = no screening level

NTX = no toxicity data available. Potential human health risk cannot be quantitatively assessed.

TABLE 11
BENZO(A)PYRENE TOXIC EQUIVALENCY FACTORS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Potentially Carcinogenic PAHs	Toxic Equivalency Factors
Benzo(a)pyrene	1
Benz(a)anthracene	0.1
Benzo(b)fluoranthene	0.1
Benzo(k)fluoranthene	0.01
Chrysene	0.001
Dibenz(ah)anthracene	1
Indeno(123-cd)pyrene	0.1

TABLE 12
2,3,7,8-TETRACHLORODIBENZO-P-DIOXIN TOXIC EQUIVALENCY FACTORS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Dioxin/Furan Congeners	Toxic Equivalency Factors
2,3,7,8-Tetrachlorodibenzo-p-dioxin	1
1,2,3,7,8-Pentachlorodibenzo-p-dioxin	1
1,2,3,4,7,8-Hexachlorodibenzo-p-dioxin	0.1
1,2,3,6,7,8-Hexachlorodibenzo-p-dioxin	0.1
1,2,3,7,8,9-Hexachlorodibenzo-p-dioxin	0.1
1,2,3,4,6,7,8-Heptachlorodibenzo-p-dioxin	0.01
Octachlorodibenzo-p-dioxin	0.0003
2,3,7,8-Tetrachlorodibenzofuran	0.1
1,2,3,7,8-Pentachlorodibenzofuran	0.03
2,3,4,7,8-Pentachlorodibenzofuran	0.3
1,2,3,4,7,8-Hexachlorodibenzofuran	0.1
1,2,3,6,7,8-Hexachlorodibenzofuran	0.1
1,2,3,7,8,9-Hexachlorodibenzofuran	0.1
2,3,4,6,7,8-Hexachlorodibenzofuran	0.1
1,2,3,4,6,7,8-Heptachlorodibenzofuran	0.01
1,2,3,4,7,8,9-Heptachlorodibenzofuran	0.01
Octachlorodibenzofuran	0.0003

**TABLE 13
SUMMARY OF EXPOSURE PATHWAYS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Pathway	Pathway Status	Rationale
On-Site Receptor Populations		
Current/Future On-Site Adult Maintenance Worker/Caretaker	Complete	Though exposure potential is limited and may be insignificant because of training and PPE, evaluated quantitatively in the HHRA at USEPA's request assuming a Site-wide exposure area.
Current/Future On-site Adult Deer Hunter and Adolescent and Child Deer Consumer	Complete	One family currently has permission to hunt on-Site. This arrangement is limited to a small portion of the Site and has rarely been utilized. Additionally, much of the Site is within the City limit and discharge of firearms is not allowed within City limits per City ordinances. However, the HHRA conservatively assumes this pathway is complete under the scenario that deer grazing at the Site could be harvested on another property.
Current/Future On-site Adult and Adolescent Recreational Crayfishers	Incomplete	Crayfish collection has not been observed on the Site nor has evidence of such collection been observed. Additionally, field crews targeted crayfish in both Piles Fork and Glade Creek but collected very few, indicating crayfish are not abundant at the Site.
Future On-site Adult and Adolescent Hikers/Bicycle Trail Users	Complete	Evaluated quantitatively in the HHRA for the southern exposure area.
Current/Future On-site Adolescent Trespasser	Complete	Evaluated quantitatively in the HHRA assuming a Site-wide exposure area.
Future On-site Adult Generic Industrial Worker	Incomplete	Future use of the Site is solar and conservation. Institutional controls will preclude generic industrial development without further evaluation to confirm planned use meets allowable risk levels.
Future On-site Solar Farm Redevelopment Worker	Complete	Evaluated quantitatively in the HHRA for the solar exposure area.
Future On-site Solar Farm Maintenance Worker	Complete	Evaluated quantitatively in the HHRA for the solar exposure area.
Future On-site Generic Redevelopment Worker	Incomplete	Institutional Controls will establish protective controls, such as the need for a HASP and management plan to eliminate future exposure in the event of any redevelopment or intrusive work. Institutional controls will preclude generic industrial development without further evaluation to confirm planned use meets allowable risk levels.
Off-Site Receptor Populations		
Current/Future Off-site Adult and Child Residents	Incomplete	USEPA's March 14, 2014 letter indicating the pattern of off-Site concentrations in the residential neighborhood to the south of the Site indicates that releases from the Site are not the source the measured concentrations.
Current/Future Off-site Adult and Adolescent Kayaker/Canoeist	Complete	Though exposure potential is limited and may be insignificant because of the nature of Crab Orchard Creek (COC) near the Site (i.e., steep banks and debris make it hard to access), evaluated quantitatively in the HHRA at USEPA's request assuming exposure to COC sediments and surface water.
Current/Future Off-site Adult and Adolescent Recreational Angler and Child Fish Consumer	Complete	Though exposure potential is limited and may be insignificant because of the nature of COC near the Site (i.e., steep banks and debris make it hard to access, few deep pools to harbor fish), evaluated quantitatively in the HHRA assuming direct exposure to COC sediments and surface water and consumption of fish from COC.
Current/Future Adolescent Trespasser	Complete	Evaluated quantitatively in the HHRA assuming exposure to soil in the railroad property, 35' swath soils, sediments and soils adjacent to creeks to the north and west of the Site, and in the Glade Creek floodplain downstream of the property boundary.
Hypothetical Future Adult and Adolescent Hikers/Bicycle Trail Users on Railroad Property	Complete	Although permission has not been granted to utilize the railroad property for the future bike path, hypothetical hikers/bicycle users are conservatively be assumed to be exposed to the railroad property in the future.

**TABLE 14
HUMAN HEALTH EXPOSURE ASSUMPTIONS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Parameter	Units	Current/Future On-Site Adult Maintenance Worker/Caretaker	Notes	Future On-site Solar Farm Redevelopment Worker	Notes	Future On-site Solar Farm Maintenance Worker	Notes	Current/Future Adolescent Trespasser	Notes
Exposure Areas		On-Site			Proposed Solar Use Area			On-Site, Railroad Property, and 35' Swath	
General									
Averaging Time (carcinogenic)	days	25550	USEPA 1991b	25550	USEPA 1991b	25550	USEPA 1991b	25550	USEPA 1991b
Averaging Time (noncarcinogenic)	days	9125	ED x 365 days/year	365	ED x 365 days/year	9125	ED x 365 days/year	3650	ED x 365 days/year
Body Weight	kg	70	USEPA 2002	70	USEPA 2002	70	USEPA 2002	46.8	USEPA 2011; 6 - 16 yr age-adjusted body weight
Exposure Duration	yr	25	USEPA 2002	1	Site-specific	25	USEPA 2002	10	Professional judgment
Soil - Ingestion									
Incidental Soil Ingestion Rate	mg/day	100	USEPA 2002	330	USEPA 2002	100	USEPA 2002	100	USEPA 2002
Fraction of Total Soil Ingested	unitless	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment
Exposure Frequency	days/yr	125	Site-specific (Brightfields' experience) 2.5 days a week; 50 weeks/year	40	Site-specific (Brightfields' experience) 5 days a week; 2 months/year	75	Professional judgment, based on experience at solar facilities; 1.5 days a week; 50 weeks/year	16	Professional judgment; 1 day/week per year; 4 warm months per year
Soil - Dermal Contact									
Exposed Skin Surface Area	cm ²	3300	USEPA 2002; head, hands, and forearms	3300	USEPA 2002; head, hands, and forearms	3300	USEPA 2002; head, hands, and forearms	4890	USEPA 2011; Lower legs, feet, forearms and hands
Skin Adherence Factor	mg/cm ² -event	0.2	USEPA 2002	0.3	USEPA 2002	0.2	USEPA 2002	0.2	USEPA 2007; age-specific & body-part specific
Exposure Frequency	days/yr	125	Site-specific (Brightfields' experience) 2.5 days a week; 50 weeks/year	40	Site-specific (Brightfields' experience) 5 days a week; 2 months/year	75	Professional judgment, based on experience at solar facilities; 1.5 days a week; 50 weeks/year	16	Professional judgment; 1 day/week per year; 4 warm months per year
Fraction Intake	unitless	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment
Soil - Inhalation of Dust									
Exposure Time, Inhalation	hr/day	8	Professional judgment	8	Professional judgment	8	Professional judgment	2	Professional judgment
Exposure Frequency	days/yr	125	Site-specific (Brightfields' experience) 2.5 days a week; 50 weeks/year	40	Site-specific (Brightfields' experience) 5 days a week; 2 months/year	75	Professional judgment, based on experience at solar facilities; 1.5 days a week; 50 weeks/year	16	Professional judgment; 1 day/week per year; 4 warm months per year
Particulate Emission Factor	m ³ /kg	1.24E+09	IEPA Default	1.24E+09	IEPA Default	1.24E+09	IEPA Default	1.24E+09	IEPA Default
Surface Water - Dermal Contact									
Exposed Skin Surface Area	cm ²	-		-		-		-	
Event Frequency	events/day	-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-	
Exposure Time, Dermal Contact with Surface Water	hr/event	-		-		-		-	
Sediment - Dermal Contact									
Exposed Skin Surface Area	cm ²	-		-		-		-	
Skin Adherence Factor	mg/cm ² -event	-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-	
Event Frequency	events/day	-		-		-		-	
Fraction Intake	unitless	-		-		-		-	
Deer - Ingestion									
Deer Ingestion Rate	g/day	-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-	
Fraction of Total Deer Ingested	unitless	-		-		-		-	
Fish - Ingestion									
Fish Ingestion Rate	g/day	-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-	
Fraction of Total Fish Ingested	unitless	-		-		-		-	

**TABLE 14
HUMAN HEALTH EXPOSURE ASSUMPTIONS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Parameter	Units	Current/Future On-site Adult Deer Hunter	Notes	Current/Future On-site Adolescent Deer Consumer	Notes	Current/Future On-site Child Deer Consumer	Notes	Future Adult Hikers/Bicycle Users	Notes	Future Adolescent Hikers/Bicycle Users	Notes
Exposure Areas		Entire Site			Entire Site			Southern Conservation Exposure Area & Railroad Property		Southern Conservation Exposure Area & Railroad Property	
General											
Averaging Time (carcinogenic)	days	25550	USEPA 1991b	25550	USEPA 1991b	25550	USEPA 1991b	25550	USEPA 1991b	25550	USEPA 1991b
Averaging Time (noncarcinogenic)	days	10950	ED x 365 days/year	3650	ED x 365 days/year	1825	ED x 365 days/year	7300	ED x 365 days/year	3650	ED x 365 days/year
Body Weight	kg	70	USEPA 2002	46.8	USEPA 2011; 6 - 16 yr age-adjusted body weight	16.2	USEPA 2011; 1 - 6 yr age-adjusted body weight	70	USEPA 2002	46.8	USEPA 2011; 6 - 16 yr age-adjusted body weight
Exposure Duration	yr	30	Professional judgment	10	Professional judgment	5	Professional judgment	20	Professional judgment	10	Professional judgment
Soil - Ingestion											
Incidental Soil Ingestion Rate	mg/day	-		-		-		100	USEPA 2002	200	USEPA 2002
Fraction of Total Soil Ingested	unitless	-		-		-		0.1	Professional judgment; Section of bike path through the Site is only a fraction of the larger community bike path	0.1	Professional judgment; Section of bike path through the Site is only a fraction of the larger community bike path
Exposure Frequency	days/yr	-		-		-		52	Professional judgment; 1 day per week	52	Professional judgment; 1 day per week
Soil - Dermal Contact											
Exposed Skin Surface Area	cm ²	-		-		-		5700	USEPA 2002; head, hands, forearms, and lower legs	4890	USEPA 2011; Lower legs, feet, forearms and hands
Skin Adherence Factor	mg/cm ² -event	-		-		-		0.07	USEPA 2002	0.2	USEPA 2002
Exposure Frequency	days/yr	-		-		-		52	Professional judgment; 1 day per week	52	Professional judgment; 1 day per week
Fraction Intake	unitless	-		-		-		0.1	Professional judgment	0.1	Professional judgment
Soil - Inhalation of Dust											
Exposure Time, Inhalation	hr/day	-		-		-		1	Professional judgment	1	Professional judgment
Exposure Frequency	days/yr	-		-		-		52	Professional judgment; 1 day per week	52	Professional judgment; 1 day per week
Particulate Emission Factor	m ³ /kg	-		-		-		1.24E+09	IEPA Default	1.24E+09	IEPA Default
Surface Water - Dermal Contact											
Exposed Skin Surface Area	cm ²	-		-		-		-		-	
Event Frequency	events/day	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Exposure Time, Dermal Contact with Surface Water	hr/event	-		-		-		-		-	
Sediment - Dermal Contact											
Exposed Skin Surface Area	cm ²	-		-		-		-		-	
Skin Adherence Factor	mg/cm ² -event	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Event Frequency	events/day	-		-		-		-		-	
Fraction Intake	unitless	-		-		-		-		-	
Deer - Ingestion											
Deer Ingestion Rate	g/day	28.1	IDNR 2013; USEPA 2011; Family of 4 (2 adults, 1 adolescent, 1 child)	25.0	IDNR 2013; USEPA 2011; Family of 4 (2 adults, 1 adolescent, 1 child)	14.2	IDNR 2013; USEPA 2011; Family of 4 (2 adults, 1 adolescent, 1 child)	-		-	
Exposure Frequency	days/yr	365	Averaged over the year	365	Averaged over the year	365	Averaged over the year	-		-	
Fraction of Total Deer Ingested	unitless	1	Professional judgment	1	Professional judgment	1	Professional judgment	-		-	
Fish - Ingestion											
Fish Ingestion Rate	g/day	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Fraction of Total Fish Ingested	unitless	-		-		-		-		-	

**TABLE 14
HUMAN HEALTH EXPOSURE ASSUMPTIONS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Parameter	Units	Current/Future Off-site Adult Kayaker/Canoeist	Notes	Current/Future Off-site Adolescent Kayaker/Canoeist	Notes	Current/Future Off-site Adult Recreational Angler	Notes	Current/Future Off-site Adolescent Recreational Angler	Notes	Current/Future Off-site Child Recreational Angler	Notes
Exposure Areas		Crab Orchard Creek		Crab Orchard Creek		Crab Orchard Creek		Crab Orchard Creek		Crab Orchard Creek	
General											
Averaging Time (carcinogenic)	days	2550	USEPA 1991b	2550	USEPA 1991b	2550	USEPA 1991b	2550	USEPA 1991b	2550	USEPA 1991b
Averaging Time (noncarcinogenic)	days	10950	ED x 365 days/year	3650	ED x 365 days/year	10950	ED x 365 days/year	3650	ED x 365 days/year	1825	ED x 365 days/year
Body Weight	kg	70	USEPA 2002	46.8	USEPA 2011; 6 - 16 yr age-adjusted body weight	70	USEPA 2002	46.8	USEPA 2011; 6 - 16 yr age-adjusted body weight	16.2	USEPA 2011; 1 - 6 yr age-adjusted body weight
Exposure Duration	yr	30	Professional judgment	10	Professional judgment	30	Professional judgment	10	Professional judgment	5	Professional judgment
Soil - Ingestion											
Incidental Soil Ingestion Rate	mg/day	-		-		-		-		-	
Fraction of Total Soil Ingested	unitless	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Soil - Dermal Contact											
Exposed Skin Surface Area	cm ²	-		-		-		-		-	
Skin Adherence Factor	mg/cm ² -event	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Fraction Intake	unitless	-		-		-		-		-	
Soil - Inhalation of Dust											
Exposure Time, Inhalation	hr/day	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Particulate Emission Factor	m ³ /kg	-		-		-		-		-	
Surface Water - Dermal Contact											
Exposed Skin Surface Area	cm ²	5700	USEPA 2002; head, hands, forearms, and lower legs	4890	USEPA 2011; Age-adjusted surface area of head, hands, forearms, feet and lower legs	5700	USEPA 2002; head, hands, forearms, and lower legs	4890	USEPA 2011; Age-adjusted surface area of head, hands, forearms, feet and lower legs	-	
Event Frequency	events/day	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment	-	
Exposure Frequency	days/yr	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment	-	
Exposure Time, Dermal Contact with Surface Water	hr/event	0.5	Professional judgment	0.5	Professional judgment	0.5	Professional judgment	0.5	Professional judgment	-	
Sediment - Dermal Contact											
Exposed Skin Surface Area	cm ²	2275	USEPA 2011; Mean for hands and feet	1576	USEPA 2011; Age-adjusted mean for hands and feet	2275	USEPA 2011; Mean for hands and feet	1576	USEPA 2011; Age-adjusted mean for hands and feet	-	
Skin Adherence Factor	mg/cm ² -event	1	Maximum possible amount based on considerations of skin monolayer loading capacity.	1	Maximum possible amount based on considerations of skin monolayer loading capacity.	1	Maximum possible amount based on considerations of skin monolayer loading capacity.	1	Maximum possible amount based on considerations of skin monolayer loading capacity.	-	
Exposure Frequency	days/yr	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment	-	
Event Frequency	events/day	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment	-	
Fraction Intake	unitless	1	Professional judgment	1	Professional judgment	1	Professional judgment	1	Professional judgment	-	
Deer - Ingestion											
Deer Ingestion Rate	g/day	-		-		-		-		-	
Exposure Frequency	days/yr	-		-		-		-		-	
Fraction of Total Deer Ingested	unitless	-		-		-		-		-	
Fish - Ingestion											
Fish Ingestion Rate	g/day	-		-		8.1	One 227 g meal per week for a family of 4 (2 adults, 1 adolescent, 1 child)	8.1	One 227 g meal per week for a family of 4 (2 adults, 1 adolescent, 1 child)	8.1	One 227 g meal per week for a family of 4 (2 adults, 1 adolescent, 1 child)
Exposure Frequency	days/yr	-		-		365	Averaged over the year	365	Averaged over the year	365	Averaged over the year
Fraction of Total Fish Ingested	unitless	-		-		1	Professional judgment	1	Professional judgment	1	Professional judgment

TABLE 14
HUMAN HEALTH EXPOSURE ASSUMPTIONS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Notes:

cm² = square centimeter

kg = kilogram

L = liter

m³ = cubic meter

mg = milligram

yr = year

IDNR 2013. Summary of 2012-2013 Illinois Deer Seasons. Illinois Department of Natural Resources. <http://www.dnr.illinois.gov/hunting/deer/Documents/IllinoisDeerHarvestReportFinal.2012.2013.pdf>

USEPA 1989 Risk Assessment Guidance for Superfund (RAGS). Volume I, Part A.

USEPA. 1991b. Risk Assessment Guidance for Superfund, Volume I, Human Health Evaluation Manual, Supplemental Guidance "Standard Default Exposure Factors." Interim Final. OSWER Directive: 9285.6-03. Office of Solid Waste and Emergency Response, Washington, DC. March.

USEPA 2002. Supplemental Guidance for Developing Soil Screening Levels for Superfund Sites. OSWER 9355.4-24. Office of Emergency and Remedial Response. Washington DC. December.

USEPA. 2004. Risk Assessment Guidance for Superfund (RAGS), Volume I: Human Health Evaluation Manual, Part E, Supplemental Guidance for Dermal Risk Assessment. EPA/540/R/99/005. U.S. Environmental Protection Agency, Office of Emergency and Remedial Response. July.

USEPA 2011. Exposure Factors Handbook 2011 Edition (Final). EPA/600/R-09/052F. Office of Research and Development. Washington, DC. 2011.

**TABLE 15
EXPOSURE POINT CONCENTRATION SUMMARY - SITE SOIL⁽¹⁾
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Medium: Soil
Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (2)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
WholeSite	SVOCs								
	Fluoranthene	mg/kg	9.0E+00	1.2E+01	4.9E+03	1.E+01	mg/kg	95 th UCL	UCL < Max
	Naphthalene	mg/kg	8.0E-01	1.4E+00	6.8E+02	1.E+00	mg/kg	95 th UCL	UCL < Max
	Pentachlorophenol	mg/kg	2.8E+00	4.3E+00	1.9E+02	4.E+00	mg/kg	95 th UCL	UCL < Max
	Pyrene	mg/kg	9.8E+00	1.3E+01	2.5E+03	1.E+01	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	9.1E+00	1.2E+01	7.0E+02	1.E+01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	9.4E+00	1.1E+01	6.4E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.9E+01	2.3E+01	1.6E+02	2.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	1.2E-03	1.8E-03	3.6E-02	2.E-03	mg/kg	95 th UCL	UCL < Max

Notes:

(1) The Site consists of the western, central, southern, and eastern conservation exposure areas as well as the non-gravel and gravel proposed solar use areas shown on Figure 1.

(2) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

mg/kg = milligrams per kilogram

SVOCs = semi-volatile organic compounds

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

TABLE 16
EXPOSURE POINT CONCENTRATION SUMMARY - PROPOSED SOLAR USE AREA SOIL⁽¹⁾
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current
Medium: Soil
Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (2)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Solar Area	SVOCs								
	Fluoranthene	mg/kg	7.2E+00	1.0E+01	3.8E+02	1.E+01	mg/kg	95 th UCL	UCL < Max
	Naphthalene	mg/kg	4.6E-01	1.2E+00	2.4E+02	1.E+00	mg/kg	95 th UCL	UCL < Max
	Pentachlorophenol	mg/kg	1.2E+00	2.2E+00	8.9E+01	2.E+00	mg/kg	95 th UCL	UCL < Max
	Pyrene	mg/kg	8.4E+00	1.2E+01	2.2E+02	1.E+01	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	7.0E+00	9.6E+00	7.8E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	6.5E+00	7.9E+00	6.4E+01	8.E+00	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.3E+01	1.9E+01	1.6E+02	2.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	3.4E-04	6.0E-04	2.6E-02	6.E-04	mg/kg	95 th UCL	UCL < Max

Notes:

(1) Proposed Solar Use Area shown in orange (non-gravel area) and yellow (gravel area) on Figure 1.

(2) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

TABLE 17
EXPOSURE POINT CONCENTRATION SUMMARY - FUTURE PROPOSED SOLAR USE AREA SOIL⁽¹⁾
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Future
 Medium: Soil
 Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (2)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Solar Area	SVOCs								
	Fluoranthene	mg/kg	5.3E+00	7.4E+00	3.4E+01	7.E+00	mg/kg	95 th UCL	UCL < Max
	Naphthalene	mg/kg	2.5E-01	3.4E-01	2.3E+00	3.E-01	mg/kg	95 th UCL	UCL < Max
	Pentachlorophenol	mg/kg	5.2E-01	8.9E-01	7.1E+01	9.E-01	mg/kg	95 th UCL	UCL < Max
	Pyrene	mg/kg	6.4E+00	9.0E+00	4.3E+01	9.E+00	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	5.2E+00	7.3E+00	6.8E+01	7.E+00	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	4.8E+00	6.1E+00	6.4E+01	6.E+00	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	7.2E+00	1.2E+01	1.6E+02	1.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	1.2E-04	2.9E-04	2.0E-02	3.E-04	mg/kg	95 th UCL	UCL < Max

Notes:

(1) Future Proposed Solar Use Area assumes a portion of the Solar Use Area is covered with gravel (shown in yellow on Figure 1) and a portion is uncovered (shown in orange on Figure 1).

(2) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

Assumes a portion of the proposed solar use area is covered with gravel during construction.

TABLE 18
EXPOSURE POINT CONCENTRATION SUMMARY - SOUTHERN CONSERVATION EXPOSURE AREA SOIL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
 Medium: Soil
 Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Southern Area	SVOCs								
	Fluoranthene	mg/kg	2.8E+01	3.6E+01	3.8E+02	4.E+01	mg/kg	95 th UCL	UCL < Max
	Naphthalene	mg/kg	2.4E+00	5.8E+00	2.4E+02	6.E+00	mg/kg	95 th UCL	UCL < Max
	Pentachlorophenol	mg/kg	1.1E+01	9.3E+00	1.4E+02	9.E+00	mg/kg	95 th UCL	UCL < Max
	Pyrene	mg/kg	3.1E+01	4.0E+01	2.2E+02	4.E+01	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	2.6E+01	3.2E+01	1.1E+02	3.E+01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	1.4E+01	1.6E+01	3.8E+01	2.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	4.1E+01	5.1E+01	7.8E+01	5.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	5.6E-03	8.0E-03	2.6E-02	8.E-03	mg/kg	95 th UCL	UCL < Max

Notes:

(1) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

TABLE 19
EXPOSURE POINT CONCENTRATION SUMMARY - RAILROAD PROPERTY SOIL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
Medium: Soil
Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Railroad Property	SVOCs								
	Fluoranthene	mg/kg	1.3E+02	3.7E+02	4.3E+03	4.E+02	mg/kg	95 th UCL	UCL < Max
	Naphthalene	mg/kg	1.6E+00	4.2E+00	4.6E+01	4.E+00	mg/kg	95 th UCL	UCL < Max
	Pentachlorophenol	mg/kg	1.3E+01	4.3E+01	4.4E+02	4.E+01	mg/kg	95 th UCL	UCL < Max
	Pyrene	mg/kg	8.5E+01	2.5E+02	2.9E+03	3.E+02	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	1.2E+01	2.7E+01	2.8E+02	3.E+01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	1.1E+01	1.3E+01	3.6E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.6E+01	1.8E+01	2.1E+01	2.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	6.9E-04	1.2E-03	7.6E-03	1.E-03	mg/kg	95 th UCL	UCL < Max

Notes:

(1) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

TABLE 20
EXPOSURE POINT CONCENTRATION SUMMARY - 35' SWATH PROPERTY SOIL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
 Medium: Soil
 Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
35' Swath	SVOCs								
	Pentachlorophenol	mg/kg	1.8E-01	5.2E-01	3.2E+00	5.E-01	mg/kg	95 th UCL	UCL < Max
	BaP-TE	mg/kg	2.2E+00	4.7E+00	9.9E+00	5.E+00	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	1.1E+01	1.2E+01	1.3E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.7E+01	1.9E+01	2.1E+01	2.E+01	mg/kg	95 th UCL	UCL < Max
	Dioxins/Furans								
	TCDD-TEQ	mg/kg	7.3E-04	1.9E-03	7.6E-03	2.E-03	mg/kg	95 th UCL	UCL < Max

Notes:

(1) Spatially-weighted 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

**TABLE 21
EXPOSURE POINT CONCENTRATION SUMMARY - SOIL NORTH AND WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Medium: Soil
Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
North & West of the Site	SVOCs								
	BaP-TE	mg/kg	3.7E-01	1.2E+00	1.7E+00	1.E+00	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	1.0E+01	1.1E+01	1.3E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.9E+01	2.2E+01	2.8E+01	2.E+01	mg/kg	95 th UCL	UCL < Max

Notes:

(1) ProUCL version 5.0 used to calculate 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TABLE 22
EXPOSURE POINT CONCENTRATION SUMMARY - SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
Medium: Soil
Exposure Medium: Soil

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
East of the Site	SVOCs								
	BaP-TE	mg/kg	1.7E-01	2.1E-01	2.4E-01	2.E-01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	7.5E+00	8.2E+00	9.4E+00	8.E+00	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	2.0E+01	2.3E+01	2.7E+01	2.E+01	mg/kg	95 th UCL	UCL < Max
Dioxins/Furans									
TCDD-TEQ	mg/kg	5.9E-05	NA	1.7E-04	2.E-04	mg/kg	95 th UCL	UCL < Max	

Notes:

(1) ProUCL version 5.0 used to calculate 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

NA = not available

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

TABLE 23
EXPOSURE POINT CONCENTRATION SUMMARY - SEDIMENT NORTH AND WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
 Medium: Sediment
 Exposure Medium: Sediment

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
North & West of the Site	SVOCs								
	BaP-TE	mg/kg	7.3E-01	1.0E+00	2.6E+00	1.E+00	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	1.2E+01	1.6E+01	2.9E+01	2.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	2.2E+01	2.8E+01	6.1E+01	3.E+01	mg/kg	95 th UCL	UCL < Max

Notes:

(1) ProUCL version 5.0 used to calculate 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

**TABLE 24
EXPOSURE POINT CONCENTRATION SUMMARY - SEDIMENT EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
 Medium: Sediment
 Exposure Medium: Sediment

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Crab Orchard Creek & Piles Fork	SVOCs								
	BaP-TE	mg/kg	4.1E+00	3.2E+01	3.7E+01	3.E+01	mg/kg	95 th UCL	UCL < Max
	Metals								
	Arsenic	mg/kg	8.9E+00	1.0E+01	1.7E+01	1.E+01	mg/kg	95 th UCL	UCL < Max
	Chromium	mg/kg	1.6E+01	1.7E+01	2.3E+01	2.E+01	mg/kg	95 th UCL	UCL < Max

Notes:

(1) ProUCL version 5.0 used to calculate 95th percentile upper confidence limits (UCLs) on the mean.

SVOCs = semi-volatile organic compounds

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

**TABLE 25
EXPOSURE POINT CONCENTRATION SUMMARY - OFF-SITE SURFACE WATER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
 Medium: Surface Water
 Exposure Medium: Surface Water

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic	Rationale
Crab Orchard Creek & Piles Fork	SVOCs								
	Acenaphthene	ug/L	0.185	NA	2.4E-01	2.4E-01	ug/L	Maximum	Not enough data to develop a 95 th UCL
	Anthracene	ug/L	0.235	NA	2.7E-01	2.7E-01	ug/L	Maximum	
	Fluoranthene	ug/L	0.296	NA	3.8E-01	3.8E-01	ug/L	Maximum	
	Fluorene	ug/L	0.253	NA	4.4E-01	4.4E-01	ug/L	Maximum	
	Pentachlorophenol	ug/L	0.568	NA	7.6E-01	7.6E-01	ug/L	Maximum	
	Pyrene	ug/L	0.0781	NA	7.4E-02	7.4E-02	ug/L	Maximum	
	Metals								
	Arsenic	ug/L	3.09	NA	4.1E+00	4.1E+00	ug/L	Maximum	Not enough data to develop a 95 th UCL
	Chromium	ug/L	1.85	NA	1.8E+00	1.8E+00	ug/L	Maximum	
Copper	ug/L	2.40	NA	2.9E+00	2.9E+00	ug/L	Maximum		

Notes:

SVOCs = semi-volatile organic compounds

ug/L = micrograms per liter

NA = not available

95th UCL = 95th percentile upper confidence limit

**TABLE 26
EXPOSURE POINT CONCENTRATION SUMMARY - OFF-SITE FISH
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Medium: Fish Tissue
Exposure Medium: Fish Tissue

Exposure Point	Compound of Potential Concern	Units	Arithmetic Mean	95% UCL (1)	Maximum Concentration	Exposure Point Concentration			
						Value	Units	Statistic (3)	Rationale
Crab Orchard Creek & Piles Fork	SVOCs								
	Acenaphthene	mg/kg ww	1.5E-02	NA	2.2E-02	2.2E-02	mg/kg ww	Maximum	Not enough data to develop a 95 th UCL
	Anthracene	mg/kg ww	4.8E-03	NA	7.7E-03	7.7E-03	mg/kg ww	Maximum	
	BaP-TE	mg/kg ww	2.3E-03	NA	5.3E-03	5.3E-03	mg/kg ww	Maximum	
	Fluoranthene	mg/kg ww	1.5E-02	NA	2.0E-02	2.0E-02	mg/kg ww	Maximum	
	Fluorene	mg/kg ww	9.7E-03	NA	1.5E-02	1.5E-02	mg/kg ww	Maximum	
	Phenol	mg/kg ww	5.4E-03	NA	8.1E-03	8.1E-03	mg/kg ww	Maximum	
	Metals								
	Arsenic	mg/kg ww	1.4E-01	NA	1.8E-01	1.8E-01	mg/kg ww	Maximum	Not enough data to develop a 95 th UCL
	Chromium	mg/kg ww	1.5E-02	NA	3.0E-02	3.0E-02	mg/kg ww	Maximum	
	Copper	mg/kg ww	3.3E-01	NA	4.3E-01	4.3E-01	mg/kg ww	Maximum	
	Dioxins/Furans								
	TCDD-TEQ	mg/kg ww	2.1E-07	NA	3.1E-07	3.1E-07	mg/kg ww	Maximum	Not enough data to develop a 95 th UCL

Notes:

SVOCs = semi-volatile organic compounds

mg/kg ww = milligrams per kilogram wet weight

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

95th UCL = 95th percentile upper confidence limit

**TABLE 27
EXPOSURE POINT CONCENTRATION SUMMARY - DEER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Medium: Soil
Exposure Medium: Deer Tissue

Exposure Point	Compound of Potential Concern	On-Site Soil EPC (1)	Units	Plant-Soil Bioconcentration Factor for Forage (2)	Above Ground Forage Concentration Due to Root Uptake (2), (3)	Biotransfer Factor for Deer (2), (4)	Metabolism Factor (2)	Concentration in Deer (5)	Units	Exposure Point Concentration				
										Value	Units	Statistic	Rationale	
Site	SVOCs													
	Fluoranthene	1.2E+01	mg/kg	4.5E-02	1.0E+01	3.1E-03	1.0E+00	8.5E-03	mg/kg ww	8.5E-03	mg/kg ww	95 th UCL	UCL < Max	
	Naphthalene	1.4E+00	mg/kg	4.4E-01	1.5E+01	5.9E-05	1.0E+00	2.4E-04	mg/kg ww	2.4E-04	mg/kg ww	95 th UCL	UCL < Max	
	Pentachlorophenol	4.3E+00	mg/kg	4.5E-02	1.6E+00	3.0E-03	1.0E+00	1.3E-03	mg/kg ww	1.3E-03	mg/kg ww	95 th UCL	UCL < Max	
	Pyrene	1.3E+01	mg/kg	5.0E-02	6.2E+00	2.5E-03	1.0E+00	4.3E-03	mg/kg ww	4.3E-03	mg/kg ww	95 th UCL	UCL < Max	
	BaP-TE	1.2E+01	mg/kg	1.3E-02	1.6E-01	3.8E-02	1.0E+00	3.9E-03	mg/kg ww	3.9E-03	mg/kg ww	95 th UCL	UCL < Max	
	Metals													
	Arsenic	1.1E+01	mg/kg	3.6E-02	4.6E-01	2.0E-03	1.0E+00	3.5E-04	mg/kg ww	3.5E-04	mg/kg ww	95 th UCL	UCL < Max	
	Chromium	2.3E+01	mg/kg	7.5E-03	3.6E-01	5.5E-03	1.0E+00	1.2E-03	mg/kg ww	1.2E-03	mg/kg ww	95 th UCL	UCL < Max	
	Dioxins/Furans													
	TCDD-TEQ	1.8E-03	mg/kg	4.6E-03	3.7E-08	2.6E-02	1.0E+00	2.4E-07	mg/kg ww	2.4E-07	mg/kg ww	95 th UCL	UCL < Max	

Notes:

(1) On-Site soil EPC shown in Table 15.

(2) HHRAP 2005.

(3) Concentration in Plant = Concentration in Soil x Plant-Soil Bioconcentration Factor for Forage

(4) Beef cattle used as a surrogate for deer.

(5) Concentration in Deer = ((Fraction of Plant Grown on Site Soil and Ingested by the Deer x Quantity of Plant Ingested by the Deer per Day x Concentration in Plant) + Quantity of Soil Ingested by the Deer per Day x Soil Concentration x Soil Bioavailability Factor) x Biotransfer Factor for Deer. Quantity of forage ingested by the animal per day (kg DW/d) = 0.261 (Sample, 1994 with wet weight conversion from EcoSSL guidance). Quantity of soil ingested by the animal per day (kg/d) = 0.00522 (Sample 1994)

EPC = exposure point concentration

mg/kg = milligrams per kilogram

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg ww - milligrams per kilogram wet weight

95th UCL = 95th percentile upper confidence limit

TABLE 28
NON-CANCER TOXICITY DATA -- ORAL/DERMAL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

CAS Number	Compound of Potential Concern (2), (3), (4)	Chronic/ Subchronic	Oral RfD		Oral Absorption Efficiency for Dermal (1)	Absorbed RfD for Dermal		Primary Target Organ(s)	Combined Uncertainty/Modifying Factors	RfD:Target Organ(s)	
			Value	Units		Value	Units			Source(s)	Date(s) (MM/DD/YYYY)
SVOCs											
83-32-9	Acenaphthene	subchronic	2.0E-01	mg/kg/day	1	2.0E-01	mg/kg/day	Liver	1000	PPRTV	4/6/2011
83-32-9	Acenaphthene	chronic	6.0E-02	mg/kg/day	1	6.0E-02	mg/kg/day	Liver	3000	IRIS	4/1/1994
120-12-7	Anthracene	subchronic	1.0E+00	mg/kg/day	1	1.0E+00	mg/kg/day	None	1000	PPRTV	6/15/2009
120-12-7	Anthracene	chronic	3.0E-01	mg/kg/day	1	3.0E-01	mg/kg/day	None	3000	IRIS	7/1/1993
50-32-8	BaP-TE	subchronic	NA			NA					
50-32-8	BaP-TE	chronic	NA			NA					
206-44-0	Fluoranthene	subchronic	1.0E-01	mg/kg/day	1	1.0E-01	mg/kg/day	Kidney	1000	PPRTV	12/27/2012
206-44-0	Fluoranthene	chronic	4.0E-02	mg/kg/day	1	4.0E-02	mg/kg/day	Kidney, liver, hematological	3000	IRIS	7/1/1993
86-73-7	Fluorene	subchronic	4.0E-02	mg/kg/day	1	4.0E-02	mg/kg/day	Hematological	3000	IRIS, chronic	11/1/1990
86-73-7	Fluorene	chronic	4.0E-02	mg/kg/day	1	4.0E-02	mg/kg/day	Hematological	3000	IRIS	11/1/1990
91-20-3	Naphthalene	subchronic	2.0E-02	mg/kg/day	1	2.0E-02	mg/kg/day	Body weight	3000	IRIS, chronic	9/17/1998
91-20-3	Naphthalene	chronic	2.0E-02	mg/kg/day	1	2.0E-02	mg/kg/day	Body weight	3000	IRIS	9/17/1998
87-86-5	Pentachlorophenol	subchronic	5.0E-03	mg/kg/day	1	5.0E-03	mg/kg/day	Liver	300	IRIS, chronic	9/30/2010
87-86-5	Pentachlorophenol	chronic	5.0E-03	mg/kg/day	1	5.0E-03	mg/kg/day	Liver	300	IRIS	9/30/2010
108-95-2	Phenol	subchronic	3.0E-01	mg/kg/day	1	3.0E-01	mg/kg/day	Reproductive	300	IRIS, chronic	9/30/2002
108-95-2	Phenol	chronic	3.0E-01	mg/kg/day	1	3.0E-01	mg/kg/day	Reproductive	300	IRIS	9/30/2002
129-00-0	Pyrene	subchronic	3.0E-01	mg/kg/day	1	3.0E-01	mg/kg/day	None	300	PPRTV	9/5/2007
129-00-0	Pyrene	chronic	3.0E-02	mg/kg/day	1	3.0E-02	mg/kg/day	Kidney	3000	IRIS	7/1/1993
Metals											
7440-38-2	Arsenic	subchronic	3.0E-04	mg/kg/day	1	3.0E-04	mg/kg/day	Skin, hair	3	IRIS, chronic	2/1/1993
7440-38-2	Arsenic	chronic	3.0E-04	mg/kg/day	1	3.0E-04	mg/kg/day	Skin, hair	3	IRIS	2/1/1993
7440-47-3	Chromium	subchronic	1.5E+00	mg/kg/day	0.025	3.8E-02	mg/kg/day	None	100	IRIS, chronic	9/3/1998
7440-47-3	Chromium	chronic	1.5E+00	mg/kg/day	0.025	3.8E-02	mg/kg/day	None	100	IRIS	9/3/1998
7440-50-8	Copper	subchronic	4.0E-02	mg/kg/day	1	4.0E-02	mg/kg/day	GI	NA	HEAST	7/31/1997
7440-50-8	Copper	chronic	4.0E-02	mg/kg/day	1	4.0E-02	mg/kg/day	GI	NA	HEAST	7/31/1997
Dioxins/Furans											
1746-01-6	TCDD-TEQ	subchronic	7.0E-10	mg/kg/day	1	7.0E-10	mg/kg/day	Reproductive	30	IRIS, chronic	2/17/2012
1746-01-6	TCDD-TEQ	chronic	7.0E-10	mg/kg/day	1	7.0E-10	mg/kg/day	Reproductive	30	IRIS	2/17/2012

Notes:
(1) Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment), July 2004, EPA/540/R/99/005. If not available, assumed to be 100%
RfD = reference dose
HEAST = Health Effect Assessment Summary Tables, <http://cfpub.epa.gov/ncea/cfm/recordisplay.cfm?deid=2877#Download>
IRIS = Integrated Risk Information System; <http://www.epa.gov/iris>
PPRTV = Provisional Peer Reviewed Toxicity Values; <http://hhpprtv.onrl.gov>
GI = gastrointestinal tract
mg/kg/day = milligrams per kilogram per day
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
NA = not available

**TABLE 29
NON-CANCER TOXICITY DATA -- INHALATION
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS Number	Compound of Potential Concern	Chronic/ Subchronic	Inhalation RfC		Primary Target Organ(s)	Combined Uncertainty/Modifying Factors	RfC : Target Organ(s)	
			Value	Units			Source(s)	Date(s) (MM/DD/YYYY)
SVOCs								
50-32-8	BaP-TE	subchronic	NA					
50-32-8	BaP-TE	chronic	NA					
206-44-0	Fluoranthene	subchronic	NA					
206-44-0	Fluoranthene	chronic	NA					
91-20-3	Naphthalene	subchronic	3.0E-03	mg/m ³	Respiratory		IRIS, chronic	9/17/1998
91-20-3	Naphthalene	chronic	3.0E-03	mg/m ³	Respiratory		IRIS	9/17/1998
87-86-5	Pentachlorophenol	subchronic	NA					
87-86-5	Pentachlorophenol	chronic	NA					
129-00-0	Pyrene	subchronic	NA					
129-00-0	Pyrene	chronic	NA					
Metals								
7440-38-2	Arsenic	subchronic	1.5E-05	mg/m ³	Development, cardiovascular, nervous system, respiratory system, skin	NA	CalEPA, chronic	June 2014
7440-38-2	Arsenic	chronic	1.5E-05	mg/m ³	Development, cardiovascular, nervous system, respiratory system, skin	NA	CalEPA	June 2014
7440-47-3	Chromium	subchronic	NA					
7440-47-3	Chromium	chronic	NA					
7440-50-8	Copper	subchronic	NA					
7440-50-8	Copper	chronic	NA					
Dioxins/Furans								
1746-01-6	TCDD-TEQ	subchronic	4.0E-08	mg/m ³	Liver, reproductive, endocrine, respiratory, hematologic, development	NA	CalEPA, chronic	June 2014
1746-01-6	TCDD-TEQ	chronic	4.0E-08	mg/m ³	Liver, reproductive, endocrine, respiratory, hematologic, development	NA	CalEPA	June 2014

Notes:

NA =not available

Cal EPA = California Environmental Protection Agency, Office of Environmental Health Hazard Assessment, Inhalation Reference Exposure Levels,

<http://www.oehha.ca.gov/air/allrels.html>

IRIS = Integrated Risk Information System; <http://www.epa.gov/iris>

mg/m³ = milligrams per cubic meter

RfC = reference concentration

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

**TABLE 30
CANCER TOXICITY DATA -- ORAL/DERMAL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS Number	Compound of Potential Concern	Oral Cancer Slope Factor		Oral Absorption Efficiency for Dermal (1)	Absorbed Cancer Slope Factor for Dermal		Weight of Evidence/ Cancer Guideline Description (2)	Oral CSF	
		Value	Units		Value	Units		Source(s)	Date(s) (MM/DD/YYYY)
SVOCs									
83-32-9	Acenaphthene	NA			NA				
120-12-7	Anthracene	NA			NA				
50-32-8	BaP-TE	7.3E+00	(mg/kg-day) ⁻¹	1	7.3E+00	(mg/kg-day) ⁻¹	B2	IRIS, Benzo(a)pyrene	11/1/1994
191-24-2	Benzo(ghi)perylene	NA			NA				
206-44-0	Fluoranthene	NA			NA				
86-73-7	Fluorene	NA			NA				
91-20-3	Naphthalene	NA			NA				
87-86-5	Pentachlorophenol	4.0E-01	(mg/kg-day) ⁻¹	1	4.0E-01	(mg/kg-day) ⁻¹	Likely to be carcinogenic to humans	IRIS	9/30/2010
108-95-2	Phenol	NA			NA				
129-00-0	Pyrene	NA			NA				
Metals									
7440-38-2	Arsenic	1.5E+00	(mg/kg-day) ⁻¹	1	1.5E+00	(mg/kg-day) ⁻¹	A	IRIS	4/10/1998
7440-47-3	Chromium	5.0E-01	(mg/kg-day) ⁻¹	0.025	2.0E+01	(mg/kg-day) ⁻¹	D	IRIS	9/3/1998
7440-50-8	Copper	NA			NA				
Dioxins/Furans									
1746-01-6	TCDD-TEQ	1.3E+05	(mg/kg-day) ⁻¹	1	1.3E+05	(mg/kg-day) ⁻¹	NA	CalEPA	7/21/2009

Notes:

(1) Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment), July 2004, EPA/540/R/99/005. If not available, assumed to be 100%.

(2) USEPA (1986) cancer weight-of-evidence categories are as follows

Group A: Carcinogenic to Humans (sufficient evidence of carcinogenicity)

Group B: Probably Carcinogenic to Humans

B1 - limited evidence of carcinogenicity in humans

B2 - sufficient evidence of carcinogenicity in animals with inadequate or lack of evidence in humans

Group C: Possible Human Carcinogen (limited evidence of carcinogenicity in animals and inadequate or lack of human data)

Group D: Not Classifiable as to Human Carcinogenicity (inadequate or no evidence)

Cal EPA = California Environmental Protection Agency, Office of Environmental Health Hazard Assessment, Cancer Potency Values, <http://www.oehha.ca.gov/risk/pdf/tcdb072109alpha.pdf>

IRIS = Integrated Risk Information System; <http://www.epa.gov/iris>

CSF = cancer slope factor

(mg/kg-day)⁻¹ = per milligram per kilogram per day

NA = not available

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

**TABLE 31
CANCER TOXICITY DATA -- INHALATION
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS Number	Compound of Potential Concern	Unit Risk		Weight of Evidence/ Cancer Guideline Description (1)	Unit Risk : Inhalation CSF	
		Value	Units		Source(s)	Date(s) (MM/DD/YYYY)
SVOCs						
83-32-9	Acenaphthene	NA				
120-12-7	Anthracene	NA				
50-32-8	BaP-TE	1.1E-03	(ug/m ³) ⁻¹	NA	CalEPA, Benzo(a)pyrene	7/21/2009
206-44-0	Fluoranthene	NA				
86-73-7	Fluorene	NA				
91-20-3	Naphthalene	3.4E-05	(ug/m ³) ⁻¹	NA	CalEPA	7/21/2009
87-86-5	Pentachlorophenol	5.1E-06	(ug/m ³) ⁻¹	NA	CalEPA	7/21/2009
108-95-2	Phenol	NA				
129-00-0	Pyrene	NA				
Metals						
7440-38-2	Arsenic	4.3E-03	(ug/m ³) ⁻¹	A	IRIS	4/10/1998
7440-47-3	Chromium	8.4E-02	(ug/m ³) ⁻¹	D	IRIS	9/3/1998
7440-50-8	Copper	NA				
Dioxins/Furans						
1746-01-6	TCDD-TEQ	3.8E+01	(ug/m ³) ⁻¹	NA	CalEPA	7/21/2009

Notes:

(1) USEPA (1986) cancer weight-of-evidence categories are as follows

Group A: Carcinogenic to Humans (sufficient evidence of carcinogenicity in humans)

Group B: Probably Carcinogenic to Humans

B1 - limited evidence of carcinogenicity in humans

B2 - sufficient evidence of carcinogenicity in animals with inadequate or lack of evidence in humans

Group C: Possible Human Carcinogen (limited evidence of carcinogenicity in animals and inadequate or lack of human data)

Group D: Not Classifiable as to Human Carcinogenicity (inadequate or no evidence)

Cal EPA = California Environmental Protection Agency, Office of Environmental Health Hazard Assessment, Cancer Potency Values, <http://www.oehha.ca.gov/risk/pdf/tcdb072109alpha.pdf>

IRIS = Integrated Risk Information System; <http://www.epa.gov/iris>

CSF = cancer slope factor

NA = not available

(ug/m³)⁻¹ = per microgram per cubic meter

BaP-TE = benzo(a)pyrene toxic equivalents

TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

**TABLE 32
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADULT MAINTENANCE WORKER/CARETAKER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Maintenance Worker/Caretaker
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations								
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ				
							Value	Units	Value	Units		Value	Units	Value	Units					
Soil	Surface Soil	Site	Ingestion	SVOCs																
				BaP-TE	1.2E+01	mg/kg	2.1E-06	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.5E-05	5.8E-06	mg/kg-day	NA	NA	NA				
				Fluoranthene	1.2E+01	mg/kg	2.1E-06	mg/kg-day	NA	NA	NA	5.8E-06	mg/kg-day	4.0E-02	mg/kg-day	1E-04				
				Naphthalene	1.4E+00	mg/kg	2.4E-07	mg/kg-day	NA	NA	NA	6.7E-07	mg/kg-day	2.0E-02	mg/kg-day	3E-05				
				Pentachlorophenol	4.3E+00	mg/kg	7.5E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.0E-07	2.1E-06	mg/kg-day	5.0E-03	mg/kg-day	4E-04				
				Pyrene	1.3E+01	mg/kg	2.2E-06	mg/kg-day	NA	NA	NA	6.2E-06	mg/kg-day	3.0E-02	mg/kg-day	2E-04				
				Metals																
				Arsenic	1.1E+01	mg/kg	1.9E-06	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.8E-06	5.2E-06	mg/kg-day	3.0E-04	mg/kg-day	2E-02				
				Chromium	2.3E+01	mg/kg	4.0E-06	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	2.0E-06	1.1E-05	mg/kg-day	1.5E+00	mg/kg-day	8E-06				
				Dioxins/Furans																
				TCDD-TEQ	1.8E-03	mg/kg	3.1E-10	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	4.0E-05	8.7E-10	mg/kg-day	7.0E-10	mg/kg-day	1E+00				
				Exp. Route Total							6E-05					1E+00				
				Dermal																
				SVOCs																
				BaP-TE	1.2E+01	mg/kg	1.8E-06	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.3E-05	5.0E-06	mg/kg-day	NA	NA	NA				
				Fluoranthene	1.2E+01	mg/kg	1.8E-06	mg/kg-day	NA	NA	NA	5.0E-06	mg/kg-day	4.0E-02	mg/kg-day	1E-04				
				Naphthalene	1.4E+00	mg/kg	2.0E-07	mg/kg-day	NA	NA	NA	5.7E-07	mg/kg-day	2.0E-02	mg/kg-day	3E-05				
				Pentachlorophenol	4.3E+00	mg/kg	6.5E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.6E-07	1.8E-06	mg/kg-day	5.0E-03	mg/kg-day	4E-04				
				Pyrene	1.3E+01	mg/kg	1.9E-06	mg/kg-day	NA	NA	NA	5.4E-06	mg/kg-day	3.0E-02	mg/kg-day	2E-04				
				Metals																
				Arsenic	1.1E+01	mg/kg	3.7E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	5.5E-07	1.0E-06	mg/kg-day	3.0E-04	mg/kg-day	3E-03				
				Chromium	2.3E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00				
				Dioxins/Furans																
				TCDD-TEQ	1.8E-03	mg/kg	6.1E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	8.0E-06	1.7E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01				
				Exp. Route Total							2E-05					2E-01				
				Exposure Point Total							8E-05					2E+00				
				Exposure Medium Total							8E-05					2E+00				
				Soil	Dust	Site	Inhalation	SVOCs												
BaP-TE	9.6E-06	ug/m ³	3.9E-07					ug/m ³	1.1E-03	(ug/m ³) ⁻¹	4.3E-10	1.1E-06	ug/m ³	NA	NA	NA				
Fluoranthene	9.5E-06	ug/m ³	3.9E-07					ug/m ³	NA	NA	NA	1.1E-06	ug/m ³	NA	NA	NA				
Naphthalene	1.1E-06	ug/m ³	4.5E-08					ug/m ³	3.4E-05	(ug/m ³) ⁻¹	1.5E-12	1.3E-07	ug/m ³	3.0E-03	mg/m ³	4E-08				
Pentachlorophenol	3.5E-06	ug/m ³	1.4E-07					ug/m ³	5.1E-06	(ug/m ³) ⁻¹	7.2E-13	4.0E-07	ug/m ³	NA	NA	NA				
Pyrene	1.0E-05	ug/m ³	4.2E-07					ug/m ³	NA	NA	NA	1.2E-06	ug/m ³	NA	NA	NA				
Metals																				
Arsenic	8.6E-06	ug/m ³	3.5E-07					ug/m ³	4.3E-03	(ug/m ³) ⁻¹	1.5E-09	9.8E-07	ug/m ³	1.5E-05	mg/m ³	7E-05				
Chromium	1.9E-05	ug/m ³	7.6E-07					ug/m ³	8.4E-02	(ug/m ³) ⁻¹	6.4E-08	2.1E-06	ug/m ³	NA	NA	NA				
Dioxins/Furans																				
TCDD-TEQ	1.4E-09	ug/m ³	5.8E-11					ug/m ³	3.8E+01	(ug/m ³) ⁻¹	2.2E-09	1.6E-10	ug/m ³	4.0E-08	mg/m ³	4E-06				
Exp. Route Total											7E-08					7E-05				
Exposure Point Total											7E-08					7E-05				
Exposure Medium Total											7E-08					7E-05				
Medium Total											8E-05					2E+00				
								Total of Receptor Hazards Across All Media					Total of Receptor Hazards Across All Media							
								8E-05					2E+00							

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 33
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADULT DEER HUNTER AND CONSUMER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Deer Hunter
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Deer Meat	Deer Meat	Site	Ingestion	SVOCs												
				BaP-TE	3.9E-03	mg/kg ww	6.8E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.9E-06	1.6E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	8.5E-03	mg/kg ww	1.5E-06	mg/kg-day	NA	NA	NA	3.4E-06	mg/kg-day	4.0E-02	mg/kg-day	9E-05
				Naphthalene	2.4E-04	mg/kg ww	4.1E-08	mg/kg-day	NA	NA	NA	9.5E-08	mg/kg-day	2.0E-02	mg/kg-day	5E-06
				Pentachlorophenol	1.3E-03	mg/kg ww	2.2E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	9.0E-08	5.2E-07	mg/kg-day	5.0E-03	mg/kg-day	1E-04
				Pyrene	4.3E-03	mg/kg ww	7.3E-07	mg/kg-day	NA	NA	NA	1.7E-06	mg/kg-day	3.0E-02	mg/kg-day	6E-05
				Metals												
				Arsenic	3.5E-04	mg/kg ww	6.1E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	9.1E-08	1.4E-07	mg/kg-day	3.0E-04	mg/kg-day	5E-04
				Chromium	1.2E-03	mg/kg ww	2.0E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.0E-07	4.8E-07	mg/kg-day	1.5E+00	mg/kg-day	3E-07
				Dioxins/Furans												
				TCDD-TEQ	2.4E-07	mg/kg ww	4.2E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	5.4E-06	9.7E-11	mg/kg-day	7.0E-10	mg/kg-day	1E-01
			Exp. Route Total								1E-05					1E-01
		Exposure Point Total									1E-05					1E-01
	Exposure Medium Total										1E-05					1E-01
Medium Total											1E-05					1E-01
											Total of Receptor Hazards Across All Media	1E-05	Total of Receptor Hazards Across All Media		1E-01	

Notes:
 EPC - exposure point concentration HQ = hazard quotient SVOCs = semi-volatile organic compounds mg/kg ww = milligram per kilogram wet weight NA = not available
 CSF = cancer slope factor RfD = reference dose BaP-TE = benzo(a)pyrene toxic equivalents (mg/kg-day)⁻¹ = per milligram per kilogram-day
 PELCR = potential excess lifetime cancer risk RfC = reference concentration TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents mg/kg-day = milligram per kilogram-day

**TABLE 34
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADOLESCENT DEER CONSUMER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Deer Hunter
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Deer Meat	Deer Meat	Site	Ingestion	SVOCs												
				BaP-TE	3.9E-03	mg/kg ww	3.0E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.2E-06	2.1E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	8.5E-03	mg/kg ww	6.5E-07	mg/kg-day	NA	NA	NA	4.6E-06	mg/kg-day	4.0E-02	mg/kg-day	1E-04
				Naphthalene	2.4E-04	mg/kg ww	1.8E-08	mg/kg-day	NA	NA	NA	1.3E-07	mg/kg-day	2.0E-02	mg/kg-day	6E-06
				Pentachlorophenol	1.3E-03	mg/kg ww	1.0E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	4.0E-08	7.0E-07	mg/kg-day	5.0E-03	mg/kg-day	1E-04
				Pyrene	4.3E-03	mg/kg ww	3.3E-07	mg/kg-day	NA	NA	NA	2.3E-06	mg/kg-day	3.0E-02	mg/kg-day	8E-05
				Metals												
				Arsenic	3.5E-04	mg/kg ww	2.7E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	4.1E-08	1.9E-07	mg/kg-day	3.0E-04	mg/kg-day	6E-04
				Chromium	1.2E-03	mg/kg ww	9.1E-08	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	4.5E-08	6.3E-07	mg/kg-day	1.5E+00	mg/kg-day	4E-07
				Dioxins/Furans												
				TCDD-TEQ	2.4E-07	mg/kg ww	1.9E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.4E-06	1.3E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01
			Exp. Route Total								5E-06					2E-01
		Exposure Point Total									5E-06					2E-01
	Exposure Medium Total										5E-06					2E-01
Medium Total											5E-06					2E-01
											Total of Receptor Hazards Across All Media		Total of Receptor Hazards Across All Media		2E-01	

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg ww = milligram per kilogram wet weight
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day
NA = not available

**TABLE 35
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE CHILD DEER CONSUMER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Deer Consumer
Receptor Age: Child

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Deer Meat	Deer Meat	Site	Ingestion	SVOCs												
				BaP-TE	3.9E-03	mg/kg ww	2.5E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.8E-06	3.5E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	8.5E-03	mg/kg ww	5.3E-07	mg/kg-day	NA	NA	NA	7.5E-06	mg/kg-day	1.0E-01	mg/kg-day	7E-05
				Naphthalene	2.4E-04	mg/kg ww	1.5E-08	mg/kg-day	NA	NA	NA	2.1E-07	mg/kg-day	2.0E-02	mg/kg-day	1E-05
				Pentachlorophenol	1.3E-03	mg/kg ww	8.2E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.3E-08	1.1E-06	mg/kg-day	5.0E-03	mg/kg-day	2E-04
				Pyrene	4.3E-03	mg/kg ww	2.7E-07	mg/kg-day	NA	NA	NA	3.7E-06	mg/kg-day	3.0E-01	mg/kg-day	1E-05
				Metals												
				Arsenic	3.5E-04	mg/kg ww	2.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	3.3E-08	3.1E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03
				Chromium	1.2E-03	mg/kg ww	7.4E-08	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	3.7E-08	1.0E-06	mg/kg-day	1.5E+00	mg/kg-day	7E-07
				Dioxins/Furans												
				TCDD-TEQ	2.4E-07	mg/kg ww	1.5E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.0E-06	2.1E-10	mg/kg-day	7.0E-10	mg/kg-day	3E-01
			Exp. Route Total								4E-06					3E-01
		Exposure Point Total									4E-06					3E-01
	Exposure Medium Total										4E-06					3E-01
Medium Total											4E-06					3E-01
Total of Receptor Hazards Across All Media											4E-06	Total of Receptor Hazards Across All Media				3E-01

Notes:

EPC = exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg ww = milligram per kilogram wet weight
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day
NA = not available

**TABLE 36
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADOLESCENT TRESPASSER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Trespasser
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Soil	Surface Soil	Site	Ingestion														
				SVOCs													
				BaP-TE	1.2E+01	mg/kg	1.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.2E-06	1.1E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	1.2E+01	mg/kg	1.6E-07	mg/kg-day	NA	NA	NA	1.1E-06	mg/kg-day	4.0E-02	mg/kg-day	3E-05	
				Naphthalene	1.4E+00	mg/kg	1.8E-08	mg/kg-day	NA	NA	NA	1.3E-07	mg/kg-day	2.0E-02	mg/kg-day	6E-06	
				Pentachlorophenol	4.3E+00	mg/kg	5.8E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.3E-08	4.0E-07	mg/kg-day	5.0E-03	mg/kg-day	8E-05	
				Pyrene	1.3E+01	mg/kg	1.7E-07	mg/kg-day	NA	NA	NA	1.2E-06	mg/kg-day	3.0E-02	mg/kg-day	4E-05	
				Metals													
				Arsenic	1.1E+01	mg/kg	1.4E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.1E-07	1.0E-06	mg/kg-day	3.0E-04	mg/kg-day	3E-03	
				Chromium	2.3E+01	mg/kg	3.1E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.5E-07	2.2E-06	mg/kg-day	1.5E+00	mg/kg-day	1E-06	
				Dioxins/Furans													
				TCDD-TEQ	1.8E-03	mg/kg	2.4E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	3.1E-06	1.7E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01	
			Exp. Route Total								5E-06					2E-01	
			Dermal														
				SVOCs													
				BaP-TE	1.2E+01	mg/kg	2.0E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.5E-06	1.4E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	1.2E+01	mg/kg	2.0E-07	mg/kg-day	NA	NA	NA	1.4E-06	mg/kg-day	4.0E-02	mg/kg-day	4E-05	
				Naphthalene	1.4E+00	mg/kg	2.3E-08	mg/kg-day	NA	NA	NA	1.6E-07	mg/kg-day	2.0E-02	mg/kg-day	8E-06	
				Pentachlorophenol	4.3E+00	mg/kg	7.3E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.9E-08	5.1E-07	mg/kg-day	5.0E-03	mg/kg-day	1E-04	
				Pyrene	1.3E+01	mg/kg	2.2E-07	mg/kg-day	NA	NA	NA	1.5E-06	mg/kg-day	3.0E-02	mg/kg-day	5E-05	
				Metals													
				Arsenic	1.1E+01	mg/kg	4.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	6.3E-08	2.9E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03	
				Chromium	2.3E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
				Dioxins/Furans													
				TCDD-TEQ	1.8E-03	mg/kg	7.0E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	9.1E-07	4.9E-11	mg/kg-day	7.0E-10	mg/kg-day	7E-02	
			Exp. Route Total								2E-06					7E-02	
			Exposure Point Total								7E-06					3E-01	
			Exposure Medium Total								7E-06					3E-01	
Soil	Dust	Site	Inhalation														
				SVOCs													
				BaP-TE	9.6E-06	ug/m3	5.0E-09	ug/m3	1.1E-03	(ug/m ³) ⁻¹	5.5E-12	3.5E-08	ug/m ³	NA	NA	NA	
				Fluoranthene	9.5E-06	ug/m3	5.0E-09	ug/m3	NA	NA	NA	3.5E-08	ug/m ³	NA	NA	NA	
				Naphthalene	1.1E-06	ug/m3	5.7E-10	ug/m3	3.4E-05	(ug/m ³) ⁻¹	2.0E-14	4.0E-09	ug/m ³	3.0E-03	mg/m3	1E-09	
				Pentachlorophenol	3.5E-06	ug/m3	1.8E-09	ug/m3	5.1E-06	(ug/m ³) ⁻¹	9.2E-15	1.3E-08	ug/m ³	NA	NA	NA	
				Pyrene	1.0E-05	ug/m3	5.4E-09	ug/m3	NA	NA	NA	3.8E-08	ug/m ³	NA	NA	NA	
				Metals													
				Arsenic	8.6E-06	ug/m3	4.5E-09	ug/m3	4.3E-03	(ug/m ³) ⁻¹	1.9E-11	3.1E-08	ug/m ³	1.5E-05	mg/m3	2E-06	
				Chromium	1.9E-05	ug/m3	9.7E-09	ug/m3	8.4E-02	(ug/m ³) ⁻¹	8.1E-10	6.8E-08	ug/m ³	NA	NA	NA	
				Dioxins/Furans													
				TCDD-TEQ	1.4E-09	ug/m3	7.5E-13	ug/m3	3.8E+01	(ug/m ³) ⁻¹	2.8E-11	5.2E-12	ug/m ³	4.0E-08	mg/m3	1E-07	
			Exp. Route Total								9E-10					2E-06	
			Exposure Point Total								9E-10					2E-06	
			Exposure Medium Total								9E-10					2E-06	
Medium Total											7E-06					3E-01	
											Total of Receptor Hazards Across All Media		7E-06		Total of Receptor Hazards Across All Media		3E-01

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 37
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADULT HIKERS/BICYCLE TRAIL USERS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Future
Receptor Population: Hikers/Bicycle Trail Users
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations						
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ		
							Value	Units	Value	Units		Value	Units	Value	Units			
Soil	Surface Soil	PMP Area	Ingestion	SVOCs														
				BaP-TE	3.2E+01	mg/kg	1.9E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.4E-06	6.5E-07	mg/kg-day	NA	NA	NA		
				Fluoranthene	3.6E+01	mg/kg	2.1E-07	mg/kg-day	NA	NA	NA	7.3E-07	mg/kg-day	4.0E-02	mg/kg-day	2E-05		
				Naphthalene	5.8E+00	mg/kg	3.4E-08	mg/kg-day	NA	NA	NA	1.2E-07	mg/kg-day	2.0E-02	mg/kg-day	6E-06		
				Pentachlorophenol	9.3E+00	mg/kg	5.4E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.2E-08	1.9E-07	mg/kg-day	5.0E-03	mg/kg-day	4E-05		
				Pyrene	4.0E+01	mg/kg	2.3E-07	mg/kg-day	NA	NA	NA	8.2E-07	mg/kg-day	3.0E-02	mg/kg-day	3E-05		
				Metals														
				Arsenic	1.6E+01	mg/kg	9.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.4E-07	3.2E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03		
				Chromium	5.1E+01	mg/kg	2.9E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.5E-07	1.0E-06	mg/kg-day	1.5E+00	mg/kg-day	7E-07		
				Dioxins/Furans														
				TCDD-TEQ	8.0E-03	mg/kg	4.7E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	6.1E-06	1.6E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01		
				Exp. Route Total							8E-06						2E-01	
							Dermal											
				SVOCs														
				BaP-TE	3.2E+01	mg/kg	9.6E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	7.0E-07	3.4E-07	mg/kg-day	NA	NA	NA		
				Fluoranthene	3.6E+01	mg/kg	1.1E-07	mg/kg-day	NA	NA	NA	3.8E-07	mg/kg-day	4.0E-02	mg/kg-day	9E-06		
				Naphthalene	5.8E+00	mg/kg	1.7E-08	mg/kg-day	NA	NA	NA	6.1E-08	mg/kg-day	2.0E-02	mg/kg-day	3E-06		
				Pentachlorophenol	9.3E+00	mg/kg	2.8E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	1.1E-08	9.8E-08	mg/kg-day	5.0E-03	mg/kg-day	2E-05		
				Pyrene	4.0E+01	mg/kg	1.2E-07	mg/kg-day	NA	NA	NA	4.2E-07	mg/kg-day	3.0E-02	mg/kg-day	1E-05		
				Metals														
				Arsenic	1.6E+01	mg/kg	1.1E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.6E-08	3.8E-08	mg/kg-day	3.0E-04	mg/kg-day	1E-04		
				Chromium	5.1E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00		
				Dioxins/Furans														
				TCDD-TEQ	8.0E-03	mg/kg	5.6E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	7.2E-07	2.0E-11	mg/kg-day	7.0E-10	mg/kg-day	3E-02		
				Exp. Route Total							1E-06						3E-02	
						Exposure Point Total											3E-01	
						Exposure Medium Total											3E-01	
Soil	Dust	PMP Area	Inhalation	SVOCs														
				BaP-TE	2.6E-05	ug/m3	4.4E-08	ug/m3	1.1E-03	(ug/m ³) ⁻¹	4.8E-11	1.5E-07	ug/m ³	NA	NA	NA		
				Fluoranthene	2.9E-05	ug/m3	4.9E-08	ug/m3	NA	NA	NA	1.7E-07	ug/m ³	NA	NA	NA		
				Naphthalene	4.7E-06	ug/m3	7.9E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	2.7E-13	2.8E-08	ug/m ³	3.0E-03	mg/m ³	9E-09		
				Pentachlorophenol	7.5E-06	ug/m3	1.3E-08	ug/m3	5.1E-06	(ug/m ³) ⁻¹	6.5E-14	4.4E-08	ug/m ³	NA	NA	NA		
				Pyrene	3.2E-05	ug/m3	5.5E-08	ug/m3	NA	NA	NA	1.9E-07	ug/m ³	NA	NA	NA		
				Metals														
				Arsenic	1.3E-05	ug/m3	2.2E-08	ug/m3	4.3E-03	(ug/m ³) ⁻¹	9.3E-11	7.5E-08	ug/m ³	1.5E-05	mg/m ³	5E-06		
				Chromium	4.1E-05	ug/m3	6.9E-08	ug/m3	8.4E-02	(ug/m ³) ⁻¹	5.8E-09	2.4E-07	ug/m ³	NA	NA	NA		
				Dioxins/Furans														
				TCDD-TEQ	6.5E-09	ug/m3	1.1E-11	ug/m3	3.8E+01	(ug/m ³) ⁻¹	4.2E-10	3.8E-11	ug/m ³	4.0E-08	mg/m ³	1E-06		
				Exp. Route Total							6E-09						6E-06	
						Exposure Point Total											6E-06	
						Exposure Medium Total											6E-06	
						Total of Receptor Hazards Across All Media											9E-06	
						Total of Receptor Hazards Across All Media											3E-01	

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 38
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE ON-SITE ADOLESCENT HIKERS/BICYCLE TRAIL USERS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Future
Receptor Population: Hikers/Bicycle Trail Users
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations									
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ					
							Value	Units	Value	Units		Value	Units	Value	Units						
Soil	Surface Soil	PMP Area	Ingestion	SVOCs																	
				BaP-TE	3.2E+01	mg/kg	2.8E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.0E-06	1.9E-06	mg/kg-day	NA	NA	NA					
				Fluoranthene	3.6E+01	mg/kg	3.1E-07	mg/kg-day	NA	NA	NA	2.2E-06	mg/kg-day	4.0E-02	mg/kg-day	5E-05					
				Naphthalene	5.8E+00	mg/kg	5.0E-08	mg/kg-day	NA	NA	NA	3.5E-07	mg/kg-day	2.0E-02	mg/kg-day	2E-05					
				Pentachlorophenol	9.3E+00	mg/kg	8.1E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.2E-08	5.6E-07	mg/kg-day	5.0E-03	mg/kg-day	1E-04					
				Pyrene	4.0E+01	mg/kg	3.5E-07	mg/kg-day	NA	NA	NA	2.4E-06	mg/kg-day	3.0E-02	mg/kg-day	8E-05					
				Metals																	
				Arsenic	1.6E+01	mg/kg	1.4E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.1E-07	9.6E-07	mg/kg-day	3.0E-04	mg/kg-day	3E-03					
				Chromium	5.1E+01	mg/kg	4.4E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	2.2E-07	3.1E-06	mg/kg-day	1.5E+00	mg/kg-day	2E-06					
				Dioxins/Furans																	
				TCDD-TEQ	8.0E-03	mg/kg	7.0E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	9.1E-06	4.9E-10	mg/kg-day	7.0E-10	mg/kg-day	7E-01					
				Exp. Route Total							1E-05						7E-01				
			Dermal	SVOCs																	
				BaP-TE	3.2E+01	mg/kg	1.8E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.3E-06	1.2E-06	mg/kg-day	NA	NA	NA					
				Fluoranthene	3.6E+01	mg/kg	2.0E-07	mg/kg-day	NA	NA	NA	1.4E-06	mg/kg-day	4.0E-02	mg/kg-day	3E-05					
				Naphthalene	5.8E+00	mg/kg	3.2E-08	mg/kg-day	NA	NA	NA	2.2E-07	mg/kg-day	2.0E-02	mg/kg-day	1E-05					
				Pentachlorophenol	9.3E+00	mg/kg	5.1E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.0E-08	3.6E-07	mg/kg-day	5.0E-03	mg/kg-day	7E-05					
				Pyrene	4.0E+01	mg/kg	2.2E-07	mg/kg-day	NA	NA	NA	1.6E-06	mg/kg-day	3.0E-02	mg/kg-day	5E-05					
				Metals																	
				Arsenic	1.6E+01	mg/kg	2.0E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	3.0E-08	1.4E-07	mg/kg-day	3.0E-04	mg/kg-day	5E-04					
				Chromium	5.1E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00					
				Dioxins/Furans																	
				TCDD-TEQ	8.0E-03	mg/kg	1.0E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	1.3E-06	7.2E-11	mg/kg-day	7.0E-10	mg/kg-day	1E-01					
				Exp. Route Total							3E-06						1E-01				
Exposure Point Total							1E-05						8E-01								
Exposure Medium Total							1E-05						8E-01								
Soil	Dust	PMP Area	Inhalation	SVOCs																	
				BaP-TE	2.6E-05	ug/m3	2.2E-08	ug/m3	1.1E-03	(ug/m ³) ⁻¹	2.4E-11	1.5E-07	ug/m ³	NA	NA	NA					
				Fluoranthene	2.9E-05	ug/m3	2.4E-08	ug/m3	NA	NA	NA	1.7E-07	ug/m ³	NA	NA	NA					
				Naphthalene	4.7E-06	ug/m3	4.0E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	1.3E-13	2.8E-08	ug/m ³	3.0E-03	mg/m ³	9E-09					
				Pentachlorophenol	7.5E-06	ug/m3	6.3E-09	ug/m3	5.1E-06	(ug/m ³) ⁻¹	3.2E-14	4.4E-08	ug/m ³	NA	NA	NA					
				Pyrene	3.2E-05	ug/m3	2.7E-08	ug/m3	NA	NA	NA	1.9E-07	ug/m ³	NA	NA	NA					
				Metals																	
				Arsenic	1.3E-05	ug/m3	1.1E-08	ug/m3	4.3E-03	(ug/m ³) ⁻¹	4.6E-11	7.5E-08	ug/m ³	1.5E-05	mg/m ³	5E-06					
				Chromium	4.1E-05	ug/m3	3.5E-08	ug/m3	8.4E-02	(ug/m ³) ⁻¹	2.9E-09	2.4E-07	ug/m ³	NA	NA	NA					
				Dioxins/Furans																	
				TCDD-TEQ	6.5E-09	ug/m3	5.5E-12	ug/m3	3.8E+01	(ug/m ³) ⁻¹	2.1E-10	3.8E-11	ug/m ³	4.0E-08	mg/m ³	1E-06					
				Exp. Route Total							3E-09						6E-06				
			Exposure Point Total							3E-09						6E-06					
			Exposure Medium Total							3E-09						6E-06					
			Medium Total							1E-05						8E-01					
										Total of Receptor Hazards Across All Media			1E-05					Total of Receptor Hazards Across All Media			8E-01

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 39
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - FUTURE ON-SITE SOLAR FARM REDEVELOPMENT WORKER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Future
Receptor Population: Solar Farm Redevelopment Worker
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Soil	Surface Soil	Solar Area	Ingestion	SVOCs													
				BaP-TE	9.6E+00	mg/kg	7.1E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	5.2E-07	5.0E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	1.0E+01	mg/kg	7.5E-08	mg/kg-day	NA	NA	NA	5.2E-06	mg/kg-day	1.0E-01	mg/kg-day	5E-05	
				Naphthalene	1.2E+00	mg/kg	9.2E-09	mg/kg-day	NA	NA	NA	6.4E-07	mg/kg-day	2.0E-02	mg/kg-day	3E-05	
				Pentachlorophenol	2.2E+00	mg/kg	1.6E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	6.4E-09	1.1E-06	mg/kg-day	5.0E-03	mg/kg-day	2E-04	
				Pyrene	1.2E+01	mg/kg	8.5E-08	mg/kg-day	NA	NA	NA	6.0E-06	mg/kg-day	3.0E-01	mg/kg-day	2E-05	
				Metals													
				Arsenic	7.9E+00	mg/kg	5.8E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	8.7E-08	4.1E-06	mg/kg-day	3.0E-04	mg/kg-day	1E-02	
				Chromium	1.9E+01	mg/kg	1.4E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	6.9E-08	9.6E-06	mg/kg-day	1.5E+00	mg/kg-day	6E-06	
				Dioxins/Furans													
				TCDD-TEQ	6.0E-04	mg/kg	4.5E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	5.8E-07	3.1E-10	mg/kg-day	7.0E-10	mg/kg-day	4E-01	
				Exp. Route Total							1E-06					5E-01	
				Dermal													
				SVOCs													
				BaP-TE	9.6E+00	mg/kg	2.8E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.0E-07	1.9E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	1.0E+01	mg/kg	2.9E-08	mg/kg-day	NA	NA	NA	2.0E-06	mg/kg-day	1.0E-01	mg/kg-day	2E-05	
				Naphthalene	1.2E+00	mg/kg	3.6E-09	mg/kg-day	NA	NA	NA	2.5E-07	mg/kg-day	2.0E-02	mg/kg-day	1E-05	
				Pentachlorophenol	2.2E+00	mg/kg	6.3E-09	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.5E-09	4.4E-07	mg/kg-day	5.0E-03	mg/kg-day	9E-05	
				Pyrene	1.2E+01	mg/kg	3.3E-08	mg/kg-day	NA	NA	NA	2.3E-06	mg/kg-day	3.0E-01	mg/kg-day	8E-06	
				Metals													
				Arsenic	7.9E+00	mg/kg	5.2E-09	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	7.8E-09	3.7E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03	
				Chromium	1.9E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
				Dioxins/Furans													
				TCDD-TEQ	6.0E-04	mg/kg	4.0E-13	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	5.2E-08	2.8E-11	mg/kg-day	7.0E-10	mg/kg-day	4E-02	
				Exp. Route Total							3E-07					4E-02	
				Exposure Point Total								2E-06					5E-01
				Exposure Medium Total								2E-06					5E-01
Soil	Dust	Solar Area	Inhalation	SVOCs													
				BaP-TE	7.8E-06	ug/m ³	4.0E-09	ug/m3	1.1E-03	(ug/m ³) ⁻¹	4.5E-12	2.8E-07	ug/m ³	NA	NA	NA	
				Fluoranthene	8.2E-06	ug/m ³	4.3E-09	ug/m3	NA	NA	NA	3.0E-07	ug/m ³	NA	NA	NA	
				Naphthalene	1.0E-06	ug/m ³	5.2E-10	ug/m3	3.4E-05	(ug/m ³) ⁻¹	1.8E-14	3.7E-08	ug/m ³	3.0E-03	mg/m ³	1E-08	
				Pentachlorophenol	1.8E-06	ug/m ³	9.2E-10	ug/m3	5.1E-06	(ug/m ³) ⁻¹	4.7E-15	6.4E-08	ug/m ³	NA	NA	NA	
				Pyrene	9.3E-06	ug/m ³	4.9E-09	ug/m3	NA	NA	NA	3.4E-07	ug/m ³	NA	NA	NA	
				Metals													
				Arsenic	6.3E-06	ug/m ³	3.3E-09	ug/m3	4.3E-03	(ug/m ³) ⁻¹	1.4E-11	2.3E-07	ug/m ³	1.5E-05	mg/m ³	2E-05	
				Chromium	1.5E-05	ug/m ³	7.8E-09	ug/m3	8.4E-02	(ug/m ³) ⁻¹	6.6E-10	5.5E-07	ug/m ³	NA	NA	NA	
				Dioxins/Furans													
				TCDD-TEQ	4.9E-10	ug/m ³	2.5E-13	ug/m3	3.8E+01	(ug/m ³) ⁻¹	9.7E-12	1.8E-11	ug/m ³	4.0E-08	mg/m ³	4E-07	
				Exp. Route Total							7E-10					2E-05	
				Exposure Point Total								7E-10					2E-05
				Exposure Medium Total								7E-10					2E-05
				Medium Total								2E-06					5E-01
				Total of Receptor Hazards Across All Media								2E-06	Total of Receptor Hazards Across All Media				5E-01

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 40
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - FUTURE ON-SITE SOLAR FARM MAINTENANCE WORKER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Future
Receptor Population: Solar Farm Maintenance Worker
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Soil	Surface Soil	Future Solar Area	Ingestion	SVOCs													
				BaP-TE	7.3E+00	mg/kg	7.7E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	5.6E-06	2.1E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	7.4E+00	mg/kg	7.7E-07	mg/kg-day	NA	NA	NA	2.2E-06	mg/kg-day	4.0E-02	mg/kg-day	5E-05	
				Naphthalene	3.4E-01	mg/kg	3.5E-08	mg/kg-day	NA	NA	NA	9.9E-08	mg/kg-day	2.0E-02	mg/kg-day	5E-06	
				Pentachlorophenol	8.9E-01	mg/kg	9.3E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.7E-08	2.6E-07	mg/kg-day	5.0E-03	mg/kg-day	5E-05	
				Pyrene	9.0E+00	mg/kg	9.4E-07	mg/kg-day	NA	NA	NA	2.6E-06	mg/kg-day	3.0E-02	mg/kg-day	9E-05	
				Metals													
				Arsenic	6.1E+00	mg/kg	6.4E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	9.6E-07	1.8E-06	mg/kg-day	3.0E-04	mg/kg-day	6E-03	
				Chromium	1.2E+01	mg/kg	1.3E-06	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	6.3E-07	3.5E-06	mg/kg-day	1.5E+00	mg/kg-day	2E-06	
				Dioxins/Furans													
				TCDD-TEQ	2.9E-04	mg/kg	3.1E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	4.0E-06	8.6E-11	mg/kg-day	7.0E-10	mg/kg-day	1E-01	
			Exp. Route Total								1E-05					1E-01	
			Dermal	SVOCs													
				BaP-TE	7.3E+00	mg/kg	6.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.8E-06	1.8E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	7.4E+00	mg/kg	6.6E-07	mg/kg-day	NA	NA	NA	1.9E-06	mg/kg-day	4.0E-02	mg/kg-day	5E-05	
				Naphthalene	3.4E-01	mg/kg	3.0E-08	mg/kg-day	NA	NA	NA	8.5E-08	mg/kg-day	2.0E-02	mg/kg-day	4E-06	
				Pentachlorophenol	8.9E-01	mg/kg	8.0E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.2E-08	2.2E-07	mg/kg-day	5.0E-03	mg/kg-day	4E-05	
				Pyrene	9.0E+00	mg/kg	8.1E-07	mg/kg-day	NA	NA	NA	2.3E-06	mg/kg-day	3.0E-02	mg/kg-day	8E-05	
				Metals													
				Arsenic	6.1E+00	mg/kg	1.3E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.9E-07	3.5E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03	
				Chromium	1.2E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
				Dioxins/Furans													
				TCDD-TEQ	2.9E-04	mg/kg	6.1E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	7.9E-07	1.7E-11	mg/kg-day	7.0E-10	mg/kg-day	2E-02	
			Exp. Route Total								6E-06					3E-02	
			Exposure Point Total								2E-05					2E-01	
			Exposure Medium Total								2E-05					2E-01	
Soil	Dust	Future Solar Area	Inhalation	SVOCs													
				BaP-TE	5.9E-06	ug/m ³	1.4E-07	ug/m3	1.1E-03	(ug/m ³) ⁻¹	1.6E-10	4.0E-07	ug/m ³	NA	NA	NA	
				Fluoranthene	6.0E-06	ug/m ³	1.5E-07	ug/m3	NA	NA	NA	4.1E-07	ug/m ³	NA	NA	NA	
				Naphthalene	2.7E-07	ug/m ³	6.7E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	2.3E-13	1.9E-08	ug/m ³	3.0E-03	mg/m ³	6E-09	
				Pentachlorophenol	7.2E-07	ug/m ³	1.7E-08	ug/m3	5.1E-06	(ug/m ³) ⁻¹	8.9E-14	4.9E-08	ug/m ³	NA	NA	NA	
				Pyrene	7.2E-06	ug/m ³	1.8E-07	ug/m3	NA	NA	NA	5.0E-07	ug/m ³	NA	NA	NA	
				Metals													
				Arsenic	4.9E-06	ug/m ³	1.2E-07	ug/m3	4.3E-03	(ug/m ³) ⁻¹	5.2E-10	3.4E-07	ug/m ³	1.5E-05	mg/m ³	2E-05	
				Chromium	9.7E-06	ug/m ³	2.4E-07	ug/m3	8.4E-02	(ug/m ³) ⁻¹	2.0E-08	6.6E-07	ug/m ³	NA	NA	NA	
				Dioxins/Furans													
				TCDD-TEQ	2.4E-10	ug/m ³	5.8E-12	ug/m3	3.8E+01	(ug/m ³) ⁻¹	2.2E-10	1.6E-11	ug/m ³	4.0E-08	mg/m ³	4E-07	
			Exp. Route Total								2E-08					2E-05	
			Exposure Point Total								2E-08					2E-05	
			Exposure Medium Total								2E-08					2E-05	
Medium Total											2E-05					2E-01	
Total of Receptor Hazards Across All Media											2E-05	Total of Receptor Hazards Across All Media				2E-01	

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 41
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADULT KAYAKER/CANOEIST
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Kayaker/Canoeist
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations						
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ		
							Value	Units	Value	Units		Value	Units	Value	Units			
Sediment	Surface Sediment	Crab Orchard Creek & Piles Fork	Dermal	SVOCs														
				BaP-TE	3.2E+01	mg/kg	1.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.4E-05	3.7E-07	mg/kg-day	NA	NA	NA		
				Metals														
				Arsenic	1.0E+01	mg/kg	1.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.7E-08	2.7E-08	mg/kg-day	3.0E-04	mg/kg-day	9E-05		
				Chromium	1.7E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00		
				Exp. Route Total							4E-05					9E-05		
				Exposure Point Total							4E-05					9E-05		
				Exposure Medium Total							4E-05					9E-05		
				Medium Total							4E-05					9E-05		
				Surface Water	Surface Water	Crab Orchard Creek & Piles Fork	Dermal	SVOCs										
Acenaphthene	2.4E-01	ug/L	3.4E-09					mg/kg-day	NA	NA	NA	8.0E-09	mg/kg-day	6.0E-02	mg/kg-day	1E-07		
Anthracene	2.7E-01	ug/L	7.4E-09					mg/kg-day	NA	NA	NA	1.7E-08	mg/kg-day	3.0E-01	mg/kg-day	6E-08		
Fluoranthene	3.8E-01	ug/L	1.9E-08					mg/kg-day	NA	NA	NA	4.5E-08	mg/kg-day	4.0E-02	mg/kg-day	1E-06		
Fluorene	4.4E-01	ug/L	8.6E-09					mg/kg-day	NA	NA	NA	2.0E-08	mg/kg-day	4.0E-02	mg/kg-day	5E-07		
Pentachlorophenol	7.6E-01	ug/L	9.2E-08					mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.7E-08	2.1E-07	mg/kg-day	5.0E-03	mg/kg-day	4E-05		
Pyrene	7.4E-02	ug/L	3.3E-09					mg/kg-day	NA	NA	NA	7.8E-09	mg/kg-day	3.0E-02	mg/kg-day	3E-07		
Metals																		
Arsenic	4.1E+00	ug/L	2.0E-10					mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.9E-10	4.6E-10	mg/kg-day	3.0E-04	mg/kg-day	2E-06		
Chromium	1.8E+00	ug/L	8.6E-11					mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	1.7E-09	2.0E-10	mg/kg-day	3.8E-02	mg/kg-day	5E-09		
Copper	2.9E+00	ug/L	1.4E-10	mg/kg-day	NA	NA	NA	3.2E-10	mg/kg-day	4.0E-02	mg/kg-day	8E-09						
Exp. Route Total							4E-08					5E-05						
Exposure Point Total							4E-08					5E-05						
Exposure Medium Total							4E-08					5E-05						
Medium Total							4E-08					5E-05						
Total of Receptor Hazards Across All Media								4E-05	Total of Receptor Hazards Across All Media				1E-04					

Notes:
 EPC = exposure point concentration HQ = hazard quotient SVOCs = semi-volatile organic compounds mg/kg = milligram per kilogram ug/L = microgram per liter
 CSF = cancer slope factor RfD = reference dose BaP-TE = benzo(a)pyrene toxic equivalents (mg/kg-day)⁻¹ = per milligram per kilogram-day
 PELCR = potential excess lifetime cancer risk RfC = reference concentration NA = not available mg/kg-day = milligram per kilogram-day

**TABLE 42
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT KAYAKER/CANOEIST
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Kayaker/Canoeist
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Sediment	Surface Sediment	Crab Orchard Creek & Piles Fork	Dermal	SVOCs												
				BaP-TE	3.2E+01	mg/kg	5.4E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.4E-05	3.8E-07	mg/kg-day	NA	NA	NA
				Metals												
				Arsenic	1.0E+01	mg/kg	4.0E-09	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	6.0E-09	2.8E-08	mg/kg-day	3.0E-04	mg/kg-day	9E-05
				Chromium	1.7E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00
			Exp. Route Total								4E-05					9E-05
		Exposure Point Total									4E-05					9E-05
	Exposure Medium Total										4E-05					9E-05
Medium Total											4E-05					9E-05
Surface Water	Surface Water	Crab Orchard Creek & Piles Fork	Dermal	SVOCs												
				Acenaphthene	2.4E-01	ug/L	1.5E-09	mg/kg-day	NA	NA	NA	1.0E-08	mg/kg-day	6.0E-02	mg/kg-day	2E-07
				Anthracene	2.7E-01	ug/L	3.2E-09	mg/kg-day	NA	NA	NA	2.2E-08	mg/kg-day	3.0E-01	mg/kg-day	7E-08
				Fluoranthene	3.8E-01	ug/L	8.2E-09	mg/kg-day	NA	NA	NA	5.7E-08	mg/kg-day	4.0E-02	mg/kg-day	1E-06
				Fluorene	4.4E-01	ug/L	3.7E-09	mg/kg-day	NA	NA	NA	2.6E-08	mg/kg-day	4.0E-02	mg/kg-day	6E-07
				Pentachlorophenol	7.6E-01	ug/L	3.9E-08	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	1.6E-08	2.7E-07	mg/kg-day	5.0E-03	mg/kg-day	5E-05
				Pyrene	7.4E-02	ug/L	1.4E-09	mg/kg-day	NA	NA	NA	1.0E-08	mg/kg-day	3.0E-02	mg/kg-day	3E-07
				Metals												
				Arsenic	4.1E+00	ug/L	8.4E-11	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.3E-10	5.9E-10	mg/kg-day	3.0E-04	mg/kg-day	2E-06
				Chromium	1.8E+00	ug/L	3.7E-11	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	7.4E-10	2.6E-10	mg/kg-day	3.8E-02	mg/kg-day	7E-09
				Copper	2.9E+00	ug/L	5.9E-11	mg/kg-day	NA	NA	NA	4.2E-10	mg/kg-day	4.0E-02	mg/kg-day	1E-08
			Exp. Route Total								2E-08					6E-05
		Exposure Point Total									2E-08					6E-05
	Exposure Medium Total										2E-08					6E-05
Medium Total											2E-08					6E-05
Total of Receptor Hazards Across All Media											4E-05	Total of Receptor Hazards Across All Media				2E-04

Notes:
 EPC - exposure point concentration HQ = hazard quotient SVOCs = semi-volatile organic compounds mg/kg = milligram per kilogram ug/L = microgram per liter
 CSF = cancer slope factor RfD = reference dose BaP-TE = benzo(a)pyrene toxic equivalents (mg/kg-day)⁻¹ = per milligram per kilogram-day
 PELCR = potential excess lifetime cancer risk RfC = reference concentration NA = not available mg/kg-day = milligram per kilogram-day

**TABLE 43
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADULT RECREATIONAL ANGLER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Angler
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations						
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ		
							Value	Units	Value	Units		Value	Units	Value	Units			
Sediment	Surface Sediment	Crab Orchard Creek & Piles Fork	Dermal	SVOCs														
				BaP-TE	3.2E+01	mg/kg	1.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.4E-05	3.7E-07	mg/kg-day	NA	NA	NA		
				Metals														
				Arsenic	1.0E+01	mg/kg	1.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.7E-08	2.7E-08	mg/kg-day	3.0E-04	mg/kg-day	9E-05		
				Chromium	1.7E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00		
				Exp. Route Total							4E-05					9E-05		
				Exposure Point Total							4E-05					9E-05		
				Exposure Medium Total							4E-05					9E-05		
				Medium Total							4E-05					9E-05		
				Surface Water	Surface Water	Crab Orchard Creek & Piles Fork	Dermal	SVOCs										
Acenaphthene	2.4E-01	ug/L	3.4E-09					mg/kg-day	NA	NA	NA	8.0E-09	mg/kg-day	6.0E-02	mg/kg-day	1E-07		
Anthracene	2.7E-01	ug/L	7.4E-09					mg/kg-day	NA	NA	NA	1.7E-08	mg/kg-day	3.0E-01	mg/kg-day	6E-08		
Fluoranthene	3.8E-01	ug/L	1.9E-08					mg/kg-day	NA	NA	NA	4.5E-08	mg/kg-day	4.0E-02	mg/kg-day	1E-06		
Fluorene	4.4E-01	ug/L	8.6E-09					mg/kg-day	NA	NA	NA	2.0E-08	mg/kg-day	4.0E-02	mg/kg-day	5E-07		
Pentachlorophenol	7.6E-01	ug/L	9.2E-08					mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.7E-08	2.1E-07	mg/kg-day	5.0E-03	mg/kg-day	4E-05		
Pyrene	7.4E-02	ug/L	3.3E-09					mg/kg-day	NA	NA	NA	7.8E-09	mg/kg-day	3.0E-02	mg/kg-day	3E-07		
Metals																		
Arsenic	4.1E+00	ug/L	2.0E-10					mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.9E-10	4.6E-10	mg/kg-day	3.0E-04	mg/kg-day	2E-06		
Chromium	1.8E+00	ug/L	8.6E-11					mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	1.7E-09	2.0E-10	mg/kg-day	3.8E-02	mg/kg-day	5E-09		
Copper	2.9E+00	ug/L	1.4E-10	mg/kg-day	NA	NA	NA	3.2E-10	mg/kg-day	4.0E-02	mg/kg-day	8E-09						
Exp. Route Total							4E-08					5E-05						
Exposure Point Total							4E-08					5E-05						
Exposure Medium Total							4E-08					5E-05						
Medium Total							4E-08					5E-05						
Fish Tissue	Fish Tissue	Crab Orchard Creek & Piles Fork	Ingestion	SVOCs														
				Acenaphthene	2.2E-02	mg/kg ww	1.1E-06	mg/kg-day	NA	NA	NA	2.5E-06	mg/kg-day	6.0E-02	mg/kg-day	4E-05		
				Anthracene	7.7E-03	mg/kg ww	3.8E-07	mg/kg-day	NA	NA	NA	8.9E-07	mg/kg-day	3.0E-01	mg/kg-day	3E-06		
				BaP-TE	5.3E-03	mg/kg ww	2.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.9E-06	6.1E-07	mg/kg-day	NA	NA	NA		
				Fluoranthene	2.0E-02	mg/kg ww	9.9E-07	mg/kg-day	NA	NA	NA	2.3E-06	mg/kg-day	4.0E-02	mg/kg-day	6E-05		
				Fluorene	1.5E-02	mg/kg ww	7.4E-07	mg/kg-day	NA	NA	NA	1.7E-06	mg/kg-day	4.0E-02	mg/kg-day	4E-05		
				Phenol	8.1E-03	mg/kg ww	4.0E-07	mg/kg-day	NA	NA	NA	9.4E-07	mg/kg-day	3.0E-01	mg/kg-day	3E-06		
				Metals														
				Arsenic	1.8E-01	mg/kg ww	8.9E-06	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.3E-05	2.1E-05	mg/kg-day	3.0E-04	mg/kg-day	7E-02		
				Chromium	3.0E-02	mg/kg ww	1.5E-06	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	7.4E-07	3.5E-06	mg/kg-day	1.5E+00	mg/kg-day	2E-06		
Copper	4.3E-01	mg/kg ww	2.1E-05	mg/kg-day	NA	NA	NA	5.0E-05	mg/kg-day	4.0E-02	mg/kg-day	1E-03						
Dioxins/Furans																		
TCDD-TEQ	3.1E-07	mg/kg ww	1.5E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.0E-06	3.6E-11	mg/kg-day	7.0E-10	mg/kg-day	5E-02						
Exp. Route Total							2E-05					1E-01						
Exposure Point Total							2E-05					1E-01						
Exposure Medium Total							2E-05					1E-01						
Medium Total							2E-05					1E-01						
Total of Receptor Hazards Across All Media								6E-05	Total of Receptor Hazards Across All Media				1E-01					

Notes:
EPC = exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk
HQ = hazard quotient
RfD = reference dose
RfC = reference concentration
SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day
NA = not available
ug/L = microgram per liter
mg/kg ww = milligram per kilogram wet weight

**TABLE 44
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT RECREATIONAL ANGLER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Angler
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Sediment	Surface Sediment	Crab Orchard Creek & Piles Fork	Dermal	SVOCs													
				BaP-TE	3.2E+01	mg/kg	5.4E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.4E-05	3.8E-07	mg/kg-day	NA	NA	NA	
				Metals													
				Arsenic	1.0E+01	mg/kg	4.0E-09	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	6.0E-09	2.8E-08	mg/kg-day	3.0E-04	mg/kg-day	9E-05	
				Chromium	1.7E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
				Exp. Route Total							4E-05					9E-05	
				Exposure Point Total							4E-05					9E-05	
				Exposure Medium Total							4E-05					9E-05	
				Medium Total							4E-05					9E-05	
				Surface Water	Surface Water	Crab Orchard Creek & Piles Fork	Dermal	SVOCs									
Acenaphthene	2.4E-01	ug/L	1.5E-09					mg/kg-day	NA	NA	NA	1.0E-08	mg/kg-day	6.0E-02	mg/kg-day	2E-07	
Anthracene	2.7E-01	ug/L	3.2E-09					mg/kg-day	NA	NA	NA	2.2E-08	mg/kg-day	3.0E-01	mg/kg-day	7E-08	
Fluoranthene	3.8E-01	ug/L	8.2E-09					mg/kg-day	NA	NA	NA	5.7E-08	mg/kg-day	4.0E-02	mg/kg-day	1E-06	
Fluorene	4.4E-01	ug/L	3.7E-09					mg/kg-day	NA	NA	NA	2.6E-08	mg/kg-day	4.0E-02	mg/kg-day	6E-07	
Pentachlorophenol	7.6E-01	ug/L	3.9E-08					mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	1.6E-08	2.7E-07	mg/kg-day	5.0E-03	mg/kg-day	5E-05	
Pyrene	7.4E-02	ug/L	1.4E-09					mg/kg-day	NA	NA	NA	1.0E-08	mg/kg-day	3.0E-02	mg/kg-day	3E-07	
Metals																	
Arsenic	4.1E+00	ug/L	8.4E-11					mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.3E-10	5.9E-10	mg/kg-day	3.0E-04	mg/kg-day	2E-06	
Chromium	1.8E+00	ug/L	3.7E-11					mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	7.4E-10	2.6E-10	mg/kg-day	3.8E-02	mg/kg-day	7E-09	
Copper	2.9E+00	ug/L	5.9E-11	mg/kg-day	NA	NA	NA	4.2E-10	mg/kg-day	4.0E-02	mg/kg-day	1E-08					
Exp. Route Total							2E-08					6E-05					
Exposure Point Total							2E-08					6E-05					
Exposure Medium Total							2E-08					6E-05					
Medium Total							2E-08					6E-05					
Fish Tissue	Fish Tissue	Crab Orchard Creek & Piles Fork	Ingestion	SVOCs													
				Acenaphthene	2.2E-02	mg/kg ww	5.4E-07	mg/kg-day	NA	NA	NA	3.8E-06	mg/kg-day	6.0E-02	mg/kg-day	6E-05	
				Anthracene	7.7E-03	mg/kg ww	1.9E-07	mg/kg-day	NA	NA	NA	1.3E-06	mg/kg-day	3.0E-01	mg/kg-day	4E-06	
				BaP-TE	5.3E-03	mg/kg ww	1.3E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	9.6E-07	9.2E-07	mg/kg-day	NA	NA	NA	
				Fluoranthene	2.0E-02	mg/kg ww	4.9E-07	mg/kg-day	NA	NA	NA	3.5E-06	mg/kg-day	4.0E-02	mg/kg-day	9E-05	
				Fluorene	1.5E-02	mg/kg ww	3.7E-07	mg/kg-day	NA	NA	NA	2.6E-06	mg/kg-day	4.0E-02	mg/kg-day	6E-05	
				Phenol	8.1E-03	mg/kg ww	2.0E-07	mg/kg-day	NA	NA	NA	1.4E-06	mg/kg-day	3.0E-01	mg/kg-day	5E-06	
				Metals													
				Arsenic	1.8E-01	mg/kg ww	4.4E-06	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	6.7E-06	3.1E-05	mg/kg-day	3.0E-04	mg/kg-day	1E-01	
				Chromium	3.0E-02	mg/kg ww	7.4E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	3.7E-07	5.2E-06	mg/kg-day	1.5E+00	mg/kg-day	3E-06	
Copper	4.3E-01	mg/kg ww	1.1E-05	mg/kg-day	NA	NA	NA	7.4E-05	mg/kg-day	4.0E-02	mg/kg-day	2E-03					
Dioxins/Furans																	
TCDD-TEQ	3.1E-07	mg/kg ww	7.7E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	1.0E-06	5.4E-11	mg/kg-day	7.0E-10	mg/kg-day	8E-02					
Exp. Route Total							9E-06					2E-01					
Exposure Point Total							9E-06					2E-01					
Exposure Medium Total							9E-06					2E-01					
Medium Total							9E-06					2E-01					
							Total of Receptor Hazards Across All Media			5E-05				Total of Receptor Hazards Across All Media			2E-01

Notes:
EPC = exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk
HQ = hazard quotient
RfD = reference dose
RfC = reference concentration
SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day
NA = not available
ug/L = microgram per liter
mg/kg ww = milligram per kilogram wet weight

**TABLE 45
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE CHILD FISH CONSUMER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Fish Consumer
Receptor Age: Child

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Fish Tissue	Fish Tissue	Crab Orchard Creek & Piles Fork	Ingestion	SVOCs												
				Acenaphthene	2.2E-02	mg/kg ww	7.9E-07	mg/kg-day	NA	NA	NA	1.1E-05	mg/kg-day	2.0E-01	mg/kg-day	6E-05
				Anthracene	7.7E-03	mg/kg ww	2.8E-07	mg/kg-day	NA	NA	NA	3.9E-06	mg/kg-day	1.0E+00	mg/kg-day	4E-06
				BaP-TE	5.3E-03	mg/kg ww	1.9E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.4E-06	2.7E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	2.0E-02	mg/kg ww	7.1E-07	mg/kg-day	NA	NA	NA	1.0E-05	mg/kg-day	1.0E-01	mg/kg-day	1E-04
				Fluorene	1.5E-02	mg/kg ww	5.4E-07	mg/kg-day	NA	NA	NA	7.5E-06	mg/kg-day	4.0E-02	mg/kg-day	2E-04
				Phenol	8.1E-03	mg/kg ww	2.9E-07	mg/kg-day	NA	NA	NA	4.1E-06	mg/kg-day	3.0E-01	mg/kg-day	1E-05
				Metals												
				Arsenic	1.8E-01	mg/kg ww	6.4E-06	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	9.6E-06	9.0E-05	mg/kg-day	3.0E-04	mg/kg-day	3E-01
				Chromium	3.0E-02	mg/kg ww	1.1E-06	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	5.4E-07	1.5E-05	mg/kg-day	1.5E+00	mg/kg-day	1E-05
				Copper	4.3E-01	mg/kg ww	1.5E-05	mg/kg-day	NA	NA	NA	2.1E-04	mg/kg-day	4.0E-02	mg/kg-day	5E-03
				Dioxins/Furans												
				TCDD-TEQ	3.1E-07	mg/kg ww	1.1E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	1.4E-06	1.6E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01
			Exp. Route Total								1E-05					5E-01
		Exposure Point Total									1E-05					5E-01
	Exposure Medium Total										1E-05					5E-01
Medium Total											1E-05					5E-01
											Total of Receptor Hazards Across All Media		1E-05	Total of Receptor Hazards Across All Media		5E-01

Notes:
 EPC - exposure point concentration HQ = hazard quotient SVOCs = semi-volatile organic compounds mg/kg ww = milligram per kilogram wet weight NA = not available
 CSF = cancer slope factor RfD = reference dose BaP-TE = benzo(a)pyrene toxic equivalents (mg/kg-day)⁻¹ = per milligram per kilogram-day
 PELCR = potential excess lifetime cancer risk RfC = reference concentration TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents mg/kg-day = milligram per kilogram-day

**TABLE 46
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT TRESPASSER - RAILROAD PROPERTY
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Trespasser
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Soil	Surface Soil	Railroad Property	Ingestion	SVOCs													
				BaP-TE	2.7E+01	mg/kg	3.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.6E-06	2.5E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	3.7E+02	mg/kg	5.0E-06	mg/kg-day	NA	NA	NA	3.5E-05	mg/kg-day	4.0E-02	mg/kg-day	9E-04	
				Naphthalene	4.2E+00	mg/kg	5.6E-08	mg/kg-day	NA	NA	NA	3.9E-07	mg/kg-day	2.0E-02	mg/kg-day	2E-05	
				Pentachlorophenol	4.3E+01	mg/kg	5.7E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.3E-07	4.0E-06	mg/kg-day	5.0E-03	mg/kg-day	8E-04	
				Pyrene	2.5E+02	mg/kg	3.4E-06	mg/kg-day	NA	NA	NA	2.4E-05	mg/kg-day	3.0E-02	mg/kg-day	8E-04	
				Metals													
				Arsenic	1.3E+01	mg/kg	1.7E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.6E-07	1.2E-06	mg/kg-day	3.0E-04	mg/kg-day	4E-03	
				Chromium	1.8E+01	mg/kg	2.4E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.2E-07	1.6E-06	mg/kg-day	1.5E+00	mg/kg-day	1E-06	
				Dioxins/Furans													
				TCDD-TEQ	1.2E-03	mg/kg	1.6E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.1E-06	1.1E-10	mg/kg-day	7.0E-10	mg/kg-day	2E-01	
				Exp. Route Total							5E-06					2E-01	
				Dermal													
				SVOCs													
				BaP-TE	2.7E+01	mg/kg	4.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	3.3E-06	3.2E-06	mg/kg-day	NA	NA	NA	
				Fluoranthene	3.7E+02	mg/kg	6.4E-06	mg/kg-day	NA	NA	NA	4.5E-05	mg/kg-day	4.0E-02	mg/kg-day	1E-03	
				Naphthalene	4.2E+00	mg/kg	7.1E-08	mg/kg-day	NA	NA	NA	5.0E-07	mg/kg-day	2.0E-02	mg/kg-day	2E-05	
				Pentachlorophenol	4.3E+01	mg/kg	7.3E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.9E-07	5.1E-06	mg/kg-day	5.0E-03	mg/kg-day	1E-03	
				Pyrene	2.5E+02	mg/kg	4.3E-06	mg/kg-day	NA	NA	NA	3.0E-05	mg/kg-day	3.0E-02	mg/kg-day	1E-03	
				Metals													
				Arsenic	1.3E+01	mg/kg	5.1E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	7.6E-08	3.6E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03	
				Chromium	1.8E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
				Dioxins/Furans													
				TCDD-TEQ	1.2E-03	mg/kg	4.7E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	6.1E-07	3.3E-11	mg/kg-day	7.0E-10	mg/kg-day	5E-02	
				Exp. Route Total							4E-06					5E-02	
				Exposure Point Total							1E-05					2E-01	
				Exposure Medium Total							1E-05					2E-01	
Soil	Dust	Railroad Property	Inhalation	SVOCs													
				BaP-TE	2.2E-05	ug/m ³	1.1E-08	ug/m3	1.1E-03	(ug/m ³) ⁻¹	1.2E-11	7.9E-08	ug/m ³	NA	NA	NA	
				Fluoranthene	3.0E-04	ug/m ³	1.6E-07	ug/m3	NA	NA	NA	1.1E-06	ug/m ³	NA	NA	NA	
				Naphthalene	3.4E-06	ug/m ³	1.8E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	6.0E-14	1.2E-08	ug/m ³	3.0E-03	mg/m ³	4E-09	
				Pentachlorophenol	3.4E-05	ug/m ³	1.8E-08	ug/m3	5.1E-06	(ug/m ³) ⁻¹	9.2E-14	1.3E-07	ug/m ³	NA	NA	NA	
				Pyrene	2.0E-04	ug/m ³	1.1E-07	ug/m3	NA	NA	NA	7.4E-07	ug/m ³	NA	NA	NA	
				Metals													
				Arsenic	1.0E-05	ug/m ³	5.4E-09	ug/m3	4.3E-03	(ug/m ³) ⁻¹	2.3E-11	3.8E-08	ug/m ³	1.5E-05	mg/m ³	3E-06	
				Chromium	1.4E-05	ug/m ³	7.4E-09	ug/m3	8.4E-02	(ug/m ³) ⁻¹	6.2E-10	5.2E-08	ug/m ³	NA	NA	NA	
				Dioxins/Furans													
				TCDD-TEQ	9.6E-10	ug/m ³	5.0E-13	ug/m3	3.8E+01	(ug/m ³) ⁻¹	1.9E-11	3.5E-12	ug/m ³	4.0E-08	mg/m ³	9E-08	
				Exp. Route Total							7E-10					3E-06	
				Exposure Point Total							7E-10					3E-06	
				Exposure Medium Total							7E-10					3E-06	
				Medium Total							1E-05					2E-01	
				Total of Receptor Hazards Across All Media							1E-05	Total of Receptor Hazards Across All Media					2E-01

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 47
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT TRESPASSER - 35' SWATH PROPERTY
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Trespasser
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations										
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ						
							Value	Units	Value	Units		Value	Units	Value	Units							
Soil	Surface Soil	35' Swath	Ingestion	SVOCs																		
				BaP-TE	4.7E+00	mg/kg	6.3E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	4.6E-07	4.4E-07	mg/kg-day	NA	NA	NA						
				Pentachlorophenol	5.2E-01	mg/kg	7.0E-09	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	2.8E-09	4.9E-08	mg/kg-day	5.0E-03	mg/kg-day	1E-05						
				Metals																		
				Arsenic	1.2E+01	mg/kg	1.6E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.4E-07	1.1E-06	mg/kg-day	3.0E-04	mg/kg-day	4E-03						
				Chromium	1.9E+01	mg/kg	2.6E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.3E-07	1.8E-06	mg/kg-day	1.5E+00	mg/kg-day	1E-06						
				Dioxins/Furans																		
				TCDD-TEQ	1.9E-03	mg/kg	2.6E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	3.4E-06	1.8E-10	mg/kg-day	7.0E-10	mg/kg-day	3E-01						
				Exp. Route Total									4E-06			3E-01						
							Dermal															
				SVOCs																		
				BaP-TE	4.7E+00	mg/kg	8.0E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	5.9E-07	5.6E-07	mg/kg-day	NA	NA	NA						
				Pentachlorophenol	5.2E-01	mg/kg	8.9E-09	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	3.6E-09	6.2E-08	mg/kg-day	5.0E-03	mg/kg-day	1E-05						
				Metals																		
				Arsenic	1.2E+01	mg/kg	4.8E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	7.1E-08	3.3E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03						
				Chromium	1.9E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00						
				Dioxins/Furans																		
				TCDD-TEQ	1.9E-03	mg/kg	7.6E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	9.9E-07	5.3E-11	mg/kg-day	7.0E-10	mg/kg-day	8E-02						
				Exp. Route Total									2E-06			8E-02						
				Exposure Point Total									6E-06			3E-01						
				Exposure Medium Total									6E-06			3E-01						
				Soil	Dust	35' Swath	Inhalation	SVOCs														
								BaP-TE	3.8E-06	ug/m ³	2.0E-09	ug/m3	1.1E-03	(ug/m ³) ⁻¹	2.2E-12	1.4E-08	ug/m ³	NA	NA	NA		
Pentachlorophenol	4.2E-07	ug/m ³	2.2E-10					ug/m3	5.1E-06	(ug/m ³) ⁻¹	1.1E-15	1.5E-09	ug/m ³	NA	NA	NA						
Metals																						
Arsenic	9.8E-06	ug/m ³	5.1E-09					ug/m3	4.3E-03	(ug/m ³) ⁻¹	2.2E-11	3.6E-08	ug/m ³	1.5E-05	mg/m ³	2E-06						
Chromium	1.5E-05	ug/m ³	8.0E-09					ug/m3	8.4E-02	(ug/m ³) ⁻¹	6.8E-10	5.6E-08	ug/m ³	NA	NA	NA						
Dioxins/Furans																						
TCDD-TEQ	1.6E-09	ug/m ³	8.1E-13					ug/m3	3.8E+01	(ug/m ³) ⁻¹	3.1E-11	5.7E-12	ug/m ³	4.0E-08	mg/m ³	1E-07						
Exp. Route Total												7E-10			3E-06							
Exposure Point Total												7E-10			3E-06							
Exposure Medium Total												7E-10			3E-06							
Medium Total												6E-06			3E-01							
									Total of Receptor Hazards Across All Media	6E-06	Total of Receptor Hazards Across All Media			3E-01								

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 48
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT TRESPASSER - SOIL NORTH & WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Trespasser
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations					
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ	
							Value	Units	Value	Units		Value	Units	Value	Units		
Soil	Surface Soil	North & West of Site	Ingestion														
				SVOCs													
				BaP-TE	1.2E+00	mg/kg	1.6E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.2E-07	1.1E-07	mg/kg-day	NA	NA	NA	
				Metals													
				Arsenic	1.1E+01	mg/kg	1.5E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.2E-07	1.0E-06	mg/kg-day	3.0E-04	mg/kg-day	3E-03	
				Chromium	2.2E+01	mg/kg	2.9E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.4E-07	2.0E-06	mg/kg-day	1.5E+00	mg/kg-day	1E-06	
			Exp. Route Total									5E-07			3E-03		
			Dermal														
				SVOCs													
				BaP-TE	1.2E+00	mg/kg	2.0E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.5E-07	1.4E-07	mg/kg-day	NA	NA	NA	
				Metals													
				Arsenic	1.1E+01	mg/kg	4.4E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	6.6E-08	3.1E-07	mg/kg-day	3.0E-04	mg/kg-day	1E-03	
				Chromium	2.2E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00	
			Exp. Route Total									2E-07			1E-03		
			Exposure Point Total									7E-07			5E-03		
			Exposure Medium Total									7E-07			5E-03		
Soil	Dust	North & West of Site	Inhalation														
				SVOCs													
				BaP-TE	9.6E-07	ug/m ³	5.0E-10	ug/m ³	1.1E-03	(ug/m ³) ⁻¹	5.5E-13	3.5E-09	ug/m ³	NA	NA	NA	
				Metals													
				Arsenic	9.0E-06	ug/m ³	4.7E-09	ug/m ³	4.3E-03	(ug/m ³) ⁻¹	2.0E-11	3.3E-08	ug/m ³	1.5E-05	mg/m ³	2E-06	
				Chromium	1.7E-05	ug/m ³	9.1E-09	ug/m ³	8.4E-02	(ug/m ³) ⁻¹	7.6E-10	6.4E-08	ug/m ³	NA	NA	NA	
			Exp. Route Total									8E-10			2E-06		
			Exposure Point Total									8E-10			2E-06		
			Exposure Medium Total									8E-10			2E-06		
Medium Total												7E-07			5E-03		
										Total of Receptor Hazards Across All Media		7E-07			Total of Receptor Hazards Across All Media		5E-03

Notes:

EPC = exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
NA = not available

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 49
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT TRESPASSER - SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Trespasser
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations							
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ			
							Value	Units	Value	Units		Value	Units	Value	Units				
Soil	Surface Soil	East of Site	Ingestion	SVOCs															
				BaP-TE	2.1E-01	mg/kg	2.8E-09	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.1E-08	2.0E-08	mg/kg-day	NA	NA	NA			
				Metals															
				Arsenic	8.2E+00	mg/kg	1.1E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.6E-07	7.7E-07	mg/kg-day	3.0E-04	mg/kg-day	3E-03			
				Chromium	2.3E+01	mg/kg	3.0E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	1.5E-07	2.1E-06	mg/kg-day	1.5E+00	mg/kg-day	1E-06			
				Dioxins/Furans															
				TCDD-TEQ	1.7E-04	mg/kg	2.2E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.9E-07	1.5E-11	mg/kg-day	7.0E-10	mg/kg-day	2E-02			
				Exp. Route Total							6E-07					2E-02			
				Dermal			SVOCs												
				BaP-TE	2.1E-01	mg/kg	3.6E-09	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	2.6E-08	2.5E-08	mg/kg-day	NA	NA	NA			
			Metals																
			Arsenic	8.2E+00	mg/kg	3.2E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	4.8E-08	2.3E-07	mg/kg-day	3.0E-04	mg/kg-day	8E-04				
			Chromium	2.3E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00				
			Dioxins/Furans																
			TCDD-TEQ	1.7E-04	mg/kg	6.5E-13	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	8.4E-08	4.5E-12	mg/kg-day	7.0E-10	mg/kg-day	6E-03				
			Exp. Route Total							2E-07					7E-03				
			Exposure Point Total							8E-07					3E-02				
			Exposure Medium Total							8E-07					3E-02				
			Soil	Dust	East of Site	Inhalation	SVOCs												
							BaP-TE	1.7E-07	ug/m ³	8.9E-11	ug/m3	1.1E-03	(ug/m ³) ⁻¹	9.7E-14	6.2E-10	ug/m ³	NA	NA	NA
Metals																			
Arsenic	6.6E-06	ug/m ³					3.4E-09	ug/m3	4.3E-03	(ug/m ³) ⁻¹	1.5E-11	2.4E-08	ug/m ³	1.5E-05	mg/m ³	2E-06			
Chromium	1.8E-05	ug/m ³					9.5E-09	ug/m3	8.4E-02	(ug/m ³) ⁻¹	8.0E-10	6.6E-08	ug/m ³	NA	NA	NA			
Dioxins/Furans																			
TCDD-TEQ	1.3E-10	ug/m ³				6.9E-14	ug/m3	3.8E+01	(ug/m ³) ⁻¹	2.6E-12	4.9E-13	ug/m ³	4.0E-08	mg/m ³	1E-08				
Exp. Route Total										8E-10					2E-06				
Exposure Point Total										8E-10					2E-06				
Exposure Medium Total										8E-10					2E-06				
Medium Total							8E-07					3E-02							
							Total of Receptor Hazards Across All Media			8E-07				Total of Receptor Hazards Across All Media			3E-02		

Notes:
 EPC - exposure point concentration
 CSF = cancer slope factor
 PELCR = potential excess lifetime cancer risk
 HQ = hazard quotient
 RfD = reference dose
 RfC = reference concentration
 SVOCs = semi-volatile organic compounds
 BaP-TE = benzo(a)pyrene toxic equivalents
 TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
 mg/kg = milligram per kilogram
 (mg/kg-day)⁻¹ = per milligram per kilogram-day
 mg/kg-day = milligram per kilogram-day
 NA = not available
 ug/m³ = microgram per cubic meter
 (ug/m³)⁻¹ = per microgram per cubic meter
 mg/m³ = milligram per cubic meter

TABLE 50
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT TRESPASSER - SEDIMENT NORTH & WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

Scenario Timeframe: Current/Future
 Receptor Population: Kayaker/Canoeist
 Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Sediment	Surface Sediment	North & West of Site	Dermal	SVOCs												
				BaP-TE	1.0E+00	mg/kg	8.8E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.4E-06	6.2E-07	mg/kg-day	NA	NA	NA
				Metals												
				Arsenic	1.6E+01	mg/kg	3.0E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	4.6E-07	2.1E-06	mg/kg-day	3.0E-04	mg/kg-day	7E-03
				Chromium	2.8E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00
			Exp. Route Total								2E-06					7E-03
		Exposure Point Total								2E-06					7E-03	
	Exposure Medium Total								2E-06					7E-03		
Medium Total								Total of Receptor Hazards Across All Media			2E-06	Total of Receptor Hazards Across All Media				7E-03

Notes:

EPC = exposure point concentration

CSF = cancer slope factor

PELCR = potential excess lifetime cancer risk

HQ = hazard quotient

RfD = reference dose

RfC = reference concentration

SVOCs = semi-volatile organic compounds

BaP-TE = benzo(a)pyrene toxic equivalents

NA = not available

mg/kg = milligram per kilogram

(mg/kg-day)⁻¹ = per milligram per kilogram-day

mg/kg-day = milligram per kilogram-day

**TABLE 51
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADULT HIKER/BICYCLE TRAIL USERS - RAILROAD PROPERTY
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Future
Receptor Population: Hikers/Bicycle Trail Users
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations						
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ		
							Value	Units	Value	Units		Value	Units	Value	Units			
Soil	Surface Soil	Railroad Property	Ingestion	SVOCs														
				BaP-TE	2.7E+01	mg/kg	1.6E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.1E-06	5.5E-07	mg/kg-day	NA	NA	NA		
				Fluoranthene	3.7E+02	mg/kg	2.2E-06	mg/kg-day	NA	0.0E+00	NA	7.6E-06	mg/kg-day	4.0E-02	mg/kg-day	2E-04		
				Naphthalene	4.2E+00	mg/kg	2.4E-08	mg/kg-day	NA	0.0E+00	NA	8.5E-08	mg/kg-day	2.0E-02	mg/kg-day	4E-06		
				Pentachlorophenol	4.3E+01	mg/kg	2.5E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	9.9E-08	8.7E-07	mg/kg-day	5.0E-03	mg/kg-day	2E-04		
				Pyrene	2.5E+02	mg/kg	1.5E-06	mg/kg-day	NA	0.0E+00	NA	5.1E-06	mg/kg-day	3.0E-02	mg/kg-day	2E-04		
				Metals														
				Arsenic	1.3E+01	mg/kg	7.5E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.1E-07	2.6E-07	mg/kg-day	3.0E-04	mg/kg-day	9E-04		
				Chromium	1.8E+01	mg/kg	1.0E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	5.1E-08	3.6E-07	mg/kg-day	1.5E+00	mg/kg-day	2E-07		
				Dioxins/Furans														
				TCDD-TEQ	1.2E-03	mg/kg	6.9E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	9.0E-07	2.4E-11	mg/kg-day	7.0E-10	mg/kg-day	3E-02		
				Exp. Route Total									2E-06			4E-02		
				Dermal														
				SVOCs														
				BaP-TE	2.7E+01	mg/kg	8.1E-08	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	5.9E-07	2.8E-07	mg/kg-day	NA	NA	NA		
				Fluoranthene	3.7E+02	mg/kg	1.1E-06	mg/kg-day	NA	0.0E+00	NA	4.0E-06	mg/kg-day	4.0E-02	mg/kg-day	1E-04		
				Naphthalene	4.2E+00	mg/kg	1.3E-08	mg/kg-day	NA	0.0E+00	NA	4.4E-08	mg/kg-day	2.0E-02	mg/kg-day	2E-06		
				Pentachlorophenol	4.3E+01	mg/kg	1.3E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	5.2E-08	4.5E-07	mg/kg-day	5.0E-03	mg/kg-day	9E-05		
				Pyrene	2.5E+02	mg/kg	7.6E-07	mg/kg-day	NA	0.0E+00	NA	2.7E-06	mg/kg-day	3.0E-02	mg/kg-day	9E-05		
				Metals														
				Arsenic	1.3E+01	mg/kg	9.0E-09	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.4E-08	3.2E-08	mg/kg-day	3.0E-04	mg/kg-day	1E-04		
				Chromium	1.8E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00		
				Dioxins/Furans														
				TCDD-TEQ	1.2E-03	mg/kg	8.3E-13	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	1.1E-07	2.9E-12	mg/kg-day	7.0E-10	mg/kg-day	4E-03		
				Exp. Route Total									8E-07			5E-03		
						Exposure Point Total							3E-06			4E-02		
						Exposure Medium Total							3E-06			4E-02		
Soil	Dust	Railroad Property	Inhalation	SVOCs														
				BaP-TE	2.2E-05	ug/m ³	3.7E-08	ug/m3	1.1E-03	(ug/m ³) ⁻¹	4.0E-11	1.3E-07	ug/m ³	NA	NA	NA		
				Fluoranthene	3.0E-04	ug/m ³	5.1E-07	ug/m3	NA	NA	NA	1.8E-06	ug/m ³	NA	NA	NA		
				Naphthalene	3.4E-06	ug/m ³	5.7E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	1.9E-13	2.0E-08	ug/m ³	3.0E-03	mg/m ³	7E-09		
				Pentachlorophenol	3.4E-05	ug/m ³	5.8E-08	ug/m3	5.1E-06	(ug/m ³) ⁻¹	3.0E-13	2.0E-07	ug/m ³	NA	NA	NA		
				Pyrene	2.0E-04	ug/m ³	3.5E-07	ug/m3	NA	NA	NA	1.2E-06	ug/m ³	NA	NA	NA		
				Metals														
				Arsenic	1.0E-05	ug/m ³	1.8E-08	ug/m3	4.3E-03	(ug/m ³) ⁻¹	7.6E-11	6.2E-08	ug/m ³	1.5E-05	mg/m ³	4E-06		
				Chromium	1.4E-05	ug/m ³	2.4E-08	ug/m3	8.4E-02	(ug/m ³) ⁻¹	2.0E-09	8.4E-08	ug/m ³	NA	NA	NA		
				Dioxins/Furans														
				TCDD-TEQ	9.6E-10	ug/m ³	1.6E-12	ug/m3	3.8E+01	(ug/m ³) ⁻¹	6.2E-11	5.7E-12	ug/m ³	4.0E-08	mg/m ³	1E-07		
				Exp. Route Total									2E-09			4E-06		
						Exposure Point Total							2E-09			4E-06		
						Exposure Medium Total							2E-09			4E-06		
				Medium Total												4E-02		
												Total of Receptor Hazards Across All Media					4E-02	
													3E-06		Total of Receptor Hazards Across All Media		4E-02	

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

**TABLE 52
CALCULATION OF CANCER RISKS AND NON-CANCER HAZARDS - CURRENT/FUTURE OFF-SITE ADOLESCENT HIKER/BICYCLE TRAIL USERS - RAILROAD PROPERTY
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

Scenario Timeframe: Current/Future
Receptor Population: Hikers/Bicycle Trail Users
Receptor Age: Adolescent

Medium	Exposure Medium	Exposure Point	Exposure Route	Compound of Potential Concern	EPC		Potential Cancer Risk Calculations					Potential Non-Cancer Hazard Calculations				
					Value	Units	Intake/Exposure Concentration		CSF/Unit Risk		PELCR	Intake/Exposure Concentration		RfD/RfC		HQ
							Value	Units	Value	Units		Value	Units	Value	Units	
Soil	Surface Soil	Railroad Property	Ingestion	SVOCs												
				BaP-TE	2.7E+01	mg/kg	2.3E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.7E-06	1.6E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	3.7E+02	mg/kg	3.3E-06	mg/kg-day	NA	NA	NA	2.3E-05	mg/kg-day	4.0E-02	mg/kg-day	6E-04
				Naphthalene	4.2E+00	mg/kg	3.6E-08	mg/kg-day	NA	NA	NA	2.5E-07	mg/kg-day	2.0E-02	mg/kg-day	1E-05
				Pentachlorophenol	4.3E+01	mg/kg	3.7E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	1.5E-07	2.6E-06	mg/kg-day	5.0E-03	mg/kg-day	5E-04
				Pyrene	2.5E+02	mg/kg	2.2E-06	mg/kg-day	NA	NA	NA	1.5E-05	mg/kg-day	3.0E-02	mg/kg-day	5E-04
				Metals												
				Arsenic	1.3E+01	mg/kg	1.1E-07	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	1.7E-07	7.9E-07	mg/kg-day	3.0E-04	mg/kg-day	3E-03
				Chromium	1.8E+01	mg/kg	1.5E-07	mg/kg-day	5.0E-01	(mg/kg-day) ⁻¹	7.7E-08	1.1E-06	mg/kg-day	1.5E+00	mg/kg-day	7E-07
				Dioxins/Furans												
				TCDD-TEQ	1.2E-03	mg/kg	1.0E-11	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	1.3E-06	7.2E-11	mg/kg-day	7.0E-10	mg/kg-day	1E-01
			Exp. Route Total								3E-06					1E-01
			Dermal	SVOCs												
				BaP-TE	2.7E+01	mg/kg	1.5E-07	mg/kg-day	7.3E+00	(mg/kg-day) ⁻¹	1.1E-06	1.0E-06	mg/kg-day	NA	NA	NA
				Fluoranthene	3.7E+02	mg/kg	2.1E-06	mg/kg-day	NA	NA	NA	1.5E-05	mg/kg-day	4.0E-02	mg/kg-day	4E-04
				Naphthalene	4.2E+00	mg/kg	2.3E-08	mg/kg-day	NA	NA	NA	1.6E-07	mg/kg-day	2.0E-02	mg/kg-day	8E-06
				Pentachlorophenol	4.3E+01	mg/kg	2.4E-07	mg/kg-day	4.0E-01	(mg/kg-day) ⁻¹	9.4E-08	1.7E-06	mg/kg-day	5.0E-03	mg/kg-day	3E-04
				Pyrene	2.5E+02	mg/kg	1.4E-06	mg/kg-day	NA	NA	NA	9.8E-06	mg/kg-day	3.0E-02	mg/kg-day	3E-04
				Metals												
				Arsenic	1.3E+01	mg/kg	1.7E-08	mg/kg-day	1.5E+00	(mg/kg-day) ⁻¹	2.5E-08	1.2E-07	mg/kg-day	3.0E-04	mg/kg-day	4E-04
				Chromium	1.8E+01	mg/kg	0.0E+00	mg/kg-day	2.0E+01	(mg/kg-day) ⁻¹	0.0E+00	0.0E+00	mg/kg-day	3.8E-02	mg/kg-day	0E+00
				Dioxins/Furans												
				TCDD-TEQ	1.2E-03	mg/kg	1.5E-12	mg/kg-day	1.3E+05	(mg/kg-day) ⁻¹	2.0E-07	1.1E-11	mg/kg-day	7.0E-10	mg/kg-day	2E-02
			Exp. Route Total								1E-06					2E-02
			Exposure Point Total								5E-06					1E-01
			Exposure Medium Total								5E-06					1E-01
Soil	Dust	Railroad Property	Inhalation	SVOCs												
				BaP-TE	2.2E-05	ug/m ³	1.8E-08	ug/m3	1.1E-03	(ug/m ³) ⁻¹	2.0E-11	1.3E-07	ug/m ³	NA	NA	NA
				Fluoranthene	3.0E-04	ug/m ³	2.6E-07	ug/m3	NA	NA	NA	1.8E-06	ug/m ³	NA	NA	NA
				Naphthalene	3.4E-06	ug/m ³	2.9E-09	ug/m3	3.4E-05	(ug/m ³) ⁻¹	9.7E-14	2.0E-08	ug/m ³	3.0E-03	mg/m ³	7E-09
				Pentachlorophenol	3.4E-05	ug/m ³	2.9E-08	ug/m3	5.1E-06	(ug/m ³) ⁻¹	1.5E-13	2.0E-07	ug/m ³	NA	NA	NA
				Pyrene	2.0E-04	ug/m ³	1.7E-07	ug/m3	NA	NA	NA	1.2E-06	ug/m ³	NA	NA	NA
				Metals												
				Arsenic	1.0E-05	ug/m ³	8.8E-09	ug/m3	4.3E-03	(ug/m ³) ⁻¹	3.8E-11	6.2E-08	ug/m ³	1.5E-05	mg/m ³	4E-06
				Chromium	1.4E-05	ug/m ³	1.2E-08	ug/m3	8.4E-02	(ug/m ³) ⁻¹	1.0E-09	8.4E-08	ug/m ³	NA	NA	NA
				Dioxins/Furans												
				TCDD-TEQ	9.6E-10	ug/m ³	8.1E-13	ug/m3	3.8E+01	(ug/m ³) ⁻¹	3.1E-11	5.7E-12	ug/m ³	4.0E-08	mg/m ³	1E-07
			Exp. Route Total								1E-09					4E-06
			Exposure Point Total								1E-09					4E-06
			Exposure Medium Total								1E-09					4E-06
Medium Total											5E-06					1E-01
											Total of Receptor Hazards Across All Media	5E-06	Total of Receptor Hazards Across All Media			1E-01

Notes:

EPC - exposure point concentration
CSF = cancer slope factor
PELCR = potential excess lifetime cancer risk

HQ = hazard quotient
RfD = reference dose
RfC = reference concentration

SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents

mg/kg = milligram per kilogram
(mg/kg-day)⁻¹ = per milligram per kilogram-day
mg/kg-day = milligram per kilogram-day

NA = not available
ug/m³ = microgram per cubic meter
(ug/m³)⁻¹ = per microgram per cubic meter
mg/m³ = milligram per cubic meter

TABLE 53
SUMMARY OF ESTIMATED POTENTIAL HUMAN HEALTH RISKS AND HAZARDS
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS


Receptor Exposure Group	Total Potential Excess Lifetime Cancer Risk	Total Potential Non-Cancer Hazard Index
On-Site Receptor Populations		
Current/Future On-Site Adult Maintenance Worker/Caretaker (1)	8E-05	1
Current/Future On-site Adult Deer Hunter and Adolescent and Child Deer Consumer		
Adult	1E-05	0.1
Adolescent	5E-06	0.2
Child	4E-06	0.3
Current/Future On-site Adolescent Trespasser	7E-06	0.3
Future On-site Adult and Adolescent Hiker/Bicycle Trail Users		
Adult	9E-06	0.3
Adolescent	1E-05	0.8
Future On-site Solar Farm Redevelopment Worker	2E-06	0.5
Future On-site Solar Farm Maintenance Worker	2E-05	0.5
Off-Site Receptor Populations		
Current/Future Off-site Adult and Adolescent Kayaker/Canoeist		
Adult	4E-05	0.0001
Adolescent	4E-05	0.0002
Current/Future Off-site Adult and Adolescent Recreational Angler and Child Fish Consumer		
Adult	6E-05	0.1
Adolescent	5E-05	0.2
Child	1E-05	0.5
Current/Future Adolescent Trespasser		
Railroad Property	1E-05	0.2
35' Swath Property	6E-06	0.3
Soil North & West of the Site	7E-07	0.005
Soil East of the Site	8E-07	0.03
Sediment North & West of the Site	2E-06	0.007
Hypothetical Future Adult and Adolescent Hiker/Bicycle Trail Users in Railroad Property		
Adult	3E-06	0.04
Adolescent	5E-06	0.1

Note:

(1) Total HI is 2. However, endpoint-specific hazard indices calculated for the on-Site adult maintenance worker/caretaker do not exceed a target HI of 1 for any endpoint evaluated (circulatory system, whole body, nervous system, development, skin, kidney, liver, respiratory system, endocrine, or reproductive).



Figures



LEGEND:

- ▼ 2005 EPA SAMPLE
- ★ 2005 SURFACE COVER
- ⊙ 2006 SOUTHERN DRAINAGE
- ⊠ 2008 SOUTHERN DRAINAGE
- ▲ 2009 SP LOCATION
- ▲ 2010 SP LOCATION
- ▲ BCWP
- ⊕ COMPOSITE AUG 2012
- ⊕ COMPOSITE NOV 2012
- ⊙ FLOODPLAIN SAMPLE
- ⊠ GRAB- AUG 2012
- ⊕ RESIDENTIAL
- ⊕ SEDIMENT-SURFACE WATER
- ⊕ SP-USEPA
- ⊕ COVERED- FORMER LAGOON
- ⊕ REMOVED SAMPLES
- ⊕ REMOVED EPA SAMPLE
- REMOVED SB- SOIL/DEBRIS PILE AREA
- DRAINAGE DITCH
- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- WETLAND
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- PROPERTY LINE
- CAMU CONTAINMENT AREA
- POTENTIAL BIKE PATH
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA


0 600 1,200
SCALE IN FEET

BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**SAMPLE LOCATIONS AND
EXPOSURE AREAS**

ARCADIS

FIGURE
1




LEGEND:
 X Incomplete Exposure Pathway
 ○ Exposure Pathway Potentially Complete but Insignificant
 ● Exposure Pathway Potentially Complete
 NA Not Applicable to Receptor
 PAHS Polynuclear Aromatic Hydrocarbons

Notes:
 (1) The adult, adolescent, and child deer consumers are assumed to eat deer that foraged on-Site but were harvested off-Site. Therefore, their exposure to Site constituents is only via uptake into deer meat.
 (2) No crayfish collection or any evidence of this activity has been observed to occur at the Site. Based on field work conducted in both Piles Fork and Glade Creek indicate crayfish are not abundant.
 (3) Future use of the Site is as a solar farm and conservation open space. Institutional controls will preclude generic industrial development without further evaluation to confirm planned use meets allowable risk levels.
 (4) Institutional controls will establish worker protective controls to eliminate any potential future exposures. Furthermore, institutional controls will preclude generic industrial development without further evaluation to confirm planned use meets allowable risk levels.

FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

HHRA CONCEPTUAL SITE MODEL FOR POTENTIAL EXPOSURE

FIGURE 2




LEGEND:

FLUORANTHENE (mg/kg)

- NOT DETECTED
- ≤ 0.2
- 0.2 - 2
- 2 - 14
- 14 - 95
- 95 - 640
- > 640

- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- - - POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA


LOCATION	FLUORANTHENE (mg/kg)	LOCATION	FLUORANTHENE (mg/kg)	LOCATION	FLUORANTHENE (mg/kg)	LOCATION	FLUORANTHENE (mg/kg)
A1-10	5.2 J	A1-5	32 J	S1	0.82	SDD-20	4
A1-11	0.81	A1-6	0.77	S13	64	SDD-20-15RB	26
A1-13	1.2	A1-9	61 J	S2	0.02	SDD-20-TLB	0.0058 J [0.0049 J]
A1-14	1.2 J	A2-13	0.26 J [1.4 J]	SB-100	67 [59]	SDD-20-TRB	2
A1-15	0.13	A2-14	18 DJ	SB-101	19	SDD-26	2.1
A1-16	0.05	A2-15	23 DJ	SB-102	8.2	SDD-26-15N	0.87 [1.1]
A1-19	1.9	A2-16	16 DJ	SB-103	0.34 J	SDD-26-15S	4.7 [3.4]
A1-2	0.17	A2-17	19 DJ	SB-104	0.27 J	SDD-27	3.5
A1-20	6.2	A2-18	4.2	SB-105	0.024 J	SDD-28	35
A1-21	14 J	A2-19	11 DJ [11 DJ]	SB-106	1.7 J	SDD-28-15LB	3.1
A1-22	0.016	A3-18	0.022	SB-107	2.8	SDD-28-15RB	7.4
A1-23	12 J	A3-19	0.21	SB-108	4.5	SDD-28-TLB	16
A1-24	30 J	A3-20	0.22 [0.23]	SB-109	2.7	SDD-28-TRB	12
A1-25	34 J	A3-21	25 DJ	SB-114	3.3	SDD-29	11
A1-26	43 J	A3-22	2.4 DJ	SB-115	12	SDD-29-15LB	40 D
A1-27	5.3 J	A3-23	1.8	SB-116	0.57	SDD-29-15RB	3.2
A1-28	0.35	A3-24	25 DJ	SB-117	1.5 J	SDD-29-TLB	23
A1-29	0.52 [0.58]	FPT1-33%L	0.092	SB-118	61	SDD-29-TRB	43
A1-3	0.013	FPT1-33%R	0.0087 U	SB-119	4300 D	SDD-30	11
A1-30	14 J	FPT1-5'L	0.19	SB-120	25	SDD-31	11
A1-31	8.2 J	FPT1-5'R	3.8	SDD-1	15	SDD-32	67 J
A1-32	19 J [0.0082 J]	FPT2-33%L	0.15	SDD-1-15LB	0.44	SDD-33	2.9
A1-33	0.0043 J	FPT2-33%R	0.056	SDD-1-15RB	1.7	SDD-34	0.23 J
A1-34	0.0017 J	FPT2-5'L	0.4	SDD-12	5.2	SDD-35	2.6
A1-35	0.047	FPT2-5'R	0.41	SDD-12-15LB	50 J	SDD-36	36
A1-36	0.056	FPT3-33%L	0.19 [0.075]	SDD-12-15RB	220 DJ	SDD-37	0.2 [0.32]
A1-37	85 DJ	FPT3-33%R	0.023	SDD-12-TLB	17	SDD-4	12
A1-38	1.8	FPT3-5'L	1.5	SDD-12-TRB	1.7	SDD-4-15LB	3.2
A1-39	1.5	FPT3-5'R	0.13	SDD-15	11	SDD-4-15RB	3
A1-4	40 J	FPT4-33%L	0.094	SDD-15-15LB	130 J	SDD-4-TLB	28
A1-40	0.75	FPT4-33%R	0.0062 J	SDD-15-15RB	5.2	SDD-4-TRB	4.9
A1-41	25 DJ	FPT4-5'L	0.27	SDD-15-TLB	5.9 J	SDD-7	380 D
A1-42	0.019	FPT4-5'R	0.39	SDD-15-TRB	23 [31]	SDD-7-15LB	33 J
A1-44	0.63 [0.39]	FPT5-33%L	0.16	SDD-16	3.9	SDD-7-15RB	9.6
A1-45	0.023	FPT5-33%R	0.019	SDD-16-SPL	14	SDD-7-TLB	120
A1-46	0.073	FPT5-5'L	0.29	SDD-1-SPL	9.8	SDD-7-TRB	2.2
A1-47	0.16	FPT5-5'R	0.12	SDD-1-TLB	2.4	SDD-9	36
A1-48	0.2	NPL	0.29	SDD-1-TRB	1.1 [1.5]	SDD-9-TRB	9.4



BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**FLUORANTHENE THIESSEN
POLYGON MAP**






LEGEND:

NAPHTHALENE (mg/kg)

- NOT DETECTED
- ≤ 0.02
- 0.02 - 0.1
- 0.1 - 0.9
- 0.9 - 6
- 6 - 37
- > 37

- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- - - POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA

LOCATION	NAPHTHALENE (mg/kg)	LOCATION	NAPHTHALENE (mg/kg)	LOCATION	NAPHTHALENE (mg/kg)	LOCATION	NAPHTHALENE (mg/kg)
A1-10	1.2 J	A1-5	2.3 J	S1	0.11	SDD-20	0.14 J
A1-11	0.067	A1-6	0.051	S13	6.8	SDD-20-15RB	1.5
A1-13	0.1	A1-9	2.5 J	S2	0.0047	SDD-20-TLB	0.0085 U [0.0085 U]
A1-14	0.037 J	A2-13	0.02 J [0.16 J]	SB-100	2.1 J [2.8 J]	SDD-20-TRB	0.14
A1-15	0.014	A2-14	0.94 DJ	SB-101	2.1 J	SDD-26	0.14
A1-16	0.0089 J	A2-15	2.3 DJ	SB-102	1.2 J	SDD-26-15N	0.043 [0.03]
A1-19	0.048	A2-16	2 DJ	SB-103	0.052 J	SDD-26-15S	0.16 [0.11]
A1-20	0.045	A2-17	1.4 DJ	SB-104	0.043 J	SDD-27	0.083 J
A1-21	0.36	A2-18	0.1	SB-105	0.35 U	SDD-28	3 J
A1-22	0.0097 U	A2-19	1.2 DJ [1.1 DJ]	SB-106	0.16 J	SDD-28-15LB	0.7
A1-23	0.46 J	A3-18	0.0016 J	SB-107	1.9 U	SDD-28-15RB	1.2
A1-24	0.72 J	A3-19	0.0093 J	SB-108	0.15 J	SDD-28-TLB	0.92 J
A1-25	1.3 J	A3-20	0.018 J [0.016 J]	SB-109	0.14 J	SDD-28-TRB	1.6 J
A1-26	2.3 J	A3-21	3.8 DJ	SB-114	0.96 J	SDD-29	0.83 J
A1-27	0.44 J	A3-22	0.11 DJ	SB-115	3.6	SDD-29-15LB	6.2
A1-28	0.05	A3-23	0.12	SB-116	0.052 J	SDD-29-15RB	0.2
A1-29	0.014 [0.019]	A3-24	0.7 DJ	SB-117	0.12 J	SDD-29-TLB	2.6 J
A1-3	0.0033 J	FPT1-33%L	0.0093 J	SB-118	17 J	SDD-29-TRB	10 J
A1-30	0.33 J	FPT1-33%R	0.0087 U	SB-119	46 J	SDD-30	0.86
A1-31	0.21 J	FPT1-5'L	0.021 J	SB-120	2.6 J	SDD-31	0.84
A1-32	0.35 J [0.014]	FPT1-5'R	0.12 J	SDD-1	1	SDD-32	1.7 J
A1-33	0.0014 J	FPT2-33%L	0.01	SDD-1-15LB	0.053	SDD-33	0.068 J
A1-34	0.0094 U	FPT2-33%R	0.0043 J	SDD-1-15RB	0.11	SDD-34	0.36 U
A1-35	0.0077 J	FPT2-5'L	0.04 J	SDD-12	0.45	SDD-35	0.99 U
A1-36	0.0072 J	FPT2-5'R	0.035 J	SDD-12-15LB	4.4 J	SDD-36	1.1
A1-37	0.84 DJ	FPT3-33%L	0.014 [0.0096]	SDD-12-15RB	74 DJ	SDD-37	0.025 [0.03]
A1-38	0.044	FPT3-33%R	0.01 U	SDD-12-TLB	1.5	SDD-4	1.7
A1-39	0.19	FPT3-5'L	0.13 J	SDD-12-TRB	0.07	SDD-4-15LB	0.28
A1-40	1.2 J	FPT3-5'R	0.014 J	SDD-15	1.6	SDD-4-15RB	0.061
A1-41	0.034	FPT4-33%L	0.013 J	SDD-15-15LB	1.1 J	SDD-4-TLB	2 J
A1-42	0.0025 J	FPT4-33%R	0.0091 U	SDD-15-15RB	0.7 J	SDD-4-TRB	0.28 J
A1-44	0.12 [0.086]	FPT4-5'L	0.03 J	SDD-15-TLB	0.64 J	SDD-7	240 D
A1-45	0.008 J	FPT4-5'R	0.044 J	SDD-15-TRB	1.2 [0.97 J]	SDD-7-15LB	1.8 J
A1-46	0.01 J	FPT5-33%L	0.01 J	SDD-16	0.5	SDD-7-15RB	0.59
A1-47	0.049	FPT5-33%R	0.0093 U	SDD-16-SPL	0.46	SDD-7-TLB	0.51 J
A1-48	0.02 J	FPT5-5'L	0.028 J	SDD-1-SPL	0.35	SDD-7-TRB	0.054
		FPT5-5'R	0.0093	SDD-1-TLB	0.06 J	SDD-9	2
		NPL	0.043	SDD-1-TRB	0.03 J [0.033 J]	SDD-9-TRB	0.4 J




BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**NAPHTHALENE THIESSEN
POLYGON MAP**



CITY: CHELMSFORD DIV/GROUP: ENV/EST DB: mbonanduci LD: PIC: PM: TM: PROJECT: \arcadis-us.com\OfficeData\Chelmsford-MAA_PRACTS\Beazer\Carbondale\GIS_SpatialData\GIS\MXD\Ds\IL-39283_fig1_ThiessenPolygons_Penta.mxd DATE: 9/30/2014 3:31:39 PM




LEGEND:

PENTACHLOROPHENOL (mg/kg)

- NOT DETECTED
- ≤ 0.06
- 0.06 - 0.3
- 0.3 - 1
- 1 - 6
- 6 - 30
- > 30

- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA

LOCATION	PENTACHLOROPHENOL (mg/kg)	LOCATION	PENTACHLOROPHENOL (mg/kg)	LOCATION	PENTACHLOROPHENOL (mg/kg)	LOCATION	PENTACHLOROPHENOL (mg/kg)
A1-16	2.2 D	A1-42	0.093 U	FPT4-5'L	0.047 J	SDD-15-15LB	17 J
A1-18	0.017 J	A1-44	0.021 J [0.04 J]	FPT4-5'R	0.075 J	SDD-15-15RB	2.9
A1-19	0.44	A1-45	0.046 U	FPT5-33%L	0.062 J	SDD-15-TLB	100 J
A1-2	0.046 U	A1-46	0.11 U	FPT5-33%R	0.01 J	SDD-15-TRB	68 [60]
A1-20	0.57	A1-47	0.022 J	NPL	0.016 J	SDD-16	89 DJ
A1-21	140 J	A1-48	0.13 U	S1	0.51 U	SDD-16-SPL	0.54 J
A1-22	0.048 U	A1-5	2.8 U	S13	2.2	SDD-20	0.51 J
A1-23	31 J	A1-9	21 J	S2	0.47 U	SDD-20-TRB	0.32
A1-24	0.7 J	A2-13	0.078 J [0.061 J]	SB-100	48 J [53 J]	SDD-26	2.8 J
A1-25	2.6 J	A2-14	71 DJ	SB-101	88 U	SDD-26-15S	1.5
A1-26	5.4 UJ	A2-15	21 DJ	SB-102	11 U	SDD-27	33 DJ
A1-27	2.2 J	A2-16	27 DJ	SB-103	1.8 U	SDD-29-TLB	1.3
A1-28	0.099	A2-17	40 DJ	SB-104	1.8 U	SDD-30	0.99 U
A1-29	0.017 J [0.018 J]	A2-18	2.3	SB-105	1.7 U	SDD-31	19
A1-3	0.044 U	A2-19	22 DJ [20 DJ]	SB-106	3.4 J	SDD-32	11 UJ
A1-30	63 J	A3-18	0.044 U	SB-107	9.4 U	SDD-33	1.4
A1-31	22 J	A3-19	0.067 J	SB-108	10 U	SDD-34	20
A1-32	1.1 UJ [0.046 U]	A3-20	0.037 J [0.053 J]	SB-109	9.1 U	SDD-35	45
A1-33	0.046 U	A3-21	18 DJ	SB-114	13 U	SDD-36	89
A1-34	0.046 U	A3-22	1.2 DJ	SB-115	3.2 J	SDD-37	0.83 [1.4]
A1-35	0.048 U	A3-23	0.57	SB-116	1.8 U	SDD-4	1.1 J
A1-36	0.022 J	A3-24	2.6 DJ	SB-117	9.6 U	SDD-7	4.2 J
A1-37	8 DJ	FPT1-33%L	0.22	SB-118	57 J	SDD-7-15LB	0.55 J
A1-38	0.033 J	FPT1-33%R	0.043 U	SB-119	870 U	SDD-7-TLB	8.4
A1-39	0.26	FPT2-5'L	0.098 J	SB-120	20 U	SDD-7-TRB	0.23
A1-4	4.5 UJ	FPT2-5'R	0.14 J	SDD-1	2.2 J	SDD-9	10 J
A1-40	0.023 J	FPT3-33%L	0.065 [0.018 J]	SDD-12	0.58 J	SDD-9-TRB	5.5
A1-41	0.79 UJ	FPT3-33%R	0.02 J	SDD-15	45 DJ		




BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**PENTACHLOROPHENOL
THIESSEN POLYGON MAP**



CITY: CHELMSFORD DIV/GROUP: ENV/EST DB: mbonanduci LD: PIC: PM: TM: 9/30/2014 3:03:08 PM
 PROJECT: PATH: \\arcadis-us.com\OfficeData\Chelmsford-MAA_PRACTICES\Beazer\Carbondale\GIS_SpatialData\GIS\MXD\DL-39283_fig5_ThiessenPolygons_Pyrene.mxd DATE: 9/30/2014 3:03:08 PM




LEGEND:

PYRENE (mg/kg)

- NOT DETECTED
- ≤ 0.4
- 0.4 - 2.4
- 2.4 - 15
- 15 - 85
- 85 - 500
- > 500
- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- - - FENCE
- OFF-SITE PROPERTY
- - - POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA

LOCATION	PYRENE (mg/kg)	LOCATION	PYRENE (mg/kg)	LOCATION	PYRENE (mg/kg)	LOCATION	PYRENE (mg/kg)
A1-10	5.2 J	A1-5	31 J	S1	0.75	SDD-20	3.7
A1-11	1.1	A1-6	0.99	S13	72	SDD-20-15RB	21
A1-13	1.2	A1-9	68 J	S2	0.019	SDD-20-TLB	0.0065 J [0.0048 J]
A1-14	1.5 J	A2-13	0.23 J [1.1 J]	SB-100	150 [130]	SDD-20-TRB	1.3
A1-15	0.13	A2-14	23 DJ	SB-101	19	SDD-26	1.9
A1-16	0.06	A2-15	23 DJ	SB-102	7.5	SDD-26-15N	0.66 [0.71]
A1-19	1.9	A2-16	18 DJ	SB-103	0.31 J	SDD-26-15S	6 [4.1]
A1-2	0.17	A2-17	19 DJ	SB-104	0.28 J	SDD-27	2.7
A1-20	5.4	A2-18	4.1	SB-105	0.024 J	SDD-28	17 J
A1-21	11 J	A2-19	11 DJ [11 DJ]	SB-106	1.7 J	SDD-28-15LB	2.2
A1-22	0.02	A3-18	0.016	SB-107	2.5	SDD-28-15RB	6.1
A1-23	17 J	A3-19	0.19	SB-108	4.1	SDD-28-TLB	7.9 J
A1-24	35 J	A3-20	0.15 J [0.16 J]	SB-109	2.2	SDD-28-TRB	5.4 J
A1-25	43 J	A3-21	13 DJ	SB-114	3	SDD-29	6.9 J
A1-26	45 J	A3-22	1.8 DJ	SB-115	9.6	SDD-29-15LB	25 D
A1-27	7.7 J	A3-23	1.4	SB-116	0.5	SDD-29-15RB	2.8
A1-28	0.39	A3-24	15 DJ	SB-117	1.5 J	SDD-29-TLB	11 J
A1-29	0.75 [0.78]	FPT1-33%L	0.088	SB-118	50	SDD-29-TRB	26 J
A1-3	0.015	FPT1-33%R	0.0087 U	SB-119	2900 D	SDD-30	6.7
A1-30	16 J	FPT1-5'L	0.23	SB-120	16	SDD-31	7.7
A1-31	8.3 J	FPT1-5'R	6.1	SDD-1	11	SDD-32	160 J
A1-32	20 J [0.0092 J]	FPT2-33%L	0.14	SDD-1-15LB	0.32	SDD-33	2.2
A1-33	0.0045 J	FPT2-33%R	0.045	SDD-1-15RB	1.4	SDD-34	0.37
A1-34	0.0094 U	FPT2-5'L	0.36	SDD-12	3.9	SDD-35	2.1
A1-35	0.04	FPT2-5'R	0.57	SDD-12-15LB	28 J	SDD-36	27
A1-36	0.053	FPT3-33%L	0.16 [0.094]	SDD-12-15RB	55 J	SDD-37	0.26 [0.24]
A1-37	58 DJ	FPT3-33%R	0.016	SDD-12-TLB	15	SDD-4	9.8
A1-38	1.8	FPT3-5'L	1.7	SDD-12-TRB	1.8	SDD-4-15LB	2.5
A1-39	0.78	FPT3-5'R	0.13	SDD-15	8	SDD-4-15RB	2.1
A1-4	39 J	FPT4-33%L	0.088	SDD-15-15LB	130 J	SDD-4-TLB	17 J
A1-40	0.6	FPT4-33%R	0.0044 J	SDD-15-15RB	5.2	SDD-4-TRB	3.3 J
A1-41	13 DJ	FPT4-5'L	0.25	SDD-15-TLB	8.3 J	SDD-7	220 D
A1-42	0.013 J	FPT4-5'R	0.39	SDD-15-TRB	18 [22]	SDD-7-15LB	18 J
A1-44	0.38 [0.26]	FPT5-33%L	0.14	SDD-16	12	SDD-7-15RB	11
A1-45	0.016	FPT5-33%R	0.013	SDD-16-SPL	14	SDD-7-TLB	98
A1-46	0.056	FPT5-5'L	0.26	SDD-1-SPL	8.3	SDD-7-TRB	1.5
A1-47	0.12 J	FPT5-5'R	0.11	SDD-1-TLB	1.8 J	SDD-9	33
A1-48	0.13	NPL	0.24	SDD-1-TRB	0.62 J [0.85 J]	SDD-9-TRB	7 J




BEAZER EAST, INC.
 FORMER KOPPERS WOOD-TREATING SITE
 CARBONDALE, ILLINOIS

**PYRENE THIESSEN
 POLYGON MAP**



CITY: CHELMSFORD DIV/GROUP: ENV/EST DB: mbonanduci LD: PIC: PM: TM: PROJECT: PATH: \arcadis-us.com\OfficeData\Chelmsford-MAA_PRACTICES\Beazer\Carbondale\GIS_SpatialData\GIS\MXD\BAP-TE\ThiessenPolygons_BaP.mxd DATE: 9/30/2014 3:06:12 PM




LEGEND:

BaP-TE (mg/kg)

- ≤ 0.2
- 0.2 - 0.95
- 0.95 - 4
- 4 - 17
- 17 - 67
- > 67
- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA

LOCATION	BaP-TE (mg/kg)	LOCATION	BaP-TE (mg/kg)	LOCATION	BaP-TE (mg/kg)	LOCATION	BaP-TE (mg/kg)
A1-10	7.13	A1-5	29.1	S1	0.63	SDD-20	5.74
A1-11	1.46	A1-6	1.42	S13	78.4	SDD-20-15RB	19.6
A1-13	1.78	A1-9	75.1	S2	0.02	SDD-20-TLB	0.00977 [0.00973]
A1-14	3.03	A2-13	0.295 [0.829]	SB-100	77.8 [79]	SDD-20-TRB	1.58
A1-15	0.134	A2-14	27.9	SB-101	21.4	SDD-26	2.23
A1-16	0.0483	A2-15	67.6	SB-102	11.3	SDD-26-15N	1.12 [0.711]
A1-19	2.09	A2-16	49.9	SB-103	0.344	SDD-26-15S	6.72 [5.2]
A1-2	0.163	A2-17	27	SB-104	0.22	SDD-27	2.2
A1-20	4.6	A2-18	5.34	SB-105	0.363	SDD-28	23
A1-21	16	A2-19	28.8 [29.2]	SB-106	2.35	SDD-28-15LB	2.58
A1-22	0.0216	A3-18	0.0197	SB-107	1.65	SDD-28-15RB	5.46
A1-23	21.7	A3-19	0.271	SB-108	4.88	SDD-28-TLB	10.3
A1-24	23.1	A3-20	0.201 [0.218]	SB-109	1.56	SDD-28-TRB	5.65
A1-25	33.6	A3-21	9.32	SB-114	11.7	SDD-29	9.22
A1-26	47.7	A3-22	2.35	SB-115	9.86	SDD-29-15LB	5.48
A1-27	10.3	A3-23	2.82	SB-116	0.442	SDD-29-15RB	4.01
A1-28	0.55	A3-24	37.2	SB-117	2.08	SDD-29-TLB	7.05
A1-29	0.751 [0.708]	FPT1-33%L	0.321	SB-118	54.8	SDD-29-TRB	50.8
A1-3	0.0187	FPT1-33%R	0.00988	SB-119	275	SDD-30	11.3
A1-30	23.6	FPT1-5'L	1.31	SB-120	26.9	SDD-31	15.3
A1-31	9.64	FPT1-5'R	24.4	SDD-1	17.5	SDD-32	107
A1-32	19.6 [0.0105]	FPT2-33%L	0.322	SDD-1-15LB	0.297	SDD-33	3.29
A1-33	0.00936	FPT2-33%R	0.108	SDD-1-15RB	1.99	SDD-34	0.44
A1-34	0.0105	FPT2-5'L	1.9	SDD-12	4.51	SDD-35	1.92
A1-35	0.0635	FPT2-5'R	4.58	SDD-12-15LB	48.1	SDD-36	28
A1-36	0.0865	FPT3-33%L	1 [0.449]	SDD-12-15RB	63	SDD-37	0.453 [0.503]
A1-37	32.4	FPT3-33%R	0.0302	SDD-12-TLB	14.1	SDD-4	12.1
A1-38	1.87	FPT3-5'L	14.8	SDD-12-TRB	3.49	SDD-4-15LB	2.86
A1-39	0.575	FPT3-5'R	0.839	SDD-15	18.7	SDD-4-15RB	1.2
A1-4	31.7	FPT4-33%L	0.559	SDD-15-15LB	74	SDD-4-TLB	18.8
A1-40	0.492	FPT4-33%R	0.00969	SDD-15-15RB	5.31	SDD-4-TRB	3.35
A1-41	9.39	FPT4-5'L	1.42	SDD-15-TLB	10.2	SDD-7	69.5
A1-42	0.0231	FPT4-5'R	2.87	SDD-15-TRB	27.3 [19]	SDD-7-15LB	21.3
A1-44	0.28 [0.268]	FPT5-33%L	0.94	SDD-16	7.32	SDD-7-15RB	15.4
A1-45	0.0155	FPT5-33%R	0.026	SDD-16-SPL	18.5	SDD-7-TLB	51.4
A1-46	0.0684	FPT5-5'L	1.64	SDD-1-SPL	20.2	SDD-7-TRB	1.94
A1-47	0.147	FPT5-5'R	0.797	SDD-1-TLB	1.97	SDD-9	28.2
A1-48	0.142	NPL	0.195	SDD-1-TRB	1.08 [0.875]	SDD-9-TRB	9.99




BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**BAP-TE THIESSEN
POLYGON MAP**



CITY: CHELMSFORD DIV/GROUP: ENV/EST DB: mbonanduci LD: PIC: PM: TM: PROJECT: \P\TH: \arcadis-us.com\OfficeData\Chelmsford-MAA_P\PROJECTS\Beazer\Carbondale\GIS_SpatialData\GIS\MXDs\IL-39283_fig7_ThiessenPolygons_Ars.mxd DATE: 9/30/2014 4:01:13 PM




LEGEND:

ARSENIC (mg/kg)

- ≤ 7
- 7 - 11
- 11 - 16
- 16 - 26
- 26 - 40
- > 40

- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- - - POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA


LOCATION	ARSENIC (mg/kg)	LOCATION	ARSENIC (mg/kg)	LOCATION	ARSENIC (mg/kg)	LOCATION	ARSENIC (mg/kg)
A1-10	10	A1-41	11.5	FPT2-5'R	6.9	SDD-20-TRB	8.8
A1-11	36.4	A1-42	8.7	FPT3-33%L	6.7	SDD-26	38.2
A1-12	14.5	A1-44	11.6 [14.1]	FPT3-33%R	9.9	SDD-26-15N	28.9 [23.8]
A1-13	13.9	A1-45	12	FPT3-5'L	8.5	SDD-26-15S	23 J [13.4 J]
A1-14	20.9	A1-46	6.5	FPT3-5'R	7.3	SDD-27	23.5
A1-15	12.2	A1-47	17.6	FPT4-33%L	9	SDD-28	25.1
A1-16	14.4	A1-48	8.4	FPT4-33%R	7.9	SDD-28-15LB	16.4
A1-17	26.5	A1-6	32.7	FPT4-5'L	6.8	SDD-28-TLB	16.2
A1-19	4.2	A1-7	11.1	FPT4-5'R	6.5	SDD-28-TRB	6.3
A1-20	8.5	A1-9	23.3	FPT5-33%L	5.8	SDD-29	26.5
A1-21	16	A2-13	12.1 [12.6]	FPT5-33%R	10.7	SDD-29-15LB	29.9
A1-22	10.5	A2-14	14.8	FPT5-5'L	6.5	SDD-29-15RB	1.1
A1-23	18.6	A2-15	63.8	FPT5-5'R	10.2	SDD-29-TLB	26.8
A1-24	14.3	A2-16	44.4	NPL	9.6	SDD-29-TRB	22.6
A1-25	12.5	A2-17	25.2	SDD-1	21.5	SDD-32	13.5 J
A1-26	7.5	A2-18	13.8	SDD-12-15LB	12.8	SDD-33	27.8
A1-27	13.8	A2-19	50.4 [35.8]	SDD-12-15RB	17.6	SDD-34	8.3
A1-28	12.5	A3-18	6	SDD-12A	37.6 J	SDD-35	36.4
A1-29	10.3 [7.8]	A3-19	14.2	SDD-12-TLB	18 J	SDD-36	18.2
A1-3	10.2	A3-20	11 [10.8]	SDD-12-TRB	21	SDD-37	10.3 [10.3]
A1-30	8.8	A3-21	43.2	SDD-15	32	SDD-4-15LB	7.6
A1-31	32.8	A3-22	9.9	SDD-15-15LB	10.1	SDD-4A	11.4
A1-32	10.8 [10]	A3-23	14.1	SDD-15-15RB	25.8	SDD-4-TLB	13.3
A1-33	11.7	A3-24	19	SDD-15-TLB	22.4	SDD-4-TRB	4.3
A1-34	9.5	FPT1-33%L	6.3	SDD-15-TRB	25.3 [23.2]	SDD-7	15.6
A1-35	10.5	FPT1-33%R	5 J	SDD-16	8	SDD-7-15LB	10
A1-36	13.5	FPT1-5'L	7.4 J	SDD-1-SPL	7.6	SDD-7-TLB	18.5
A1-37	9	FPT1-5'R	7.1 J	SDD-1-TLB	6.7	SDD-7-TRB	9.3
A1-38	9.3	FPT2-33%L	8.1	SDD-1-TRB	1.9 [3.5]	SDD-9	13.5
A1-39	5.2	FPT2-33%R	8.3	SDD-20A	18.7 J	SDD-9-TRB	32.5
A1-40	10.3	FPT2-5'L	11.6	SDD-20-TLB	8 J [6.9 J]		



BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**ARSENIC THIESSEN
POLYGON MAP**






LEGEND:

CHROMIUM (mg/kg)

- ≤ 16
- 16 - 18
- 18 - 23
- 23 - 36
- 36 - 68
- > 68


- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- ABANDONED RAILROAD
- SITE FEATURES
- FENCE
- OFF-SITE PROPERTY
- POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA



BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**CHROMIUM THIESSEN
POLYGON MAP**

LOCATION	CHROMIUM (mg/kg)	LOCATION	CHROMIUM (mg/kg)	LOCATION	CHROMIUM (mg/kg)
A1-35	15.5 J	A2-16	155 J	FPT2-33%R	23.2
A1-36	19.4 J	A2-17	78.3 J	FPT2-5'L	18.3
A1-37	15.3 J	A2-18	42.4 J	FPT2-5'R	18.4
A1-38	15.8 J	A2-19	154 J [153 J]	FPT3-33%L	17
A1-39	11.9 J	A3-18	18.1	FPT3-33%R	23.3
A1-40	17.8	A3-19	22.5	FPT3-5'L	18.5
A1-41	19.6	A3-20	25.4 [23.6]	FPT3-5'R	19.6
A1-42	17.1	A3-21	53.4	FPT4-33%L	19.1
A1-44	18.6 [14.5]	A3-22	26.7	FPT4-33%R	17
A1-45	20.7	A3-23	21.6	FPT4-5'L	16.7
A1-46	20.1	A3-24	41.1	FPT4-5'R	17.1
A1-47	18.8	FPT1-33%L	17.7	FPT5-33%L	13.7
A1-48	18.5	FPT1-33%R	18.7	FPT5-33%R	20.2
A2-13	17.1 [19.2 J]	FPT1-5'L	16.5	FPT5-5'L	16.3
A2-14	32.9 J	FPT1-5'R	17	FPT5-5'R	24.9
A2-15	138 J	FPT2-33%L	21.7	NPL	12.9 J




LEGEND:

TCDD-TEQ (ug/kg)

- ≤ 0.05
- 0.05 - 0.7
- 0.7 - 1
- 1 - 5
- 5 - 20
- > 20

- GLADE CREEK OLD LOCATION
- RIVER/CREEK
- DRAINAGE DITCH
- WETLAND
- - - CAMU CONTAINMENT AREA
- - - ABANDONED RAILROAD
- - - SITE FEATURES
- - - FENCE
- - - OFF-SITE PROPERTY
- - - POTENTIAL BIKE PATH
- - - PROPERTY BOUNDARY
- POTENTIAL BIKE PATH LOCATION
- WESTERN CONSERVATION EXPOSURE AREA
- CENTRAL CONSERVATION EXPOSURE AREA
- PROPOSED NON-GRAVEL SOLAR USE AREA
- PROPOSED GRAVEL SOLAR USE AREA
- SOUTHERN CONSERVATION EXPOSURE AREA
- EASTERN CONSERVATION EXPOSURE AREA
- RAILROAD PROPERTY EXPOSURE AREA
- 35' SWATH EXPOSURE AREA
- SOIL CAP
- SOIL REMOVAL AREA

LOCATION	TCDD-TEQ (ug/kg)	LOCATION	TCDD-TEQ (ug/kg)	LOCATION	TCDD-TEQ (ug/kg)	LOCATION	TCDD-TEQ (ug/kg)
A1-1	9.82 [5.39]	A1-41	0.0712	A3-1	1.36	A3-5	1.23 [0.529]
A1-12	0.814	A1-42	0.00651	A3-10	1.66 [1.94]	A3-6	1.77
A1-16	5.61	A1-44	0.0291	A3-11	0.279	A3-7	0.00861
A1-17	2.01	A1-45	0.00431	A3-12	4.63	A3-8	1.28
A1-18	0.052	A1-46	0.00442	A3-13	0.128	A3-9	1.54
A1-19	0.704	A1-47	0.0212	A3-14	35.6	A5-1	0.0115 [0.011]
A1-20	1.03	A1-48	0.183	A3-15	1.21	A5-2	0.00299
A1-21	26.1	A1-5	0.463	A3-16	0.73	A5-3	0.0191
A1-22	0.0064	A1-50	0.0211 [0.0224]	A3-17	2.39	A5-4	0.0192
A1-23	7.12	A1-62	1.77	A3-18	0.00448	FPT1-5'L	0.0584
A1-24	0.906	A1-8	4.64	A3-19	0.0672	FPT1-5'R	0.283
A1-25	1.87	A1-9	8.98	A3-2	2.54	FPT2-33%L	0.433
A1-26	1.7	A2-1	0.114	A3-20	0.124 [0.138]	FPT2-33%R	0.0812
A1-27	4.01	A2-10	0.005	A3-21	4.27	FPT3-5'L	0.188
A1-28	0.0626	A2-13	0.0297 [0.0729]	A3-22	2.75	FPT3-5'R	0.0716
A1-29	0.0223	A2-14	6.3	A3-23	0.771	FPT4-33%L	0.0598
A1-3	0.00877	A2-15	1.56	A3-24	5.08	FPT4-33%R	0.0699
A1-30	24.8	A2-16	5.09	A3-25	0.0241	FPT5-5'L	0.0844
A1-31	5.84	A2-17	3.84	A3-26	0.153	FPT5-5'R	0.212
A1-32	0.0285 [0.0454]	A2-18	1.06	A3-27	0.0224	NPL	0.016
A1-33	0.00318	A2-19	5.08	A3-28	7.31	SDD-1	2.51
A1-34	0.00484	A2-2	2.54	A3-3	0.376	SDD-15	6.29
A1-35	0.0126	A2-3	0.0238	A3-31	0.0517	SDD-16	13.2
A1-36	0.0104	A2-5	0.00901	A3-32	0.707 [0.835]	SDD-26	0.796
A1-37	0.261 [0.396]	A2-7	11.7	A3-33	0.965	SDD-27	7.93
A1-38	0.00819	A2-8	8.73	A3-34	0.155	SDD-7	1.81
A1-39	0.074	A2-9	19.6	A3-4	1.5	SDD-9	5.43
A1-40	0.0154						



BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

**DIOXIN-FURAN THIESSEN
POLYGON MAP**





Appendix A

Data by Media

**APPENDIX A
ON-SITE SOIL
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Units	SDD-7 0 - 0.5 03/08/06	SDD-7-15LB 0 - 0.5 03/10/08	SDD-7-15RB 0 - 0.5 03/10/08	SDD-7-TLB 0 - 0.5 03/13/08	SDD-7-TLB 0.5 - 2 03/13/08	SDD-7-TLB 2 - 6 03/13/08	SDD-7-TRB 0 - 0.5 03/10/08	SDD-9 0 - 0.5 03/08/06	SDD-9 1.5 - 2 03/08/06	SDD-9-TRB 0 - 0.5 03/08/08	S13 0 - 0.5 3/3/05
SVOCs													
120-82-1	1,2,4-Trichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
106-46-7	1,4-Dichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
90-12-0	1-Methylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
832-69-9	1-Methylphenanthrene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2245-38-7	2,3,5-Trimethylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
121-14-2	2,4-Dinitrotoluene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
28804-88-8	2,6-Dimethylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
95-57-8	2-Chlorophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
91-57-6	2-Methylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
101-55-3	4-Bromophenyl Phenyl Ether	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
59-50-7	4-Chloro-3-methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
106-44-5	4-Methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
100-02-7	4-Nitrophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
83-32-9	Acenaphthene	ug/kg	170,000 D	460 J	120 J	10,000	1,100,000 DJ	180,000 D	24	1,100	110,000 D [68,000 D]	390	1200
208-96-8	Acenaphthylene	ug/kg	16,000	5,500 J	3,000	7,400	81,000 J	8,500	400	6,600	2,100 [1,200]	3,500	34000
120-12-7	Anthracene	ug/kg	87,000	9,000 J	2,600	13,000	500,000 J	97,000 D	460	14,000	53,000 D [27,000 D]	5,400	200000
56-55-3	Benzo(a)anthracene	ug/kg	66,000	19,000 J	7,000	41,000	1,100,000 J	44,000 D	1,100	20,000	23,000 D [14,000 D]	5,500	44000
50-32-8	Benzo(a)pyrene	ug/kg	44,000	11,000 J	9,800	31,000	420,000 J	18,000	1,100	17,000	6,900 [4,100]	5,600	49000
205-99-2	Benzo(b)fluoranthene	ug/kg	62,000	40,000 JX	17,000	73,000 JX	780,000 JX	35,000 JX	2,600 JX	33,000	9,400 [5,700]	15,000	80000
192-97-2	Benzo(e)pyrene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
191-24-2	Benzo(ghi)perylene	ug/kg	34,000	8,100 J	7,400	19,000	220,000 J	9,000	1,300 J	15,000	3,100 [1,800]	5,200	42000
207-08-9	Benzo(k)fluoranthene	ug/kg	28,000	40,000 JX	8,100	77,000 JX	850,000 JX	38,000 JX	2,900 JX	10,000	3,400 [2,000]	7,700	58000
92-52-4	Biphenyl	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
85-68-7	Butyl Benzyl Phthalate	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
86-74-8	Carbazole	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
218-01-9	Chrysene	ug/kg	81,000	30,000 J	11,000	57,000	930,000 J	50,000 D	1,700	32,000	28,000 D [14,000 D]	9,100	71000
53-70-3	Dibenzo(a,h)anthracene	ug/kg	9,200	2,900 J	2,400	6,200	61,000 J	2,900	320	4,400	940 [550]	1,700	11000
132-65-0	Dibenzothiophene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
206-44-0	Fluoranthene	ug/kg	380,000 D	33,000 J	9,600	120,000	4,900,000 DJ	260,000 D	2,200	36,000	150,000 D [92,000 D]	9,400	64000
86-73-7	Fluorene	ug/kg	160,000 D	830 J	390	1,500	670,000 J	180,000 D	38	1,400	90,000 D [55,000 D]	520	1700
67-72-1	Hexachloroethane	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
193-39-5	Indeno(1,2,3-cd)pyrene	ug/kg	31,000	11,000 J	7,100	20,000	210,000 J	8,900	1,200	14,000	2,900 [1,700]	5,500	53000
91-20-3	Naphthalene	ug/kg	240,000 D	1,800 J	590	510 J	7,000 J	680,000 D	54	2,000	80,000 D [49,000 D]	400 J	6800
621-64-7	N-nitrosodi-n-propylamine	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
87-86-5	Pentachlorophenol	ug/kg	4,200 J	550 J	NA	8,400	26,000 J	2,000	230	10,000 J	7,200 J [4,300 J]	5,500	2200
198-55-0	Perylene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
85-01-8	Phenanthrene	ug/kg	390,000 D	4,200 J	1,600	3,800	1,800,000 DJ	620,000 D	180	6,600	230,000 D [150,000 D]	1,900	11000
108-95-2	Phenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
129-00-0	Pyrene	ug/kg	220,000 D	18,000 J	11,000	98,000	2,500,000 DJ	150,000 D	1,500	33,000	73,000 D [48,000 D]	7,000 J	72000
50-32-8	BaP-TE (NDs = 1/2 DL)	ug/kg	69,500	21,300	15,400	51,400	699,000	30,100	1,940	28,200	11,400 [6,820]	9,900	78400
Metals													
7440-38-2	Arsenic	ug/kg	15,600	10,000	NA	18,500	9,400	19,100	9,300	13,500	8,600 [8,800]	32,500	NA
7440-47-3	Chromium	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
7440-50-8	Copper	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Dioxins/Furans													
35822-46-9	1,2,3,4,6,7,8-HpCDD	ug/kg	78.5	NA	NA	NA	NA	NA	NA	225	2.57 [2.58]	NA	NA
67562-39-4	1,2,3,4,6,7,8-HpCDF	ug/kg	13.6	NA	NA	NA	NA	NA	NA	33.2 J	0.282 [0.259]	NA	NA
55673-89-7	1,2,3,4,7,8,9-HpCDF	ug/kg	1.04	NA	NA	NA	NA	NA	NA	2.63	0.0176 [0.0151]	NA	NA
39227-28-6	1,2,3,4,7,8-HxCDD	ug/kg	0.34	NA	NA	NA	NA	NA	NA	1.2	0.00713 [0.00607]	NA	NA
70648-26-9	1,2,3,4,7,8-HxCDF	ug/kg	0.549	NA	NA	NA	NA	NA	NA	3.9 J	0.0114 [0.0114]	NA	NA
57653-85-7	1,2,3,6,7,8-HxCDD	ug/kg	2.07	NA	NA	NA	NA	NA	NA	5.91	0.0472 [0.0464]	NA	NA
57117-44-9	1,2,3,6,7,8-HxCDF	ug/kg	0.158 J	NA	NA	NA	NA	NA	NA	0.902 J	0.00343 [0.00309 J]	NA	NA
19408-74-3	1,2,3,7,8,9-HxCDD	ug/kg	0.683	NA	NA	NA	NA	NA	NA	1.68	0.0153 [0.0152]	NA	NA
72918-21-9	1,2,3,7,8,9-HxCDF	ug/kg	0.0241	NA	NA	NA	NA	NA	NA	0.808	0.000535 J [0.000655 J]	NA	NA
40321-76-4	1,2,3,7,8-PeCDD	ug/kg	0.0789	NA	NA	NA	NA	NA	NA	0.297	0.00133 J [0.00133 J]	NA	NA
57117-41-6	1,2,3,7,8-PeCDF	ug/kg	0.0191	NA	NA	NA	NA	NA	NA	0.169	0.00114 J [0.00108 J]	NA	NA
60851-34-5	2,3,4,6,7,8-HxCDF	ug/kg	0.4	NA	NA	NA	NA	NA	NA	1.3	0.0056 [0.00501]	NA	NA
57117-31-4	2,3,4,7,8-PeCDF	ug/kg	0.129	NA	NA	NA	NA	NA	NA	1.27	0.00426 [0.00465]	NA	NA
1746-01-6	2,3,7,8-TCDD	ug/kg	0.00666	NA	NA	NA	NA	NA	NA	0.0268	0.000479 J [0.000476 U]	NA	NA
51207-31-9	2,3,7,8-TCDF	ug/kg	0.00418	NA	NA	NA	NA	NA	NA	0.0382	0.000374 J [0.000346 J]	NA	NA
3268-87-9	OCDD	ug/kg	1,030	NA	NA	NA	NA	NA	NA	1,600	104 [98.8]	NA	NA
39001-02-0	OCDF	ug/kg	85	NA	NA	NA	NA	NA	NA	187	2.18 [1.97]	NA	NA
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	ug/kg	1.81	NA	NA	NA	NA	NA	NA	5.43	0.0728 [0.0706]	NA	NA

ug/kg = microgram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
NDs = non-detects
DL = detection limit
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equi
NA = not available

**APPENDIX A
SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Units	GC-BC-FPT6-33%L	GC-BC-FPT6-33%L	GC-BC-FPT6-33%R	GC-BC-FPT6-33%R	GC-BC-FPT6-5L	GC-BC-FPT6-5L	GC-BC-FPT6-5R	GC-BC-FPT6-5R
			0 - 0.5 03/12/08	0.5 - 2 03/12/08	0 - 0.5 03/12/08	0.5 - 2 03/12/08	0 - 0.5 03/12/08	0.5 - 2 03/12/08	0 - 0.5 03/12/08	0.5 - 2 03/12/08
SVOCs										
120-82-1	1,2,4-Trichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
106-46-7	1,4-Dichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
90-12-0	1-Methylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
832-69-9	1-Methylphenanthrene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
2245-38-7	2,3,5-Trimethylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
121-14-2	2,4-Dinitrotoluene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
28804-88-8	2,6-Dimethylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
95-57-8	2-Chlorophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
91-57-6	2-Methylnaphthalene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
101-55-3	4-Bromophenyl Phenyl Ether	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
59-50-7	4-Chloro-3-methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
106-44-5	4-Methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
100-02-7	4-Nitrophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
83-32-9	Acenaphthene	ug/kg	3.2 J	8.7 U	5.1 J	9.1 U	4.4 J	3.3 J	7.3 J	3.7 J [3.4 J]
208-96-8	Acenaphthylene	ug/kg	23	19	16	10	37	67	41	38 [39]
120-12-7	Anthracene	ug/kg	32	27	25	15	49	80	48	50 [52]
56-55-3	Benzo(a)anthracene	ug/kg	56	25	95	44	91	80	110	88 [83]
50-32-8	Benzo(a)pyrene	ug/kg	80	39	130	49	120	140	140	120 [130]
205-99-2	Benzo(b)fluoranthene	ug/kg	150 JX	71 JX	230 JX	86 JX	220 JX	250 JX	260 JX	180 [220 JX]
192-97-2	Benzo(e)pyrene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
191-24-2	Benzo(ghi)perylene	ug/kg	71	49	140	48	120	200	160	130 [130]
207-08-9	Benzo(k)fluoranthene	ug/kg	150 JX	77 JX	230 JX	93 JX	220 JX	280 JX	260 JX	50 [240 JX]
92-52-4	Biphenyl	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
85-68-7	Butyl Benzyl Phthalate	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
86-74-8	Carbazole	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
218-01-9	Chrysene	ug/kg	83	32	140	49	120	110	140	95 [110]
53-70-3	Dibenzo(a,h)anthracene	ug/kg	20	12	32	9.9	24	42	36	26 [27]
132-65-0	Dibenzothiophene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
206-44-0	Fluoranthene	ug/kg	34	21	160	58	85	49	130	88 [79]
86-73-7	Fluorene	ug/kg	7.6 J	4 J	7.5 J	3.7 J	12	11	14	8 J [7.7 J]
67-72-1	Hexachloroethane	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
193-39-5	Indeno(1,2,3-cd)pyrene	ug/kg	62	42	120	41	100	180	140	110 [120]
91-20-3	Naphthalene	ug/kg	3.4 J	3.1 J	6 J	4.2 J	4.6 J	8.6 J	9.4	8.5 J [9.5]
621-64-7	N-nitrosodi-n-propylamine	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
87-86-5	Pentachlorophenol	ug/kg	NA	52	NA	8 J	8.7 J	NA	7.2 J	NA
198-55-0	Perylene	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
85-01-8	Phenanthrene	ug/kg	17	13	53	29	30	26	52	36 [30]
108-95-2	Phenol	ug/kg	NA	NA	NA	NA	NA	NA	NA	NA
129-00-0	Pyrene	ug/kg	47	22	160	49	94	54	140	72 [76]
50-32-8	BaP-TE (NDs = 1/2 DL)	ug/kg	128	65.6	209	77	187	236	230	184 [202]
Metals										
7440-38-2	Arsenic	ug/kg	7,600	9,400	7,200	7,700	6,300	7,500	6,400	8,000 [8,300]
7440-47-3	Chromium	ug/kg	18,900	20,400	16,600	27,400	15,800	21,700	16,500	22,800 [21,800]
7440-50-8	Copper	ug/kg	18,200	19,400	18,700	27,600	16,000	22,800	17,000	24,700 [23,600]
Dioxins/Furans										
35822-46-9	1,2,3,4,6,7,8-HpCDD	ug/kg	0.603	NA	0.436	NA	NA	7.34	NA	2.1 [1.27]
67562-39-4	1,2,3,4,6,7,8-HpCDF	ug/kg	0.099	NA	0.0696	NA	NA	1.57	NA	0.328 [0.22]
55673-89-7	1,2,3,4,7,8,9-HpCDF	ug/kg	0.0078	NA	0.00525	NA	NA	0.115	NA	0.0208 [0.0163]
39227-28-6	1,2,3,4,7,8-HxCDD	ug/kg	0.00526	NA	0.0041	NA	NA	0.0283	NA	0.0135 [0.0102]
70648-26-9	1,2,3,4,7,8-HxCDF	ug/kg	0.00444	NA	0.00312	NA	NA	0.0481	NA	0.011 [0.00852]
57653-85-7	1,2,3,6,7,8-HxCDD	ug/kg	0.0182	NA	0.0126	NA	NA	0.232	NA	0.0519 [0.0316]
57117-44-9	1,2,3,6,7,8-HxCDF	ug/kg	0.00168 J	NA	0.00168 J	NA	NA	0.0163 J	NA	0.0037 [0.0027]
19408-74-3	1,2,3,7,8,9-HxCDD	ug/kg	0.00703	NA	0.00696	NA	NA	0.0546	NA	0.0184 [0.0108]
72918-21-9	1,2,3,7,8,9-HxCDF	ug/kg	0.00111 J	NA	0.000768 J	NA	NA	0.00825	NA	0.0025 J [0.00223 J]
40321-76-4	1,2,3,7,8-PeCDD	ug/kg	0.0016 J	NA	0.00148 J	NA	NA	0.00521	NA	0.0029 [0.00177 J]
57117-41-6	1,2,3,7,8-PeCDF	ug/kg	0.000435 J	NA	0.000492 J	NA	NA	0.00202 J	NA	0.00101 J [0.000755 J]
60851-34-5	2,3,4,6,7,8-HxCDF	ug/kg	0.00374	NA	0.00255	NA	NA	0.0303	NA	0.00776 [0.00578]
57117-31-4	2,3,4,7,8-PeCDF	ug/kg	0.00233 J	NA	0.00155 J	NA	NA	0.0123	NA	0.00567 [0.00458]
1746-01-6	2,3,7,8-TCDD	ug/kg	0.000313 J	NA	0.00032 UX	NA	NA	0.000416 J	NA	0.000575 [0.000387 J]
51207-31-9	2,3,7,8-TCDF	ug/kg	0.000529	NA	0.000609	NA	NA	0.0012	NA	0.000974 [0.000741]
3268-87-9	OCDD	ug/kg	8.82	NA	8.69	NA	NA	68.1 D	NA	29.7 [18.3]
39001-02-0	OCDF	ug/kg	0.55	NA	0.328	NA	NA	8.66	NA	1.88 [1.31]
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	ug/kg	0.0167	NA	0.0132	NA	NA	0.165	NA	0.0501 [0.0318]

ug/kg = microgram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
NDs = non-detects
DL = detection limit
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents
NA = not available

**APPENDIX A
CRAB ORCHARD CREEK AND PILES FORK SEDIMENT
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

CAS	Parameter	Units	GC-BC-16 0 - 0.5 06/26/08	GC-BC-17 0 - 0.5 06/26/08	PF-BC-03 0 - 0.5 06/26/08	PF-BC-03 0 - 0.5 07/21/10	PF-BC-03-NAPL 07/22/10	PF-BC-04 0 - 0.5 06/26/08	PF-BC-04 0 - 0.5 07/15/10
SVOCs									
120-82-1	1,2,4-Trichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA
106-46-7	1,4-Dichlorobenzene	ug/kg	NA	NA	NA	NA	NA	NA	NA
90-12-0	1-Methylnaphthalene	ug/kg	NA	NA	NA	92	1,000	NA	NA
832-69-9	1-Methylphenanthrene	ug/kg	NA	NA	NA	110	1,500	NA	NA
2245-38-7	2,3,5-Trimethylnaphthalene	ug/kg	NA	NA	NA	37	460	NA	NA
121-14-2	2,4-Dinitrotoluene	ug/kg	NA	NA	NA	NA	NA	NA	NA
28804-88-8	2,6-Dimethylnaphthalene	ug/kg	NA	NA	NA	65	890	NA	NA
95-57-8	2-Chlorophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA
91-57-6	2-Methylnaphthalene	ug/kg	NA	NA	NA	32	560	NA	NA
101-55-3	4-Bromophenyl Phenyl Ether	ug/kg	NA	NA	NA	NA	NA	NA	NA
59-50-7	4-Chloro-3-methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA
106-44-5	4-Methylphenol	ug/kg	NA	NA	NA	NA	NA	NA	NA
100-02-7	4-Nitrophenol	ug/kg	NA	NA	NA	NA	NA	NA	NA
83-32-9	Acenaphthene	ug/kg	83 UJ	56 UJ [55 UJ]	720 J	450 D	2,600	140 J	82
208-96-8	Acenaphthylene	ug/kg	280 J	32 J [29 J]	120 J	11	110	76 J	110
120-12-7	Anthracene	ug/kg	240 J	41 J [57 J]	530 J	170	2,300	150 J	210
56-55-3	Benzo(a)anthracene	ug/kg	320 J	180 J [200 J]	2,000 J	410 DJ	4,000	410 J	950
50-32-8	Benzo(a)pyrene	ug/kg	630 J	270 J [270 J]	1,800 J	400 DJ	3,100	480 J	720
205-99-2	Benzo(b)fluoranthene	ug/kg	800 J	470 JX [520 JX]	2,900 JX	490 DJ	4,100	850 JX	1,300 JY
192-97-2	Benzo(e)pyrene	ug/kg	NA	NA	NA	230	2,100	NA	NA
191-24-2	Benzo(ghi)perylene	ug/kg	700 J	280 J [330 J]	1,200 J	180	1,100	420 J	530
207-08-9	Benzo(k)fluoranthene	ug/kg	300 J	440 JX [540 JX]	2,700 JX	200	1,500	800 JX	1,300 JY
92-52-4	Biphenyl	ug/kg	NA	NA	NA	1.4	50 U	NA	NA
85-68-7	Butyl Benzyl Phthalate	ug/kg	NA	NA	NA	NA	NA	NA	NA
86-74-8	Carbazole	ug/kg	NA	NA	NA	NA	NA	NA	NA
218-01-9	Chrysene	ug/kg	450 J	330 J [370 J]	2,100 J	570 DJ	5,800	640 J	1,200
53-70-3	Dibenzo(a,h)anthracene	ug/kg	160 J	57 J [54 J]	360 J	44	250	75 UJ	130
132-65-0	Dibenzothiophene	ug/kg	NA	NA	NA	94	1,000	NA	NA
206-44-0	Fluoranthene	ug/kg	480 J	640 J [460 J]	6,500 J	1,600 DJ	15,000 DJ	1,500 J	2,100
86-73-7	Fluorene	ug/kg	64 J	56 UJ [20 J]	590 J	300 DJ	2,700	180 J	130
67-72-1	Hexachloroethane	ug/kg	NA	NA	NA	NA	NA	NA	NA
193-39-5	Indeno(1,2,3-cd)pyrene	ug/kg	640 J	230 J [270 J]	1,200 J	150	980	380 J	450
91-20-3	Naphthalene	ug/kg	83 UJ	56 UJ [55 UJ]	37 J	14 J	1,000 U	75 UJ	13 J
621-64-7	N-nitrosodi-n-propylamine	ug/kg	NA	NA	NA	NA	NA	NA	NA
87-86-5	Pentachlorophenol	ug/kg	97 J	280 UJ [270 UJ]	280 UJ	950 UJ	150 J	370 UJ	290 U
198-55-0	Perylene	ug/kg	NA	NA	NA	86	490	NA	NA
85-01-8	Phenanthrene	ug/kg	130 J	210 J [200 J]	3,400 J	1,400 DJ	15,000 DJ	610 J	840
108-95-2	Phenol	ug/kg	NA	NA	NA	NA	NA	NA	NA
129-00-0	Pyrene	ug/kg	370 J	410 J [390 J]	4,100 J	1,100 DJ	12,000	930 J	1,700
50-32-8	BaP-TE (NDs = 1/2 DL)	ug/kg	969	420 [429]	2,800	NA	NA	690	NA
Metals									
7440-38-2	Arsenic	ug/kg	6,700	5,800 [6,100]	6,000	10,200	15,300	8,100	12,800
7440-47-3	Chromium	ug/kg	22,500	15,000 [13,400]	13,900	14,800 J	12,700 J	16,100	15,000 J
7440-50-8	Copper	ug/kg	23,500	15,100 [14,000]	14,000	15,800	15,600	17,400	15,600
Dioxins/Furans									
35822-46-9	1,2,3,4,6,7,8-HpCDD	ug/kg	2.06 J	NA	0.24 J	0.41	NA	1.89 J	1.27
67562-39-4	1,2,3,4,6,7,8-HpCDF	ug/kg	0.276 J	NA	0.0276 J	0.034	NA	0.272 J	0.167
55673-89-7	1,2,3,4,7,8,9-HpCDF	ug/kg	0.0194 J	NA	0.0025 J	0.00346 J	NA	0.0288 J	0.012
39227-28-6	1,2,3,4,7,8-HxCDD	ug/kg	0.0171 J	NA	0.00249 J	0.00403 J	NA	0.0197 J	0.00827
70648-26-9	1,2,3,4,7,8-HxCDF	ug/kg	0.0102 J	NA	0.00146 J	0.0023 J	NA	0.012 J	0.00676
57653-85-7	1,2,3,6,7,8-HxCDD	ug/kg	0.0464 J	NA	0.00554 J	0.00994	NA	0.0385 J	0.0262
57117-44-9	1,2,3,6,7,8-HxCDF	ug/kg	0.00391 J	NA	0.00108 J	0.000619 J	NA	0.00577 J	0.0025 J
19408-74-3	1,2,3,7,8,9-HxCDD	ug/kg	0.0202 J	NA	0.00423 J	0.00297 J	NA	0.0162 J	0.00914
72918-21-9	1,2,3,7,8,9-HxCDF	ug/kg	0.0023 J	NA	0.000546 J	0.00082 J	NA	0.00356 J	0.00156 J
40321-76-4	1,2,3,7,8-PeCDD	ug/kg	0.00432 J	NA	0.00102 J	0.000928 J	NA	0.00262 J	0.00166 J
57117-41-6	1,2,3,7,8-PeCDF	ug/kg	0.000925 J	NA	0.000283 J	0.000243 UJ	NA	0.000953 J	0.000379 UJ
60851-34-5	2,3,4,6,7,8-HxCDF	ug/kg	0.00702 J	NA	0.00154 J	0.00156 J	NA	0.011 J	0.00407 J
57117-31-4	2,3,4,7,8-PeCDF	ug/kg	0.003 J	NA	0.000847 J	0.00147 J	NA	0.00369 J	0.00261 J
1746-01-6	2,3,7,8-TCDD	ug/kg	0.000701 J	NA	0.000295 UJ	0.000263 UJ	NA	0.000518 J	0.000362 UJ
51207-31-9	2,3,7,8-TCDF	ug/kg	0.000689 J	NA	0.000354 J	0.000341 J	NA	0.00132 J	0.000568 J
3268-87-9	OCDD	ug/kg	47.3 J	NA	8.21 J	5.57	NA	23.8 DJ	24.2 EJ
39001-02-0	OCDF	ug/kg	1.62 J	NA	0.105 J	0.212	NA	1.33 J	0.992
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	ug/kg	0.055	NA	0.00835	0.00997	NA	0.0445	0.0306

ug/kg = microgram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
NDs = non-detects
DL = detection limit
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalent
NA = not available

APPENDIX A
CRAB OCHARD CREEK AND PILES FORK SURFACE WATER
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

CAS	Parameter	Units	GC-BC-05	GC-BC-08	GC-BC-10	GC-BC-11
			06/27/08	06/27/08	06/26/08	06/26/08
SVOCs						
87-86-5	Pentachlorophenol	ug/L	0.76 J	0.98 UJ	1.1 UJ	0.94 UJ [0.94 UJ]
83-32-9	Acenaphthene	ug/L	0.22 J	0.2 UJ	0.24 J	0.18 J [0.18 J]
208-96-8	Acenaphthylene	ug/L	0.15 J	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
120-12-7	Anthracene	ug/L	0.27 J	0.22 J	0.23 J	0.19 UJ [0.22 J]
56-55-3	Benzo(a)anthracene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
50-32-8	Benzo(a)pyrene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
205-99-2	Benzo(b)fluoranthene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
191-24-2	Benzo(ghi)perylene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
207-08-9	Benzo(k)fluoranthene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
218-01-9	Chrysene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
53-70-3	Dibenzo(a,h)anthracene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
206-44-0	Fluoranthene	ug/L	0.38 J	0.2 UJ	0.37 J	0.33 J [0.34 J]
86-73-7	Fluorene	ug/L	0.44 J	0.2 UJ	0.21 UJ	0.37 J [0.36 J]
193-39-5	Indeno(1,2,3-cd)pyrene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
91-20-3	Naphthalene	ug/L	0.21 UJ	0.2 UJ	0.21 UJ	0.19 UJ [0.19 UJ]
85-01-8	Phenanthrene	ug/L	0.37 J	0.23 J	0.28 J	0.31 J [0.25 J]
129-00-0	Pyrene	ug/L	0.074 J	0.2 UJ	0.071 J	0.064 J [0.071 J]
Metals						
7440-38-2	Arsenic	ug/L	4.1 B	2.6 B	3 B	3 B [2.3 B]
7440-47-3	Chromium	ug/L	1.8 B	1.8 B	1.3 B	5 U [5 U]
7440-50-8	Copper	ug/L	2.8 B	2.9 B	2.5 B	1.4 B [1.4 B]
Miscellaneous						
NA	Total Suspended Solids	mg/L	38	22	11.6	6 [4 U]

ug/L = microgram per liter

COPC = constituent of potential concern

SVOCs = semi-volatile organic compounds

APPENDIX A
CATFISH
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS

CAS	Parameter	Units	COC-BC-04-EDCAT	COC-BC-07-EDCAT	COC-BC-09-EDCAT
			03/12/08	03/12/08	03/12/08
SVOCs					
87-86-5	Pentachlorophenol	mg/kg wet	0.03 U	0.03 U	0.03 U
83-32-9	Acenaphthene	mg/kg wet	0.0047 J	0.022	0.019
208-96-8	Acenaphthylene	mg/kg wet	0.00069 U	0.0018 J	0.00092 J
120-12-7	Anthracene	mg/kg wet	0.0016 J	0.0077	0.005
56-55-3	Benzo(a)anthracene	mg/kg wet	0.00066 U	0.0059	0.00063 U
50-32-8	Benzo(a)pyrene	mg/kg wet	0.0008 U	0.0023 J	0.00077 U
205-99-2	Benzo(b)fluoranthene	mg/kg wet	0.0007 U	0.0027 J	0.00067 U
191-24-2	Benzo(ghi)perylene	mg/kg wet	0.00073 U	0.0025 J	0.0007 U
207-08-9	Benzo(k)fluoranthene	mg/kg wet	0.00056 U	0.003 J	0.00054 U
218-01-9	Chrysene	mg/kg wet	0.00076 U	0.0032 J	0.00072 U
53-70-3	Dibenzo(a,h)anthracene	mg/kg wet	0.00059 U	0.0018 J	0.00056 U
206-44-0	Fluoranthene	mg/kg wet	0.006	0.02	0.019
86-73-7	Fluorene	mg/kg wet	0.0032 J	0.015	0.011
193-39-5	Indeno(1,2,3-cd)pyrene	mg/kg wet	0.00064 U	0.0026 J	0.00061 U
91-20-3	Naphthalene	mg/kg wet	0.004 U	0.0038 U	0.0038 U
85-01-8	Phenanthrene	mg/kg wet	0.0064	0.024	0.016
108-95-2	Phenol	mg/kg wet	0.0019 J	0.0081	0.0063
129-0-00	Pyrene	mg/kg wet	0.028865	0.1245	0.08172
50-32-8	BaP-TE (NDs = 1/2 DL)		0.0016 U	0.0053	0.0015 U
Metals					
7440-38-2	Arsenic	mg/kg wet	0.06 B	0.17958	0.17802
7440-47-3	Chromium	mg/kg wet	0.03 B	0.01533 U	0.01449 U
7440-50-8	Copper	mg/kg wet	0.24	0.42924	0.30429
Dioxins/Furans					
35822-46-9	1,2,3,4,6,7,8-HPCDD	mg/kg wet	0.000000594	6.789E-07	2.8359E-06
67562-39-4	1,2,3,4,6,7,8-HPCDF	mg/kg wet	0.0000000638 J	0.00000046647 J	0.00000027738 J
55673-89-7	1,2,3,4,7,8,9-HPCDF	mg/kg wet	0.0000000216 U	0.000000031317 U	0.000000027117 U
39227-28-6	1,2,3,4,7,8-HXCDD	mg/kg wet	0.0000000856 U	0.000000088914 U	0.000000126477 J
70648-26-9	1,2,3,4,7,8-HXCDF	mg/kg wet	0.0000000266 U	0.000000026937 J	0.000000029601 J
57653-85-7	1,2,3,6,7,8-HXCDD	mg/kg wet	0.00000026 J	0.00000032631 J	0.0000003933 J
57117-44-9	1,2,3,6,7,8-HXCDF	mg/kg wet	0.0000000266 U	0.000000177171 U	0.000000176157 U
19408-74-3	1,2,3,7,8,9-HXCDD	mg/kg wet	0.0000000776 U	0.000000095922 J	0.000000090666 J
72918-21-9	1,2,3,7,8,9-HXCDF	mg/kg wet	0.0000000145 U	0.000000027594 U	0.000000027324 U
40321-76-4	1,2,3,7,8-PECDD	mg/kg wet	0.0000001316 U	0.000000167973 J	0.000000138483 J
57117-41-6	1,2,3,7,8-PECDF	mg/kg wet	0.00000000842 U	0.000000030003 U	0.000000028152 U
60851-34-5	2,3,4,6,7,8-HXCDF	mg/kg wet	0.000000127 J	0.0000000206298 U	0.0000000207 U
57117-31-4	2,3,4,7,8-PECDF	mg/kg wet	0.0000000556 J	0.000000056064 J	0.000000057339 J
1746-01-6	2,3,7,8-TCDD	mg/kg wet	0.0000000402 U	0.000000061977 J	0.000000062514 J
51207-31-9	2,3,7,8-TCDF	mg/kg wet	0.0000000228 J	0.000000027594 U	0.0000000206379 U
3268-87-9	OCDD	mg/kg wet	0.000000312	3.6573E-06	0.000056097
39001-02-0	OCDF	mg/kg wet	0.00000001074 U	0.000000077526 U	1.40139E-06
1746-01-6	TCDD-TEQ (NDs = 1/2 DL)	mg/kg wet	1.62855E-07	3.09779E-07	1.60405E-07
Miscellaneous					
NA	Solids, Total	%	20	21.9	20.7
NA	Lipids, Total	%	3.1	2.9	2.3

mg/kg = miligram per kilogram
COPC = constituent of potential concern
SVOCs = semi-volatile organic compounds
BaP-TE = benzo(a)pyrene toxic equivalents
TCDD-TEQ = 2,3,7,8-tetrachlorodibenzo-p-dioxin toxic equivalents



Appendix B

USEPA March 14, 2014
Letter, Work Plans and
Characterization Data for the
Neighborhood South of the
Site



C. Bury
105 W. Madison Street, Suite 900
Chicago, IL 60602
(312) 345-8990
(312) 345-8979 (Fax)
www.techlawinc.com

RZ2.R05902.20.ID.726

June 2, 2005

Mr. Allen Wojtas
U.S. Environmental Protection Agency
Region 5, DM-7J
77 W. Jackson Boulevard
Chicago, IL 60604

Reference: EPA Contract No. 68-W-02-019; EPA Work Assignment No. R05902; Corrective Action Support; Beazer East, Inc. (former Koppers Company, Inc.), Carbondale, IL; EPA ID No. ILD 000819946; Field Sampling Activity Report; Task 4 Deliverable

Dear Mr. Wojtas:

Please find enclosed a Field Sampling Activity Report that describes soil sample collection and analysis activities associated with the Former Koppers Company, Inc. facility in Carbondale, Illinois. The soil samples were collected in the field by a team consisting of U.S. EPA, Illinois EPA and TechLaw representatives. The samples were collected on March 3, 2005 and were transferred (via chain of custody) to the U.S. EPA Region 5 Central Regional Laboratory (CRL) on March 4, 2005. TechLaw performed data validation (DV) on the CRL analytical data package and the resulting DV Report is included as Attachment 4 of the enclosed deliverable. For your convenience, this report has also been E-mailed to both you and Ms. Carolyn Bury in Word Perfect for Windows, Excel (analytical table) and Adobe pdf (sample location map and entire report) formats. Please note that due to the size of the electronic version of the Photographic Log, the Word Perfect for Windows version of the Log was not forwarded electronically, but has been included on the enclosed computer diskette.

If you have any questions, please contact me at (312) 345-8966 or Ms. Kristi Hogan, TechLaw's Work Assignment Manager, at (312) 345-8963.

Sincerely,



Robert Young
Regional Project Manager

cc: F. Norling, EPA Region 5 RPO, w/out attachment
C. Bury, EPA Region 5
P. Brown-Derocher/Central Files
K. Hogan
Chicago Central Files

FIELD SAMPLING ACTIVITY REPORT
FORMER KOPPERS WOOD-TREATING FACILITY
BEAZER EAST, INC.
CARBONDALE, ILLINOIS
EPA ID No. ILD000819946

Submitted to:

Mr. Allen Wojtas
Work Assignment Manager
U.S. Environmental Protection Agency
Region 5, DM-7J
77 West Jackson Boulevard
Chicago, Illinois 60604

Submitted by:

TechLaw, Inc.
105 West Madison
Suite 900
Chicago, Illinois 60602

EPA Work Assignment No.	R05902
Contract No.	68-W-02-019
EPA WAM	Allen Wojtas
Telephone No.	(312) 886-6194
EPA Technical Advisor	Carolyn Bury
Telephone No.	(312) 886-3020
TechLaw WAM	Kristi Hogan
Telephone No.	(312) 345-8963

June 2, 2005

FIELD SAMPLING ACTIVITY REPORT
FORMER KOPPERS WOOD-TREATING FACILITY
BEAZER EAST, INC.
CARBONDALE, ILLINOIS
EPA ID No. ILD000819946

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SITE DESCRIPTION AND HISTORY	1
3.0 SAMPLE COLLECTION	2
4.0 SAMPLING ACTIVITIES	4
5.0 ANALYTICAL RESULTS	5
6.0 CONCLUSIONS	5

FIGURES

Figure 1: Sampling Locations

TABLES

Table 1: Summary of Soil Sample Analytical Results

ATTACHMENTS

- NOT INCLUDED IN COPY* (Attachment 1: Field Log Book
Attachment 2: Photographic Log
Attachment 3: Laboratory Chain of Custody Forms
Attachment 4: Data Validation Report




Figure 1
Soil Sampling Locations
Former Koppers Facility, Carbondale, IL

● Soil Sample Location



Note:
 Aerial Source: USGS
 Aerial Date: 1998
 Sample Locations were GPS'd
 utilizing a submeter system

FIELD SAMPLING ACTIVITY REPORT
FORMER KOPPERS WOOD-TREATING FACILITY
BEAZER EAST, INC.
CARBONDALE, ILLINOIS
EPA ID No. ILD000819946

1. INTRODUCTION

The purpose of this report is to summarize sample collection procedures and present analytical results for samples collected in the vicinity of the Former Koppers Wood Treating facility in Carbondale, Illinois (Koppers Facility), currently owned by Beazer East, Inc. (Beazer). The sampling took place on March 3, 2005. Fourteen soil samples were collected by the Sampling Team, including one sample from the Koppers Facility in an area of known contamination and one background sample from a residential area in north-central Carbondale. The Sampling Team was comprised of U.S. EPA, Illinois EPA and TechLaw representatives. The samples were analyzed for polycyclic aromatic hydrocarbons (PAHs) and pentachlorophenol (PCP) to determine whether contamination from the Koppers Facility had migrated offsite. Chemical analysis of the samples was conducted by the U.S. EPA Region 5 Central Regional Laboratory (CRL) in Chicago, Illinois. Results were compared to U.S. EPA Region 9 Preliminary Remediation Goals (PRGs) and the Illinois Tiered Approach to Corrective Action Objectives (TACO) for residential properties to determine if the concentrations of PAHs and PCP detected in the soils could be potentially harmful to residents. This report describes the sample collection and preparation procedures, presents the results of the chemical analyses, and provides an evaluation of the results.

The Field Log Book for the sampling event is presented in Attachment 1. A Photographic Log depicting the sampling activities is provided in Attachment 2. Attachment 3 contains copies of the applicable Chain of Custody Form and Attachment 4 includes the Data Validation (DV) Report prepared by TechLaw.

2.0 SITE DESCRIPTION AND HISTORY

The Former Koppers Wood Treating facility is located at 1555 North Marion Street, Carbondale, Illinois. The facility operated as a wood-treating facility from 1905 until 1991. A variety of chemicals were used during the wood treating process, including creosote and PCP. In 1991, wood-treating activities at the site were discontinued. Previous investigations indicate that surface and subsurface soils within the site property are contaminated with PAHs and PCP. Ongoing site remediation activities include the relocation of Glade Creek, installation of a dense non-aqueous phase liquid (DNAPL) barrier trench upgradient of the creek, the removal of sediments from downstream areas of Glade Creek and the disposal of remediation wastes in an

on-site Corrective Action Management Unit (CAMU). A surface cover is also being constructed over a portion of the former process area to reduce the potential for exposure to contaminated soils.

Previous soil sampling conducted as part of the Remedial Investigation (RI) and Feasibility Study (FS) indicates on-site soils contain PAHs and PCP at concentrations that exceed PRGs and Illinois TACO criteria for industrial and residential exposures. This additional off-site soil sampling event was conducted in response to concerns expressed by residents that contamination may have migrated from the facility into their neighborhood. The sampling team met with representatives of the neighboring community the day before the sampling event. The community representatives input was used in establishing the soil sample locations.

3.0 SAMPLE COLLECTION

On March 3, 2005, 14 soil samples were collected for PAH and PCP analysis. In addition, two duplicate soil samples were also collected. The samples were analyzed using SW-846 Method 8270. The Sampling Team consisted of Ms. Carolyn Bury of U.S. EPA, Mr. Tom Edmundson of the Illinois EPA and Mr. Rob Young of TechLaw. The samples were collected from depths of approximately 0 to 6-inches below ground surface (bgs). The location of each sample was recorded using a Global Positioning System (GPS) unit with sub-meter accuracy. The locations were downloaded and plotted a USGS topographic map, as shown on Figure 1. Representatives of Beazer accompanied the Sampling Team and collected split samples at each location.

The location for each of the 14 samples is described below. The sample locations were determined based on a review of the existing on-site soil data and input from community representatives (as discussed above).

- Sample S1: This surface soil sample was collected from the area immediately south of historical onsite sample location SL-324, in a 35-foot strip of land which was apparently previously owned by Koppers, as indicated on the base map used in the RI Report. Historical documents, including the RI Report, indicate that soils in the boring collected at SL-324 contained visible staining. The sample was collected approximately five feet north of a large drainage swale/ditch that runs west of, and parallel to, Knight Street.
- Sample S2: This surface soil sample was collected approximately 30 feet south of Sample S1, to the south of the drainage swale/ditch, in the 35-foot strip of land marked as "Koppers" on the RI Report base map.
- Sample S3: This surface soil sample was collected south of an area that contained ponded water (north of Knight Street, between Robert A. Stalls and Pierce Streets), on the south side of the 35-foot strip of land marked as "Koppers" on the RI Report base map. This sample was collected south of historical sample SL-342, which was

collected on-site during the RI. According to historical documents, soils in SI-342 contained elevated concentrations of PAHs and PCP. Sample S21 was collected as a duplicate at this location.

- Sample S4: This surface soil sample was collected approximately 60 feet south of Sample 3, in a grassy area, approximately 65 feet north of Knight Street. The lot from which S3 and S4 were collected was a vacant, grass-covered area.
- Sample S5: This surface soil sample was collected immediately south of the Former Process Area, approximately 125 feet south of the Koppers facility property line. The Former Process Area contained many of the highest historical PAH and PCP concentrations found in soils at the facility.
- Sample S6: This surface soil sample was collected directly south of the Koppers Former Process Area, and 75 feet south of Sample S5.
- Sample S7: This surface soil sample was collected to the southeast of the Koppers Former Process Area, approximately 105 feet south of the property line and approximately 150 feet west of the MW102 well cluster. A community representative indicated that a large area southeast of the Former Process Area, and south of the property line, had reportedly been used to store treated railroad ties several years ago. The Sampling Team collected samples S7, S8, S9 and S10 from this reported storage area. A community representative also reported that the area surrounding soil sample S7 had recently been used for agricultural purposes.
- Sample S8: This surface soil sample was collected approximately 110 feet south of Sample S7. Sample S8 was collected from an area that a community representative indicated had recently been used for agricultural purposes.
- Sample S9: This surface soil sample was collected approximately 700 feet east of Sample S7 and approximately 80 feet south of the access road that runs along the south property line of the Koppers Site. Sample S9 was collected from an area that a community representative indicated had recently been used for agricultural purposes.
- Sample S10: This surface soil sample was collected approximately 80 feet south of Sample S9. Sample S10 was collected from an area that a community representative indicated had recently been used for agricultural purposes.
- Sample S11: This surface soil sample was collected between two drainage features (gullies), approximately 1,000 feet south of the property line. The drainage features did not appear to be man-made, and appeared to drain a large field south of the area where soil samples S9 and S10 were collected.

- Sample S12: This surface soil sample was collected along the north edge of a tree line, about 400 feet west of Sample S11. The sample was collected adjacent to a drainage feature which did not appear to be man-made. Sample S22 was collected as a duplicate at this location.
- Sample S13: This surface soil sample was collected in the Koppers Former Process Area, from soils that appeared to be visibly impacted by creosote.
- Sample S14: This surface soil sample was collected from Oakdale Park, a recreation area located in north-central Carbondale. The sample was collected approximately 125 feet west of North Oakland Street. This location was considered a background sample, and was located approximately one mile west of the facility.

4.0 SAMPLING ACTIVITIES

The Sampling Team collected, handled, prepared, and delivered the soil samples to the U.S. EPA Region 5 CRL. Each sample was collected in an 8- or 16-ounce, unpreserved glass container with a Teflon-lined lid. The pre-cleaned sample containers were provided to the Sampling Team by the U.S. EPA Region 5 CRL. An additional 8-ounce unpreserved glass container was also collected at each location and immediately transferred to Beazer representatives as a split sample. All soil samples were analyzed for PAHs and PCP using SW-846 Method 8270. During the sampling activities, appropriate quality control samples were collected in accordance with TechLaw's U.S. EPA-approved Region 5 Generic Quality Assurance Project Plan (QAPP). One matrix spike/matrix duplicate (MS/MSD) and two duplicate samples were collected. The Sampling Team used disposable sampling equipment to collect the samples, minimizing the need for decontamination.

As discussed previously, soil samples were collected from the 0-inch to 6-inch bgs depth interval at each surface soil sampling location. Separate pre-cleaned stainless steel trowels were used at each location. The samples were scooped into a stainless steel bowl, homogenized, and then transferred into the sample containers. Large organic material, rock, and slag were removed from the bowl or avoided when placing the material into the sample containers. The bowls were lined with clean aluminum foil at each location, and the foil was disposed of after sample collection.

As necessary, the outside of the sample containers were cleaned following sample collection to avoid any potential cross-contamination between samples and sample containers. Samples remained in the custody of the Sampling Team until relinquished to the U.S. EPA Region 5 CRL. The sample containers were appropriately labeled (directly on the face of the bottle). In addition, sample tags were affixed to each container. The samples were placed in a cooler with ice and were hand delivered to the U.S. EPA Region 5 CRL on March 4, 2005. A chain-of-custody (COC) form accompanied the samples from the point of origin to the laboratory. A copy of the COC form is presented in Attachment 3.

5.0 ANALYTICAL RESULTS

Analytical results for soil samples are summarized in Table 1. TechLaw performed data validation on all the PAH and PCP laboratory data. A copy of the Data Validation Report is included in Attachment 4. Results of the PAH and PCP analyses are discussed below.

Results of PAH Analyses

PAHs were either not detected or were present at concentrations below PRGs and/or Illinois TACO criteria for residential exposures at each sample location, with the exception of samples S1 and S13. These exceptions are discussed below:

- Benzo(a)pyrene was detected above the PRG and Illinois TACO criteria for residential exposures at S1. Benzo(b)fluoranthene was detected above the PRG, but below the TACO criteria for residential exposures at S1. The following factors should be noted with respect to the PRG/TACO exceedences. First, S1 was collected adjacent to a large drainage feature that appeared to potentially convey stormwater runoff from ditches in the community. Overtopping of the drainage feature could have contributed PAHs to the soils near S1. Second, soil sample S2 was collected as a “step-out” location to determine if potential contaminants were migrating from the Former Koppers facility to the south of S1. All PAHs were below the PRGs and TACO criteria for residential exposures at soil sample location S2.
- Soil sample S13 was collected from the Former Process Area, within the facility’s boundaries. The sample was collected from soils that contained visible creosote staining. The objective of the sample was to obtain a “signature” of the PAHs present in the creosote-impacted soils at the facility.

Results of PCP Analyses

PCP was only detected in one sample (S13) at a concentration exceeding PRGs and Illinois TACO criteria. The exceedence was expected, since sample S13 was collected from on-site soil material that contained visible creosote. PCP results were rejected (indicated as “R” in Table 1) in six of the soil samples, including S5, S9, S10, S12, S21 and S22 (as discussed above, S21 and S22 are duplicate samples of S3 and S12, respectively). The laboratory rejected these results because of low surrogate recoveries or low calibration response, as shown in the laboratory quality control data.

6.0 CONCLUSIONS

Soil sample S1 was the only location outside the Former Koppers facility that contained PAHs or PCP at concentrations exceeding PRGs and Illinois TACO criteria for residential exposures. As

discussed above, sample S1 was collected adjacent to a large drainage feature, and an associated sample (S2) collected in a "step-out" pattern to the south of S1 did not contain PAHs or PCP at concentrations exceeding the residential criteria.

With the exception of S1 and S13, the soil samples collected outside the boundaries of the Former Koppers facility appeared to contain concentrations of PAHs that were comparable to background concentrations (in S14). PCP was not detected in the background sample, nor was the chemical detected in any soil supplies collected outside the boundaries of the Former Koppers facility.

TABLE 1
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS
FORMER KOPPERS COMPANY, CARBONDALE, IL
March 3, 2005 Sampling Event

ANALYTE	Residential Soil PRGs (ug/Kg)	Tier I Soil Remediation Objectives for Residential Properties (via Ingestion) (ug/kg)	S1		S2		S3		S4		S5	
			RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q
Semivolatile Organics												
Naphthalene (ug/Kg)	5.60E+04	1.60E+06	74.4	J	60	U	236	U	236	U	55.2	U
2-Methylnaphthalene (ug/Kg)*	NA	3.10E+05	61	UJ	60	U	236	U	236	U	55.2	U
Acenaphthylene (ug/Kg)*	NA	2.30E+06	70.2	J	60	U	236	U	236	U	55.2	U
Acenaphthene (ug/Kg)	3.70E+06	4.70E+06	61	UJ	60	U	236	U	236	U	55.2	U
Fluorene (ug/Kg)	2.70E+06	3.10E+06	61	UJ	60	U	236	U	236	U	55.2	U
Phenanthrene (ug/Kg)*	NA	2.30E+06	286	J	40.3	J	274		205	J	55.2	U
Anthracene (ug/Kg)	2.20E+07	2.30E+07	93.4	J	60	U	236	U	236	U	55.2	U
Fluoranthene (ug/Kg)	2.30E+06	3.10E+06	527	J	60	U	236	U	236	U	44.8	J
Pyrene (ug/Kg)	2.30E+06	2.30E+06	531	J	43.3	J	168	J	236	U	55.2	U
Chrysene (ug/Kg)	6.20E+04	8.80E+04	536	J	43.3	J	118	J	84.9	J	47.6	J
Benzo(a)anthracene (ug/Kg)	620	900	309	J	30.0	J	123	J	236	U	55.2	U
Benzo(b)fluoranthene (ug/Kg)	620	900	719	J	53.5	J	236	U	236	U	55.2	U
Benzo(k)fluoranthene (ug/Kg)	6,200	9,000	299	J	60	U	236	U	236	U	55.2	U
Benzo(a)pyrene (ug/Kg)	62	90	301	J	24.0	J	236	U	236	U	55.2	U
Indeno(1,2,3-cd)pyrene (ug/Kg)	620	900	239	J	60	U	236	U	236	U	55.2	U
Dibenzo(a,h)anthracene (ug/Kg)	62	90	61	UJ	60	U	236	U	236	U	55.2	U
Benzo(g,h,i)perylene (ug/Kg)*	NA	2.30E+06	266	J	60	U	236	U	236	U	55.2	U
Pentachlorophenol (ug/Kg)	3,000	NA	732	U	721	U	1180	U	2830	U	664	R

NOTES:

Bold numbers = Exceeded PRGs or TACO criteria for Residential Exposures

* = Soil Remediation Objectives for Residential Properties, Non-TACO Chemicals. Prepared by the Illinois EPA Toxicity Unit, October 1, 2004

Q = Qualification or description.

R = The analyte is rejected due to serious deficiencies in the ability to analyze the sample and meet QC criteria.

U = The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

The associated value is either the sample quantitation limit or the sample detection limit.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

ND=Not determined

a=Sample S21 is a duplicate of Sample S3

b=Sample S22 is a duplicate of Sample S12

TABLE 1
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS
FORMER KOPPERS COMPANY, CARBONDALE, IL
March 3, 2005 Sampling Event

ANALYTE	Residential Soil PRGs (ug/kg)	Tier I/Soil Remediation Objectives for Residential Properties (via Ingestion) (ug/kg)	S6		S7		S8		S9		S10	
			RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q
Semi-volatile Organics												
Naphthalene (ug/Kg)	5.60E+04	1.60E+06	61	U	59	U	59.6	U	58.2	U	59.8	U
2-Methylnaphthalene (ug/Kg)*	NA	3.10E+05	61	U	59	U	59.6	U	58.2	U	59.8	U
Acenaphthylene (ug/Kg)*	NA	2.30E+06	61	U	59	U	59.6	U	58.2	U	59.8	U
Acenaphthene (ug/Kg)	3.70E+06	4.70E+06	61	U	59	U	59.6	U	58.2	U	59.8	U
Fluorene (ug/Kg)	2.70E+06	3.10E+06	61	U	59	U	59.6	U	58.2	U	59.8	U
Phenanthrene (ug/Kg)*	NA	2.30E+06	61	U	181	J	59.6	U	58.2	U	59.8	U
Anthracene (ug/Kg)	2.20E+07	2.30E+07	61	U	59	U	59.6	U	58.2	U	59.8	U
Fluoranthene (ug/Kg)	2.30E+06	3.10E+06	61	U	141	J	51.9	J	46.6	J	59.8	U
Pyrene (ug/Kg)	2.30E+06	2.30E+06	61	U	109	J	37.0	J	38.4	J	59.8	U
Chrysene (ug/Kg)	6.20E+04	8.80E+04	61	U	118	J	52.5	J	42.5	J	29.4	J
Benzo(a)anthracene (ug/Kg)	620	900	61	U	52.0	J	59.6	U	58.2	U	59.8	U
Benzo(b)fluoranthene (ug/Kg)	620	900	61	U	119	J	53.0	J	60.5	J	40.8	J
Benzo(k)fluoranthene (ug/Kg)	6,200	9,000	61	U	49.0	J	59.6	U	58.2	U	59.8	U
Benzo(a)pyrene (ug/Kg)	62	90	61	U	46.7	J	59.6	U	58.2	U	59.8	U
Indeno(1,2,3-cd)pyrene (ug/Kg)	620	900	61	U	44.9	J	59.6	U	58.2	U	59.8	U
Dibenzo(a,h)anthracene (ug/Kg)	62	90	61	U	59	U	59.6	U	58.2	U	59.8	U
Benzo(g,h,i)perylene (ug/Kg)*	NA	2.30E+06	61	U	37.8	J	59.6	U	58.2	U	59.8	U
Pentachlorophenol (ug/Kg)	3,000	NA	734	U	709	UJ	715	UJ	699	R	719	R

NOTES:

Bold numbers = Exceeded PRGs or TACO criteria for Residential Exposures

* = Soil Remediation Objectives for Residential Properties, Non-TACO Chemicals. Prepared by the Illinois EPA Toxicity Unit, October 1, 2004

Q = Qualification or description.

R = The analyte is rejected due to serious deficiencies in the ability to analyze the sample and meet QC criteria.

U = The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

The associated value is either the sample quantitation limit or the sample detection limit.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

ND=Not determined

a=Sample S21 is a duplicate of Sample S3

b=Sample S22 is a duplicate of Sample S12

TABLE 1
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS
FORMER KOPPERS COMPANY, CARBONDALE, IL
March 3, 2005 Sampling Event

ANALYTE	Residential Soil PRGs (ug/Kg)	Tier I Soil Remediation Objectives for Residential Properties (via Ingestion) (ug/Kg)	S11		S12		(Soil Collected from with In Facility Property) S13		(Background Sample) S14		S21 ^a	
			RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q	RESULT	Q
Semi-volatile Organics												
Naphthalene (ug/Kg)	5.60E+04	1.60E+06	61.8	U	60	UJ	5120		60.4	UJ	232	UJ
2-Methylnaphthalene (ug/Kg)*	NA	3.10E+05	61.8	U	60	UJ	1770		62.3	J	232	UJ
Acenaphthylene (ug/Kg)*	NA	2.30E+06	61.8	U	60	UJ	10100		60.4	UJ	232	UJ
Acenaphthene (ug/Kg)	3.70E+06	4.70E+06	61.8	U	60	UJ	643		60.4	UJ	232	UJ
Fluorene (ug/Kg)	2.70E+06	3.10E+06	61.8	U	60	UJ	931		60.4	UJ	232	UJ
Phenanthrene (ug/Kg)*	NA	2.30E+06	61.8	U	60	UJ	9070		122	J	305	J
Anthracene (ug/Kg)	2.20E+07	2.30E+07	61.8	U	60	UJ	17000		60.4	UJ	232	UJ
Fluoranthene (ug/Kg)	2.30E+06	3.10E+06	61.8	U	60	UJ	28200		64.7	J	232	UJ
Pyrene (ug/Kg)	2.30E+06	2.30E+06	61.8	U	60	UJ	33000		58.1	J	140	J
Chrysene (ug/Kg)	6.20E+04	8.80E+04	61.8	U	60	UJ	25600		48.4	J	116	J
Benzo(a)anthracene (ug/Kg)	620	900	61.8	U	60	UJ	17500		51.4	J	97.7	J
Benzo(b)fluoranthene (ug/Kg)	620	900	61.8	U	60	UJ	48800		45.4	J	107	J
Benzo(k)fluoranthene (ug/Kg)	6,200	9,000	61.8	U	60	UJ	15800		60.4	UJ	232	UJ
Benzo(a)pyrene (ug/Kg)	62	90	61.8	U	60	UJ	23000		35.1	J	232	UJ
Indeno(1,2,3-cd)pyrene (ug/Kg)	620	900	61.8	U	60	UJ	7730		60.4	UJ	232	UJ
Dibenzo(a,h)anthracene (ug/Kg)	62	90	61.8	U	60	UJ	364	U	60.4	UJ	232	UJ
Benzo(g,h,i)perylene (ug/Kg)*	NA	2.30E+06	61.8	U	60	UJ	6640		42.3	J	232	UJ
Pentachlorophenol (ug/Kg)	3,000	NA	742	UJ	721	R	19400	J	726	UJ	2790	R

NOTES:

Bold numbers = Exceeded PRGs or TACO criteria for Residential Exposures

* = Soil Remediation Objectives for Residential Properties, Non-TACO Chemicals. Prepared by the Illinois EPA Toxicity Unit, October 1, 2004

Q = Qualification or description.

R = The analyte is rejected due to serious deficiencies in the ability to analyze the sample and meet QC criteria.

U = The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

The associated value is either the sample quantitation limit or the sample detection limit.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

ND=Not determined

a=Sample S21 is a duplicate of Sample S3

b=Sample S22 is a duplicate of Sample S12

TABLE 1
SUMMARY OF SOIL SAMPLE ANALYTICAL RESULTS
FORMER KOPPERS COMPANY, CARBONDALE, IL
March 3, 2005 Sampling Event

ANALYTE	Residential Soil PRGs (ug/kg)	Tier I Soil Remediation Objectives for Residential Properties (via Ingestion) (ug/kg)	S22 ^a	
			RESULT	Q
Semivolatile Organics				
Naphthalene (ug/Kg)	5.60E+04	1.60E+06	59.2	UJ
2-Methylnaphthalene (ug/Kg)*	NA	3.10E+05	59.2	UJ
Acenaphthylene (ug/Kg)*	NA	2.30E+06	59.2	UJ
Acenaphthene (ug/Kg)	3.70E+06	4.70E+06	59.2	UJ
Fluorene (ug/Kg)	2.70E+06	3.10E+06	59.2	UJ
Phenanthrene (ug/Kg)*	NA	2.30E+06	59.2	UJ
Anthracene (ug/Kg)	2.20E+07	2.30E+07	59.2	UJ
Fluoranthene (ug/Kg)	2.30E+06	3.10E+06	59.2	UJ
Pyrene (ug/Kg)	2.30E+06	2.30E+06	59.2	UJ
Chrysene (ug/Kg)	6.20E+04	8.80E+04	59.2	UJ
Benzo(a)anthracene (ug/Kg)	620	900	59.2	UJ
Benzo(b)fluoranthene (ug/Kg)	620	900	20.7	J
Benzo(k)fluoranthene (ug/Kg)	6,200	9,000	59.2	UJ
Benzo(a)pyrene (ug/Kg)	62	90	59.2	UJ
Indeno(1,2,3-cd)pyrene (ug/Kg)	620	900	59.2	UJ
Dibenzo(a,h)anthracene (ug/Kg)	62	90	59.2	UJ
Benzo(g,h,i)perylene (ug/Kg)*	NA	2.30E+06	59.2	UJ
Pentachlorophenol (ug/Kg)	3,000	NA	711	R

NOTES:

Bold numbers = Exceeded PRGs or TACO criteria for Residential Exposures

* = Soil Remediation Objectives for Residential Properties, Non-TACO Chemicals. Prepared by the Illinois EPA Toxicity Unit, October 1, 2004

Q = Qualification or description.

R = The analyte is rejected due to serious deficiencies in the ability to analyze the sample and meet QC criteria.

U = The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

The associated value is either the sample quantitation limit or the sample detection limit.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

ND=Not determined

a=Sample S21 is a duplicate of Sample S3

b=Sample S22 is a duplicate of Sample S12

DATA VALIDATION REPORT

To: Robert Young – TechLaw, Inc
From: Bill Fear – TechLaw, Inc.
Report Date: June 1, 2005
Project/Site: Koppers, Carbondale
Laboratory No: 0503003

This memo presents the organic data validation report for the data obtained during the field activities for the above referenced work assignment. The purpose of this review is to provide a technical validation of the semivolatile organic results for polyaromatic hydrocarbons (PAH) and pentachlorophenol (PCP) by GC/MS method SW-846 Method 8270C for Laboratory No. 0503003 from the Region 5 Central Regional Laboratory. This report consists of the validation of 16 soil samples collected on March 3, 2005 and analyzed on March 17, 18, 29 and April 28 and 29, 2005 by the Region 5 Central Regional Laboratory. The field sample numbers and corresponding laboratory numbers are presented below:

Field Sample Number	Laboratory Sample Number
S1	0503003-01
S2	0503003-02
S3	0503003-03
S4	0503003-04
S5	0503003-05
S6	0503003-06
S7	0503003-07
S8	0503003-08
S9	0503003-09
S10	0503003-10
S11	0503003-11
S12	0503003-12
S13	0503003-13
S14	0503003-14
S21	0503003-15
S22	0503003-16

Data validation was conducted in accordance with the documents "Test Methods for Evaluating Solid Wastes, SW-846, 3rd Edition," (Third update 1996), and the "USEPA CLP National Functional Guidelines for Evaluating Organics Analyses," October 1999.

Full validation was performed on all samples. The data were evaluated based on the following parameters:

- * Data Completeness
Holding Times and Preservation
- * GC/MS Instrument Tune
Calibrations
- * Blanks
Surrogate Recoveries
- * Internal Standard Criteria
- * Matrix Spike/Matrix Spike Duplicates
- * Blank Spikes (Laboratory Control Samples)
- * Compound Identification (full validation only)
Compound Quantitation and Reporting Limits (full validation only)

- * **All criteria were met for this parameter**

Data Completeness

All data necessary to complete data validation on the samples were provided with the following exceptions.

A tune summary form was not provided for 3/25/05 (7:45) tune. However, no action was taken as the raw data were available for evaluation.

The acid surrogate recoveries were not listed on the sample results summary form. No action was required as the recoveries were listed on the surrogate recovery Form 2 and were verified from the raw data.

Holding Times and Preservation

Analytical holding times were assessed to determine whether the holding time requirements were met by the laboratory. These soil samples were extracted within 14 days of sample collection and the extracts were analyzed within 40 days of extraction with the exceptions noted below. The laboratory case narrative did not indicate any problems with sample receipt.

Samples S12 and 14 were analyzed 48 days after extraction and sample S22 was analyzed 49 days after extraction which exceeds the 40 day holding time by eight and nine days, respectively. The following sample results are qualified as estimated (J/UJ) because the sample extracts were not analyzed with 40 days of extraction:

- All results in samples S12, S14, and S22

Note, the non-detected results for PCP in samples S12 and S22 were ultimately rejected because of extremely low surrogate recoveries.

GC/MS Instrument Tune

Decafluorotriphenylphosphine (DFTPP) instrument performance checks were run for each 12 hours of analysis. Ion abundance technical criteria were met and were verified from the raw data for all associated DFTPP tunes.

Calibrations

The instruments were calibrated at the required frequency. Continuing calibrations were analyzed with each 12-hour period of analysis. No calculation errors or transcription errors were found.

Initial Calibration

The percent relative standard deviations (%RSDs) for all target PAH compounds in the initial calibrations were less than or equal to 30% (and less than the method criteria of 15%) with the exception noted below. The average relative response factors (RRFs) for all target compounds were greater than or equal to 0.05.

The % RSD for pentachlorophenol at 39.2% exceeded 30% in the March 25, 2005 initial calibration. As a result the following detected result was qualified as estimated (J):

- Pentachlorophenol in sample S13

Sample S21 was also associated with this calibration; however, the result for PCP is ultimately rejected due to a low RRF.

Continuing Calibration

The percent differences (%Ds) for all target compounds in the continuing calibrations were less than or equal to 25% and the RRFs for all target compounds were greater than or equal to 0.05 with the exception noted below.

The following non-detected result was rejected (R) and the detected result was qualified as estimated (J) because the RRF at 0.002 in the March 29, 2005 continuing calibration was well below 0.05:

- Pentachlorophenol in sample S21 (R)
- Pentachlorophenol in sample S13 (J)

Note, the associated %D for pentachlorophenol exceeded 25% which would also lead to estimating the detected result in sample S13.

A 1PPM standard was analyzed on April 29, 2005. The results for all target compounds with the exception of pentachlorophenol were within 0.75 and 1.25 PPM (25% criteria). Pentachlorophenol was not found in this standard. This compound is reported at a higher reporting limit.

Blanks

The method blank was extracted and analyzed at the required frequency. No contamination was found in the method blank. Summary forms and raw data were evaluated.

Although the samples were analyzed on one instrument, the samples were analyzed over three different analytical sequences. However the blank was not analyzed with each sequence. No action is required.

Surrogate Recoveries

Surrogate compounds were added to the samples and QC samples. The surrogate percent recoveries were within the laboratory QC limits, with the exception noted below. The recoveries were verified from the raw data.

Various surrogate recoveries were below laboratory QC limits in the samples. Action is taken when at least two surrogate recoveries per fraction (bas/neutral or acid) were outside QC limits or when one recovery was less than 10%. The PAH compounds were qualified using the base/neutral surrogates and pentachlorophenol was qualified using the acid surrogates.

The following non-detected results were rejected (R) because the recoveries of the acid surrogates 2-fluorphenol and/or phenol-d5 were less than 10%:

- Pentachlorophenol in samples S5, S9, S10, S12, and S22

The following detected result was qualified as estimated (J) because the recoveries of the acid surrogate 2-fluorphenol at 7% was less than 10% and the recovery for phenol-d5 at 14% was less than the QC limit:

- Pentachlorophenol in sample S13

The following non-detected results were qualified as estimated (UJ) because the recoveries of the acid surrogates 2-fluorphenol and phenol-d5 were less than the QC limits but greater than 10%:

- Pentachlorophenol in samples S7, S8, S11, and S14

The following results were qualified as estimated (J/UJ) because the recoveries of two of the three base/neutral surrogates (nitrobenzene-d5, terphenyl-d14, or 2-fluorobipheny) were less than the QC limits but greater than 10%:

- All PAH compounds in samples S1 and S14
-

(The surrogate recovery for terphenyl-d14 was listed as 62.9% in sample S14; however, the actual raw data recovery was 62.8 which is just below the QC limit of 63%.)

The recoveries for the base/neutral surrogate 2-fluorobiphenyl in samples S3, S10, S12, and S22 and for acid surrogate phenol-d5 in samples S6 and S21 were below the QC limits but greater than 10%. No qualification was required for these low recoveries because only one surrogate recovery per fraction was outside QC limits. (Note, pentachlorophenol was however, rejected in sample S21 due to a low calibration RRF.)

The surrogate compounds from the dilution of sample S13 were diluted below the calibration range and no action was taken on diluted out surrogate compounds.

Internal Standard Criteria

Internal standard area counts did not vary by more than a factor of two from the associated 12-hour calibration standard. The internal standard retention times did not vary more than ± 30 seconds from the retention time of the associated 12-hour calibration standards. Summary forms and raw data were evaluated.

Matrix Spike/Matrix Spike Duplicates

Matrix spike/matrix spike duplicate (MS/MSD) analyses were performed on sample S8. All percent recoveries and relative percent differences (RPDs) were within laboratory QC limits. Summary forms and raw data were evaluated.

The laboratory indicated that the RPDs for naphthalene and benzo(k)fluoranthene exceeded the QC limits. However, because different sample sizes were used for the spike and spike duplicate, different spike amounts were reported. This resulted in the discrepancy for the found amounts. Review of the actual raw data indicated that precision was met and the RPDs were within QC limits.

Blank Spikes (Laboratory Control Samples)

Precision and accuracy criteria were met as the percent recoveries and RPDs of the laboratory control sample and laboratory control sample duplicate were within laboratory QC limits. No calculation errors or transcription errors were found.

Compound Identification (Full Validation Only)

Compound identification was evaluated for the samples. Sample relative retention times (RRTs) were within ± 0.06 RRT units of the standard RRT. Ions present in the standard mass spectrum at a relative intensity greater than 10% were present in the sample spectrum. Relative intensities of ions agreed within $\pm 30\%$ between standard and sample spectra.

Tentatively identified compounds (TICs) were not reported for this analysis.

Compound Quantitation and Reporting Limits (Full Validation Only)

Compound quantitation and reporting limits were evaluated for the samples. The results and reporting limits were correctly reported.

The laboratory reporting limits are based on the concentration of the low standard from the initial calibration (5.0 ppm) and are corrected for the initial sample size, extraction final volumes, percent solids, and analytical dilution. Laboratory MDLs were compound specific and were not verified other than by the analysis of one 1 PPM standard. In order to meet project requirements the laboratory reporting limits were lowered by a factor of five to reflect the 1 ppm standard. All non-detected results are reported to this adjusted reporting limit on the data validation summary table. Several samples had a 4 ml final volume which resulted in elevated reporting limits. The new reporting limit is adjusted for this sample volume.

The laboratory did not estimate the detected results reported between the MDL and reporting limit. Therefore all detected results reported between the MDL and new adjusted reporting limit are considered estimated quantities and are qualified (J).

Sample S13 was analyzed at a secondary dilution because the result for benzo(b)fluoranthene exceeded the linear calibration in the initial analysis. The laboratory reported the result for this compound from the 4 times dilution and all other results from the initial undiluted analysis.

Overall Assessment

The majority of the pentachlorophenol sample results were qualified as estimated (with low bias) or rejected because of low surrogate recoveries or calibration problems. Six results were rejected and five were estimated.

All results in three samples were qualified as the extracts were analyzed outside holding times.

All PAH results in two samples were qualified as estimated (with low bias) due to low surrogate recoveries

The various detected sample results which were below the new adjusted reporting limits were qualified as estimated.

The laboratory rejected the result for pentachlorophenol in sample S1; however, there was no apparent reasoning for this action. The others samples with rejected pentachlorophenol results had extremely low acid surrogate recoveries.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- N J - Estimated value of a tentatively identified compound. (Identified with a CAS number.) ORGANICS analysis only.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for a compound is reported due to dilutions and reanalyses.

HR

HURST-ROSCHÉ
ENGINEERS, INC.

July 25, 2006
Revised August 4, 2006



SUBJECT: Supplemental Investigation
Former Koppers Wood Treating Facility
Carbondale, Jackson County, IL

re: H-R 180-3285

1400 East Tremont St.
P. O. Box 130
Hillsboro, IL 62049
Telephone 217-532-3959
Facsimile 217-532-3212
E-Mail hillsboro@hurst-rosche.com
Web Page—www.hurst-rosche.com

Mr. Donald D. Monty
Assistant City Manager
City of Carbondale, Illinois
200 S. Illinois Avenue
P. O. Box 2047
Carbondale, Illinois 62902-2047

Dear Mr. Monty:

At the request of the City of Carbondale, we have completed a supplemental investigation to assess off site impacts of potential past and/or present contamination from the former Koppers Wood Treating Facility. Specifically, a supplemental investigation has been completed in the residential area directly south of the Koppers facility.

In March 2005, USEPA coordinated an investigation in which 13 surface soil samples were collected at locations south of the Koppers facility. Soil samples were collected within 6 inches of ground surface at each of the designated locations. A majority of these samples were collected northeast of the residential neighborhood. The collected samples were analyzed for indicator parameters, and results suggested minimal if any presence of the parameters.

A supplemental investigation has been completed in which 11 subsurface soil samples were collected at six locations throughout the local neighborhood. Sample locations were designated by city personnel. Approximate sample locations have been identified on a site map developed by city personnel and presented in Attachment A. Actual sample locations have been described in the written narrative below.

Sample Collection

Soil sampling was completed on July 11, 2006. Sample collection was completed by Mr. Cody Greenwood and Mr. David Kimmle with Hurst-Rosche Engineers, Inc. Ms. Jennifer Sandorf with Blasland, Bouck, and Lee, Inc. (BBL) was present during sample collection. Ms. Sandorf collected split samples on behalf of Beazer East, Inc. Mr. Don Monty, Assistant City Manager, also accompanied the sampling team.

T. E. Connor, President
T. G. Baker, Sr. Vice President
J. W. Roth, Sr. Vice President
D. H. Kimmle, Treasurer

Rec'd	Sent	Routing	Date	Rec'd	Attr.
	8-4-06	TEG			
		DVK			✓
		MAR			
		JBL			
		MAR2			
		SLH			
		SKK			
		ESL			
		Marion			
		Spil			

East St. Louis, Illinois
Marion, Illinois
Springfield, Illinois
Barnhart, Missouri
Joplin, Missouri

Mr. Donald D. Monty
Page Two
August 4, 2006

In general, a post-hole digger was used to dig down to the 1 ft. depth at each designated location. A soil sample was obtained from this depth and split with Ms. Sandorf. An auger was then used to auger down to the 2 ft. depth, where a second soil sample was obtained and split with Ms. Sandorf. The post-hole digger and auger were cleaned with distilled water prior to initiating work at each boring location. New plastic gloves were used by the person collecting the soil samples. Each hole was backfilled with soil cuttings following sampling activities.

Each sample was placed in an 8 oz., unpreserved glass container with a Teflon-lined lid. The sample containers were provided by the laboratory. Each sample jar was appropriately labeled following sample collection. All samples were delivered to Teklab, Inc., Collinsville, Illinois the same day for testing. A chain of custody (COC) form accompanied the samples from the point of origin to the laboratory. A copy of the COC form is presented in Attachment No. 2.

Photographs taken at the time of sampling have been presented in Attachment No. 3

Analytical Testing

All collected samples were analyzed for polycyclic aromatic hydrocarbons (PAHs) and pentachlorophenol (PCP). These are the same parameters analyzed during the March 2005 investigation. These parameters have also been identified as being present on the Koppers facility property at concentrations above regulatory limits. Analysis of PAH concentrations was completed using SW-846 Method 8310. Analysis of PCP concentrations was completed using SW-846 Method 8270. Analytical results have been presented in Attachment No. 2. A summary of the analytical results has also been presented in Attachment No. 2.

Analytical Results

Following are comments regarding sampling and analytical results for each of the six locations. Analytical results have been compared to Tier 1 remediation objectives presented in 35 IAC Part 742 for residential properties.

Location A: This boring was originally designated to be completed in the northern half of open Lot 400 along Birch St. (see Photos 16 through 18). It is understood there use to be a few homes located on the property that have since been raised. Several initial borings were completed throughout the lot, and apparent fill consisting of soil, rock, brick, cinders, etc. was encountered at each of the locations. Considering this, it was decided to complete the boring at the southeast corner of Lot 441, which is the Erma Hayes Center (see Photos 19 & 20). Soil encountered at this location

Mr. Donald D. Monty
Page Three
August 4, 2006

consisted of a light brown, dry, very hard, silty clay (CL) with traces of aggregate and brick remnants down to approximately 12 inches. This was apparent fill material. Considering this, no sample was taken from the 1 ft. depth at this location. Soil below 12 inches was light brown, dry, hard, silty clay (CL). This appeared to be native soil, and a sample was taken at the 24 inch depth. There were no visible signs of contamination at this location. Trace amounts of several parameters were detected in the collected soil sample, however the parameter concentrations were below remediation objectives established for the respective parameters.

Location B: This location is at the eastern edge of Lot 1209 on Allman St. (see Photos 10 through 12). The boring location was initially established within the dedicated alleyway, however cinders and apparent fill were identified at the initial location. The boring location was moved approximately 20 ft. westward. Soil encountered at this location was a light brown, dry to moist, firm, silty clay (CL) down to the 24 inch depth. There were no visible signs of contamination at the final boring location. PAHs and PCP were not detected in either soil sample collected at this location.

Location C: This location is along the northern edge of Lot 608 on East Jenkins St. (see Photos 3 through 6). The boring location is at the northern edge of the residential lot. Soil encountered at this location included approximately 10 inches of gray/brown silty clay (CL) with cinders and rock. This soil appeared to be fill. From the approximate 10 inch to 14 inch depth, a gray/brown, moist to wet, silty clay (CL) was present. This appeared to be native soil and is what was sampled. Below 14 inches the soil was a gray/brown, mottled, moist, silty clay (CL). There were no visible signs of contamination at this location. Based on analytical results, trace amounts of benzopyrene, chrysene, and pyrene were detected in the soil sample collected from the 12 inch depth, however the parameter concentrations were below remediation objectives established for the respective parameters.

Location D: This location is at the eastern edge of an open lot immediately south of Lot 1201 on Pierce St. (see Photos 7 through 9). The boring location is at the northeastern corner of the open lot. Soil encountered at this location included approximately 10 inches of light brown/gray, mottled, moist, silty clay (CL). Below 10 inches was a light gray/brown, mottled, moist silty clay (CL). There were no visible signs of contamination at this location. PAHs or PCP were not detected in either soil sample collected at this location.

Mr. Donald D. Monty
Page Four
August 4, 2006

Location E: This location is adjacent to the northwest corner of Lot 1004 on Robert A. Stalls Ave. (formerly Barnes St.) (see Photos 13 through 15). The boring was completed in the open lot. Soil encountered at this location was a light brown, dry to moist, firm, silty clay (CL) down to the 24 inch depth. There were no visible signs of contamination at this location. PAHs and PCP were not detected in either soil sample collected at this location.

Location F: This location is at the eastern edge of the open lot behind Thomas School. The actual sample location was approximately 100 ft. south of the location shown on the site map (see Photos 1 & 2). Soil encountered at this location consisted of a light brown, dry, hard, silty clay (CL) down to approximately 16 inches. Below 16 inches, the soil was a light brown, moist, hard, silty clay (CL). There were no visible signs of contamination at this location. PAHs or PCP were not detected in either soil sample collected at this location.


Summary

Soil samples were collected from the 1 ft. and 2 ft. depths at five locations throughout the neighborhood located directly south of the former Koppers facility. A soil sample was collected from the 2 ft. depth at a sixth location in the neighborhood. Collected samples were analyzed for polycyclic aromatic hydrocarbons (PAHs) and pentachlorophenol (PCP) concentrations. Test results indicate that no PAH concentrations in excess of statewide remediation objectives established by the IEPA for residential properties were detected in any of the collected soil samples. A statewide remediation objective has not been established for PCP.

If you have any questions or require additional information, please let us know.

Sincerely,

HURST-ROSCHE ENGINEERS, INC.




David H. Kimmle, P.E.

DHK:bz
Enclosures




Attachment 1

Sample Location Maps

Y:\GIS FILES\GIS SPECIALIST CONSTRUCTION FILES\CLIENTS\B&H\KOPPER SOIL SITES.dwg, KOPPERS 11X17, 6/15/2006 2:59:59 PM, toomce



LEGEND

-  KOPPERS SOIL SAMPLE SITES
-  PROPOSED SOIL SAMPLE SITES
-  CITY LIMITS



- A) CITY OF CARBONDALE**
15-16-478-015
- B) MAE GULLY**
15-16-276-011,12
- C) VIRGINIA NESBITT**
15-15-151-016

- D) WILLIE JAMES**
15-16-282-005 TO 007
- E) CITY OF CARBONDALE - RIGHT OF WAY**
15-16-426-019
- F) SCHOOL DISTRICT #95**
15-15-301-002

SCALE: 1 INCH = 350 FT











1555

OUT

1482

1431

612



10.

IL. Route 13

Attachment 2

**Summary of Analytical Results
Analytical Results
Chain of Custody**

**Summary of Analytical Results
Supplemental Investigation
Former Koppers Wood Treating Facility
Carbondale, Jackson County, IL**

Parameter	Units	Remediation Objective ⁽¹⁾	Sample Location										
			A2	B1	B2	C1	C2	D1	D2	E1	E2	F1	F2
Pentachlorophenol	mg/Kg	(2)	<4.70	<2.24	<2.42	<2.50	<2.46	<2.50	<2.63	<2.39	<2.51	<2.28	<2.40
Acenaphthene	mg/Kg	570	<0.033	<0.034	<0.038	<0.036	<0.038	<0.037	<0.039	<0.036	<0.037	<0.034	<0.037
Acenaphthylene	mg/Kg	15	<0.033	<0.034	<0.038	<0.036	<0.038	<0.037	<0.039	<0.036	<0.037	<0.034	<0.037
Anthracene	mg/Kg	12,000	<0.011	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Benzo(a)anthracene	mg/Kg	0.9	0.026	<0.009	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.009	<0.010
*Benzo(a)pyrene	mg/Kg	0.09	0.031	<0.011	<0.013	0.021	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Benzo(b)fluoranthene	mg/Kg	9	0.040	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
Benzo(g,h,l)perylene	mg/Kg	2,300	0.064	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Benzo(k)fluoranthene	mg/Kg	9	0.014	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Chrysene	mg/Kg	88	0.040	<0.011	<0.013	0.014	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Dibenzo(a,h)anthracene	mg/Kg	0.09	<0.011	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
Fluoranthene	mg/Kg	3,100	0.081	<0.022	<0.013	<0.024	<0.025	<0.025	<0.026	<0.024	<0.024	<0.023	<0.025
Fluorene	mg/Kg	560	<0.011	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
*Indeno(1,2,3-cd)pyrene	mg/Kg	0.9	0.026	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
Naphthalene	mg/Kg	84	<0.044	<0.045	<0.051	<0.048	<0.050	<0.049	<0.052	<0.048	<0.049	<0.046	<0.050
Phenanthrene	mg/Kg	140	0.066	<0.011	<0.013	<0.012	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012
Pyrene	mg/Kg	2,300	0.057	<0.011	<0.013	0.017	<0.013	<0.012	<0.013	<0.012	<0.012	<0.011	<0.012

Notes:

1. Tier 1 soil remediation objectives for residential properties as presented in 35 IAC Part 742, Appendix B, Table A. Objectives for ingestion, inhalation, and migration have been considered with the lowest value presented.
2. No remediation objective has been established for pentachlorophenol in 35 IAC Part 742. Documentation indicates a preliminary remediation goal of 3 mg/Kg has been established for this parameter for the former Koppers Wood Treating Facility.

* Denotes carcinogen.

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

August 03, 2006

David Kimmle
Hurst-Rosche Engineers, Inc.
1400 E. Tremont
P.O. Box 130
Hillsboro, IL 62049
TEL: (217) 532-3959
FAX: (217) 532-3212



RE: Koppers Facility/ 180-3285

OrderNo. 06070246

Dear David Kimmle:

TEKLAB, INC received 11 samples on 7/11/2006 3:45:00 PM for the analysis presented in the following report. A list of report contents can be found on the following page.

Samples are analyzed on an as received basis unless otherwise requested and documented. The sample results contained in this report relate only to the requested analytes of interest that have been tested. IL ELAP and NELAP accredited fields of testing are indicated by the letters NELAP under the Certification column.

All quality control criteria applicable to the test methods employed for this project have been satisfactorily met and are in accordance with NELAP except where noted in the Case Narrative. The following report shall not be reproduced, except in full, without the written approval of Teklab, Inc.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

A handwritten signature in cursive script that reads "Kelly A. Klostermann".

Kelly A. Klostermann
Project Manager
618-344-1004 ex.11

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Client: Hurst-Rosche Engineers, Inc.
Project: Koppers Facility/ 180-3285
LabOrder: 06070246
Report Date: August 03, 2006

REPORT CONTENTS

This reporting package includes the following:

Analysis Results (this document)	14	pages
Chain of Custody	2	pages
Associated Information	1	pages
Sample Summary	NA	pages
Dates Report	NA	pages
QC Report	NA	pages
Sub Contracted Lab Report	NA	pages
MDL Report	NA	pages

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Client: Hurst-Rosche Engineers, Inc.
Project: Koppers Facility/ 180-3285
LabOrder: 06070246
Report Date: August 03, 2006

CASE NARRATIVE

Cooler Receipt Temp 17.4 °C

This is a revised report to lower the calculated reporting limit for pentachlorophenol by SW846 Method 8270 on sample "A2" to reflect the lowest standard of the calibration curve. Please replace your original report dated 7/18/06 for this work order with this revised report.

Qualifiers

DF - Dilution Factor	B - Analyte detected in the associated Method Blank	E - Value above quantitation range
RL - Reporting Limit	J - Analyte detected below reporting limits	H - Holding time exceeded
ND - Not Detected at the Reporting Limit	R - RPD outside accepted recovery limits	D - Diluted out of sample
Surr - Surrogate Standard added by lab	S - Spike Recovery outside accepted recovery limits	MI - Matrix interference
TNTC - Too numerous to count	X - Value exceeds Maximum Contaminant Level	DNI Did Not Ignite
IDPH - Illinois Department of Public Health	NELAP - IL ELAP and NELAP Accredited Field of Testing	

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004

FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-001
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID A2
Collection Date: 7/11/2006 12:50:00 PM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		11.3	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		88.7	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	4.70		ND	mg/Kg-dry	25	7/13/2006 10:29:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		49.3	%REC	25	7/13/2006 10:29:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		68.9	%REC	25	7/13/2006 10:29:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		53.6	%REC	25	7/13/2006 10:29:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		51.9	%REC	25	7/13/2006 10:29:00 PM	TDN
Surr: Phenol-d5		34.9-110		59.1	%REC	25	7/13/2006 10:29:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		71.4	%REC	25	7/13/2006 10:29:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.033		ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Acenaphthylene	NELAP	0.033		ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Anthracene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Benzo(a)anthracene	NELAP	0.009		0.026	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Benzo(a)pyrene	NELAP	0.011		0.031	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Benzo(b)fluoranthene	NELAP	0.011		0.040	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.011	R	0.064	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Benzo(k)fluoranthene	NELAP	0.011		0.014	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Chrysene	NELAP	0.011		0.040	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.011	R	ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Fluoranthene	NELAP	0.022		0.081	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Fluorene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.011	R	0.026	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Naphthalene	NELAP	0.044		ND	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Phenanthrene	NELAP	0.011		0.066	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Pyrene	NELAP	0.011		0.057	mg/Kg-dry	1	7/12/2006 3:01:57 PM	MAM
Surr: Terphenyl-d14		29.2-141		77.4	%REC	1	7/12/2006 3:01:57 PM	MAM

Sample Narrative

SW-846 3550B, 8270C, Semi-Volatile Organic Compounds by GC/MS

Elevated reporting limit due to high levels of target and/or non-target analytes.

SW-846 3550B, 8310, PolyNuclear Aromatic Hydrocarbons by HPLC

RPD for spikes was not within acceptable limits because of sample composition.

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-002
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID B1
Collection Date: 7/11/2006 11:30:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		11.0	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		89.0	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.24		ND	mg/Kg-dry	1	7/13/2006 1:31:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		67.3	%REC	1	7/13/2006 1:31:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		57.7	%REC	1	7/13/2006 1:31:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		46.0	%REC	1	7/13/2006 1:31:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		46.3	%REC	1	7/13/2006 1:31:00 PM	TDN
Surr: Phenol-d5		34.9-110		52.2	%REC	1	7/13/2006 1:31:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		70.6	%REC	1	7/13/2006 1:31:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.034		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Acenaphthylene	NELAP	0.034		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Anthracene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Benzo(a)anthracene	NELAP	0.009		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Benzo(a)pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Benzo(b)fluoranthene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Benzo(k)fluoranthene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Chrysene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Fluoranthene	NELAP	0.022		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Fluorene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Naphthalene	NELAP	0.045		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Phenanthrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 3:54:22 PM	MAM
Surr: Terphenyl-d14		29.2-141		79.4	%REC	1	7/12/2006 3:54:22 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004

FAX: 618-344-1005

Laboratory Results

CLIENT:	Hurst-Rosche Engineers, Inc.	Client Project:	Koppers Facility/ 180-3285
WorkOrder:	06070246	Client Sample ID	B2
Lab ID:	06070246-003	Collection Date:	7/11/2006 11:40:00 AM
Report Date:	03-Aug-06	Matrix:	SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		19.9	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		80.1	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.42		ND	mg/Kg-dry	1	7/13/2006 3:20:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		69.0	%REC	1	7/13/2006 3:20:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		66.7	%REC	1	7/13/2006 3:20:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		57.0	%REC	1	7/13/2006 3:20:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		57.7	%REC	1	7/13/2006 3:20:00 PM	TDN
Surr: Phenol-d5		34.9-110		59.0	%REC	1	7/13/2006 3:20:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		70.8	%REC	1	7/13/2006 3:20:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.038		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Acenaphthylene	NELAP	0.038		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Benzo(a)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Benzo(b)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Benzo(k)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Chrysene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Fluoranthene	NELAP	0.025		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Fluorene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Naphthalene	NELAP	0.051		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Phenanthrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:11:52 PM	MAM
Surr: Terphenyl-d14		29.2-141		67.4	%REC	1	7/12/2006 4:11:52 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004

FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-004
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID C1
Collection Date: 7/11/2006 10:35:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		18.9	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		81.1	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.50		ND	mg/Kg-dry	1	7/13/2006 3:56:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		75.0	%REC	1	7/13/2006 3:56:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		69.2	%REC	1	7/13/2006 3:56:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		60.6	%REC	1	7/13/2006 3:56:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		57.2	%REC	1	7/13/2006 3:56:00 PM	TDN
Surr: Phenol-d5		34.9-110		63.4	%REC	1	7/13/2006 3:56:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		74.1	%REC	1	7/13/2006 3:56:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.036		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Acenaphthylene	NELAP	0.036		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Benzo(a)pyrene	NELAP	0.012		0.021	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Benzo(b)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Benzo(k)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Chrysene	NELAP	0.012		0.014	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Fluoranthene	NELAP	0.024		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Fluorene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Naphthalene	NELAP	0.048		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Phenanthrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Pyrene	NELAP	0.012		0.017	mg/Kg-dry	1	7/12/2006 4:29:20 PM	MAM
Surr: Terphenyl-d14		29.2-141		77.6	%REC	1	7/12/2006 4:29:20 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-005
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID C2
Collection Date: 7/11/2006 10:42:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		20.2	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		79.8	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.46		ND	mg/Kg-dry	1	7/13/2006 4:32:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		66.7	%REC	1	7/13/2006 4:32:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		59.0	%REC	1	7/13/2006 4:32:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		47.7	%REC	1	7/13/2006 4:32:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		47.6	%REC	1	7/13/2006 4:32:00 PM	TDN
Surr: Phenol-d5		34.9-110		52.7	%REC	1	7/13/2006 4:32:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		71.5	%REC	1	7/13/2006 4:32:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.038		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Acenaphthylene	NELAP	0.038		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Benzo(a)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Benzo(b)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Benzo(k)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Chrysene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Fluoranthene	NELAP	0.025		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Fluorene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Naphthalene	NELAP	0.050		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Phenanthrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 4:46:49 PM	MAM
Surr: Terphenyl-d14		29.2-141		71.3	%REC	1	7/12/2006 4:46:49 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004

FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-006
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID D1
Collection Date: 7/11/2006 11:00:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		18.9	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		81.1	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.50		ND	mg/Kg-dry	1	7/13/2006 5:08:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		75.3	%REC	1	7/13/2006 5:08:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		67.1	%REC	1	7/13/2006 5:08:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		59.4	%REC	1	7/13/2006 5:08:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		57.6	%REC	1	7/13/2006 5:08:00 PM	TDN
Surr: Phenol-d5		34.9-110		64.1	%REC	1	7/13/2006 5:08:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		72.7	%REC	1	7/13/2006 5:08:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Acenaphthylene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Benzo(a)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Benzo(b)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Benzo(k)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Chrysene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Fluoranthene	NELAP	0.025		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Fluorene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Naphthalene	NELAP	0.049		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Phenanthrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:04:17 PM	MAM
Surr: Terphenyl-d14		29.2-141		69.0	%REC	1	7/12/2006 5:04:17 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-007
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID D2
Collection Date: 7/11/2006 11:05:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		23.2	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		76.8	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.63		ND	mg/Kg-dry	1	7/13/2006 5:43:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		68.3	%REC	1	7/13/2006 5:43:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		59.8	%REC	1	7/13/2006 5:43:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		51.2	%REC	1	7/13/2006 5:43:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		49.8	%REC	1	7/13/2006 5:43:00 PM	TDN
Surr: Phenol-d5		34.9-110		55.1	%REC	1	7/13/2006 5:43:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		72.5	%REC	1	7/13/2006 5:43:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.039		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Acenaphthylene	NELAP	0.039		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Benzo(a)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Benzo(b)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Benzo(k)fluoranthene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Chrysene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Fluoranthene	NELAP	0.026		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Fluorene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Naphthalene	NELAP	0.052		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Phenanthrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Pyrene	NELAP	0.013		ND	mg/Kg-dry	1	7/12/2006 5:21:46 PM	MAM
Surr: Terphenyl-d14		29.2-141		66.9	%REC	1	7/12/2006 5:21:46 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-008
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID E1
Collection Date: 7/11/2006 11:55:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		16.9	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		83.1	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.39		ND	mg/Kg-dry	1	7/13/2006 6:19:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		74.3	%REC	1	7/13/2006 6:19:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		64.2	%REC	1	7/13/2006 6:19:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		55.3	%REC	1	7/13/2006 6:19:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		53.1	%REC	1	7/13/2006 6:19:00 PM	TDN
Surr: Phenol-d5		34.9-110		59.0	%REC	1	7/13/2006 6:19:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		72.1	%REC	1	7/13/2006 6:19:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.036		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Acenaphthylene	NELAP	0.036		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Benzo(a)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Benzo(b)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Benzo(k)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Chrysene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Fluoranthene	NELAP	0.024		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Fluorene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Naphthalene	NELAP	0.048		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Phenanthrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:39:14 PM	MAM
Surr: Terphenyl-d14		29.2-141		74.8	%REC	1	7/12/2006 5:39:14 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-009
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID E2
Collection Date: 7/11/2006 12:03:00 PM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		19.1	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		80.9	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.51		ND	mg/Kg-dry	1	7/13/2006 6:55:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		77.3	%REC	1	7/13/2006 6:55:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		76.1	%REC	1	7/13/2006 6:55:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		61.3	%REC	1	7/13/2006 6:55:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		59.0	%REC	1	7/13/2006 6:55:00 PM	TDN
Surr: Phenol-d5		34.9-110		65.6	%REC	1	7/13/2006 6:55:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		78.5	%REC	1	7/13/2006 6:55:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Acenaphthylene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Benzo(a)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Benzo(b)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Benzo(k)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Chrysene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Fluoranthene	NELAP	0.024		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Fluorene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Naphthalene	NELAP	0.049		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Phenanthrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 5:56:43 PM	MAM
Surr: Terphenyl-d14		29.2-141		69.1	%REC	1	7/12/2006 5:56:43 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-010
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID F1
Collection Date: 7/11/2006 9:55:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		11.9	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		88.1	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.28		ND	mg/Kg-dry	1	7/13/2006 7:31:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		75.6	%REC	1	7/13/2006 7:31:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		68.7	%REC	1	7/13/2006 7:31:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		53.5	%REC	1	7/13/2006 7:31:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		53.7	%REC	1	7/13/2006 7:31:00 PM	TDN
Surr: Phenol-d5		34.9-110		59.5	%REC	1	7/13/2006 7:31:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		74.8	%REC	1	7/13/2006 7:31:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.034		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Acenaphthylene	NELAP	0.034		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Anthracene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Benzo(a)anthracene	NELAP	0.009		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Benzo(a)pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Benzo(b)fluoranthene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Benzo(k)fluoranthene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Chrysene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Fluoranthene	NELAP	0.023		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Fluorene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Naphthalene	NELAP	0.046		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Phenanthrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Pyrene	NELAP	0.011		ND	mg/Kg-dry	1	7/12/2006 6:14:12 PM	MAM
Surr: Terphenyl-d14		29.2-141		81.0	%REC	1	7/12/2006 6:14:12 PM	MAM

Sample Narrative

ENVIRONMENTAL TESTING LABORATORY

TEL: 618-344-1004
FAX: 618-344-1005

Laboratory Results

CLIENT: Hurst-Rosche Engineers, Inc.
WorkOrder: 06070246
Lab ID: 06070246-011
Report Date: 03-Aug-06

Client Project: Koppers Facility/ 180-3285
Client Sample ID: F2
Collection Date: 7/11/2006 10:14:00 AM
Matrix: SOLID

Analyses	Certification	RL	Qual	Result	Units	DF	Date Analyzed	Analyst
ASTM D2974								
Percent Moisture		0.1		18.7	%	1	7/12/2006	CDH
STANDARD METHODS 18TH ED. 2540 G								
Total Solids		0.1		81.3	%	1	7/12/2006	CDH
SW-846 3550B, 8270C, SEMI-VOLATILE ORGANIC COMPOUNDS BY GC/MS								
Pentachlorophenol	NELAP	2.40		ND	mg/Kg-dry	1	7/13/2006 8:06:00 PM	TDN
Surr: 2,4,6-Tribromophenol		32.7-130		74.0	%REC	1	7/13/2006 8:06:00 PM	TDN
Surr: 2-Fluorobiphenyl		34.1-116		58.5	%REC	1	7/13/2006 8:06:00 PM	TDN
Surr: 2-Fluorophenol		30.5-99		54.1	%REC	1	7/13/2006 8:06:00 PM	TDN
Surr: Nitrobenzene-d5		34.1-101		52.0	%REC	1	7/13/2006 8:06:00 PM	TDN
Surr: Phenol-d5		34.9-110		60.3	%REC	1	7/13/2006 8:06:00 PM	TDN
Surr: p-Terphenyl-d14		41.7-124		70.3	%REC	1	7/13/2006 8:06:00 PM	TDN
SW-846 3550B, 8310, POLYNUCLEAR AROMATIC HYDROCARBONS BY HPLC								
Acenaphthene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Acenaphthylene	NELAP	0.037		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Benzo(a)anthracene	NELAP	0.010		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Benzo(a)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Benzo(b)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Benzo(g,h,i)perylene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Benzo(k)fluoranthene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Chrysene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Dibenzo(a,h)anthracene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Fluoranthene	NELAP	0.025		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Fluorene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Indeno(1,2,3-cd)pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Naphthalene	NELAP	0.050		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Phenanthrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Pyrene	NELAP	0.012		ND	mg/Kg-dry	1	7/12/2006 6:31:40 PM	MAM
Surr: Terphenyl-d14		29.2-141		54.6	%REC	1	7/12/2006 6:31:40 PM	MAM

Sample Narrative

CHAIN OF CUSTODY

pg. 2 of 2 Work Order # 06070246

TEKLAB, INC. 5445 Horseshoe Lake Road ~ Collinsville, IL 62234 ~ Phone: (618) 344-1004 ~ Fax: (618) 344-1005

Client: Hurst-Rosche Engineers, Inc.
 Address: 1400 E. Tremont St.
 City / State / Zip: Hillsboro, IL 62049
 Contact: D. Kimmick Phone: 217/532-3959
 E-Mail: _____ Fax: 217/532-3212

Samples on: Ice Blue Ice No Ice _____ °C
 Preserved in: Lab Field
 Lab Notes:
 Comments:

- Are these samples known to be involved in litigation? If yes, a surcharge will apply. Yes No
- Are these samples known to be hazardous? Yes No
- Are there any required reporting limits to be met on the requested analysis? If yes, please provide limits in comment section. Yes No

Project Name / Number			Sample Collector's Name								MATRIX					INDICATE ANALYSIS REQUESTED																
<u>Koppers Facility / 180-3285</u>			<u>David Kimmick</u>								Water	Drinking Water	Soil	Sludge	Sp. Waste	PAH's	PCP															
Results Requested		Billing Instructions		# and Type of Containers																												
<input checked="" type="checkbox"/> Standard <input type="checkbox"/> 1-2 Day (100% Surcharge)		<input type="checkbox"/> Other <input type="checkbox"/> 3 Day (50% Surcharge)		UNPRES	HNO ₃	NaOH	H ₂ SO ₄	HCL	MeOH	NaHSO ₄								Other														
Lab Use Only	Sample Identification	Date/Time Sampled																														
<u>06070246-010</u>	<u>F1</u>	<u>7/11/06</u>	<u>9:55 am</u>																X	X												
<u>-011</u>	<u>F2</u>	<u>7/11/06</u>	<u>10:14 am</u>																X	X												
Relinquished By			Date / Time					Received By					Date / Time																			
<u>W.D.H.A.</u>			<u>7/11/06 3:00 pm 1545</u>					<u>Shelby Hennery</u>					<u>7/11/06 1545</u>																			

The individual signing this agreement on behalf of client acknowledges that he/she has read and understands the terms and conditions of this agreement. WHITE & YELLOW - LAB PINK - SAMPLER'S COPY

Attachment 3

Photographs

Note: Photographs have been presented in the order taken.



No. 1 Looking west. Thomas School is in the background.
Location F



No. 2 Looking south along eastern edge of open lot behind Thomas School.
Location F



No. 3 Looking west along northern edge of residential lot #608 on E. Jenkins Street. Location C



No. 4 Looking north at Location C.



No. 5 Looking north at Location C.



No. 6 Looking northwest at home located on Lot 608 on E. Jenkins Street.
Location C.



No. 7 Looking west at Location D.




No. 8 Looking northeast at Location D (in the background) from Pierce St.



No. 9 Looking northwest at Location D.



No. 10 Looking north along eastern edge of Lot 1209. Location B. Stake laying on ground to the right is the original/proposed boring location.



No. 11 Looking northeast at Location B.



No. 12 Looking northeast at home located on Lot 1209 on Allman St.
Location B.



No. 13 Looking east at Location E.



No. 14 Looking southeast at Location E.



No. 15 Looking southwest at Location E from Robert A. Stalls Ave. (formerly Barnes St.)



No. 16 Looking southwest at planned Location A. Apparent fill was encountered at this location, so boring location was moved.




No. 17 Looking north at Lot 400 (Location A). Probes were completed on north side of lot and apparent fill was encountered.



No. 18 Looking northwest at Lot 400 (Location A).



No. 19 Looking north at new Location A at the southeast corner of the Erma Hayes Center.



No. 20. Looking north across Birch St. at the new Location A.

FINAL DRAFT**WORK PLAN FOR ADDITIONAL PCDD/PCDF SAMPLING****BEAZER EAST, INC.
FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS**Introduction/Purpose

As a follow-up to a letter submitted to the United States Environmental Protection Agency (USEPA) dated June 30, 2010 and discussions during a September 9, 2010 conference call, Beazer East, Inc. (Beazer) has prepared this Work Plan for additional soil sampling activities within and south of the southern drainage ditches area and at the western end of the Former Koppers Wood-Treating Site in Carbondale, Illinois (the Site; Figure 1). The proposed scope of work is a follow-up to sampling conducted in these areas in December 2009 and March 2010, and incorporates USEPA's comments received in a letter dated January 5, 2011.

Background

Surficial soil samples from within, near and south of the southern drainage ditches area and the western end of the Site have been collected on multiple occasions over the last several years:

- In March 2005, USEPA collected surficial soil samples from residential areas south of the Site; samples were analyzed for polycyclic aromatic hydrocarbons (PAHs) and pentachlorophenol
- In May 2005, Beazer collected surficial soil samples to confirm/modify the proposed Former Process Area surface cover limits; samples were analyzed for PAHs and pentachlorophenol
- In March 2006, March 2008 and June 2008, Beazer collected surficial soil samples to characterize the nature and extent of impacts in the southern drainage ditches area; samples were analyzed for PAHs, pentachlorophenol, polychlorinated dibenzo-p-dioxins and polychlorinated dibenzofurans (PCDDs/PCDFs), and/or arsenic
- In July 2006, the City of Carbondale collected surficial soil samples from residential areas south of the Site; samples were analyzed for PAHs and pentachlorophenol
- In December 2009 and March 2010, Beazer collected additional samples to characterize and delineate the extent of Site-related constituents in the southern drainage ditches area and western end of the Site, among other areas; samples were analyzed for PAHs, pentachlorophenol, PCDDs/PCDFs, and/or arsenic

The sample locations associated with these sampling events, and that lie near or within areas where additional investigations are proposed herein, are shown on Figure 1.

Scope/Procedures

Additional soil sampling is proposed at a total of 22 locations (Figure 1), including:

- Four locations (A1-50, A1-51, A1-56 and A1-57) in the vicinity of previous sample locations A1-37 and A1-48, as initially proposed on Beazer's June 30, 2010 letter to the USEPA;
- Two locations (A3-33 and A3-34) north and northeast of previous sample location A1-48, as requested in USEPA's January 5, 2011 letter;

FINAL DRAFT

- Four locations (A3-29 through A3-32) north of the main Site access road as described/requested by USEPA during a conference call on September 9, 2010¹ (the locations of three of these were subsequently moved approximately 100 feet north per USEPA's January 5, 2011 letter);
- Four locations (A3-25 through A3-28) at the western end of the Site to further characterize an area noted by USEPA in email correspondence to Beazer dated September 10, 2010;
- Three locations (A1-58 through A1-60) within and adjacent to Glade Creek upstream of the western end of the Site, one of which (A1-59) also represents the residential area south of the Site, to further characterize an area noted by USEPA in email correspondence to Beazer dated September 10, 2010; and
- Five additional locations (A1-52 through A1-55, and A1-61) in the residential area south of the Site, one of which corresponds to a 2005 soil sample collected by the USEPA and analyzed for other Site-related constituents

The location description and rationale for each sample location are summarized in Table 1. Note that a residential area in closest proximity to the southern portion of the Site was identified for further investigation during the September 9, 2010 conference call. An appropriate number of samples to be collected from this area was not stated on the call, although USEPA indicated that the number of samples should be consistent with the prior sampling conducted in 2006 by the City of Carbondale. Based on this suggestion, Beazer reviewed the prior scopes of work associated with the USEPA's 2005 and the City's 2006 sampling south of the Site. Recall that neither of these sampling events indicated the presence of Site-related constituents (PAHs and pentachlorophenol) at concentrations above Illinois Tiered Approach to Corrective Action Objectives (TACO) criteria for residential properties. In total, the City collected 11 samples from six locations in 2006, of which one location was within the area identified for sampling during the September 9, 2010 call. The USEPA collected 13 off-site samples in 2005, 12 of which were south of the Site property line near the residential area, and four of those were within the area identified for sampling during the September 9, 2010 call. Based on these prior investigations, Beazer proposed five additional sample locations within the area identified for sampling during the September 9, 2010 call (i.e., exceeding the scope of either prior investigation within this area). A sixth sample was added to this area based on USEPA's January 5, 2011 letter. These samples are also in addition to the nine locations that have been previously sampled along the Beazer and/or railroad property lines that abut this residential area.

At each of the proposed 22 sample locations, soils will be collected from the 0- to 0.5-foot depth interval using a stainless-steel trowel. At each of the 16 non-residential sample locations, a single, discrete soil sample will be collected. At each of the six residential sample locations (A1-52 through A1-55, A1-59 and A1-61), soils will be collected at a minimum of five² discrete locations spatially distributed throughout the parcel, and composited into a single sample for laboratory analysis.

Soil types/characteristics and descriptions of any non-aqueous phase liquid (NAPL), staining, odors and/or sheens will be recorded in a field notebook. Recovered soils will be homogenized prior to placing them into sample containers. Excess soils will be placed back into the hole following sample collection. All sample locations will be staked and surveyed (or GPS-located) so that they can be accurately depicted

¹ One of the proposed locations, A3-32 was moved from the location discussed with USEPA on September 9, 2010, to a location outside of the re-worked soil area near the office building, construction trailers and wastewater treatment system.

² Sampling densities may be adjusted upward once individual residential access agreements are obtained, and in the event that a particular parcel is larger than average. Efforts will be made to avoid collecting discrete samples from any visibly evident potential property-specific sources (e.g., burn pits or barrels).

FINAL DRAFT

on the site plan and re-established in the future, if necessary. Samples will be analyzed for PCDDs/PCDFs via USEPA SW-846 Method 8290.

Property Access

Sixteen of the 22 proposed sample locations are located on non-Beazer-owned properties. Following USEPA approval of the proposed sample locations and prior to mobilizing for the sampling work, Beazer will attempt to obtain permission from the associated property owners to collect samples from these locations. Any difficulties in obtaining property access will be communicated to USEPA.

Quality Assurance/Quality Control

PCDD/PCDF samples will be analyzed by Vista Analytical Laboratory in El Dorado Hills, California. Quality assurance/quality control (QA/QC) samples will be collected at the frequencies specified in the Quality Assurance Project Plan (QAPP; ARCADIS, February 2008). Analytical data will be validated in accordance with USEPA National Functional Guidelines for Data Review, as discussed in the QAPP.

Equipment Cleaning and Waste Management

Non-dedicated/non-disposable sampling equipment will be cleaned prior to use at each sample location following procedures outlined in the QAPP (i.e., non-phosphate detergent wash, distilled/deionized water rinse, and triple rinse sequence of solvent followed by distilled/deionized water).

Equipment cleaning fluids will be collected for treatment at the onsite wastewater treatment system (WWTS). Used personal protective equipment, disposable sampling equipment, and other miscellaneous wastes will be placed into a 55-gallon drum and staged at a designated area near the WWTS for subsequent characterization and disposal by Beazer.

Data Review and Reporting

Following completion of the sampling and receipt/validation of the laboratory analytical data, Beazer will prepare data summary tables and sample locations maps for review/discussion with USEPA. Data summary tables will include 2,3,7,8-TCDD Toxic Equivalents (TEQ; calculated using WHO-2005 Toxic Equivalency Factors).

Schedule

It is anticipated that the field work will be initiated within approximately two weeks following USEPA approval of the sampling scope and the receipt of necessary access approvals, pending suitable weather and field conditions. The work described herein will require approximately three days to complete once all access approvals are obtained. To account for the data validation timeframe, data summary tables and sample location maps will be submitted to the USEPA within approximately six weeks following receipt of all associated laboratory analytical data.


**TABLE 1
 PROPOSED SAMPLING SCOPE AND RATIONALE**

**Beazer East, Inc.
 Former Koppers Wood-Treating Site
 Carbondale, Illinois**

Sample ID	Location Description	Depth Interval (ft)	Rationale
A1-50	Approximately 10 feet north of the top of ditch bank at A1-48	0-0.5	Delineate PCDD/PCDFs near A1-48 as proposed in 6/30/2010 letter
A1-51	Approximately 10 feet south of the top of ditch bank at A1-48	0-0.5	Delineate PCDD/PCDFs near A1-48 as proposed in 6/30/2010 letter
A1-52*	Approximately 150 feet south/southeast of A1-45 at north end of N. Allman St	0-0.5	Assess the presence of PCDDs/PCDFs in residential area south of the Site
A1-53*	Approximately 100 feet south of A1-43 along west side of N. Robert A Stalls Ave	0-0.5	Assess the presence of PCDDs/PCDFs in residential area south of the Site
A1-54*	Approximately 100 feet south of A1-42 adjacent to 2005 USEPA sample location S3	0-0.5	Assess the presence of PCDDs/PCDFs in residential area south of the Site; corresponds to prior USEPA sample location
A1-55*	Approximately 100 feet south of A1-41 along west side of N. Wall St	0-0.5	Assess the presence of PCDDs/PCDFs in residential area south of the Site
A1-56	Approximately 50 feet southwest of A1-37	0-0.5	Delineate PCDD/PCDFs near A1-37 as proposed in 6/30/2010 letter
A1-57	Approximately 50 feet east of A1-37	0-0.5	Delineate PCDD/PCDFs near A1-37 as proposed in 6/30/2010 letter
A1-58	Approximately 50 feet west of Glade Creek, approximately 450 feet downstream of A1-60	0-0.5	Assess the presence of PCDDs/PCDFs along Glade Creek upstream of the Site; characterize area noted by USEPA via email on 9/10/2010
A1-59*	Approximately 200 feet south and 425 feet west of A1-52	0-0.5	Assess the presence of PCDDs/PCDFs toward residential area south of the Site; characterize area noted by USEPA via email on 9/10/2010
A1-60	In Glade Creek, approximately 180 feet downstream of North Marion Street crossing	0-0.5	Supplement existing PCDD/PCDF dataset for Glade Creek sediment upstream of the Site; characterize area noted by USEPA via email on 9/10/2010
A1-61*	Between samples A1-54 and A1-55 (on a separate residential property)	0-0.5	Assess the presence of PCDDs/PCDFs in residential area south of the Site, as requested by USEPA's 1/5/2011 letter
A3-25	In southwest corner of Beazer's property on west side of North Marion Street	0-0.5	Supplement existing PCDD/PCDF dataset for western portion of the Site; assess potential migration beyond Glade Creek; characterize area noted by USEPA via email on 9/10/10
A3-26	Approximately midway between A3-25 and A3-27, on east side of Glade Creek	0-0.5	Supplement existing PCDD/PCDF dataset for western portion of the Site, specifically near prior location A3-20; characterize area noted by USEPA via email on 9/10/2010
A3-27	Approximately midway between A3-8 and A3-20, on west side of North Marion Street	0-0.5	Supplement existing PCDD/PCDF dataset for western portion of the Site, specifically near prior location A3-20; characterize area noted by USEPA via email on 9/10/2010
A3-28	Approximately 300 feet north/northwest of A3-8, between North Marion Street and former RR tracks	0-0.5	Supplement existing PCDD/PCDF dataset for western portion of the Site adjacent to public roadway; characterize area noted by USEPA via email on 9/10/2010
A3-29	Approximately 120 feet north of main Site access road	0-0.5	Assess the presence of PCDDs/PCDFs in previously unsampled area north of main Site access road; location specifically identified by USEPA on 9/9/2010, and revised as requested by USEPA's 1/5/2011 letter
A3-30	Approximately 120 feet north of main Site access road	0-0.5	Assess the presence of PCDDs/PCDFs in previously unsampled area north of main Site access road; location specifically identified by USEPA on 9/9/2010, and revised as requested by USEPA's 1/5/2011 letter
A3-31	Approximately 120 feet north of main Site access road	0-0.5	Assess the presence of PCDDs/PCDFs in previously unsampled area north of main Site access road; location specifically identified by USEPA on 9/9/2010, and revised as requested by USEPA's 1/5/2011 letter
A3-32	Near intersection of Site access road and Beazer property line	0-0.5	Assess the presence of PCDDs/PCDFs in previously unsampled area north of main Site access road; location specifically identified by USEPA on 9/9/2010, but modified to account for presence of the office building, construction trailers and WWTS.
A3-33	Within the 390-foot contour southwest of the Site	0-0.5	As requested by USEPA's 1/5/2011 letter
A3-34	Approximately 175 feet east of sample A3-33	0-0.5	As requested by USEPA's 1/5/2011 letter

PCDDs/PCDFs = polychlorinated dibenzo-p-dioxins/polychlorinated dibenzofurans (USEPA SW-846 Method 8290)

* - indicates sample will be composited from a minimum of five locations on the target property




LEGEND:

- EDGE OF WATER
- DRAINAGE DITCH AND DIRECTION OF FLOW
- - - PROPERTY BOUNDARY (SEE NOTE 2)
- x - FENCELINE
- - - EXISTING CONTOUR LINE
- FORMER PROCESS AREA SURFACE COVER
- SOIL REMOVAL AREA (SOIL/DEBRIS PILES AND SURFICIAL ASPHALT-LIKE MATERIALS)
- PORTIONS OF SOUTHERN DRAINAGE DITCHES THAT HAVE BEEN FILLED IN PRIOR TO OR DURING SURFACE COVER CONSTRUCTION OR REMOVAL OF SOIL AND DEBRIS PILES.
- S1 ● 2005 RESIDENTIAL SAMPLE LOCATIONS (USEPA)
- SB-102 ● 2005-2010 SAMPLE LOCATIONS (BEAZER)
- B ● 2006 RESIDENTIAL SAMPLE LOCATIONS (CITY OF CARBONDALE)
- A1-30 ● PROPOSED SAMPLE LOCATIONS
- A3-33 ● NEW EPA-PROPOSED LOCATIONS (JANUARY 5, 2011)

NOTES:

1. SITE FEATURES AND TOPOGRAPHY OBTAINED FROM PHOTOGRAMMETRIC MAPPING PROVIDED BY LOCKWOOD MAPPING COMPANY IN SEPTEMBER 2001 AND SURVEY DATA PROVIDED BY ENGINEERING SOURCE, INC. IN JANUARY 2004, AND BASED ON AERIAL PHOTOGRAPHY PROVIDED BY LOCKWOOD MAPPING, INC. TAKEN ON NOVEMBER 22, 1996 AT AN APPROXIMATE SCALE OF 1"=500'. TOPOGRAPHY IN THE EASTERN SOUTHERN DRAINAGE DITCHES AREA BASED ON TOPOGRAPHIC FIELD SURVEY CONDUCTED IN AUGUST 2007.
2. PROPERTY BOUNDARY IS APPROXIMATE; OBTAINED FROM A COMBINATION OF SITE SURVEY DATA, HISTORICAL MAPS AND TAX MAPS.
3. THE 2006 RESIDENTIAL SAMPLE LOCATIONS ARE APPROXIMATE.
4. FIVE RESIDENTIAL SAMPLES (A1-52 THROUGH A1-55, AND A1-61) WILL EACH BE COMPOSITES FROM FIVE LOCATIONS ON THE RESPECTIVE PROPERTIES.




FINAL DRAFT

BEAZER EAST, INC.
FORMER KOPPERS WOOD TREATING SITE
CARBONDALE, ILLINOIS

**PROPOSED ADDITIONAL PCDD/PCDF
SAMPLE LOCATIONS**



FIGURE
1



CITY: SYRACUSE DIV/GROUP: ENVCAD DB: L. FORAKER LD: PIC: R. ANDERSON PM: J. HOLDEN TM: D. BESSINGPAS LYR: ONE OFF=REF
 G:\ENVCAD\SYRACUSE\ACT\800381432010\00001\DWG\PCDD-PCDF\38143G01.DWG LAYOUT: 1 SAVED: 1/24/2011 11:27 AM ACADVER: 18.05 (LMS TECH) PAGES: 10 PLOTSETUP: C-LD-PDF PLOTSTYLETABLE: PLT\FULL\CTB PLOTTED: 1/24/2011 4:30 PM BY: FORAKER, LYDIA
 XREFS: IMAGES: 38143X01 PROJECTNAME: 38143X01

Beazer

BEAZER EAST, INC. C/O THREE RIVERS MANAGEMENT, INC.
MANOR OAK ONE, SUITE 200, 1910 COCHRAN ROAD, PITTSBURGH, PA 15220

October 17, 2012

Ms. Carolyn Bury
U.S. Environmental Protection Agency, Region V
77 West Jackson Boulevard
Mail Code DE-9J
Chicago, IL 60604-3590

Re: Former Koppers Wood-Treating Site – Carbondale, Illinois
August 2012 Dioxin Sampling Final/Validated Data Submittal

Dear Ms. Bury:

In accordance with the January 24, 2011 *Final Draft Work Plan for Additional PCDD/PCDF Sampling*, which was conditionally approved by the USEPA on June 1, 2012 and subsequently expanded,¹ Beazer conducted sampling at and near the Former Koppers Wood-Treating Site in Carbondale, Illinois on August 8 and 9, 2012. The purpose of this letter is to transmit the final/validated laboratory analytical data associated with the August 2012 sampling to the USEPA. The following are attached to this letter:

- Attachment 1 – Validated Analytical Data Summary Table
- Attachment 2 – Sample Location Maps
- Attachment 3 – Data Validation Reports (includes validated laboratory analytical data sheets)

Please feel contact me at 412-208-8867 if you have any questions or comments regarding this submittal.

Sincerely,



Michael Slenska, P.E.
Environmental Manager

Enclosure

cc: James Moore, IEPA
Jeffrey Holden, ARCADIS
Paul Anderson, ARCADIS
David Bessingpas, ARCADIS

¹ Revised/alternate locations for residential sample locations were discussed with USEPA during a June 19, 2012 conference call, were documented in an e-mail from Jeffrey Holden (ARCADIS) to USEPA, and were approved in an e-mail from Carolyn Bury (USEPA) dated June 22, 2012.

Writer's Direct Dial: 412/208-8867

Attachment 1

Validated Analytical Data
Summary Table

**TABLE 1
VALIDATED ANALYTICAL DATA SUMMARY - AUGUST 2012 SAMPLES**

**FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS**

Sample ID: Depth (ft bgs): Sample Date:	Units	A1-50 0 - 0.5 08/09/12	A1-51 0 - 0.5 08/09/12	A1-52 0 - 0.5 08/08/12	A1-53 0 - 0.5 08/08/12	A1-54 0 - 0.5 08/08/12	A1-55 0 - 0.5 08/08/12	A1-56 0 - 0.5 08/08/12	A1-57 0 - 0.5 08/08/12	A1-58 0 - 0.5 08/09/12	A1-59 0 - 0.5 08/08/12	A1-60 0 - 0.5 08/08/12
PCDDs/PCDFs												
1,2,3,4,6,7,8-HpCDD	ug/kg	0.626 [0.781]	0.918	0.309 [0.325]	1.59	0.545	1.47	0.541	0.488	0.602	2.85 EJ	0.00423
1,2,3,4,6,7,8-HpCDF	ug/kg	0.0588 [0.0491]	0.136	0.062 [0.0721]	0.194	0.0639	0.165	0.0613	0.0465	0.0839	0.452	0.000297 J
1,2,3,4,7,8,9-HpCDF	ug/kg	0.00482 [0.00424]	0.0107	0.00397 [0.00563]	0.00883	0.00425	0.0122	0.00543	0.0042	0.00415	0.0279	0.000115 U
1,2,3,4,7,8-HxCDD	ug/kg	0.00408 [0.00513]	0.0114	0.00357 [0.00364]	0.0264	0.00367	0.0159	0.00563	0.00554	0.00568	0.0241	0.000129 U
1,2,3,4,7,8-HxCDF	ug/kg	0.00377 [0.00334]	0.00889	0.00585 [0.0121]	0.00597	0.00415	0.00635	0.00409	0.00334	0.00429	0.016	0.0000584 U
1,2,3,6,7,8-HxCDD	ug/kg	0.0158 [0.0145]	0.0311	0.0101 [0.0121]	0.0579	0.0129	0.05	0.0133	0.0128	0.014	0.0834	0.000153 U
1,2,3,6,7,8-HxCDF	ug/kg	0.00225 J [0.00161 J]	0.00775	0.00339 [0.00681]	0.0067	0.00289	0.0043	0.00148 J	0.00121 J	0.00291	0.00951	0.0000556 U
1,2,3,7,8,9-HxCDD	ug/kg	0.0117 [0.0118]	0.0257	0.00761 [0.00847]	0.0664	0.00893	0.0315	0.0104	0.01	0.0113	0.0536	0.00024 J
1,2,3,7,8,9-HxCDF	ug/kg	0.000545 J [0.000345 J]	0.000793 J	0.000312 J [0.000913 J]	0.000585 J	0.000614 J	0.000928 J	0.000296 J	0.00019 UX	0.000638 J	0.00152 J	0.0000858 U
1,2,3,7,8-PeCDD	ug/kg	0.00251 [0.0019 J]	0.00597	0.00235 J [0.00295]	0.0157	0.00197 J	0.00859	0.00244 J	0.00247 J	0.00261	0.0096	0.000188 J
1,2,3,7,8-PeCDF	ug/kg	0.000752 J [0.000465 J]	0.0016 J	0.00214 J [0.00811 J]	0.000782 J	0.00102 J	0.00121 J	0.00037 UX	0.000326 J	0.000889 J	0.00164 J	0.0000424 U
2,3,4,6,7,8-HxCDF	ug/kg	0.00394 [0.00325]	0.0135	0.00417 [0.00582]	0.00926	0.004	0.00721	0.00235 J	0.00202 J	0.00522	0.0164	0.0000644 U
2,3,4,7,8-PeCDF	ug/kg	0.00138 J [0.00138 J]	0.00357	0.00229 J [0.00456]	0.00149 J	0.00144 J	0.00243 J	0.00107 J	0.000711 J	0.00366	0.00291	0.0000449 U
2,3,7,8-TCDD	ug/kg	0.000558 [0.000416 J]	0.00162	0.000491 J [0.000675]	0.00118	0.000654	0.0013	0.000699	0.000636	0.000587	0.000761	0.000291 J
2,3,7,8-TCDF	ug/kg	0.000633 [0.000436 J]	0.00184	0.0025 [0.00638]	0.000333 J	0.001	0.000999	0.000362 U	0.000305 J	0.00108	0.00144	0.0000579 U
OCDD	ug/kg	21.1 EJ [23.9 EJ]	24.5 EJ	7.67 EJ [8.5 EJ]	25.7 EJ	15.7 EJ	26.8 EJ	14.8 EJ	13.4 EJ	31.3 EJ	47.2 EDJ	0.214
OCDF	ug/kg	0.421 [0.351]	0.523	0.186 [0.187]	0.706	0.238	0.819	0.327	0.254	0.233	1.99	0.000995 J
Total HpCDD	ug/kg	1.47 [2.46]	1.81	0.604 [0.648]	3.07	1.12	2.67	1.16	1.09	1.31	5.29	0.00911
Total HpCDF	ug/kg	0.295 [0.24]	0.483	0.168 [0.187]	0.518	0.197	0.645	0.25	0.192	0.27	1.55	0.000876
Total HxCDD	ug/kg	0.164 [0.235]	0.254	0.0977 [0.124]	0.52	0.124	0.43	0.146	0.15	0.142	0.603	0.0119
Total HxCDF	ug/kg	0.0909 [0.0777]	0.253	0.0796 [0.106]	0.206	0.0837	0.192	0.0717	0.056	0.115	0.453	0.000392
Total PeCDD	ug/kg	0.0227 [0.0203]	0.046	0.0365 [0.0459]	0.0683	0.0211	0.108	0.0209	0.021	0.0239	0.0759	0.0115
Total PeCDF	ug/kg	0.0504 [0.0339]	0.168 PJ	0.0534 [0.0948 J]	0.0436	0.0181	0.0572	0.0114	0.0104	0.0556	0.0984	0.000148
Total TCDD	ug/kg	0.0126 [0.0104]	0.0153	0.0341 [0.0337]	0.00719	0.00729	0.0286	0.00686	0.00589	0.00914	0.0301	0.00468
Total TCDF	ug/kg	0.018 [0.0135]	0.0576	0.0576 [0.104]	0.00874	0.021	0.0272	0.00348	0.0052	0.0229	0.042	0.0000887
2,3,7,8-TCDD TEQ	ug/kg	0.0211 [0.0224]	0.037	0.0134 [0.0175]	0.0606	0.0178	0.0471	0.0178	0.0163	0.0252	0.0799	0.000613

See Notes on Page 3

TABLE 1
VALIDATED ANALYTICAL DATA SUMMARY - AUGUST 2012 SAMPLES

FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

Sample ID: Depth (ft bgs): Sample Date:	Units	A1-61 0 - 0.5 08/08/12	A1-62 0 - 0.5 08/08/12	A1-63 0 - 0.5 08/08/12	A3-25 0 - 0.5 08/09/12	A3-26 0 - 0.5 08/09/12	A3-27 0 - 0.5 08/09/12	A3-28 0 - 0.5 08/09/12	A3-29 0 - 0.5 08/08/12	A3-30 0 - 0.5 08/09/12	A3-31 0 - 0.5 08/09/12	A3-32 0 - 0.5 08/08/12	A3-33 0 - 0.5 08/09/12	A3-34 0 - 0.5 08/09/12
PCDDs/PCDFs														
1,2,3,4,6,7,8-HpCDD	ug/kg	3.12 EJ	81.8 D	0.446	0.715	5 EJ	0.532	343 EDJ	0.249	0.606	1.46	23.9 EDJ [28.6 EJ]	43.1 EDJ	5.16 EJ
1,2,3,4,6,7,8-HpCDF	ug/kg	0.309 J	17.1 EDJ	0.0401	0.0349	0.864	0.0692	68.9 EDJ	0.0147	0.045	0.14	5.5 EJ [5.81 EJ]	7.04 D	0.986
1,2,3,4,7,8,9-HpCDF	ug/kg	0.0234	1.68 D	0.00359	0.00351	0.0697	0.00537	6.06 D	0.00131 J	0.00352	0.00994	0.379 [0.423]	0.586 D	0.076
1,2,3,4,7,8-HxCDD	ug/kg	0.052	0.306	0.00472	0.00533	0.039	0.0069	1.82	0.0034	0.00592	0.0198	0.233 [0.28]	0.199	0.0586
1,2,3,4,7,8-HxCDF	ug/kg	0.0229	0.435	0.00311	0.00257	0.0476	0.00701	1.84	0.0014 J	0.00365	0.00748	0.229 [0.242]	0.273	0.0734
1,2,3,6,7,8-HxCDD	ug/kg	0.123	2.21 EJ	0.0108	0.0145	0.16	0.0179	6.66 EJ	0.00682	0.0131	0.0585	1.01 [1.22]	1.03	0.167
1,2,3,6,7,8-HxCDF	ug/kg	0.00772	0.153	0.00122 J	0.00116 J	0.0255	0.0042	0.98 PJ	0.000675 J	0.00165 J	0.00386	0.132 [0.142]	0.0909	0.0335
1,2,3,7,8,9-HxCDD	ug/kg	0.0801	0.629	0.00923	0.0104	0.0861	0.011	3.02 EJ	0.00666	0.0121	0.0475	0.514 [0.632]	0.36	0.118
1,2,3,7,8,9-HxCDF	ug/kg	0.00211 J	0.0419	0.00034 J	0.000317 UX	0.00997	0.000638 J	0.125	0.000171 J	0.00027 J	0.000771 J	0.0558 [0.0324]	0.0499	0.00516
1,2,3,7,8-PeCDD	ug/kg	0.0229	0.0818	0.00233 J	0.00224 J	0.0175	0.00466	0.616	0.00156 J	0.00228 J	0.0123	0.0837 [0.0968]	0.0626	0.0185
1,2,3,7,8-PeCDF	ug/kg	0.00194 J	0.0108	0.000281 UX	0.000402 J	0.0043	0.00172 J	0.0667	0.000243 J	0.0004 J	0.000973 J	0.0209 [0.0229]	0.0123	0.00517
2,3,4,6,7,8-HxCDF	ug/kg	0.0114	0.341	0.00175 J	0.00203 J	0.049	0.00608	1.84	0.00102 J	0.00254	0.00568	0.24 [0.248]	0.184	0.0548
2,3,4,7,8-PeCDF	ug/kg	0.0031	0.0308 D	0.000772 J	0.000519 UX	0.013	0.00368	0.11	0.000351 J	0.00123 J	0.00161 J	0.0422 [0.0819]	0.0432	0.0167
2,3,7,8-TCDD	ug/kg	0.0036	0.00535	0.000478 UX	0.000361 J	0.00372	0.000808	0.0388	0.000225 UX	0.000341 J	0.00135	0.00305 [0.00375]	0.00384	0.00222
2,3,7,8-TCDF	ug/kg	0.000859	0.00322	0.000233 U	0.000233 UX	0.00369	0.00181	0.00931	0.000253 J	0.000311 J	0.00081	0.00419 [0.00509]	0.00412	0.00352
OCDD	ug/kg	38.6 EJ	727 EDJ	14.9 EJ	34.4 EJ	84 D	13.6 EJ	2,270 EDJ	7.77 EJ	29.4 EJ	22.5 EJ	198 [240 EDJ]	487 EDJ	45.8 EJ
OCDF	ug/kg	2.16	123 EDJ	0.193	0.147	4.62 EJ	0.327	438 EDJ	0.0655	0.219	0.803	27.3 EJ [28.4 EJ]	41.5 EDJ	4.24 EJ
Total HpCDD	ug/kg	6.09	150	0.966	2.28	9	1.12	732	0.593	1.49	3.04	39.3 [47.3 J]	82.3	13
Total HpCDF	ug/kg	1.5 J	92.6 PJ	0.153	0.143	3.71	0.268	337	0.0582	0.18	0.582	20.5 [21.9 J]	33.7	3.66
Total HxCDD	ug/kg	1.38	12.3 J	0.123	0.239	0.914	0.177	55.3	0.092	0.176	0.646	4.77 [6.06]	5.13	1.49
Total HxCDF	ug/kg	0.383	16.5 PJ	0.0482	0.0541	1.14	0.119	72.8 PJ	0.0234	0.06	0.155	6.11 [6.79]	6.13	1.41
Total PeCDD	ug/kg	0.361	0.401	0.0188	0.0579	0.112	0.0873	3.78	0.016	0.0254	0.121	0.448 [0.543]	0.414	0.109
Total PeCDF	ug/kg	0.0681	0.775 PJ	0.00915	0.00494	0.367	0.0707	5.45 PJ	0.00667	0.0124	0.0306	0.911 [1.08]	0.652	0.261 PJ
Total TCDD	ug/kg	0.0991	0.118	0.00472	0.0127	0.0272	0.0793	0.332	0.00685	0.00837	0.0227	0.104 [0.14]	0.102	0.0468
Total TCDF	ug/kg	0.0308	0.111 PJ	0.00318	0.00302	0.101	0.0456	0.45 PJ	0.0052	0.00621	0.0133	0.107 [0.132]	0.0978	0.0701
2,3,7,8-TCDD TEQ	ug/kg	0.104	1.77	0.0151	0.0241	0.153	0.0224	7.31	0.00871	0.0224	0.0517	0.707 [0.835]	0.965	0.155

See Notes on Page 3

**TABLE 1
VALIDATED ANALYTICAL DATA SUMMARY - AUGUST 2012 SAMPLES**

**FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS**

Notes:

1. Samples A1-52, A1-53, A1-54, A1-55, A1-59 and A1-61 were composites of five discrete sample locations. All remaining samples were collected from a single, discrete location.
2. Sample A1-60 was a sediment sample collected from the Glade Creek channel bottom. All remaining samples were soil samples.

Definitions:

PCDDs/PCDFs = polychlorinated dibenzo-p-dioxins/polychlorinated dibenzofurans

ug/kg = micrograms per kilogram, or parts per billions (ppb)

ft bgs = feet below ground surface

TEQ = Toxicity Equivalent, calculated using 2005 World Health Organization (WHO) Toxicity Equivalent Factors (TEFs)

[] = analytical result for duplicate sample

Data Qualifiers:

D = result based on analysis of diluted sample

E = the amount detected is above the High Calibration Limit

J = the amount detected is below the Low Calibration Limit; or estimated value based on data validation

P = the amount reported is the maximum possible concentration due to possible chlorinated diphenylether interference


U = compound not detected; reported value is the sample specific estimated detection limit

UX = non-detect; reported value is the estimated maximum possible concentration

Attachment 2

Sample Location Maps

CITY: CARBONDALE; PROJECT: BEAZER EAST; DRAWING: AUGUST 2012 SAMPLE LOCATIONS AND TCDD-TEQ CONCENTRATIONS; DATE: 10/17/2012; TIME: 1:21 PM; BY: KOPPER, LYON
 DRAWING: AUGUST 2012 SAMPLE LOCATIONS AND TCDD-TEQ CONCENTRATIONS; DATE: 10/17/2012; TIME: 1:21 PM; BY: KOPPER, LYON





LEGEND:

- EDGE OF WATER
- DRAINAGE DITCH AND DIRECTION OF FLOW
- PROPERTY BOUNDARY (SEE NOTE 2)
- PARCEL BOUNDARY
- FENCELINE
- EXISTING CONTOUR LINE
- FORMER PROCESS AREA SURFACE COVER
- SOIL REMOVAL AREA (SOIL/DEBRIS PILES AND SURFICIAL ASPHALT-LIKE MATERIALS)
- PORTIONS OF SOUTHERN DRAINAGE DITCHES THAT HAVE BEEN FILLED IN PRIOR TO OR DURING SURFACE COVER CONSTRUCTION OR REMOVAL OF SOIL AND DEBRIS PILES
- 2008 RESIDENTIAL SAMPLE LOCATIONS (USEPA)
- 2005-2010 SAMPLE LOCATIONS (BEAZER)
- 2008 RESIDENTIAL SAMPLE LOCATIONS (CITY OF CARBONDALE)
- 2012 GRAB SAMPLE LOCATION
- 2012 COMPOSITE SAMPLE LOCATION
- TCDD-TEQ CONCENTRATION (ppt) AND SAMPLE DEPTH INTERVAL


- NOTES:**
1. SITE FEATURES AND TOPOGRAPHY OBTAINED FROM PHOTOGRAMMETRIC MAPPING PROVIDED BY LOCKWOOD MAPPING COMPANY IN SEPTEMBER 2001 AND SURVEY DATA PROVIDED BY ENGINEERING DESIGN SOURCE, INC. IN JANUARY 2004, AND BASED ON AERIAL PHOTOGRAPHY PROVIDED BY LOCKWOOD MAPPING, INC. TAKEN ON NOVEMBER 23, 1988 AT AN APPROXIMATE SCALE OF 1"=350'. TOPOGRAPHY IN THE EASTERN SOUTHERN DRAINAGE DITCHES AREA BASED ON TOPOGRAPHIC FIELD SURVEY CONDUCTED IN AUGUST 2007.
 2. PROPERTY BOUNDARY IS APPROXIMATE; OBTAINED FROM A COMBINATION OF SITE SURVEY DATA, HISTORICAL MAPS AND TAX MAPS.
 3. THE 2008 RESIDENTIAL SAMPLE LOCATIONS ARE APPROXIMATE.
 4. AERIAL IMAGE OBTAINED FROM GOOGLE EARTH AND DATED APRIL 2, 2012.
 5. TCDD-TEQ CONCENTRATIONS ARE BASED ON UNVALIDATED LABORATORY RESULTS.



BEAZER EAST, INC.
 FORMER KOPPER'S WOOD TREATING SITE
 CARBONDALE, ILLINOIS

**AUGUST 2012 SAMPLE LOCATIONS
 AND TCDD-TEQ CONCENTRATIONS**

CITY: STURGEON LAKE, WI COUNTY: DODGE COUNTY, WI PROJECT: CARBONDALE, IL; DATE: 08/18/2010 12:00 PM; SCALE: 1" = 500'; SHEET: 2 OF 2; DRAWN BY: R. ANDERSON; CHECKED BY: M. J. HOLLER; APPROVED BY: M. J. HOLLER; DATE: 08/18/2010 12:00 PM; PLOTTED: 08/18/2010 12:00 PM; BY: R. ANDERSON, LISA



NOTES:

1. SITE FEATURES AND TOPOGRAPHY OBTAINED FROM PHOTOGRAMMETRIC MAPPING PROVIDED BY LOCKWOOD MAPPING COMPANY IN SEPTEMBER 2004 AND SURVEY DATA PROVIDED BY ENGINEERING DESIGN SOURCE, INC. IN JANUARY 2004, AND BASED ON AERIAL PHOTOGRAPHY PROVIDED BY LOCKWOOD MAPPING, INC. TAKEN ON NOVEMBER 22, 1995 AT AN APPROXIMATE SCALE OF 1"=500'. TOPOGRAPHY IN THE EASTERN SOUTHERN DRAINAGE DITCHES AREA BASED ON TOPOGRAPHIC FIELD SURVEY CONDUCTED IN AUGUST 2007.
2. PROPERTY BOUNDARY IS APPROXIMATE, OBTAINED FROM A COMBINATION OF SITE SURVEY DATA, HISTORICAL MAPS AND TAX MAPS.
3. THIS FIGURE SHOWS ALL SAMPLE LOCATIONS WHERE DIOXINS/FURANS HAVE BEEN ANALYZED, INCLUDING SOME LOCATIONS THAT HAVE SINCE BEEN REMOVED OR COVERED AS PART OF REMEDIATION ACTIVITIES.

**BEAZER EAST, INC.
 FORMER KOPPERS WOOD TREATING SITE
 CARBONDALE, ILLINOIS**

**SUMMARY OF TCDD-TEQ
 CONCENTRATIONS**



Attachment 3

Data Validation Reports

Beazer East Inc.

Former Koppers Wood-Treating Site

Data Review

CARBONDALE, ILLINOIS

Dioxins/Furans Analyses

SDG # 33932

Analyses Performed By:
Vista Analytical Laboratories
El Dorado Hills, California

Report #17380
Review Level: Tier III
Project: B0039262.0000.00003

SUMMARY

This data quality assessment summarizes the review of Sample Delivery Group (SDG) # 33932 for samples collected in association with the Beazer East Inc. Former Koppers Wood-Treating Site. The review was conducted as a Tier III evaluation and included review of data package completeness. Only analytical data associated with constituents of concern were reviewed for this validation. Field documentation was not included in this review. Included with this assessment are the validation annotated sample result sheets and chain of custody. Analyses were performed on the following samples:

Sample ID	Lab ID	Matrix	Sample Collection Date	Parent Sample	Analysis
					Dioxins/Furans
A1-62	33932-001	Soil	8/8/2012		X
A1-56	33932-002	Soil	8/8/2012		X
A1-57	33932-003	Soil	8/8/2012		X
A1-63	33932-004	Soil	8/8/2012		X
A1-52	33932-005	Soil	8/8/2012		X
A1-53	33932-006	Soil	8/8/2012		X
A1-59	33932-007	Soil	8/8/2012		X
A1-54	33932-008	Soil	8/8/2012		X
A1-55	33932-009	Soil	8/8/2012		X
A1-60	33932-010	Soil	8/8/2012		X
DUP-1	33932-011	Soil	8/8/2012	A1-52	X
DUP-2	33932-012	Soil	8/8/2012	A3-32	X
EB 8/8/12	33932-013	Water	8/8/2012		X

1. The matrix spike/matrix spike duplicate (MS/MSD) analysis was performed on sample location A1-55.
2. Sample results were reported on a dry-weight basis.

ANALYTICAL DATA PACKAGE DOCUMENTATION

The table below is the evaluation of the data package completeness.

Items Reviewed	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample receipt condition		X		X	
2. Requested analyses and sample results		X		X	
3. Master tracking list		X		X	
4. Methods of analysis		X		X	
5. Reporting limits		X		X	
6. Sample collection date		X		X	
7. Laboratory sample received date		X		X	
8. Sample preservation verification (as applicable)		X		X	
9. Sample preparation/extraction/analysis dates		X		X	
10. Fully executed Chain-of-Custody (COC) form		X		X	
11. Narrative summary of QA or sample problems provided		X		X	
12. Data Package Completeness and Compliance		X		X	

QA - Quality Assurance

ORGANIC ANALYSIS INTRODUCTION

Analyses were performed according to United States Environmental Protection Agency (USEPA) SW-846 Method 8290. Data were reviewed in accordance with USEPA National Functional Guidelines of January 2005.

The data review process is an evaluation of data on a technical basis rather than a determination of contract compliance. As such, the standards against which the data are being weighed may differ from those specified in the analytical method. It is assumed that the data package represents the best efforts of the laboratory and had already been subjected to adequate and sufficient quality review prior to submission.

During the review process, laboratory qualified and unqualified data are verified against the supporting documentation. Based on this evaluation, qualifier codes may be added, deleted, or modified by the data reviewer. Results are qualified with the following codes in accordance with USEPA National Functional Guidelines:

- Concentration (C) Qualifiers
 - U The compound was analyzed for but not detected. The associated value is the compound quantitation limit.
 - B The compound has been found in the sample as well as its associated blank, its presence in the sample may be suspect.
- Quantitation (Q) Qualifiers
 - E The compound was quantitated above the calibration range.
 - D Concentration is based on a diluted sample analysis.
- Validation Qualifiers
 - J The compound was positively identified; however, the associated numerical value is an estimated concentration only.
 - UJ The compound was not detected above the reported sample quantitation limit. However, the reported limit is approximate and may or may not represent the actual limit of quantitation.
 - JN The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification. The associated numerical value is an estimated concentration only.
 - UB Compound considered non-detect at the listed value due to associated blank contamination.
 - N The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification.
 - R The sample results are rejected as unusable. The analyte may or may not be present in the sample.

Two facts should be noted by all data users. First, the "R" flag means that the associated value is unusable. In other words, due to significant quality control (QC) problems, the analysis is invalid and provides no information as to whether the compound is present or not. "R" values should not appear on data tables because they cannot be relied upon, even as a last resort. The second fact to keep in mind is that no compound concentration, even if it has passed all QC tests, is guaranteed to be accurate. Strict QC serves to increase confidence in data but any value potentially contains error.

POLYCHLORINATED DIBENZODIOXINS AND POLYCHLORINATED DIBENZOFURANS (PCDD/PCDF) ANALYSES

1. Holding Times

The specified holding times for the following methods are presented in the following table.

Method	Matrix	Holding Time	Preservation
SW-846 8290	Water	30 days from collection to extraction and 45 days from extraction to analysis	Cooled @ 4±2 °C
	Soil	30 days from collection to extraction and 45 days from extraction to analysis	Cooled @ 4±2 °C

The samples were received at the laboratory at acceptable temperatures and all samples were analyzed within the specified holding times.

2. Blank Contamination

Quality assurance (QA) blanks (i.e. laboratory method blanks and equipment rinse blanks) are prepared to identify any contamination which may have been introduced into the samples during sample preparation or field activity. Method blanks measure laboratory contamination. Equipment rinse blanks also measure contamination of samples during field operations.

A blank action level (BAL) of five times the concentration of a detected compound in an associated blank is calculated for QA blanks containing concentrations greater than the method detection limit (MDL). The BAL is compared to the associated sample results to determine the appropriate qualification of the sample results, if needed.

Compounds were detected in an associated method blank (which was analyzed with SDG 33932); however, the associated sample results were either greater than the BAL or non-detect. Therefore, qualification of the sample results was not required.

3. Mass Spectrometer Tuning

Mass spectrometer performance was acceptable; system performance and column resolution were acceptable.

4. Calibration

Satisfactory instrument calibration is established to insure that the instrument is capable of producing acceptable quantitative data. An initial calibration demonstrates that the instrument is capable of acceptable performance at the beginning of an experimental sequence. The continuing calibration verifies that the instrument daily performance is satisfactory.

4.1 Initial Calibration

A maximum relative standard deviation (RSD) of 20% is allowed for all non-labeled compounds (target) and 30% is allowed for all labeled compounds (internal standards and recovery standards)

4.2 Continuing Calibration

All target compounds associated with the continuing calibration standard must exhibit percent difference (%D) less than the control limit (20%).

All initial and continuing calibration criteria were within the control limits.

5. Internal Standard Performance

All samples to be analyzed for PCDD/PCDF compounds are spiked with internal standards prior to extraction. Internal standard performance criteria insure that the GC/MS sensitivity and response are stable during every sample analysis. The criteria require the internal standard compounds exhibit recoveries within the control limits of 40% to 135%.

Sample locations associated with internal standards exhibiting responses outside of the control limits are presented in the following table.

Sample Locations	Internal Standard	Response
A1-62	¹³ C-OCDD	<LL but >40%

The criteria used to evaluate the internal standard responses are presented in the following table. In the case of an internal standard deviation, the compounds quantitated under the deviant internal standard are qualified as documented in the table below.

Control limit	Sample Result	Qualification
> the upper control limit (UL)	Non-detect	No action
	Detect	J
< the lower control limit (LL) but > 40%	Non-detect	J
	Detect	J
< 25%	Non-detect	R
	Detect	J

6. Recovery Standard Performance

The recovery standard (³⁷Cl-2,3,7,8-TCDD) is added to the sample extract prior to the extract clean-up steps. The concentrations of the labeled standards (internal standards) are determined using the recovery standard.

All recovery standard recoveries were acceptable.

7. Matrix Spike/Matrix Spike Duplicate (MS/MSD) Analysis

MS/MSD data are used to assess the precision and accuracy of the analytical method. The compounds spiked in the MS/MSD analysis must exhibit a percent recovery within the laboratory-established acceptance limits. The relative percent differences (RPDs) between the MS and MSD must be within the laboratory-established acceptance limits.

Note: The MS/MSD recovery control limits do not apply for MS/MSD performed on sample locations where the compounds concentration detected in the parent sample exceeds the MS/MSD concentration by a factor of four or greater.

The MS/MSD exhibited acceptable recoveries and RPD between the MS/MSD recoveries.

8. Laboratory Control Sample (LCS) Analysis

The LCS analysis is used to assess the precision and accuracy of the analytical method independent of matrix interferences. The compounds associated with the LCS analysis must exhibit recoveries within the laboratory-established acceptance limits.

All compounds associated with the LCS analyses exhibited recoveries within the control limits.

9. Field Duplicate Sample Analysis

Field duplicate analysis is used to assess the precision of the field sampling procedures and analytical method. A control limit of 100% for soil matrices is applied to the RPD between the parent and the field duplicate samples. In the case where the parent and/or duplicate sample concentrations are less than or equal to 5 times the RL, a control limit of three times the RL is applied for soil matrices.

Results (in ug/kg) for the field duplicate samples are summarized in the following table.

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
A1-52/ DUP-1	1,2,3,4,6,7,8-HpCDD	0.309	0.325	5.0%
	1,2,3,4,6,7,8-HpCDF	0.062	0.0721	15.0%
	1,2,3,4,7,8,9-HpCDF	0.00397	0.00563	34.5%
	1,2,3,4,7,8-HxCDD	0.00357	0.00364	1.9%
	1,2,3,4,7,8-HxCDF	0.00585	0.0121	69.6%
	1,2,3,6,7,8-HxCDD	0.0101	0.0121	18.0%
	1,2,3,6,7,8-HxCDF	0.00339	0.00681	67.0%
	1,2,3,7,8,9-HxCDD	0.00761	0.00847	10.6%
	1,2,3,7,8,9-HxCDF	0.000312 J	0.000913 J	98.1%
	1,2,3,7,8-PeCDD	0.00235 J	0.00295	22.6%
	1,2,3,7,8-PeCDF	0.00214 J	0.00811	116.4%
	2,3,4,6,7,8-HxCDF	0.00417	0.00582	33.0%
	2,3,4,7,8-PeCDF	0.00229 J	0.00456	66.2%
	2,3,7,8-TCDD	0.000491 J	0.000675	31.5%
	2,3,7,8-TCDF	0.0025	0.00638	87.3%
	37Cl-2,3,7,8-TCDD	0.0808	0.0776	4.0%

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
	OCDD	7.67 E	8.5 E	10.2%
	OCDF	0.186	0.187	0.5%
	TEQ(Min)	0.0134	0.0175	26.5%
	Total HpCDD	0.604	0.648	7.0%
	Total HpCDF	0.168	0.187	10.7%
	Total HxCDD	0.0977	0.124	23.7%
	Total HxCDF	0.0796	0.106	28.4%
	Total PeCDD	0.0365	0.0459	22.8%
	Total PeCDF	0.0534	0.0948	55.8%
	Total TCDD	0.0341	0.0337	1.1%
	Total TCDF	0.0576	0.104	57.4%
	WHO Dioxin TEQ(Human/Mammal- NDs Excluded)	0.0134	0.0175	26.5%
	WHO Dioxin TEQ(Human/Mammal- NDs used at 1/2 DL)	0.0134	0.0175	26.5%
	A3-32/ DUP-2	1,2,3,4,6,7,8-HpCDD	23.9	28.6
1,2,3,4,6,7,8-HpCDF		5.5	5.81	5.4%
1,2,3,4,7,8,9-HpCDF		0.379	0.423	10.9%
1,2,3,4,7,8-HxCDD		0.233	0.28	18.3%
1,2,3,4,7,8-HxCDF		0.229	0.242	5.5%
1,2,3,6,7,8-HxCDD		1.01	1.22	18.8%
1,2,3,6,7,8-HxCDF		0.132	0.142	7.2%
1,2,3,7,8,9-HxCDD		0.514	0.632	20.5%
1,2,3,7,8,9-HxCDF		0.0558	0.0324	53.0%
1,2,3,7,8-PeCDD		0.0837	0.0968	14.5%
1,2,3,7,8-PeCDF		0.0209	0.0229	9.1%
2,3,4,6,7,8-HxCDF		0.24	0.248	3.2%
2,3,4,7,8-PeCDF		0.0422	0.0819	63.9%
2,3,7,8-TCDD		0.00305	0.00375	20.5%
2,3,7,8-TCDF		0.00419	0.00509	19.3%
37Cl-2,3,7,8-TCDD		0.0747	0.0781	4.4%
OCDD		198	240	19.1%
OCDF		27.3	28.4	3.9%
TEQ(Min)		0.707	0.835	16.6%
Total HpCDD		39.3	47.3	18.4%
Total HpCDF		20.5	21.9	6.6%
Total HxCDD		4.77	6.06	23.8%
Total HxCDF		6.11	6.79	10.5%
Total PeCDD		0.448	0.543	19.1%
Total PeCDF		0.911	1.08	16.9%

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
	Total TCDD	0.104	0.14	29.5%
	Total TCDF	0.107	0.132	20.9%
	WHO Dioxin TEQ(Human/Mammal- NDs Excluded)	0.707	0.835	16.6%
	WHO Dioxin TEQ(Human/Mammal- NDs used at 1/2 DL)	0.707	0.835	16.6%

AC Acceptable

The compound 1,2,3,7,8-PeCDF associated with samples locations A1-52 and DUP-1 exhibited a RPD greater than the control limit. The compound 1,2,3,7,8-PeCDF results for sample locations A1-52 and DUP-1 were qualified as estimated ("J").

10. Compound Identification

PCDD/PCDF compounds are identified by using the compound's ion abundance ratios, signal-to-noise ratios, and retention times relative to the internal standards'.

An estimated maximum possible concentration (EMPC) designation is given to compounds which have signals eluting within the established retention time window which would, if positively identified, be greater than the detection limit. The signals do not, however, meet the ion abundance ratio criteria and therefore cannot be identified as the compound of interest. The EMPC value is the estimated concentration of the interferant quantitated "as the compound of interest". This value should be considered an elevated detection limit based on potential compound identification and quantitation interference. The "UX" qualifier has been added to the following sample results (in ug/kg) to indicate the elevated detection limit as EMPC.

Sample ID	Compound	Laboratory Result	Reported Result
A1-57	1,2,3,7,8,9-HxCDF	0.0019 EMPC	0.0019 UX
A1-56	1,2,3,7,8-PeCDF	0.00037 EMPC	0.00037 UX
A1-63	1,2,3,7,8-PeCDF	0.000281 EMPC	0.000281 UX
	2,3,7,8-TCDD	0.000478 EMPC	0.000478 UX

The following results exhibited evidence of interference by chlorodiphenyl ethers. The results were flagged "P" by the laboratory indicating the result is the maximum concentrations of the analytes in the case that all of the quantified area is due to the target analyte and none due to the interference. Therefore, these results have been qualified as estimated ("J").

Sample ID	Compound
A1-62	Total TCDF Total PeCDF Total HxCDF Total HpCDF

Sample results that exhibited a concentration greater than the linear range of the instrument calibration are summarized in the following table (ug/kg).

Sample ID	Compound	Original Analysis	Diluted Analysis	Reported Analysis
A1-62	1,2,3,6,7,8-HxCDD	2.210 E	—	2.210 EJ
	OCDD	727 ED	—	727 EDJ
	1,2,3,4,6,7,8-HpCDF	17.1 ED	—	17.1 EDJ
	OCDF	123 ED	—	123 EDJ
A1-57	OCDD	13.4 E	—	13.4 EJ
A1-52	OCDD	7.67 E	—	7.67 EJ
A1-53	OCDD	25.7 E	—	25.7 EJ
A1-59	1,2,3,4,6,7,8-HpCDD	2.85 E	—	2.85 EJ
	OCDD	47.2 ED	—	47.2 EDJ
A1-54	OCDD	15.7 E	—	15.7 EJ
A1-55	OCDD	26.8 E	—	26.8 EJ
DUP-1	OCDD	8.5 E	—	8.5 EJ
DUP-2	1,2,3,4,6,7,8-HpCDD	28.6 E	—	28.6 EJ
	OCDD	240 ED	—	240 EDJ
	1,2,3,4,6,7,8-HpCDF	5.81 E	—	5.81 EJ
	OCDF	28.4 E	—	28.4 EJ
A1-56	OCDD	14.8 E	—	14.8 EJ
A1-63	OCDD	14.9 E	—	14.9 EJ

Note: In the instance where both the original analysis and the diluted analysis sample results exhibited a concentration greater than and/or less than the calibration linear range of the instrument; the sample result exhibiting the greatest concentration will be reported as the final result.

Sample results associated with compounds exhibiting concentration greater than the linear range qualified as documented in the table below when reported as the final reported sample result.

Reported Sample Results	Qualification
Diluted sample result within calibration range	D
Diluted sample result less than the calibration range	DJ
Diluted sample result greater than the calibration range	EDJ
Original sample result greater than the calibration range	EJ

11. System Performance and Overall Assessment

Please note that when individual compounds are qualified as estimated (J) during validation, this qualification is applied to the totals as well.

Overall system performance was acceptable. Except for those deviations specifically mentioned in this review, the overall data quality is within the guidelines specified in the method.


DATA VALIDATION CHECKLIST FOR PCDD/PCDF

PCDDs/PCDFs; SW-846 8290	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS)					
Tier II Validation					
Holding times		X		X	
Reporting limits (units)		X		X	
Blanks					
A. Method blanks		X		X	
B. Equipment blanks		X		X	
Laboratory Control Sample (LCS) Accuracy (%R)		X		X	
Laboratory Control Sample Duplicate (LCSD) %R					X
LCS/LCSD Precision (RPD)					X
Matrix Spike (MS) %R		X		X	
Matrix Spike Duplicate (MSD) %R		X		X	
MS/MSD RPD		X		X	
Field/Laboratory Duplicate Sample RPD		X	X		
Dilution Factor		X		X	
Moisture Content		X		X	
Tier III Validation					
System performance and column resolution		X		X	
Initial calibration %RSDs		X		X	
Continuing calibration %Ds		X		X	
Instrument tune and performance check		X		X	
Ion abundance criteria for each instrument used		X		X	
Signal-to-noise ratio \geq 10:1		X		X	
Internal standard performance		X	X		
Recovery standard performance		X		X	
Resolution mix \leq 25%		X		X	
Compound identification and quantitation					
A. Reconstructed ion chromatograms		X		X	
B. Quantitation Reports		X		X	
C. RT of sample compounds within the established RT windows		X		X	
D. Transcription/calculation errors present		X		X	
E. Reporting limits adjusted to reflect sample dilutions		X		X	

RSD – relative standard deviation
 %R - percent recovery
 RPD - relative percent difference
 %D – difference

VALIDATION PERFORMED BY: Jeffrey L. Davin

SIGNATURE:



DATE: September 27, 2012

PEER REVIEW: Dennis Capria

DATE: October 1, 2012

**CHAIN OF CUSTODY /
CORRECTED SAMPLE ANALYSIS DATA SHEETS**

Sample ID: A1-62					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-001	Date Received:	10-Aug-12	
Project:		Sample Size:	13.8 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	73.3	Date Analyzed DB-5:	20-Aug-12	Dates Analyzed DB-225:	21-Aug-12	
Time Collected:	0805							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	5.35				<u>IS</u> 13C-2,3,7,8-TCDD	96.0	40 - 135	
1,2,3,7,8-PeCDD	81.8				13C-1,2,3,7,8-PeCDD	99.2	40 - 135	
1,2,3,4,7,8-HxCDD	306				13C-1,2,3,4,7,8-HxCDD	80.9	40 - 135	
1,2,3,6,7,8-HxCDD	2210			E J	13C-1,2,3,6,7,8-HxCDD	86.9	40 - 135	
1,2,3,7,8,9-HxCDD	629				13C-1,2,3,7,8,9-HxCDD	75.0	40 - 135	
1,2,3,4,6,7,8-HpCDD	81800			D	13C-1,2,3,4,6,7,8-HpCDD	80.9	40 - 135	D
OCDD	727000			D,E J	13C-OCDD	34.8	40 - 135	D,H
2,3,7,8-TCDF	3.22				13C-2,3,7,8-TCDF	92.8	40 - 135	
1,2,3,7,8-PeCDF	10.8				13C-1,2,3,7,8-PeCDF	107	40 - 135	
2,3,4,7,8-PeCDF	30.8			D	13C-2,3,4,7,8-PeCDF	102	40 - 135	D
1,2,3,4,7,8-HxCDF	435				13C-1,2,3,4,7,8-HxCDF	93.1	40 - 135	
1,2,3,6,7,8-HxCDF	153				13C-1,2,3,6,7,8-HxCDF	97.0	40 - 135	
2,3,4,6,7,8-HxCDF	341				13C-2,3,4,6,7,8-HxCDF	90.5	40 - 135	
1,2,3,7,8,9-HxCDF	41.9				13C-1,2,3,7,8,9-HxCDF	90.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	17100			D,E J	13C-1,2,3,4,6,7,8-HpCDF	87.5	40 - 135	D
1,2,3,4,7,8,9-HpCDF	1680			D	13C-1,2,3,4,7,8,9-HpCDF	86.9	40 - 135	D
OCDF	123000			D,E J	13C-OCDF	74.1	40 - 135	D
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	103	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	118		118		TEQ (Min):	1770		
Total PeCDD	401				a. Sample specific estimated detection limit.			
Total HxCDD	12300			J	b. Estimated maximum possible concentration.			
Total HpCDD	150000				c. Method detection limit.			
Total TCDF	111			P J	d. Lower control limit - upper control limit.			
Total PeCDF	775		822	P J	e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	16500			P J	The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	92600			P J				

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:56

Sample ID: A1-57					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-003	Date Received:	10-Aug-12	
Project:		Sample Size:	12.6 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	79.7	Date Analyzed DB-5:	20-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	0830							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.636				IS 13C-2,3,7,8-TCDD	92.0	40 - 135	
1,2,3,7,8-PeCDD	2.47			J	13C-1,2,3,7,8-PeCDD	95.5	40 - 135	
1,2,3,4,7,8-HxCDD	5.54				13C-1,2,3,4,7,8-HxCDD	78.1	40 - 135	
1,2,3,6,7,8-HxCDD	12.8				13C-1,2,3,6,7,8-HxCDD	82.2	40 - 135	
1,2,3,7,8,9-HxCDD	10.0				13C-1,2,3,7,8,9-HxCDD	79.5	40 - 135	
1,2,3,4,6,7,8-HpCDD	488				13C-1,2,3,4,6,7,8-HpCDD	84.8	40 - 135	
OCDD	13400			E J	13C-OCDD	96.1	40 - 135	
2,3,7,8-TCDF	0.305			J	13C-2,3,7,8-TCDF	90.6	40 - 135	
1,2,3,7,8-PeCDF	0.326			J	13C-1,2,3,7,8-PeCDF	105	40 - 135	
2,3,4,7,8-PeCDF	0.711			J	13C-2,3,4,7,8-PeCDF	102	40 - 135	
1,2,3,4,7,8-HxCDF	3.34				13C-1,2,3,4,7,8-HxCDF	87.3	40 - 135	
1,2,3,6,7,8-HxCDF	1.21			J	13C-1,2,3,6,7,8-HxCDF	92.1	40 - 135	
2,3,4,6,7,8-HxCDF	2.02			J	13C-2,3,4,6,7,8-HxCDF	90.1	40 - 135	
1,2,3,7,8,9-HxCDF	ND		0.190	UX	13C-1,2,3,7,8,9-HxCDF	86.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	46.5				13C-1,2,3,4,6,7,8-HpCDF	86.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.20				13C-1,2,3,4,7,8,9-HpCDF	86.3	40 - 135	
OCDF	254				13C-OCDF	90.7	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	99.7	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	5.89		6.15		TEQ (Min):	16.3		
Total PeCDD	21.0				a. Sample specific estimated detection limit.			
Total HxCDD	150				b. Estimated maximum possible concentration.			
Total HpCDD	1090				c. Method detection limit.			
Total TCDF	5.20		5.66		d. Lower control limit - upper control limit.			
Total PeCDF	10.4		10.6		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	56.0		56.4		The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	192							

Analyst: FEB

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-52					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-005	Date Received:	10-Aug-12	
Project:		Sample Size:	13.3 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	75.3	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	21-Aug-12	
Time Collected:	0920							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.491			J	<u>IS</u> 13C-2,3,7,8-TCDD	90.6	40 - 135	
1,2,3,7,8-PeCDD	2.35			J	13C-1,2,3,7,8-PeCDD	93.8	40 - 135	
1,2,3,4,7,8-HxCDD	3.57				13C-1,2,3,4,7,8-HxCDD	75.8	40 - 135	
1,2,3,6,7,8-HxCDD	10.1				13C-1,2,3,6,7,8-HxCDD	84.7	40 - 135	
1,2,3,7,8,9-HxCDD	7.61				13C-1,2,3,7,8,9-HxCDD	78.7	40 - 135	
1,2,3,4,6,7,8-HpCDD	309				13C-1,2,3,4,6,7,8-HpCDD	83.4	40 - 135	
OCDD	7670			E J	13C-OCDD	94.9	40 - 135	
2,3,7,8-TCDF	2.50				13C-2,3,7,8-TCDF	90.1	40 - 135	
1,2,3,7,8-PeCDF	2.14			J	13C-1,2,3,7,8-PeCDF	103	40 - 135	
2,3,4,7,8-PeCDF	2.29			J	13C-2,3,4,7,8-PeCDF	102	40 - 135	
1,2,3,4,7,8-HxCDF	5.85				13C-1,2,3,4,7,8-HxCDF	85.8	40 - 135	
1,2,3,6,7,8-HxCDF	3.39				13C-1,2,3,6,7,8-HxCDF	91.9	40 - 135	
2,3,4,6,7,8-HxCDF	4.17				13C-2,3,4,6,7,8-HxCDF	87.8	40 - 135	
1,2,3,7,8,9-HxCDF	0.312			J	13C-1,2,3,7,8,9-HxCDF	84.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	62.0				13C-1,2,3,4,6,7,8-HpCDF	85.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	3.97				13C-1,2,3,4,7,8,9-HpCDF	83.7	40 - 135	
OCDF	186				13C-OCDF	90.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	101	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	34.1				TEQ (Min):	13.4		
Total PeCDD	36.5				a. Sample specific estimated detection limit.			
Total HxCDD	97.7				b. Estimated maximum possible concentration.			
Total HpCDD	604				c. Method detection limit.			
Total TCDF	57.6		58.4		d. Lower control limit - upper control limit.			
Total PeCDF	53.4		53.6		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	79.6				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	168							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-53					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-006	Date Received:	10-Aug-12	
Project:		Sample Size:	11.9 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	83.8	Date Analyzed DB-5:	21-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	0935							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	1.18				<u>IS</u> 13C-2,3,7,8-TCDD	93.4	40 - 135	
1,2,3,7,8-PeCDD	15.7				13C-1,2,3,7,8-PeCDD	97.4	40 - 135	
1,2,3,4,7,8-HxCDD	26.4				13C-1,2,3,4,7,8-HxCDD	76.8	40 - 135	
1,2,3,6,7,8-HxCDD	57.9				13C-1,2,3,6,7,8-HxCDD	84.7	40 - 135	
1,2,3,7,8,9-HxCDD	66.4				13C-1,2,3,7,8,9-HxCDD	78.3	40 - 135	
1,2,3,4,6,7,8-HpCDD	1590				13C-1,2,3,4,6,7,8-HpCDD	87.8	40 - 135	
OCDD	25700			E J	13C-OCDD	101	40 - 135	
2,3,7,8-TCDF	0.333			J	13C-2,3,7,8-TCDF	92.8	40 - 135	
1,2,3,7,8-PeCDF	0.782			J	13C-1,2,3,7,8-PeCDF	107	40 - 135	
2,3,4,7,8-PeCDF	1.49			J	13C-2,3,4,7,8-PeCDF	104	40 - 135	
1,2,3,4,7,8-HxCDF	5.97				13C-1,2,3,4,7,8-HxCDF	88.4	40 - 135	
1,2,3,6,7,8-HxCDF	6.70				13C-1,2,3,6,7,8-HxCDF	92.0	40 - 135	
2,3,4,6,7,8-HxCDF	9.26				13C-2,3,4,6,7,8-HxCDF	90.2	40 - 135	
1,2,3,7,8,9-HxCDF	0.585			J	13C-1,2,3,7,8,9-HxCDF	85.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	194				13C-1,2,3,4,6,7,8-HpCDF	85.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	8.83				13C-1,2,3,4,7,8,9-HpCDF	85.9	40 - 135	
OCDF	706				13C-OCDF	93.4	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	100	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	7.19				TEQ (Min): 60.5			
Total PeCDD	68.3							
Total HxCDD	520				a. Sample specific estimated detection limit.			
Total HpCDD	3070				b. Estimated maximum possible concentration.			
Total TCDF	8.74		9.73		c. Method detection limit.			
Total PeCDF	43.6				d. Lower control limit - upper control limit.			
Total HxCDF	206				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HpCDF	518				The results are reported in dry weight. The sample size is reported in wet weight.			

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-59				EPA Method 8290				
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-007	Date Received:	10-Aug-12	
Project:		Sample Size:	12.6 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	79.9	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	21-Aug-12	
Time Collected:	0955							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.761				<u>IS</u> 13C-2,3,7,8-TCDD	93.0	40 - 135	
1,2,3,7,8-PeCDD	9.60				13C-1,2,3,7,8-PeCDD	95.2	40 - 135	
1,2,3,4,7,8-HxCDD	24.1				13C-1,2,3,4,7,8-HxCDD	78.7	40 - 135	
1,2,3,6,7,8-HxCDD	83.4				13C-1,2,3,6,7,8-HxCDD	84.9	40 - 135	
1,2,3,7,8,9-HxCDD	53.6				13C-1,2,3,7,8,9-HxCDD	79.0	40 - 135	
1,2,3,4,6,7,8-HpCDD	2850			E J	13C-1,2,3,4,6,7,8-HpCDD	90.6	40 - 135	
OCDD	47200			D,E J	13C-OCDD	75.9	40 - 135	D
2,3,7,8-TCDF	1.44				13C-2,3,7,8-TCDF	93.5	40 - 135	
1,2,3,7,8-PeCDF	1.64			J	13C-1,2,3,7,8-PeCDF	106	40 - 135	
2,3,4,7,8-PeCDF	2.91				13C-2,3,4,7,8-PeCDF	104	40 - 135	
1,2,3,4,7,8-HxCDF	16.0				13C-1,2,3,4,7,8-HxCDF	87.9	40 - 135	
1,2,3,6,7,8-HxCDF	9.51				13C-1,2,3,6,7,8-HxCDF	93.9	40 - 135	
2,3,4,6,7,8-HxCDF	16.4				13C-2,3,4,6,7,8-HxCDF	89.2	40 - 135	
1,2,3,7,8,9-HxCDF	1.52			J	13C-1,2,3,7,8,9-HxCDF	87.3	40 - 135	
1,2,3,4,6,7,8-HpCDF	452				13C-1,2,3,4,6,7,8-HpCDF	85.8	40 - 135	
1,2,3,4,7,8,9-HpCDF	27.9				13C-1,2,3,4,7,8,9-HpCDF	87.0	40 - 135	
OCDF	1990				13C-OCDF	99.1	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	97.8	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	30.1				TEQ (Min):	80.0		
Total PeCDD	75.9							
Total HxCDD	603							
Total HpCDD	5290							
Total TCDF	42.0		43.4					
Total PeCDF	98.4							
Total HxCDF	453							
Total HpCDF	1550							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:56

Sample ID: A1-54					EPA Method 8290			
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-008	Date Received:	10-Aug-12	
Project:		Sample Size:	11.4 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	88.2	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	21-Aug-12	
Time Collected:	1040							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.654				<u>IS</u> 13C-2,3,7,8-TCDD	94.0	40 - 135	
1,2,3,7,8-PeCDD	1.97			J	13C-1,2,3,7,8-PeCDD	96.9	40 - 135	
1,2,3,4,7,8-HxCDD	3.67				13C-1,2,3,4,7,8-HxCDD	78.4	40 - 135	
1,2,3,6,7,8-HxCDD	12.9				13C-1,2,3,6,7,8-HxCDD	82.0	40 - 135	
1,2,3,7,8,9-HxCDD	8.93				13C-1,2,3,7,8,9-HxCDD	78.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	545				13C-1,2,3,4,6,7,8-HpCDD	84.0	40 - 135	
OCDD	15700			EJ	13C-OCDD	97.1	40 - 135	
2,3,7,8-TCDF	1.00				13C-2,3,7,8-TCDF	91.9	40 - 135	
1,2,3,7,8-PeCDF	1.02			J	13C-1,2,3,7,8-PeCDF	102	40 - 135	
2,3,4,7,8-PeCDF	1.44			J	13C-2,3,4,7,8-PeCDF	102	40 - 135	
1,2,3,4,7,8-HxCDF	4.15				13C-1,2,3,4,7,8-HxCDF	86.3	40 - 135	
1,2,3,6,7,8-HxCDF	2.89				13C-1,2,3,6,7,8-HxCDF	92.5	40 - 135	
2,3,4,6,7,8-HxCDF	4.00				13C-2,3,4,6,7,8-HxCDF	88.0	40 - 135	
1,2,3,7,8,9-HxCDF	0.614			J	13C-1,2,3,7,8,9-HxCDF	86.9	40 - 135	
1,2,3,4,6,7,8-HpCDF	63.9				13C-1,2,3,4,6,7,8-HpCDF	84.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.25				13C-1,2,3,4,7,8,9-HpCDF	85.8	40 - 135	
OCDF	238				13C-OCDF	89.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	99.6	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	7.29		7.57		TEQ (Min):	17.8		
Total PeCDD	21.1							
Total HxCDD	124							
Total HpCDD	1120							
Total TCDF	21.0		21.7					
Total PeCDF	18.1							
Total HxCDF	83.7		84.0					
Total HpCDF	197							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-55					EPA Method 8290			
Client Data			Sample Data		Laboratory Data			
Name:	ARCADIS		Matrix:	Soil	Lab Sample:	33932-009	Date Received:	10-Aug-12
Project:			Sample Size:	12.1 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12
Date Collected:	8-Aug-12		%Solids:	83.3	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	21-Aug-12
Time Collected:	1115							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	1.30				<u>IS</u> 13C-2,3,7,8-TCDD	91.2	40 - 135	
1,2,3,7,8-PeCDD	8.59				13C-1,2,3,7,8-PeCDD	93.9	40 - 135	
1,2,3,4,7,8-HxCDD	15.9				13C-1,2,3,4,7,8-HxCDD	76.7	40 - 135	
1,2,3,6,7,8-HxCDD	50.0				13C-1,2,3,6,7,8-HxCDD	84.6	40 - 135	
1,2,3,7,8,9-HxCDD	31.5				13C-1,2,3,7,8,9-HxCDD	78.8	40 - 135	
1,2,3,4,6,7,8-HpCDD	1470				13C-1,2,3,4,6,7,8-HpCDD	86.5	40 - 135	
OCDD	26800			E J	13C-OCDD	103	40 - 135	
2,3,7,8-TCDF	0.999				13C-2,3,7,8-TCDF	88.1	40 - 135	
1,2,3,7,8-PeCDF	1.21			J	13C-1,2,3,7,8-PeCDF	105	40 - 135	
2,3,4,7,8-PeCDF	2.43			J	13C-2,3,4,7,8-PeCDF	101	40 - 135	
1,2,3,4,7,8-HxCDF	6.35				13C-1,2,3,4,7,8-HxCDF	86.8	40 - 135	
1,2,3,6,7,8-HxCDF	4.30				13C-1,2,3,6,7,8-HxCDF	91.6	40 - 135	
2,3,4,6,7,8-HxCDF	7.21				13C-2,3,4,6,7,8-HxCDF	87.5	40 - 135	
1,2,3,7,8,9-HxCDF	0.928			J	13C-1,2,3,7,8,9-HxCDF	86.5	40 - 135	
1,2,3,4,6,7,8-HpCDF	165				13C-1,2,3,4,6,7,8-HpCDF	83.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	12.2				13C-1,2,3,4,7,8,9-HpCDF	84.4	40 - 135	
OCDF	819				13C-OCDF	96.8	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	99.8	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	28.6				TEQ (Min):	47.1		
Total PeCDD	108				a. Sample specific estimated detection limit.			
Total HxCDD	430				b. Estimated maximum possible concentration.			
Total HpCDD	2670				c. Method detection limit.			
Total TCDF	27.2		28.1		d. Lower control limit - upper control limit.			
Total PeCDF	57.2				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	192				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	645							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-60					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-010	Date Received:	10-Aug-12	
Project:		Sample Size:	13.6 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	74.6	Date Analyzed DB-5:	21-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	1330							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.291			J	<u>IS</u> 13C-2,3,7,8-TCDD	93.8	40 - 135	
1,2,3,7,8-PeCDD	0.188			J	13C-1,2,3,7,8-PeCDD	98.5	40 - 135	
1,2,3,4,7,8-HxCDD	ND	0.129			13C-1,2,3,4,7,8-HxCDD	81.2	40 - 135	
1,2,3,6,7,8-HxCDD	ND	0.153			13C-1,2,3,6,7,8-HxCDD	83.3	40 - 135	
1,2,3,7,8,9-HxCDD	0.240			J	13C-1,2,3,7,8,9-HxCDD	81.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	4.23				13C-1,2,3,4,6,7,8-HpCDD	84.9	40 - 135	
OCDD	214				13C-OCDD	84.4	40 - 135	
2,3,7,8-TCDF	ND	0.0579			13C-2,3,7,8-TCDF	93.1	40 - 135	
1,2,3,7,8-PeCDF	ND	0.0424			13C-1,2,3,7,8-PeCDF	108	40 - 135	
2,3,4,7,8-PeCDF	ND	0.0449			13C-2,3,4,7,8-PeCDF	105	40 - 135	
1,2,3,4,7,8-HxCDF	ND	0.0584			13C-1,2,3,4,7,8-HxCDF	88.6	40 - 135	
1,2,3,6,7,8-HxCDF	ND	0.0556			13C-1,2,3,6,7,8-HxCDF	93.6	40 - 135	
2,3,4,6,7,8-HxCDF	ND	0.0644			13C-2,3,4,6,7,8-HxCDF	90.8	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.0858			13C-1,2,3,7,8,9-HxCDF	89.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	0.297			J	13C-1,2,3,4,6,7,8-HpCDF	86.3	40 - 135	
1,2,3,4,7,8,9-HpCDF	ND	0.115			13C-1,2,3,4,7,8,9-HpCDF	84.2	40 - 135	
OCDF	0.995			J	13C-OCDF	85.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	100	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	4.68				TEQ (Min):	0.613		
Total PeCDD	11.5				a. Sample specific estimated detection limit.			
Total HxCDD	11.9				b. Estimated maximum possible concentration.			
Total HpCDD	9.11				c. Method detection limit.			
Total TCDF	0.0887				d. Lower control limit - upper control limit.			
Total PeCDF	0.148				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	0.392				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	0.876							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: DUP-1					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-011	Date Received:	10-Aug-12	
Project:		Sample Size:	13.4 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	74.5	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	0000							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.675				<u>IS</u> 13C-2,3,7,8-TCDD	94.9	40 - 135	
1,2,3,7,8-PeCDD	2.95				13C-1,2,3,7,8-PeCDD	98.6	40 - 135	
1,2,3,4,7,8-HxCDD	3.64				13C-1,2,3,4,7,8-HxCDD	80.6	40 - 135	
1,2,3,6,7,8-HxCDD	12.1				13C-1,2,3,6,7,8-HxCDD	82.6	40 - 135	
1,2,3,7,8,9-HxCDD	8.47				13C-1,2,3,7,8,9-HxCDD	80.4	40 - 135	
1,2,3,4,6,7,8-HpCDD	325				13C-1,2,3,4,6,7,8-HpCDD	85.6	40 - 135	
OCDD	8500			E J	13C-OCDD	95.4	40 - 135	
2,3,7,8-TCDF	6.38				13C-2,3,7,8-TCDF	91.3	40 - 135	
1,2,3,7,8-PeCDF	8.11			J	13C-1,2,3,7,8-PeCDF	106	40 - 135	
2,3,4,7,8-PeCDF	4.56				13C-2,3,4,7,8-PeCDF	104	40 - 135	
1,2,3,4,7,8-HxCDF	12.1				13C-1,2,3,4,7,8-HxCDF	89.5	40 - 135	
1,2,3,6,7,8-HxCDF	6.81				13C-1,2,3,6,7,8-HxCDF	93.4	40 - 135	
2,3,4,6,7,8-HxCDF	5.82				13C-2,3,4,6,7,8-HxCDF	89.8	40 - 135	
1,2,3,7,8,9-HxCDF	0.913			J	13C-1,2,3,7,8,9-HxCDF	87.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	72.1				13C-1,2,3,4,6,7,8-HpCDF	85.0	40 - 135	
1,2,3,4,7,8,9-HpCDF	5.63				13C-1,2,3,4,7,8,9-HpCDF	85.0	40 - 135	
OCDF	187				13C-OCDF	89.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	96.5	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	33.7				TEQ (Min):	17.5		
Total PeCDD	45.9				a. Sample specific estimated detection limit.			
Total HxCDD	124				b. Estimated maximum possible concentration.			
Total HpCDD	648				c. Method detection limit.			
Total TCDF	104		105		d. Lower control limit - upper control limit.			
Total PeCDF	94.8			J	e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	106				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	187							

Analyst: MAS

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: DUP-2					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-012	Date Received:	10-Aug-12	
Project:		Sample Size:	12.9 g	QC Batch No.:	4618	Date Extracted:	15-Aug-12	
Date Collected:	8-Aug-12	%Solids:	78.0	Date Analyzed DB-5:	21-Aug-12	Dates Analyzed DB-225:	21-Aug-12	
Time Collected:	0000							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	3.75				<u>IS</u> 13C-2,3,7,8-TCDD	95.4	40 - 135	
1,2,3,7,8-PeCDD	96.8				13C-1,2,3,7,8-PeCDD	96.8	40 - 135	
1,2,3,4,7,8-HxCDD	280				13C-1,2,3,4,7,8-HxCDD	83.2	40 - 135	
1,2,3,6,7,8-HxCDD	1220				13C-1,2,3,6,7,8-HxCDD	88.9	40 - 135	
1,2,3,7,8,9-HxCDD	632				13C-1,2,3,7,8,9-HxCDD	82.6	40 - 135	
1,2,3,4,6,7,8-HpCDD	28600			E J	13C-1,2,3,4,6,7,8-HpCDD	112	40 - 135	
OCDD	240000			D,E J	13C-OCDD	106	40 - 135	D
2,3,7,8-TCDF	5.09				13C-2,3,7,8-TCDF	92.2	40 - 135	
1,2,3,7,8-PeCDF	22.9				13C-1,2,3,7,8-PeCDF	107	40 - 135	
2,3,4,7,8-PeCDF	81.9				13C-2,3,4,7,8-PeCDF	102	40 - 135	
1,2,3,4,7,8-HxCDF	242				13C-1,2,3,4,7,8-HxCDF	93.1	40 - 135	
1,2,3,6,7,8-HxCDF	142				13C-1,2,3,6,7,8-HxCDF	96.5	40 - 135	
2,3,4,6,7,8-HxCDF	248				13C-2,3,4,6,7,8-HxCDF	91.3	40 - 135	
1,2,3,7,8,9-HxCDF	32.4				13C-1,2,3,7,8,9-HxCDF	88.1	40 - 135	
1,2,3,4,6,7,8-HpCDF	5810			E J	13C-1,2,3,4,6,7,8-HpCDF	101	40 - 135	
1,2,3,4,7,8,9-HpCDF	423				13C-1,2,3,4,7,8,9-HpCDF	91.3	40 - 135	
OCDF	28400			E J	13C-OCDF	130	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	98.4	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	140				TEQ (Min):	835		
Total PeCDD	543				a. Sample specific estimated detection limit.			
Total HxCDD	6060				b. Estimated maximum possible concentration.			
Total HpCDD	47300			J	c. Method detection limit.			
Total TCDF	132		133		d. Lower control limit - upper control limit.			
Total PeCDF	1080				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	6790				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	21900			J				

Analyst: FEB

Approved By: Rose Harrelson 30-Aug-2012 16:16

Sample ID: A1-56					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33932-002	Date Received:	10-Aug-12	
Project:		Sample Size:	12.5 g	QC Batch No.:	4629	Date Extracted:	22-Aug-12	
Date Collected:	8-Aug-12	%Solids:	80.8	Date Analyzed DB-5:	29-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	0820							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.699				<u>IS</u> 13C-2,3,7,8-TCDD	92.4	40 - 135	
1,2,3,7,8-PeCDD	2.44			J	13C-1,2,3,7,8-PeCDD	100	40 - 135	
1,2,3,4,7,8-HxCDD	5.63				13C-1,2,3,4,7,8-HxCDD	77.6	40 - 135	
1,2,3,6,7,8-HxCDD	13.3				13C-1,2,3,6,7,8-HxCDD	87.3	40 - 135	
1,2,3,7,8,9-HxCDD	10.4				13C-1,2,3,7,8,9-HxCDD	81.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	541				13C-1,2,3,4,6,7,8-HpCDD	84.8	40 - 135	
OCDD	14800			B,E J	13C-OCDD	95.5	40 - 135	
2,3,7,8-TCDF	ND	0.362			13C-2,3,7,8-TCDF	92.4	40 - 135	
1,2,3,7,8-PeCDF	ND		0.370	UX	13C-1,2,3,7,8-PeCDF	107	40 - 135	
2,3,4,7,8-PeCDF	1.07			J	13C-2,3,4,7,8-PeCDF	108	40 - 135	
1,2,3,4,7,8-HxCDF	4.09				13C-1,2,3,4,7,8-HxCDF	87.5	40 - 135	
1,2,3,6,7,8-HxCDF	1.48			J	13C-1,2,3,6,7,8-HxCDF	95.0	40 - 135	
2,3,4,6,7,8-HxCDF	2.35			J	13C-2,3,4,6,7,8-HxCDF	91.4	40 - 135	
1,2,3,7,8,9-HxCDF	0.296			J	13C-1,2,3,7,8,9-HxCDF	90.1	40 - 135	
1,2,3,4,6,7,8-HpCDF	61.3				13C-1,2,3,4,6,7,8-HpCDF	91.8	40 - 135	
1,2,3,4,7,8,9-HpCDF	5.43				13C-1,2,3,4,7,8,9-HpCDF	91.5	40 - 135	
OCDF	327				13C-OCDF	93.7	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	97.3	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	6.86				TEQ (Min):	17.8		
Total PeCDD	20.9				a. Sample specific estimated detection limit.			
Total HxCDD	146				b. Estimated maximum possible concentration.			
Total HpCDD	1160				c. Method detection limit.			
Total TCDF	3.48		4.10		d. Lower control limit - upper control limit.			
Total PeCDF	11.4		11.8		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	71.7				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	250							

Analyst: ANP

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: A1-63					EPA Method 8290			
Client Data			Sample Data		Laboratory Data			
Name:	ARCADIS		Matrix:	Soil	Lab Sample:	33932-004	Date Received:	10-Aug-12
Project:			Sample Size:	12.8 g	QC Batch No.:	4629	Date Extracted:	22-Aug-12
Date Collected:	8-Aug-12		%Solids:	80.4	Date Analyzed DB-5:	29-Aug-12	Date Analyzed DB-225:	NA
Time Collected:	0845							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	ND		0.478	UX	<u>IS</u> 13C-2,3,7,8-TCDD	93.8	40 - 135	
1,2,3,7,8-PeCDD	2.33			J	13C-1,2,3,7,8-PeCDD	99.0	40 - 135	
1,2,3,4,7,8-HxCDD	4.72				13C-1,2,3,4,7,8-HxCDD	78.3	40 - 135	
1,2,3,6,7,8-HxCDD	10.8				13C-1,2,3,6,7,8-HxCDD	87.4	40 - 135	
1,2,3,7,8,9-HxCDD	9.23				13C-1,2,3,7,8,9-HxCDD	80.6	40 - 135	
1,2,3,4,6,7,8-HpCDD	446				13C-1,2,3,4,6,7,8-HpCDD	85.5	40 - 135	
OCDD	14900			B,E J	13C-OCDD	94.1	40 - 135	
2,3,7,8-TCDF	ND	0.233			13C-2,3,7,8-TCDF	93.5	40 - 135	
1,2,3,7,8-PeCDF	ND		0.281	UX	13C-1,2,3,7,8-PeCDF	109	40 - 135	
2,3,4,7,8-PeCDF	0.772			J	13C-2,3,4,7,8-PeCDF	106	40 - 135	
1,2,3,4,7,8-HxCDF	3.11				13C-1,2,3,4,7,8-HxCDF	87.1	40 - 135	
1,2,3,6,7,8-HxCDF	1.22			J	13C-1,2,3,6,7,8-HxCDF	93.1	40 - 135	
2,3,4,6,7,8-HxCDF	1.75			J	13C-2,3,4,6,7,8-HxCDF	90.5	40 - 135	
1,2,3,7,8,9-HxCDF	0.340			J	13C-1,2,3,7,8,9-HxCDF	88.1	40 - 135	
1,2,3,4,6,7,8-HpCDF	40.1				13C-1,2,3,4,6,7,8-HpCDF	90.9	40 - 135	
1,2,3,4,7,8,9-HpCDF	3.59				13C-1,2,3,4,7,8,9-HpCDF	88.8	40 - 135	
OCDF	193				13C-OCDF	94.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	95.0	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	4.72		5.20		TEQ (Min):	15.1		
Total PeCDD	18.8				a. Sample specific estimated detection limit.			
Total HxCDD	123				b. Estimated maximum possible concentration.			
Total HpCDD	966				c. Method detection limit.			
Total TCDF	3.18		3.60		d. Lower control limit - upper control limit.			
Total PeCDF	9.15		9.56		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	48.2		48.4		The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	153							

Analyst: ANP

Approved By: Calvin Tanaka 30-Aug-2012 14:46

Sample ID: EB 8/8/12					EPA Method 8290			
Client Data			Sample Data		Laboratory Data			
Name:	ARCADIS		Matrix:	Aqueous	Lab Sample:	33932-013	Date Received:	10-Aug-12
Project:			Sample Size:	0.907 L	QC Batch No.:	4616	Date Extracted:	15-Aug-12
Date Collected:	8-Aug-12				Date Analyzed DB-5:	17-Aug-12	Date Analyzed DB-225:	NA
Time Collected:	0000							
Analyte	Conc. (pg/L)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	ND	0.638			<u>IS</u> 13C-2,3,7,8-TCDD	85.8	40 - 135	
1,2,3,7,8-PeCDD	ND	0.655			13C-1,2,3,7,8-PeCDD	82.3	40 - 135	
1,2,3,4,7,8-HxCDD	ND	0.778			13C-1,2,3,4,7,8-HxCDD	72.7	40 - 135	
1,2,3,6,7,8-HxCDD	ND	0.875			13C-1,2,3,6,7,8-HxCDD	72.5	40 - 135	
1,2,3,7,8,9-HxCDD	ND	0.910			13C-1,2,3,7,8,9-HxCDD	70.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	ND	0.892			13C-1,2,3,4,6,7,8-HpCDD	72.2	40 - 135	
OCDD	ND	0.914			13C-OCDD	65.8	40 - 135	
2,3,7,8-TCDF	ND	0.645			13C-2,3,7,8-TCDF	85.0	40 - 135	
1,2,3,7,8-PeCDF	ND	0.350			13C-1,2,3,7,8-PeCDF	102	40 - 135	
2,3,4,7,8-PeCDF	ND	0.433			13C-2,3,4,7,8-PeCDF	87.6	40 - 135	
1,2,3,4,7,8-HxCDF	ND	0.384			13C-1,2,3,4,7,8-HxCDF	78.1	40 - 135	
1,2,3,6,7,8-HxCDF	ND	0.358			13C-1,2,3,6,7,8-HxCDF	81.2	40 - 135	
2,3,4,6,7,8-HxCDF	ND	0.390			13C-2,3,4,6,7,8-HxCDF	82.0	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.561			13C-1,2,3,7,8,9-HxCDF	76.6	40 - 135	
1,2,3,4,6,7,8-HpCDF	ND	0.355			13C-1,2,3,4,6,7,8-HpCDF	68.5	40 - 135	
1,2,3,4,7,8,9-HpCDF	ND	0.461			13C-1,2,3,4,7,8,9-HpCDF	70.4	40 - 135	
OCDF	ND	1.06			13C-OCDF	68.9	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	98.9	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	ND	0.638			TEQ (Min):	0		
Total PeCDD	ND	0.655						
Total HxCDD	ND	0.910						
Total HpCDD	ND	0.892						
Total TCDF	ND	0.645						
Total PeCDF	ND	0.433						
Total HxCDF	ND	0.561						
Total HpCDF	ND	0.461						

Analyst: FEB

Approved By: Calvin Tanaka 21-Aug-2012 13:25



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

Laboratory Project ID: 33932 Storage Secured: Yes No

Storage ID: WR-7 Temp: 1.3 °C

Project I.D.: _____ P.O.# 80031212.0000.06002 Sampler: I. STEWART
C. McKendrick
 (Name)

TAT: (Check One): 2.1°C

Standard: 21 Days

Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGPASS Company ARCADIS Address 11002 EXCELSIOR RD City BAKTER State MN Zip 55425 Ph# 218-829-4101 Fax# _____

Relinquished by: (Signature and Printed Name) [Signature] Date: 8/9/12 Time: 1:00 Received by: (Signature and Printed Name) B. Benedict Date: 8/10/12 Time: 08:44

Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

ATTN: _____

Add Analysis(es) Requested			EPA1613	EPA8290	EPA8280	EPA1668	EPA1614	CARB429										
Container(s)																		
Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	CORLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	
* A1-02	1	G SD							X									
* A1-50	1	G SD							X									
* A1-57	1	G SD							X									
* A1-03	1	G SD							X									
* A1-52	1	G SD							X									
* A1-53	1	G SD							X									
* A1-59	1	G SD							X									
* A1-54	1	G SD							X									
* A1-55	1	G SD							X									
* A1-01	1	G SD							X									

Special Instructions/Comments:
* project 33932
* project 33933

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGPASS
 Company: ARCADIS
 Address: _____
 City: _____ State: _____ Zip: _____
 Phone: _____ Fax: _____
 Email: DAVID.BESSINGPASS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other _____

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MMS Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
 O = Other _____



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

Storage Secured

Laboratory Project ID: 33932

Yes No

Storage ID: WR-2

Temp: 1.3°/2.1°C

Project I.D.: _____

P.O.# 810392102.0000.00002

Sampler: I. STEWART & C. MCKENDRICK
(Name)

TAT: (Check One):

Standard: 21 Days

Rush (surcharge may apply):

14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGTASS Company ARCADIS Address 1002 EXCELSIOR RD City BAXTER State MIN Zip 55425 Ph# 218-829-4607 Fax# _____

Relinquished by: (Signature and Printed Name) C. McKendrick Date: 8/9/12 Time: 1:00 PM Received by: (Signature and Printed Name) B. Benedict Date: 8/10/12 Time: 0841

Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Add Analysis(es) Requested

ATTN: _____

Tracking No.: _____

Container(s)

Sample ID	Date	Time	Location/Sample Description	Add Analysis(es) Requested																		
				Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	CORPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	CARB429
* A1-100	8/8/12	1330		2	G	SD																
* A3-32	8/8/12	1440		1	G	SD																
* A3-29	8/8/12	1500		1	G	SD																
* DUP-1	8/8/12	-		1	G	SD																
* DUP-2	8/8/12	-		1	G	SD																
* MS/MSD 1	8/8/12	-		2	G	SD																
* MS/MSD 2	8/8/12	-		2	G	SD																
* EB	8/8/12	-		2	A	N																
* A3-34	8/9/12	0900		1	G	SD																
* A3-33	8/9/12	0915		1	G	SD																

Special Instructions/Comments:

* project 33932

* project 33933

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGTASS
Company: ARCADIS
Address: 1002 EXCELSIOR RD
City: BAXTER State: MIN Zip: 55425
Phone: 218-829-4607 Fax: _____
Email: DAVID.BESSINGTASS@ARCADIS-US.COM
Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
P = PUF, T = MM5 Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
O = Other _____

Beazer East Inc.

Former Koppers Wood-Treating Site

Data Review

CARBONDALE, ILLINOIS

Dioxins/Furans Analyses

SDG # 33933

Analyses Performed By:
Vista Analytical Laboratories
El Dorado Hills, California

Report #17381
Review Level: Tier III
Project: B0039262.0000.00003

SUMMARY

This data quality assessment summarizes the review of Sample Delivery Group (SDG) # 33933 for samples collected in association with the Beazer East Inc. Former Koppers Wood-Treating Site. The review was conducted as a Tier III evaluation and included review of data package completeness. Only analytical data associated with constituents of concern were reviewed for this validation. Field documentation was not included in this review. Included with this assessment are the validation annotated sample result sheets and chain of custody. Analyses were performed on the following samples:

Sample ID	Lab ID	Matrix	Sample Collection Date	Parent Sample	Analysis
					Dioxins/Furans
A1-50	33933-001	Soil	8/9/2012		X
A1-51	33933-002	Soil	8/9/2012		X
A3-28	33933-003	Soil	8/9/2012		X
A3-27	33933-004	Soil	8/9/2012		X
A3-26	33933-005	Soil	8/9/2012		X
A3-25	33933-006	Soil	8/9/2012		X
A3-31	33933-007	Soil	8/9/2012		X
A3-30	33933-008	Soil	8/9/2012		X
A1-58	33933-009	Soil	8/9/2012		X
DUP-3	33933-010	Soil	8/9/2012	A1-50	X
A3-32	33933-011	Soil	8/8/2012		X
A3-29	33933-012	Soil	8/8/2012		X
A3-34	33933-013	Soil	8/9/2012		X
A3-33	33933-014	Soil	8/9/2012		X
A1-61	33933-015	Soil	8/8/2012		X
EB 8/9/12	33933-016	Water	8/9/2012		X

1. The matrix spike/matrix spike duplicate (MS/MSD) analysis was performed on sample location A1-61.
2. Sample results were reported on a dry-weight basis.

ANALYTICAL DATA PACKAGE DOCUMENTATION

The table below is the evaluation of the data package completeness.

Items Reviewed	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample receipt condition		X		X	
2. Requested analyses and sample results		X		X	
3. Master tracking list		X		X	
4. Methods of analysis		X		X	
5. Reporting limits		X		X	
6. Sample collection date		X		X	
7. Laboratory sample received date		X		X	
8. Sample preservation verification (as applicable)		X		X	
9. Sample preparation/extraction/analysis dates		X		X	
10. Fully executed Chain-of-Custody (COC) form		X		X	
11. Narrative summary of QA or sample problems provided		X		X	
12. Data Package Completeness and Compliance		X		X	

QA - Quality Assurance

ORGANIC ANALYSIS INTRODUCTION

Analyses were performed according to United States Environmental Protection Agency (USEPA) SW-846 Method 8290. Data were reviewed in accordance with USEPA National Functional Guidelines of January 2005.

The data review process is an evaluation of data on a technical basis rather than a determination of contract compliance. As such, the standards against which the data are being weighed may differ from those specified in the analytical method. It is assumed that the data package represents the best efforts of the laboratory and had already been subjected to adequate and sufficient quality review prior to submission.

During the review process, laboratory qualified and unqualified data are verified against the supporting documentation. Based on this evaluation, qualifier codes may be added, deleted, or modified by the data reviewer. Results are qualified with the following codes in accordance with USEPA National Functional Guidelines:

- Concentration (C) Qualifiers
 - U The compound was analyzed for but not detected. The associated value is the compound quantitation limit.
 - B The compound has been found in the sample as well as its associated blank, its presence in the sample may be suspect.
- Quantitation (Q) Qualifiers
 - E The compound was quantitated above the calibration range.
 - D Concentration is based on a diluted sample analysis.
- Validation Qualifiers
 - J The compound was positively identified; however, the associated numerical value is an estimated concentration only.
 - UJ The compound was not detected above the reported sample quantitation limit. However, the reported limit is approximate and may or may not represent the actual limit of quantitation.
 - JN The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification. The associated numerical value is an estimated concentration only.
 - UB Compound considered non-detect at the listed value due to associated blank contamination.
 - N The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification.
 - R The sample results are rejected as unusable. The analyte may or may not be present in the sample.

Two facts should be noted by all data users. First, the "R" flag means that the associated value is unusable. In other words, due to significant quality control (QC) problems, the analysis is invalid and provides no information as to whether the compound is present or not. "R" values should not appear on data tables because they cannot be relied upon, even as a last resort. The second fact to keep in mind is that no compound concentration, even if it has passed all QC tests, is guaranteed to be accurate. Strict QC serves to increase confidence in data but any value potentially contains error.

POLYCHLORINATED DIBENZODIOXINS AND POLYCHLORINATED DIBENZOFURANS (PCDD/PCDF) ANALYSES

1. Holding Times

The specified holding times for the following methods are presented in the following table.

Method	Matrix	Holding Time	Preservation
SW-846 8290	Water	30 days from collection to extraction and 45 days from extraction to analysis	Cooled @ 4±2 °C
	Soil	30 days from collection to extraction and 45 days from extraction to analysis	Cooled @ 4±2 °C

The samples were received at the laboratory at acceptable temperatures and all samples were analyzed within the specified holding times.

2. Blank Contamination

Quality assurance (QA) blanks (i.e. laboratory method blanks and equipment rinse blanks) are prepared to identify any contamination which may have been introduced into the samples during sample preparation or field activity. Method blanks measure laboratory contamination. Equipment rinse blanks also measure contamination of samples during field operations.

A blank action level (BAL) of five times the concentration of a detected compound in an associated blank is calculated for QA blanks containing concentrations greater than the method detection limit (MDL). The BAL is compared to the associated sample results to determine the appropriate qualification of the sample results, if needed.

Compounds were detected in an associated method blank and equipment blank (which were analyzed with SDG 33933); however, the associated sample results were either greater than the BAL or non-detect. Therefore, qualification of the sample results was not required.

3. Mass Spectrometer Tuning

Mass spectrometer performance was acceptable; system performance and column resolution were acceptable.

4. Calibration

Satisfactory instrument calibration is established to insure that the instrument is capable of producing acceptable quantitative data. An initial calibration demonstrates that the instrument is capable of acceptable performance at the beginning of an experimental sequence. The continuing calibration verifies that the instrument daily performance is satisfactory.

4.1 Initial Calibration

A maximum relative standard deviation (RSD) of 20% is allowed for all non-labeled compounds (target) and 30% is allowed for all labeled compounds (internal standards and recovery standards)

4.2 Continuing Calibration

All target compounds associated with the continuing calibration standard must exhibit percent difference (%D) less than the control limit (20%).

All initial and continuing calibration criteria were within the control limits.

5. Internal Standard Performance

All samples to be analyzed for PCDD/PCDF compounds are spiked with internal standards prior to extraction. Internal standard performance criteria insure that the GC/MS sensitivity and response are stable during every sample analysis. The criteria require the internal standard compounds exhibit recoveries within the control limits of 40% to 135%.

Sample locations associated with internal standards exhibiting responses outside of the control limits are presented in the following table.

Sample Locations	Internal Standard	Response
A3-28	¹³ C-OCDD	>UL

The criteria used to evaluate the internal standard responses are presented in the following table. In the case of an internal standard deviation, the compounds quantitated under the deviant internal standard are qualified as documented in the table below.

Control limit	Sample Result	Qualification
> the upper control limit (UL)	Non-detect	No action
	Detect	J
< the lower control limit (LL) but > 40%	Non-detect	J
	Detect	J
< 25%	Non-detect	R
	Detect	J

6. Recovery Standard Performance

The recovery standard (³⁷Cl-2,3,7,8-TCDD) is added to the sample extract prior to the extract clean-up steps. The concentrations of the labeled standards (internal standards) are determined using the recovery standard.

All recovery standard recoveries were acceptable.

7. Matrix Spike/Matrix Spike Duplicate (MS/MSD) Analysis

MS/MSD data are used to assess the precision and accuracy of the analytical method. The compounds spiked in the MS/MSD analysis must exhibit a percent recovery within the laboratory-established acceptance limits. The relative percent differences (RPDs) between the MS and MSD must be within the laboratory-established acceptance limits.

Note: The MS/MSD recovery control limits do not apply for MS/MSD performed on sample locations where the compounds concentration detected in the parent sample exceeds the MS/MSD concentration by a factor of four or greater.

Sample locations associated with the MS/MSD exhibiting recoveries outside of the control limits are presented in the following table.

Sample Locations	Compound	MS Recovery	MSD Recovery
A1-61	1,2,3,4,6,7,8-HpCDF	< LL but > 10%	< LL but > 10%

AC = Acceptable

The criteria used to evaluate the MS/MSD recoveries are presented in the following table. In the case of an MS/MSD deviation, the sample results are qualified as documented in the table below.

Control Limit	Sample Result	Qualification
> the upper control limit (UL)	Non-detect	No Action
	Detect	J
< the lower control limit (LL) but > 10%	Non-detect	J
	Detect	J
< 10%	Non-detect	R
	Detect	J

8. Laboratory Control Sample (LCS) Analysis

The LCS analysis is used to assess the precision and accuracy of the analytical method independent of matrix interferences. The compounds associated with the LCS analysis must exhibit recoveries within the laboratory-established acceptance limits.

All compounds associated with the LCS analyses exhibited recoveries within the control limits.

9. Field Duplicate Sample Analysis

Field duplicate analysis is used to assess the precision of the field sampling procedures and analytical method. A control limit of 100% for soil matrices is applied to the RPD between the parent and the field duplicate samples. In the case where the parent and/or duplicate sample concentrations are less than or equal to 5 times the RL, a control limit of three times the RL is applied for soil matrices.

Results (in ug/kg) for the field duplicate samples are summarized in the following table.

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
A1-50 DUP-3	1,2,3,4,6,7,8-HpCDD	0.626	0.781	22.0%
	1,2,3,4,6,7,8-HpCDF	0.0588	0.0491	17.9%
	1,2,3,4,7,8,9-HpCDF	0.00482	0.00424	12.8%
	1,2,3,4,7,8-HxCDD	0.00408	0.00513	22.8%
	1,2,3,4,7,8-HxCDF	0.00377	0.00334	12.0%
	1,2,3,6,7,8-HxCDD	0.0158	0.0145	8.5%
	1,2,3,6,7,8-HxCDF	0.00225 J	0.00161 J	33.1%
	1,2,3,7,8,9-HxCDD	0.0117	0.0118	0.8%
	1,2,3,7,8,9-HxCDF	0.000545 J	0.000345 J	44.9%
	1,2,3,7,8-PeCDD	0.00251	0.0019 J	27.6%
	1,2,3,7,8-PeCDF	0.000752 J	0.000465 J	47.1%
	2,3,4,6,7,8-HxCDF	0.00394	0.00325	19.1%
	2,3,4,7,8-PeCDF	0.00138 J	0.00138 J	0%
	2,3,7,8-TCDD	0.000558	0.000416 J	29.1%
	2,3,7,8-TCDF	0.000633	0.000436 J	36.8%
	37Cl-2,3,7,8-TCDD	0.0746	0.0822	9.6%
	OCDD	21.1	23.9	12.4%
	OCDF	0.421	0.351	18.1%
	TEQ(Min)	0.0211	0.0224	5.9%
	Total HpCDD	1.47	2.46	50.3%
	Total HpCDF	0.295	0.24	20.5%
	Total HxCDD	0.164	0.235	35.5%
	Total HxCDF	0.0909	0.0777	15.6%
	Total PeCDD	0.0227	0.0203	11.1%
	Total PeCDF	0.0504	0.0339	39.1%
	Total TCDD	0.0126	0.0104	19.1%
	Total TCDF	0.018	0.0135	28.5%
	WHO Dioxin TEQ(Human/Mammal- NDs Excluded)	0.0211	0.0224	5.9%
WHO Dioxin TEQ(Human/Mammal- NDs used at 1/2 DL)	0.0211	0.0224	5.9%	

AC Acceptable

The calculated RPDs between the parent sample and field duplicate were acceptable.

10. Compound Identification

PCDD/PCDF compounds are identified by using the compound's ion abundance ratios, signal-to-noise ratios, and retention times relative to the internal standards'.

An estimated maximum possible concentration (EMPC) designation is given to compounds which have signals eluting within the established retention time window which would, if positively identified, be greater than the detection limit. The signals do not, however, meet the ion abundance ratio criteria and therefore cannot be identified as the compound of interest. The EMPC value is the estimated concentration of the interferant quantitated "as the compound of interest". This value should be considered an elevated detection limit based on potential compound identification and quantitation interference. The "UX" qualifier has been added to the following sample results (in ug/kg) to indicate the elevated detection limit as EMPC.

Sample ID	Compound	Laboratory Result	Reported Result
A3-29	2,3,7,8-TCDD	0.000225 EMPC	0.000225 UX
A3-25	2,3,7,8-TCDF	0.000233 EMPC	0.000233 UX
	2,3,4,7,8-PeCDF	0.000519 EMPC	0.000519 UX
	1,2,3,7,8,9-HxCDF	0.000317 EMPC	0.000317 UX

The following results exhibited evidence of interference by chlorodiphenyl ethers. The results were flagged "P" by the laboratory indicating the result is the maximum concentrations of the analytes in the case that all of the quantified area is due to the target analyte and none due to the interference. Therefore, these results have been qualified as estimated ("J").

Sample ID	Compound
A1-51	Total PeCDF
A3-28	1,2,3,6,7,8-HxCDF Total TCDF Total PeCDF Total HxCDF
A3-34	Total PeCDF

Sample results that exhibited a concentration greater than the linear range of the instrument calibration are summarized in the following table (ug/kg).

Sample ID	Compound	Original Analysis	Diluted Analysis	Reported Analysis
A1-50	OCDD	21.1 E	—	21.1 EJ
A1-51	OCDD	24.5 E	—	24.5 EJ
A3-28	1,2,3,6,7,8-HxCDD	6.66 E	—	6.66 EJ
	1,2,3,7,8,9-HxCDD	3.02 E	—	3.02 EJ
	1,2,3,4,6,7,8-HpCDD	343 ED	—	343 EDJ
	OCDD	2270 ED	—	2270 EDJ
	1,2,3,4,6,7,8-HpCDF	68.9 ED	—	68.9 EDJ
	OCDF	438 ED	—	438 EDJ
A3-27	OCDD	13.6 E	—	13.6 EJ
A3-26	1,2,3,4,6,7,8-HpCDD	5 E	—	5 EJ
	OCDF	4.62 E	—	4.62 EJ
A3-31	OCDD	22.5 E	—	22.5 EJ
A3-30	OCDD	29.4 E	—	29.4 EJ

Sample ID	Compound	Original Analysis	Diluted Analysis	Reported Analysis
A1-58	OCDD	31.3 E	—	31.3 EJ
DUP-3	OCDD	23.9 E	—	23.9 EJ
A3-32	1,2,3,4,6,7,8-HpCDD	23.9 ED	—	23.9 EDJ
	1,2,3,4,6,7,8-HpCDF	5.5 E	—	5.5 EJ
	OCDF	27.3 E	—	27.3 EJ
A3-29	OCDD	7.77 E	—	7.77 EJ
A3-34	1,2,3,4,6,7,8-HpCDD	5.16 E	—	5.16 EJ
	OCDD	45.8 E	—	45.8 EJ
	OCDF	4.24 E	—	4.24 EJ
A3-33	1,2,3,4,6,7,8-HpCDD	43.1 ED	—	43.1 EDJ
	OCDD	487 ED	—	487 EDJ
	OCDF	41.5 ED	—	41.5 EDJ
A3-25	OCDD	34.4 E	—	34.4 EJ
A1-61	1,2,3,4,6,7,8-HpCDD	3.12 E	—	3.12 EJ
	OCDD	38.6 E	—	38.6 EJ

Note: In the instance where both the original analysis and the diluted analysis sample results exhibited a concentration greater than and/or less than the calibration linear range of the instrument; the sample result exhibiting the greatest concentration will be reported as the final result.

Sample results associated with compounds exhibiting concentration greater than the linear range qualified as documented in the table below when reported as the final reported sample result.

Reported Sample Results	Qualification
Diluted sample result within calibration range	D
Diluted sample result less than the calibration range	DJ
Diluted sample result greater than the calibration range	EDJ
Original sample result greater than the calibration range	EJ

11. System Performance and Overall Assessment

Please note that when individual compounds are qualified as estimated (J) during validation, this qualification is applied to the totals as well.

Overall system performance was acceptable. Except for those deviations specifically mentioned in this review, the overall data quality is within the guidelines specified in the method.


DATA VALIDATION CHECKLIST FOR PCDD/PCDF

PCDDs/PCDFs; SW-846 8290	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS)					
Tier II Validation					
Holding times		X		X	
Reporting limits (units)		X		X	
Blanks					
A. Method blanks		X		X	
B. Equipment blanks		X		X	
Laboratory Control Sample (LCS) Accuracy (%R)		X		X	
Laboratory Control Sample Duplicate (LCSD) %R					X
LCS/LCSD Precision (RPD)					X
Matrix Spike (MS) %R		X	X		
Matrix Spike Duplicate (MSD) %R		X	X		
MS/MSD RPD		X		X	
Field/Laboratory Duplicate Sample RPD		X		X	
Dilution Factor		X		X	
Moisture Content		X		X	
Tier III Validation					
System performance and column resolution		X		X	
Initial calibration %RSDs		X		X	
Continuing calibration %Ds		X		X	
Instrument tune and performance check		X		X	
Ion abundance criteria for each instrument used		X		X	
Signal-to-noise ratio \geq 10:1		X		X	
Internal standard performance		X	X		
Recovery standard performance		X		X	
Resolution mix \leq 25%		X		X	
Compound identification and quantitation					
A. Reconstructed ion chromatograms		X		X	
B. Quantitation Reports		X		X	
C. RT of sample compounds within the established RT windows		X		X	
D. Transcription/calculation errors present		X		X	
E. Reporting limits adjusted to reflect sample dilutions		X		X	

RSD – relative standard deviation
 %R - percent recovery
 RPD - relative percent difference
 %D – difference

VALIDATION PERFORMED BY: Jeffrey L. Davin

SIGNATURE:



DATE: September 27, 2012

PEER REVIEW: Dennis Capria

DATE: October 1, 2012

**CHAIN OF CUSTODY /
CORRECTED SAMPLE ANALYSIS DATA SHEETS**

Sample ID: A1-50					EPA Method 8290			
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-001	Date Received:	10-Aug-12	
Project:		Sample Size:	12.7 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	79.9	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	0930							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.558				<u>IS</u> 13C-2,3,7,8-TCDD	91.6	40 - 135	
1,2,3,7,8-PeCDD	2.51				13C-1,2,3,7,8-PeCDD	95.9	40 - 135	
1,2,3,4,7,8-HxCDD	4.08				13C-1,2,3,4,7,8-HxCDD	89.6	40 - 135	
1,2,3,6,7,8-HxCDD	15.8				13C-1,2,3,6,7,8-HxCDD	82.3	40 - 135	
1,2,3,7,8,9-HxCDD	11.7				13C-1,2,3,7,8,9-HxCDD	84.3	40 - 135	
1,2,3,4,6,7,8-HpCDD	626				13C-1,2,3,4,6,7,8-HpCDD	94.1	40 - 135	
OCDD	21100			<u>B,E J</u>	13C-OCDD	97.3	40 - 135	
2,3,7,8-TCDF	0.633				13C-2,3,7,8-TCDF	92.5	40 - 135	
1,2,3,7,8-PeCDF	0.752			J	13C-1,2,3,7,8-PeCDF	91.9	40 - 135	
2,3,4,7,8-PeCDF	1.38			J	13C-2,3,4,7,8-PeCDF	88.5	40 - 135	
1,2,3,4,7,8-HxCDF	3.77				13C-1,2,3,4,7,8-HxCDF	89.8	40 - 135	
1,2,3,6,7,8-HxCDF	2.25			J	13C-1,2,3,6,7,8-HxCDF	83.8	40 - 135	
2,3,4,6,7,8-HxCDF	3.94				13C-2,3,4,6,7,8-HxCDF	87.3	40 - 135	
1,2,3,7,8,9-HxCDF	0.545			J	13C-1,2,3,7,8,9-HxCDF	82.9	40 - 135	
1,2,3,4,6,7,8-HpCDF	58.8				13C-1,2,3,4,6,7,8-HpCDF	90.2	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.82				13C-1,2,3,4,7,8,9-HpCDF	90.9	40 - 135	
OCDF	421				13C-OCDF	87.3	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	94.5	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	12.6				TEQ (Min):	21.1		
Total PeCDD	22.7							
Total HxCDD	164							
Total HpCDD	1470							
Total TCDF	18.0		19.2					
Total PeCDF	50.4							
Total HxCDF	90.9							
Total HpCDF	295							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A1-51					EPA Method 8290			
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-002	Date Received:	10-Aug-12	
Project:		Sample Size:	12.9 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	78.0	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	0945							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	1.62				<u>IS</u> 13C-2,3,7,8-TCDD	92.8	40 - 135	
1,2,3,7,8-PeCDD	5.97				13C-1,2,3,7,8-PeCDD	104	40 - 135	
1,2,3,4,7,8-HxCDD	11.4				13C-1,2,3,4,7,8-HxCDD	83.3	40 - 135	
1,2,3,6,7,8-HxCDD	31.1				13C-1,2,3,6,7,8-HxCDD	83.2	40 - 135	
1,2,3,7,8,9-HxCDD	25.7				13C-1,2,3,7,8,9-HxCDD	81.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	918				13C-1,2,3,4,6,7,8-HpCDD	95.4	40 - 135	
OCDD	24500			B, E J	13C-OCDD	107	40 - 135	
2,3,7,8-TCDF	1.84				13C-2,3,7,8-TCDF	91.4	40 - 135	
1,2,3,7,8-PeCDF	1.60			J	13C-1,2,3,7,8-PeCDF	96.6	40 - 135	
2,3,4,7,8-PeCDF	3.57				13C-2,3,4,7,8-PeCDF	90.7	40 - 135	
1,2,3,4,7,8-HxCDF	8.89				13C-1,2,3,4,7,8-HxCDF	92.2	40 - 135	
1,2,3,6,7,8-HxCDF	7.75				13C-1,2,3,6,7,8-HxCDF	84.9	40 - 135	
2,3,4,6,7,8-HxCDF	13.5				13C-2,3,4,6,7,8-HxCDF	88.4	40 - 135	
1,2,3,7,8,9-HxCDF	0.793			J	13C-1,2,3,7,8,9-HxCDF	85.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	136				13C-1,2,3,4,6,7,8-HpCDF	90.4	40 - 135	
1,2,3,4,7,8,9-HpCDF	10.7				13C-1,2,3,4,7,8,9-HpCDF	94.3	40 - 135	
OCDF	523				13C-OCDF	92.1	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	97.1	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	15.3		16.2		TEQ (Min):	37.0		
Total PeCDD	46.0				a. Sample specific estimated detection limit.			
Total HxCDD	254				b. Estimated maximum possible concentration.			
Total HpCDD	1810				c. Method detection limit.			
Total TCDF	57.6		58.7		d. Lower control limit - upper control limit.			
Total PeCDF	168			P J	e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	253				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	483							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-28					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-003	Date Received:	10-Aug-12	
Project:		Sample Size:	12.7 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	79.5	Date Analyzed DB-5:	30-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1040							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	38.8				<u>IS</u> 13C-2,3,7,8-TCDD	94.6	40 - 135	
1,2,3,7,8-PeCDD	616				13C-1,2,3,7,8-PeCDD	92.4	40 - 135	
1,2,3,4,7,8-HxCDD	1820				13C-1,2,3,4,7,8-HxCDD	93.5	40 - 135	
1,2,3,6,7,8-HxCDD	6660			E J	13C-1,2,3,6,7,8-HxCDD	92.7	40 - 135	
1,2,3,7,8,9-HxCDD	3020			E J	13C-1,2,3,7,8,9-HxCDD	66.8	40 - 135	
1,2,3,4,6,7,8-HpCDD	343000			D,E J	13C-1,2,3,4,6,7,8-HpCDD	78.2	40 - 135	D
OCDD	2270000			D,E J	13C-OCDD	136	40 - 135	D,H
2,3,7,8-TCDF	9.31			B	13C-2,3,7,8-TCDF	77.4	40 - 135	
1,2,3,7,8-PeCDF	66.7				13C-1,2,3,7,8-PeCDF	83.9	40 - 135	
2,3,4,7,8-PeCDF	110				13C-2,3,4,7,8-PeCDF	81.5	40 - 135	
1,2,3,4,7,8-HxCDF	1840				13C-1,2,3,4,7,8-HxCDF	89.2	40 - 135	
1,2,3,6,7,8-HxCDF	980			P J	13C-1,2,3,6,7,8-HxCDF	91.2	40 - 135	
2,3,4,6,7,8-HxCDF	1840				13C-2,3,4,6,7,8-HxCDF	90.0	40 - 135	
1,2,3,7,8,9-HxCDF	125				13C-1,2,3,7,8,9-HxCDF	104	40 - 135	
1,2,3,4,6,7,8-HpCDF	68900			D,E J	13C-1,2,3,4,6,7,8-HpCDF	84.4	40 - 135	D
1,2,3,4,7,8,9-HpCDF	6060			D	13C-1,2,3,4,7,8,9-HpCDF	81.6	40 - 135	D
OCDF	438000			D,E J	13C-OCDF	90.3	40 - 135	D
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	96.6	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	332				TEQ (Min):	7310		
Total PeCDD	3780				a. Sample specific estimated detection limit.			
Total HxCDD	55300				b. Estimated maximum possible concentration.			
Total HpCDD	732000				c. Method detection limit.			
Total TCDF	450		451	P J	d. Lower control limit - upper control limit.			
Total PeCDF	5450			P J	e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	72800			P J	The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	337000							

Analyst: MAS

Approved By: Rose Harrelson 31-Aug-2012 16:32

Sample ID: A3-27					EPA Method 8290			
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-004	Date Received:	10-Aug-12	
Project:		Sample Size:	12.2 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	82.2	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1050							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.808				<u>IS</u> 13C-2,3,7,8-TCDD	86.3	40 - 135	
1,2,3,7,8-PeCDD	4.66				13C-1,2,3,7,8-PeCDD	93.2	40 - 135	
1,2,3,4,7,8-HxCDD	6.90				13C-1,2,3,4,7,8-HxCDD	83.5	40 - 135	
1,2,3,6,7,8-HxCDD	17.9				13C-1,2,3,6,7,8-HxCDD	77.5	40 - 135	
1,2,3,7,8,9-HxCDD	11.0				13C-1,2,3,7,8,9-HxCDD	79.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	532				13C-1,2,3,4,6,7,8-HpCDD	90.7	40 - 135	
OCDD	13600			B, E J	13C-OCDD	90.9	40 - 135	
2,3,7,8-TCDF	1.81				13C-2,3,7,8-TCDF	85.3	40 - 135	
1,2,3,7,8-PeCDF	1.72			J	13C-1,2,3,7,8-PeCDF	86.0	40 - 135	
2,3,4,7,8-PeCDF	3.68				13C-2,3,4,7,8-PeCDF	79.3	40 - 135	
1,2,3,4,7,8-HxCDF	7.01				13C-1,2,3,4,7,8-HxCDF	86.4	40 - 135	
1,2,3,6,7,8-HxCDF	4.20				13C-1,2,3,6,7,8-HxCDF	82.9	40 - 135	
2,3,4,6,7,8-HxCDF	6.08				13C-2,3,4,6,7,8-HxCDF	80.9	40 - 135	
1,2,3,7,8,9-HxCDF	0.638			J	13C-1,2,3,7,8,9-HxCDF	81.8	40 - 135	
1,2,3,4,6,7,8-HpCDF	69.2				13C-1,2,3,4,6,7,8-HpCDF	88.6	40 - 135	
1,2,3,4,7,8,9-HpCDF	5.37				13C-1,2,3,4,7,8,9-HpCDF	88.9	40 - 135	
OCDF	327				13C-OCDF	86.2	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	93.5	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	79.3				TEQ (Min):	22.4		
Total PeCDD	87.3							
Total HxCDD	177				a. Sample specific estimated detection limit.			
Total HpCDD	1120				b. Estimated maximum possible concentration.			
Total TCDF	45.6		46.1		c. Method detection limit.			
Total PeCDF	70.7		70.9		d. Lower control limit - upper control limit.			
Total HxCDF	119				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HpCDF	268				The results are reported in dry weight. The sample size is reported in wet weight.			

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

<u>Client Data</u>	<u>Sample Data</u>	<u>Laboratory Data</u>		
Name: ARCADIS	Matrix: Soil	Lab Sample: 33933-005	Date Received: 10-Aug-12	
Project:	Sample Size: 14.2 g	QC Batch No.: 4619	Date Extracted: 19-Aug-12	
Date Collected: 9-Aug-12	%Solids: 70.4	Date Analyzed DB-5: 30-Aug-12	Dates Analyzed DB-225: 30-Aug-12	
Time Collected: 1055				

Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	3.72				<u>IS</u> 13C-2,3,7,8-TCDD	92.1	40 - 135	
1,2,3,7,8-PeCDD	17.5				13C-1,2,3,7,8-PeCDD	94.0	40 - 135	
1,2,3,4,7,8-HxCDD	39.0				13C-1,2,3,4,7,8-HxCDD	90.2	40 - 135	
1,2,3,6,7,8-HxCDD	160				13C-1,2,3,6,7,8-HxCDD	86.3	40 - 135	
1,2,3,7,8,9-HxCDD	86.1				13C-1,2,3,7,8,9-HxCDD	87.0	40 - 135	
1,2,3,4,6,7,8-HpCDD	5000			E J	13C-1,2,3,4,6,7,8-HpCDD	102	40 - 135	
OCDD	84000			D	13C-OCDD	82.9	40 - 135	D
2,3,7,8-TCDF	3.69			B	13C-2,3,7,8-TCDF	90.5	40 - 135	
1,2,3,7,8-PeCDF	4.30				13C-1,2,3,7,8-PeCDF	99.2	40 - 135	
2,3,4,7,8-PeCDF	13.0				13C-2,3,4,7,8-PeCDF	94.1	40 - 135	
1,2,3,4,7,8-HxCDF	47.6				13C-1,2,3,4,7,8-HxCDF	90.4	40 - 135	
1,2,3,6,7,8-HxCDF	25.5				13C-1,2,3,6,7,8-HxCDF	82.7	40 - 135	
2,3,4,6,7,8-HxCDF	49.0				13C-2,3,4,6,7,8-HxCDF	85.5	40 - 135	
1,2,3,7,8,9-HxCDF	9.97				13C-1,2,3,7,8,9-HxCDF	86.1	40 - 135	
1,2,3,4,6,7,8-HpCDF	864				13C-1,2,3,4,6,7,8-HpCDF	92.8	40 - 135	
1,2,3,4,7,8,9-HpCDF	69.7				13C-1,2,3,4,7,8,9-HpCDF	95.0	40 - 135	
OCDF	4620			E J	13C-OCDF	96.0	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	93.7	40 - 135	

Totals				Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	27.2		27.9	TEQ (Min):	153		
Total PeCDD	112			a. Sample specific estimated detection limit.			
Total HxCDD	914			b. Estimated maximum possible concentration.			
Total HpCDD	9000			c. Method detection limit.			
Total TCDF	101		103	d. Lower control limit - upper control limit.			
Total PeCDF	367			e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	1140			The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	3710						

Analyst: MAS

Approved By: Rose Harrelson 31-Aug-2012 16:32

Sample ID: A3-31					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-007	Date Received:	10-Aug-12	
Project:		Sample Size:	13.3 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	75.7	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1150							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	1.35				<u>IS</u> 13C-2,3,7,8-TCDD	89.8	40 - 135	
1,2,3,7,8-PeCDD	12.3				13C-1,2,3,7,8-PeCDD	96.0	40 - 135	
1,2,3,4,7,8-HxCDD	19.8				13C-1,2,3,4,7,8-HxCDD	79.7	40 - 135	
1,2,3,6,7,8-HxCDD	58.5				13C-1,2,3,6,7,8-HxCDD	74.2	40 - 135	
1,2,3,7,8,9-HxCDD	47.5				13C-1,2,3,7,8,9-HxCDD	73.4	40 - 135	
1,2,3,4,6,7,8-HpCDD	1460				13C-1,2,3,4,6,7,8-HpCDD	89.2	40 - 135	
OCDD	22500			B,E J	13C-OCDD	93.8	40 - 135	
2,3,7,8-TCDF	0.810				13C-2,3,7,8-TCDF	86.0	40 - 135	
1,2,3,7,8-PeCDF	0.973			J	13C-1,2,3,7,8-PeCDF	85.3	40 - 135	
2,3,4,7,8-PeCDF	1.61			J	13C-2,3,4,7,8-PeCDF	82.8	40 - 135	
1,2,3,4,7,8-HxCDF	7.48				13C-1,2,3,4,7,8-HxCDF	83.8	40 - 135	
1,2,3,6,7,8-HxCDF	3.86				13C-1,2,3,6,7,8-HxCDF	77.8	40 - 135	
2,3,4,6,7,8-HxCDF	5.68				13C-2,3,4,6,7,8-HxCDF	80.3	40 - 135	
1,2,3,7,8,9-HxCDF	0.771			J	13C-1,2,3,7,8,9-HxCDF	78.9	40 - 135	
1,2,3,4,6,7,8-HpCDF	140				13C-1,2,3,4,6,7,8-HpCDF	85.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	9.94				13C-1,2,3,4,7,8,9-HpCDF	86.4	40 - 135	
OCDF	803				13C-OCDF	83.9	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	95.8	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	22.7				TEQ (Min):	51.7		
Total PeCDD	121				a. Sample specific estimated detection limit.			
Total HxCDD	646				b. Estimated maximum possible concentration.			
Total HpCDD	3040				c. Method detection limit.			
Total TCDF	13.3		13.9		d. Lower control limit - upper control limit.			
Total PeCDF	30.6		30.8		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	155				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	582							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-30					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-008	Date Received:	10-Aug-12	
Project:		Sample Size:	11.9 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	83.9	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1200							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.341			J	<u>IS</u> 13C-2,3,7,8-TCDD	87.6	40 - 135	
1,2,3,7,8-PeCDD	2.28			J	13C-1,2,3,7,8-PeCDD	102	40 - 135	
1,2,3,4,7,8-HxCDD	5.92				13C-1,2,3,4,7,8-HxCDD	79.6	40 - 135	
1,2,3,6,7,8-HxCDD	13.1				13C-1,2,3,6,7,8-HxCDD	74.6	40 - 135	
1,2,3,7,8,9-HxCDD	12.1				13C-1,2,3,7,8,9-HxCDD	78.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	606				13C-1,2,3,4,6,7,8-HpCDD	89.9	40 - 135	
OCDD	29400			J , E, J	13C-OCDD	97.7	40 - 135	
2,3,7,8-TCDF	0.311			J	13C-2,3,7,8-TCDF	87.8	40 - 135	
1,2,3,7,8-PeCDF	0.400			J	13C-1,2,3,7,8-PeCDF	89.8	40 - 135	
2,3,4,7,8-PeCDF	1.23			J	13C-2,3,4,7,8-PeCDF	81.4	40 - 135	
1,2,3,4,7,8-HxCDF	3.65				13C-1,2,3,4,7,8-HxCDF	87.6	40 - 135	
1,2,3,6,7,8-HxCDF	1.65			J	13C-1,2,3,6,7,8-HxCDF	80.2	40 - 135	
2,3,4,6,7,8-HxCDF	2.54				13C-2,3,4,6,7,8-HxCDF	82.9	40 - 135	
1,2,3,7,8,9-HxCDF	0.270			J	13C-1,2,3,7,8,9-HxCDF	81.8	40 - 135	
1,2,3,4,6,7,8-HpCDF	45.0				13C-1,2,3,4,6,7,8-HpCDF	85.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	3.52				13C-1,2,3,4,7,8,9-HpCDF	89.7	40 - 135	
OCDF	219				13C-OCDF	86.1	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	94.6	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	8.37		8.92		TEQ (Min):	22.4		
Total PeCDD	25.4				a. Sample specific estimated detection limit.			
Total HxCDD	176				b. Estimated maximum possible concentration.			
Total HpCDD	1490				c. Method detection limit.			
Total TCDF	6.21		6.72		d. Lower control limit - upper control limit.			
Total PeCDF	12.4		12.4		e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	60.0				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	180							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A1-58					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-009	Date Received:	10-Aug-12	
Project:		Sample Size:	12.5 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	81.8	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1330							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.587				<u>IS</u> 13C-2,3,7,8-TCDD	93.1	40 - 135	
1,2,3,7,8-PeCDD	2.61				13C-1,2,3,7,8-PeCDD	109	40 - 135	
1,2,3,4,7,8-HxCDD	5.68				13C-1,2,3,4,7,8-HxCDD	80.7	40 - 135	
1,2,3,6,7,8-HxCDD	14.0				13C-1,2,3,6,7,8-HxCDD	81.2	40 - 135	
1,2,3,7,8,9-HxCDD	11.3				13C-1,2,3,7,8,9-HxCDD	79.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	602				13C-1,2,3,4,6,7,8-HpCDD	93.5	40 - 135	
OCDD	31300			B,E J	13C-OCDD	100	40 - 135	
2,3,7,8-TCDF	1.08				13C-2,3,7,8-TCDF	94.7	40 - 135	
1,2,3,7,8-PeCDF	0.889			J	13C-1,2,3,7,8-PeCDF	95.4	40 - 135	
2,3,4,7,8-PeCDF	3.66				13C-2,3,4,7,8-PeCDF	90.4	40 - 135	
1,2,3,4,7,8-HxCDF	4.29				13C-1,2,3,4,7,8-HxCDF	89.7	40 - 135	
1,2,3,6,7,8-HxCDF	2.91				13C-1,2,3,6,7,8-HxCDF	83.3	40 - 135	
2,3,4,6,7,8-HxCDF	5.22				13C-2,3,4,6,7,8-HxCDF	86.9	40 - 135	
1,2,3,7,8,9-HxCDF	0.638			J	13C-1,2,3,7,8,9-HxCDF	86.5	40 - 135	
1,2,3,4,6,7,8-HpCDF	83.9				13C-1,2,3,4,6,7,8-HpCDF	89.3	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.15				13C-1,2,3,4,7,8,9-HpCDF	95.4	40 - 135	
OCDF	233				13C-OCDF	86.9	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	105	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	9.14		9.26		TEQ (Min):	25.2		
Total PeCDD	23.9				a. Sample specific estimated detection limit.			
Total HxCDD	142				b. Estimated maximum possible concentration.			
Total HpCDD	1310				c. Method detection limit.			
Total TCDF	22.9		23.6		d. Lower control limit - upper control limit.			
Total PeCDF	55.6				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	115				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	270							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: DUP-3					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-010	Date Received:	10-Aug-12	
Project:		Sample Size:	12.5 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	80.5	Date Analyzed DB-5:	29-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	0000							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.416			J	<u>IS</u> 13C-2,3,7,8-TCDD	95.7	40 - 135	
1,2,3,7,8-PeCDD	1.90			J	13C-1,2,3,7,8-PeCDD	112	40 - 135	
1,2,3,4,7,8-HxCDD	5.13				13C-1,2,3,4,7,8-HxCDD	81.7	40 - 135	
1,2,3,6,7,8-HxCDD	14.5				13C-1,2,3,6,7,8-HxCDD	83.2	40 - 135	
1,2,3,7,8,9-HxCDD	11.8				13C-1,2,3,7,8,9-HxCDD	85.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	781				13C-1,2,3,4,6,7,8-HpCDD	97.1	40 - 135	
OCDD	23900			B,E,J	13C-OCDD	107	40 - 135	
2,3,7,8-TCDF	0.436			J	13C-2,3,7,8-TCDF	94.7	40 - 135	
1,2,3,7,8-PeCDF	0.465			J	13C-1,2,3,7,8-PeCDF	97.3	40 - 135	
2,3,4,7,8-PeCDF	1.38			J	13C-2,3,4,7,8-PeCDF	89.3	40 - 135	
1,2,3,4,7,8-HxCDF	3.34				13C-1,2,3,4,7,8-HxCDF	93.3	40 - 135	
1,2,3,6,7,8-HxCDF	1.61			J	13C-1,2,3,6,7,8-HxCDF	85.1	40 - 135	
2,3,4,6,7,8-HxCDF	3.25				13C-2,3,4,6,7,8-HxCDF	90.0	40 - 135	
1,2,3,7,8,9-HxCDF	0.345			J	13C-1,2,3,7,8,9-HxCDF	88.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	49.1				13C-1,2,3,4,6,7,8-HpCDF	92.1	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.24				13C-1,2,3,4,7,8,9-HpCDF	96.9	40 - 135	
OCDF	351				13C-OCDF	92.0	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	104	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	10.4		11.2		TEQ (Min):	22.4		
Total PeCDD	20.3				a. Sample specific estimated detection limit.			
Total HxCDD	235				b. Estimated maximum possible concentration.			
Total HpCDD	2460				c. Method detection limit.			
Total TCDF	13.5		14.4		d. Lower control limit - upper control limit.			
Total PeCDF	33.9				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	77.7				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	240							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-32					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-011	Date Received:	10-Aug-12	
Project:		Sample Size:	12.9 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	8-Aug-12	%Solids:	77.6	Date Analyzed DB-5:	30-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1440							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	3.05				<u>IS</u> 13C-2,3,7,8-TCDD	91.9	40 - 135	
1,2,3,7,8-PeCDD	83.7				13C-1,2,3,7,8-PeCDD	92.3	40 - 135	
1,2,3,4,7,8-HxCDD	233				13C-1,2,3,4,7,8-HxCDD	95.6	40 - 135	
1,2,3,6,7,8-HxCDD	1010				13C-1,2,3,6,7,8-HxCDD	91.1	40 - 135	
1,2,3,7,8,9-HxCDD	514				13C-1,2,3,7,8,9-HxCDD	91.7	40 - 135	
1,2,3,4,6,7,8-HpCDD	23900			D, E J	13C-1,2,3,4,6,7,8-HpCDD	113	40 - 135	
OCDD	198000				13C-OCDD	97.9	40 - 135	D
2,3,7,8-TCDF	4.19			β	13C-2,3,7,8-TCDF	87.7	40 - 135	
1,2,3,7,8-PeCDF	20.9				13C-1,2,3,7,8-PeCDF	98.7	40 - 135	
2,3,4,7,8-PeCDF	42.2				13C-2,3,4,7,8-PeCDF	94.4	40 - 135	
1,2,3,4,7,8-HxCDF	229				13C-1,2,3,4,7,8-HxCDF	92.6	40 - 135	
1,2,3,6,7,8-HxCDF	132				13C-1,2,3,6,7,8-HxCDF	84.1	40 - 135	
2,3,4,6,7,8-HxCDF	240				13C-2,3,4,6,7,8-HxCDF	88.8	40 - 135	
1,2,3,7,8,9-HxCDF	55.8				13C-1,2,3,7,8,9-HxCDF	91.1	40 - 135	
1,2,3,4,6,7,8-HpCDF	5500			E J	13C-1,2,3,4,6,7,8-HpCDF	100	40 - 135	
1,2,3,4,7,8,9-HpCDF	379				13C-1,2,3,4,7,8,9-HpCDF	102	40 - 135	
OCDF	27300			E J	13C-OCDF	103	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	93.5	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	104		104		TEQ (Min):	707		
Total PeCDD	448				a. Sample specific estimated detection limit.			
Total HxCDD	4770				b. Estimated maximum possible concentration.			
Total HpCDD	39300				c. Method detection limit.			
Total TCDF	107				d. Lower control limit - upper control limit.			
Total PeCDF	911				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	6110				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	20500							

Analyst: ANP

Approved By: Rose Harrelson 31-Aug-2012 16:32

Sample ID: A3-29					EPA Method 8290			
Client Data		Sample Data			Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-012	Date Received:	10-Aug-12	
Project:		Sample Size:	12.2 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	8-Aug-12	%Solids:	83.2	Date Analyzed DB-5:	29-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	1500							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	ND		0.225	UX	<u>IS</u> 13C-2,3,7,8-TCDD	91.1	40 - 135	
1,2,3,7,8-PeCDD	1.56			J	13C-1,2,3,7,8-PeCDD	112	40 - 135	
1,2,3,4,7,8-HxCDD	3.40				13C-1,2,3,4,7,8-HxCDD	81.7	40 - 135	
1,2,3,6,7,8-HxCDD	6.82				13C-1,2,3,6,7,8-HxCDD	79.1	40 - 135	
1,2,3,7,8,9-HxCDD	6.66				13C-1,2,3,7,8,9-HxCDD	84.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	249				13C-1,2,3,4,6,7,8-HpCDD	98.3	40 - 135	
OCDD	7770			B,EJ	13C-OCDD	95.7	40 - 135	
2,3,7,8-TCDF	0.253			J	13C-2,3,7,8-TCDF	94.8	40 - 135	
1,2,3,7,8-PeCDF	0.243			J	13C-1,2,3,7,8-PeCDF	96.5	40 - 135	
2,3,4,7,8-PeCDF	0.351			J	13C-2,3,4,7,8-PeCDF	90.0	40 - 135	
1,2,3,4,7,8-HxCDF	1.40			J	13C-1,2,3,4,7,8-HxCDF	91.3	40 - 135	
1,2,3,6,7,8-HxCDF	0.675			J	13C-1,2,3,6,7,8-HxCDF	86.8	40 - 135	
2,3,4,6,7,8-HxCDF	1.02			J	13C-2,3,4,6,7,8-HxCDF	89.4	40 - 135	
1,2,3,7,8,9-HxCDF	0.171			J	13C-1,2,3,7,8,9-HxCDF	88.5	40 - 135	
1,2,3,4,6,7,8-HpCDF	14.7				13C-1,2,3,4,6,7,8-HpCDF	91.9	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.31			J	13C-1,2,3,4,7,8,9-HpCDF	95.0	40 - 135	
OCDF	65.5				13C-OCDF	90.5	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	102	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	6.85		8.00		TEQ (Min):	8.71		
Total PeCDD	16.0		16.4					
Total HxCDD	92.0							
Total HpCDD	593							
Total TCDF	5.20		5.48					
Total PeCDF	6.67		6.97					
Total HxCDF	23.4							
Total HpCDF	58.2							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-34

EPA Method 8290

Client Data			Sample Data		Laboratory Data			
Name:	ARCADIS		Matrix:	Soil	Lab Sample:	33933-013	Date Received:	10-Aug-12
Project:			Sample Size:	12.6 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12
Date Collected:	9-Aug-12		%Solids:	80.7	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	31-Aug-12
Time Collected:	0900							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	2.22				<u>IS</u> 13C-2,3,7,8-TCDD	93.1	40 - 135	
1,2,3,7,8-PeCDD	18.5				13C-1,2,3,7,8-PeCDD	113	40 - 135	
1,2,3,4,7,8-HxCDD	58.6				13C-1,2,3,4,7,8-HxCDD	80.7	40 - 135	
1,2,3,6,7,8-HxCDD	167				13C-1,2,3,6,7,8-HxCDD	80.9	40 - 135	
1,2,3,7,8,9-HxCDD	118				13C-1,2,3,7,8,9-HxCDD	78.9	40 - 135	
1,2,3,4,6,7,8-HpCDD	5160			E J	13C-1,2,3,4,6,7,8-HpCDD	102	40 - 135	
OCDD	45800			Ø, E J	13C-OCDD	109	40 - 135	
2,3,7,8-TCDF	3.52				13C-2,3,7,8-TCDF	91.8	40 - 135	
1,2,3,7,8-PeCDF	5.17				13C-1,2,3,7,8-PeCDF	95.7	40 - 135	
2,3,4,7,8-PeCDF	16.7				13C-2,3,4,7,8-PeCDF	92.3	40 - 135	
1,2,3,4,7,8-HxCDF	73.4				13C-1,2,3,4,7,8-HxCDF	89.0	40 - 135	
1,2,3,6,7,8-HxCDF	33.5				13C-1,2,3,6,7,8-HxCDF	84.3	40 - 135	
2,3,4,6,7,8-HxCDF	54.8				13C-2,3,4,6,7,8-HxCDF	87.4	40 - 135	
1,2,3,7,8,9-HxCDF	5.16				13C-1,2,3,7,8,9-HxCDF	87.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	986				13C-1,2,3,4,6,7,8-HpCDF	92.0	40 - 135	
1,2,3,4,7,8,9-HpCDF	76.0				13C-1,2,3,4,7,8,9-HpCDF	95.2	40 - 135	
OCDF	4240			E J	13C-OCDF	93.9	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	108	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	46.8				TEQ (Min):	154		
Total PeCDD	109				a. Sample specific estimated detection limit.			
Total HxCDD	1490				b. Estimated maximum possible concentration.			
Total HpCDD	13000				c. Method detection limit.			
Total TCDF	70.1				d. Lower control limit - upper control limit.			
Total PeCDF	261			P J	e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	1410				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	3660							

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-33

EPA Method 8290

Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-014	Date Received:	10-Aug-12	
Project:		Sample Size:	14.9 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	9-Aug-12	%Solids:	67.8	Date Analyzed DB-5:	30-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	0915							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	3.84				<u>IS</u> 13C-2,3,7,8-TCDD	92.7	40 - 135	
1,2,3,7,8-PeCDD	62.6				13C-1,2,3,7,8-PeCDD	87.4	40 - 135	
1,2,3,4,7,8-HxCDD	199				13C-1,2,3,4,7,8-HxCDD	90.8	40 - 135	
1,2,3,6,7,8-HxCDD	1030				13C-1,2,3,6,7,8-HxCDD	84.7	40 - 135	
1,2,3,7,8,9-HxCDD	360				13C-1,2,3,7,8,9-HxCDD	84.7	40 - 135	
1,2,3,4,6,7,8-HpCDD	43100			D, E J	13C-1,2,3,4,6,7,8-HpCDD	73.1	40 - 135	D
OCDD	487000			D, E J	13C-OCDD	62.8	40 - 135	D
2,3,7,8-TCDF	4.12			B	13C-2,3,7,8-TCDF	93.9	40 - 135	
1,2,3,7,8-PeCDF	12.3				13C-1,2,3,7,8-PeCDF	97.1	40 - 135	
2,3,4,7,8-PeCDF	43.2				13C-2,3,4,7,8-PeCDF	91.4	40 - 135	
1,2,3,4,7,8-HxCDF	273				13C-1,2,3,4,7,8-HxCDF	90.6	40 - 135	
1,2,3,6,7,8-HxCDF	90.9				13C-1,2,3,6,7,8-HxCDF	82.9	40 - 135	
2,3,4,6,7,8-HxCDF	184				13C-2,3,4,6,7,8-HxCDF	87.0	40 - 135	
1,2,3,7,8,9-HxCDF	49.9				13C-1,2,3,7,8,9-HxCDF	88.3	40 - 135	
1,2,3,4,6,7,8-HpCDF	7040			D	13C-1,2,3,4,6,7,8-HpCDF	81.2	40 - 135	D
1,2,3,4,7,8,9-HpCDF	586			D	13C-1,2,3,4,7,8,9-HpCDF	75.3	40 - 135	D
OCDF	41500			D, E J	13C-OCDF	84.3	40 - 135	D
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	96.7	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	102				TEQ (Min):	965		
Total PeCDD	414							
Total HxCDD	5130							
Total HpCDD	82300							
Total TCDF	97.8							
Total PeCDF	652		665					
Total HxCDF	6130							
Total HpCDF	33700							

Analyst: FEB

Approved By: Rose Harrelson 31-Aug-2012 16:32

Sample ID: A1-61					EPA Method 8290			
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	33933-015	Date Received:	10-Aug-12	
Project:		Sample Size:	12.0 g	QC Batch No.:	4619	Date Extracted:	19-Aug-12	
Date Collected:	8-Aug-12	%Solids:	83.9	Date Analyzed DB-5:	29-Aug-12	Dates Analyzed DB-225:	30-Aug-12	
Time Collected:	1140							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	3.60				<u>IS</u> 13C-2,3,7,8-TCDD	92.9	40 - 135	
1,2,3,7,8-PeCDD	22.9				13C-1,2,3,7,8-PeCDD	110	40 - 135	
1,2,3,4,7,8-HxCDD	52.0				13C-1,2,3,4,7,8-HxCDD	86.4	40 - 135	
1,2,3,6,7,8-HxCDD	123				13C-1,2,3,6,7,8-HxCDD	77.2	40 - 135	
1,2,3,7,8,9-HxCDD	80.1				13C-1,2,3,7,8,9-HxCDD	82.3	40 - 135	
1,2,3,4,6,7,8-HpCDD	3120			E J	13C-1,2,3,4,6,7,8-HpCDD	101	40 - 135	
OCDD	38600			B,E J	13C-OCDD	103	40 - 135	
2,3,7,8-TCDF	0.859				13C-2,3,7,8-TCDF	94.6	40 - 135	
1,2,3,7,8-PeCDF	1.94			J	13C-1,2,3,7,8-PeCDF	88.8	40 - 135	
2,3,4,7,8-PeCDF	3.10				13C-2,3,4,7,8-PeCDF	85.2	40 - 135	
1,2,3,4,7,8-HxCDF	22.9				13C-1,2,3,4,7,8-HxCDF	89.2	40 - 135	
1,2,3,6,7,8-HxCDF	7.72				13C-1,2,3,6,7,8-HxCDF	83.5	40 - 135	
2,3,4,6,7,8-HxCDF	11.4				13C-2,3,4,6,7,8-HxCDF	88.1	40 - 135	
1,2,3,7,8,9-HxCDF	2.11			J	13C-1,2,3,7,8,9-HxCDF	89.0	40 - 135	
1,2,3,4,6,7,8-HpCDF	309			J	13C-1,2,3,4,6,7,8-HpCDF	92.3	40 - 135	
1,2,3,4,7,8,9-HpCDF	23.4				13C-1,2,3,4,7,8,9-HpCDF	94.6	40 - 135	
OCDF	2160				13C-OCDF	93.5	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	105	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	99.1				TEQ (Min): 104			
Total PeCDD	361							
Total HxCDD	1380							
Total HpCDD	6090							
Total TCDF	30.8		31.1					
Total PeCDF	68.1		68.4					
Total HxCDF	383							
Total HpCDF	1500			J				

Analyst: MAS

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: A3-25

EPA Method 8290

Client Data			Sample Data		Laboratory Data			
Name:	ARCADIS		Matrix:	Soil	Lab Sample:	33933-006	Date Received:	10-Aug-12
Project:			Sample Size:	13.0 g	QC Batch No.:	4623	Date Extracted:	20-Aug-12
Date Collected:	9-Aug-12		%Solids:	78.5	Date Analyzed DB-5:	24-Aug-12	Date Analyzed DB-225:	NA
Time Collected:	1100							
Analyte	Conc. (pg/g)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	0.361			J	<u>IS</u> 13C-2,3,7,8-TCDD	93.5	40 - 135	
1,2,3,7,8-PeCDD	2.24			J	13C-1,2,3,7,8-PeCDD	89.6	40 - 135	
1,2,3,4,7,8-HxCDD	5.33				13C-1,2,3,4,7,8-HxCDD	75.3	40 - 135	
1,2,3,6,7,8-HxCDD	14.5				13C-1,2,3,6,7,8-HxCDD	77.9	40 - 135	
1,2,3,7,8,9-HxCDD	10.4				13C-1,2,3,7,8,9-HxCDD	74.4	40 - 135	
1,2,3,4,6,7,8-HpCDD	715				13C-1,2,3,4,6,7,8-HpCDD	80.0	40 - 135	
OCDD	34400			EJ	13C-OCDD	102	40 - 135	
2,3,7,8-TCDF	ND		0.233	UX	13C-2,3,7,8-TCDF	89.4	40 - 135	
1,2,3,7,8-PeCDF	0.402			J	13C-1,2,3,7,8-PeCDF	102	40 - 135	
2,3,4,7,8-PeCDF	ND		0.519	UX	13C-2,3,4,7,8-PeCDF	103	40 - 135	
1,2,3,4,7,8-HxCDF	2.57				13C-1,2,3,4,7,8-HxCDF	84.2	40 - 135	
1,2,3,6,7,8-HxCDF	1.16			J	13C-1,2,3,6,7,8-HxCDF	86.6	40 - 135	
2,3,4,6,7,8-HxCDF	2.03			J	13C-2,3,4,6,7,8-HxCDF	85.2	40 - 135	
1,2,3,7,8,9-HxCDF	ND		0.317	UX	13C-1,2,3,7,8,9-HxCDF	82.0	40 - 135	
1,2,3,4,6,7,8-HpCDF	34.9				13C-1,2,3,4,6,7,8-HpCDF	82.0	40 - 135	
1,2,3,4,7,8,9-HpCDF	3.51				13C-1,2,3,4,7,8,9-HpCDF	81.7	40 - 135	
OCDF	147				13C-OCDF	87.4	40 - 135	
					<u>CRS</u> 37Cl-2,3,7,8-TCDD	94.3	40 - 135	
Totals					Toxic Equivalent Quotient (TEQ) Data ^e			
Total TCDD	12.7				TEQ (Min):	24.1		
Total PeCDD	57.9				a. Sample specific estimated detection limit.			
Total HxCDD	239				b. Estimated maximum possible concentration.			
Total HpCDD	2280				c. Method detection limit.			
Total TCDF	3.02				d. Lower control limit - upper control limit.			
Total PeCDF	4.94				e. TEQ based on (2005) World Health Organization Toxic Equivalent Factors (WHO)			
Total HxCDF	54.1				The results are reported in dry weight. The sample size is reported in wet weight.			
Total HpCDF	143							

Analyst: FEB

Approved By: Calvin Tanaka 31-Aug-2012 14:40

Sample ID: EB 8/9/12				EPA Method 8290				
Client Data		Sample Data		Laboratory Data				
Name:	ARCADIS	Matrix:	Aqueous	Lab Sample:	33933-016	Date Received:	10-Aug-12	
Project:		Sample Size:	0.841 L	QC Batch No.:	4616	Date Extracted:	15-Aug-12	
Date Collected:	9-Aug-12			Date Analyzed DB-5:	17-Aug-12	Date Analyzed DB-225:	NA	
Time Collected:	0000							
Analyte	Conc. (pg/L)	DL ^a	EMPC ^b	Qualifiers	Labeled Standard	%R	LCL-UCL ^d	Qualifiers
2,3,7,8-TCDD	ND	0.779			IS 13C-2,3,7,8-TCDD	88.0	40 - 135	
1,2,3,7,8-PeCDD	ND	0.834			13C-1,2,3,7,8-PeCDD	83.1	40 - 135	
1,2,3,4,7,8-HxCDD	ND	0.781			13C-1,2,3,4,7,8-HxCDD	77.4	40 - 135	
1,2,3,6,7,8-HxCDD	ND	0.891			13C-1,2,3,6,7,8-HxCDD	78.4	40 - 135	
1,2,3,7,8,9-HxCDD	ND	0.905			13C-1,2,3,7,8,9-HxCDD	76.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	ND	0.976			13C-1,2,3,4,6,7,8-HpCDD	76.8	40 - 135	
OCDD	2.97			J	13C-OCDD	67.4	40 - 135	
2,3,7,8-TCDF	ND	0.838			13C-2,3,7,8-TCDF	86.5	40 - 135	
1,2,3,7,8-PeCDF	ND	0.498			13C-1,2,3,7,8-PeCDF	106	40 - 135	
2,3,4,7,8-PeCDF	ND	0.613			13C-2,3,4,7,8-PeCDF	87.4	40 - 135	
1,2,3,4,7,8-HxCDF	ND	0.396			13C-1,2,3,4,7,8-HxCDF	82.6	40 - 135	
1,2,3,6,7,8-HxCDF	ND	0.366			13C-1,2,3,6,7,8-HxCDF	86.8	40 - 135	
2,3,4,6,7,8-HxCDF	ND	0.398			13C-2,3,4,6,7,8-HxCDF	88.4	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.569			13C-1,2,3,7,8,9-HxCDF	80.8	40 - 135	
1,2,3,4,6,7,8-HpCDF	ND	0.428			13C-1,2,3,4,6,7,8-HpCDF	74.5	40 - 135	
1,2,3,4,7,8,9-HpCDF	ND	0.537			13C-1,2,3,4,7,8,9-HpCDF	74.0	40 - 135	
OCDF	ND	1.02			13C-OCDF	71.4	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	96.1	40 - 135	
Totals				Toxic Equivalent Quotient (TEQ) Data ^e				
Total TCDD	ND	0.779			TEQ (Min): 0.000891			
Total PeCDD	ND	0.834						
Total HxCDD	ND	0.905						
Total HpCDD	ND	0.976						
Total TCDF	ND	0.838						
Total PeCDF	ND	0.613						
Total HxCDF	ND	0.569						
Total HpCDF	ND	0.537						

Analyst: FEB

Approved By: Calvin Tanaka 31-Aug-2012 14:40



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

1 of 4
Storage Secured
Yes No
Temp _____ °C

Laboratory Project ID: 33933
Storage ID: WR 2

Project I.D.: _____ P.O.#: PA03921212.0000.00002 Sampler: I. STEWART & C. MCLENDRICK (Name)

TAT: (Check One):
Standard: 21 Days
Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGPASS Company ARCADIS Address 11002 EXCELSIOR RD City BAXTER State MINN Zip 56425 Ph# 218-829-4100 Fax# 4100
Relinquished by: (Signature and Printed Name) Claire McLeन्द्रick Date: 8/9/12 Time: 1600 Received by: (Signature and Printed Name) B. Benedict Date: 8/10/12 Time: 0842
Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

Add Analysis(es) Requested

Container(s)

ATTN: _____

Sample ID	Date	Time	Location/Sample Description	Add Analysis(es) Requested																		
				Quantity	Type	Matrix	2376-TCDD	2376-TCDD/TCDF	TCDD/TCDF	2378-TCDD	2378-TCDD/TCDF	TCDD/TCDF	2378-TCDD	2378-TCDD/TCDF	TCDD/TCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	
A1-50	8/9/12	0930		1	G	SD						X										
A1-51	8/9/12	0945		1	G	SD						X										
A3-28	8/9/12	1040		1	G	SD						X										
A3-27	8/9/12	1050		1	G	SD						X										
A3-20	8/9/12	1055		1	G	SD						X										
A3-25	8/9/12	1100		1	G	SD						X										
A3-31	8/9/12	1150		1	G	SD						X										
A3-30	8/9/12	1200		1	G	SD						X										
A1-53	8/9/12	1330		1	G	SD						X										
DUP-3	8/9/12	-		1	G	SD						X										

Special Instructions/Comments: _____

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGPASS
Company: ARCADIS
Address: 11002 EXCELSIOR RD
City: BAXTER State: MINN Zip: 56425
Phone: 218-829-4100 Fax: _____
Email: DAVID.BESSINGPASS@ARCADIS-US.COM
Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
P = PUF, T = MMS Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
O = Other _____



CHAIN OF CUSTODY

2044
FOR LABORATORY USE ONLY
 Storage Secured
 Laboratory Project ID: 33933 Yes No
 Storage ID _____ Temp _____ °C

Project I.D.: _____ P.O.# 80N392102.0000.00002 Sampler: I. STEWART & C. MCKENDRICK
 (Name)

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGTHASS ARCADIS Company ARCADIS Address 10012 EXCELSIOR RD BAXTER City BAXTER State MN Zip 56425 Ph# 218-829-4107 Fax#
 Relinquished by: (Signature and Printed Name) [Signature] Date: 8/11/12 Time: 1100AM Received by: (Signature and Printed Name) [Signature] Date: 8/10/12 Time: 0841
 Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____
 Tracking No.: _____

ATTN: _____

Add Analysis(es) Requested		EPA1613	EPA8290	EPA8280	EPA1668	EPA1614	CARB429										
Container(s)																	
Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29

Sample ID	Date	Time	Location/Sample Description	Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29					
* H1-100	8/11/12	1330		2	G	SD																				
* A3-32	8/11/12	1440		1	G	SD																				
* A3-29	8/11/12	1500		1	G	SD																				
* DUP-1	8/11/12	-		1	G	SD																				
* DUP-2	8/11/12	-		1	G	SD																				
* MS/MSD 1	8/11/12	-		2	G	SD																				
* MS/MSD 2	8/11/12	-		2	G	SD																				
* EB	8/11/12	-		2	A	W																				
* A3-34	8/11/12	0900		1	G	SD																				
* A3-33	8/11/12	0915		1	G	SD																				

Special Instructions/Comments:
 * project 33932
 * project 33933

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGTHASS
 Company: ARCADIS
 Address: 10012 EXCELSIOR RD
 City: BAXTER State: MN Zip: 56425
 Phone: 218-829-4107 Fax: _____
 Email: DAVID.BESSINGTHASS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper, SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum, AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MM5 Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate, O = Other _____



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

Storage Secured
 Yes No
 Storage ID _____ Temp _____ °C

3 of 4
 Laboratory Project ID: 33933

Project I.D.: _____ P.O.# B0039212.0000.0002 Sampler: I. STEWART
C. MICKANDRICK (Name)

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGPASS Company ARCADIS Address 1104 WINDFIELD WAY City EL DORADO HILLS State CA Zip 95762 Ph# _____ Fax# _____
 Relinquished by: (Signature and Printed Name) David Mickandruck Date: 8/11/12 Time: _____ Received by: (Signature and Printed Name) B. Benedict Date: 8/10/12 Time: 0841
 Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106
 Method of Shipment: _____
 Tracking No.: _____

Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	Add Analysis(es) Requested					
																		EPA1613	EPA8290	EPA8280	EPA1668	EPA1614	CARB429

Sample ID	Date	Time	Location/Sample Description
* A1-02	8/8/12	0805	
* A1-50	8/8/12	0820	
* A1-57	8/10/12	0830	
* A1-103	8/8/12	0845	
* A1-52	8/8/12	0920	
* A1-53	8/9/12	0935	
* A1-59	8/8/12	0955	
* A1-54	8/8/12	1040	
* A1-55	8/8/12	1115	
* A1-01	8/8/12	1140	

Special Instructions/Comments:
 * project 33932
 * project 33933

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGPASS
 Company: ARCADIS
 Address: _____
 City: _____ State: _____ Zip: _____
 Phone: _____ Fax: _____
 Email: DAVID.BESSINGPASS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MMS Train, O = Other _____
 *Bottle Preservative Type: T = Thiosulfate, O = Other _____



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

4 of 4
Storage Secured Yes No
Temp _____ °C

Laboratory Project ID: 33933
Storage ID: WR2

TAT: (Check One):
Standard: 21 Days
Rush (surcharge may apply):
 14 days 7 days Specify: _____

Project I.D.: _____ P.O.# BUDWIZ W. 0000. 00002 Sampler: I. STEWART, C. MCKENDRICK
(Name)

Invoice to: Name DAVID BESSINGPASS Company ARCADIS Address 1602 EXCELSIOR RD, BAXTER City MINN State SD Zip 58425 Ph# 218-829-4407 Fax# _____
Relinquished by: (Signature and Printed Name) Claire McKe... Date: 8/9/12 Time: 1:00 Received by: (Signature and Printed Name) B. Benedict Date: 8/10/12 Time: 9:30
Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106
ATTN: _____
Method of Shipment: _____
Tracking No.: _____

Quantity	Type	Matrix	Add Analysis(es) Requested																			
			2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB'S	209 CONGENERS	PBDE	PAH	WHO-29					
2	A	W						X														

Special Instructions/Comments: _____

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGPASS
Company: ARCADIS
Address: _____
City: _____ State: _____ Zip: _____
Phone: _____ Fax: _____
Email: DAVID.BESSINGPASS@ARCADIS-US.COM
Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
AQ = Aqueous, O = Other _____

Container Types: A = 1 Liter Amber, G = Glass Jar
P = PUF, T = MMS Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
O = Other _____

November 19, 2012

WORK PLAN FOR ADDITIONAL SOIL SAMPLING AND PCDD/PCDF ANALYSIS

BEAZER EAST, INC. FORMER KOPPERS WOOD-TREATING SITE CARBONDALE, ILLINOIS

Introduction/Purpose

As a follow-up to the sampling activities conducted in August 2012, and discussions with the United States Environmental Protection Agency (USEPA) during a November 9, 2012 conference call, Beazer East, Inc. (Beazer) has prepared this Work Plan for the collection of additional soil samples from the residential area south of the Former Koppers Wood-Treating Site in Carbondale, Illinois (the Site). The samples will be analyzed for polychlorinated dibenzo-p-dioxins and polychlorinated dibenzofurans (PCDDs/PCDFs).

Scope/Procedures

Soil samples will be collected from a total of 16 locations in the residential area south of the Site (A1-64 through A1-79; Figure 1). As shown on Figure 1, samples will be collected from rights-of-way along North Allman Street, North Robert A. Stalls Avenue, North Pierce Street, and North Wall Street. Consistent with the sampling approach used during the August 2012 sampling event, samples representing the 16 proposed sample locations will each be a composite from five discrete locations near the target sample area. For a given location, each discrete sample will be collected using a stainless-steel trowel and composited into a single sample for laboratory analysis. The five discrete locations will be collected from the surveyed sample location, as well as from four additional locations (5 feet and 10 feet from either side of the surveyed location, parallel to the road). To the extent possible, samples will be collected from areas that do not collect runoff from roads or driveways and are at least 10 feet from potential sources of dioxins (e.g., utility poles, fences, and landscape materials from treated wood). For example, where drainage ditches parallel the road, try to collect samples on the far side of the ditch from the road if accommodated by the right-of-way boundary. All samples will be collected from the 0- to 0.5-foot depth interval.

Soil types/characteristics and descriptions of staining, odors or other noteworthy characteristics will be recorded in a field notebook. Recovered soils will be homogenized prior to placing them into sample containers. Excess soils will be placed back into the holes following sample collection. Each sample location will be staked and surveyed at the central discrete sample location so that they can be accurately depicted on the site plan and re-established in the future, if necessary.

All 16 samples will be submitted to Vista Analytical Laboratory in El Dorado Hills, California for PCDDs/PCDFs analysis via USEPA SW-846 Method 8290. Initially, eight samples (A1-68 through A1-75) will be analyzed on a 21-day turn-around-time. The remaining eight samples (A1-64 through A1-67 and A1-76 through A1-79) will be held at the lab pending the results of the eight initially analyzed samples (see Data Review and Reporting section below for additional details). The hold times for Method 8290 are 30 days from collection to extraction, and 45 days from extraction to analysis. If necessary depending on the timing of a decision following the initial analyses, Beazer will instruct the laboratory to extract the remaining samples before the hold time expires until a decision is made regarding which, if any, of the held samples require analysis.

Table 1 provides additional details on the sample location description, and summarizes the “analyze vs. hold” approach for each sample.

November 19, 2012

Property Access

All of the proposed sample locations are located in public rights-of-way adjacent to roadways. Individual access agreements with adjacent property owners will not be necessary. The City of Carbondale will be contacted to provide a representative to be present during the surveying and sampling activities in the event there are any disputes over ownership of the rights-of-way.

Quality Assurance/Quality Control

Quality assurance/quality control (QA/QC) samples will be collected at the frequencies specified in the Quality Assurance Project Plan (QAPP; ARCADIS, February 2008): one blind duplicate per 10 field samples, one matrix spike/matrix spike duplicate per 20 field samples, one equipment rinse blank per day. Analytical data will be validated in accordance with USEPA National Functional Guidelines for Data Review, as discussed in the QAPP.

Equipment Cleaning and Waste Management

Non-dedicated/non-disposable sampling equipment will be cleaned prior to use at each sample location following procedures outlined in the QAPP (i.e., non-phosphate detergent wash, distilled/deionized water rinse, and triple rinse sequence of solvent followed by distilled/deionized water).

Equipment cleaning fluids will be collected for treatment at the onsite wastewater treatment system (WWTS). Used personal protective equipment, disposable sampling equipment, and other miscellaneous wastes will be placed into a 55-gallon drum and staged at a designated area near the WWTS for subsequent characterization and disposal by Beazer.

Data Review and Reporting

Following receipt of the preliminary laboratory results for the eight initially analyzed samples, Beazer will prepare a figure showing the calculated 2,3,7,8-TCDD Toxic Equivalent (TEQ) concentration for each sample, and participate in a web meeting/conference call with USEPA to discuss the results and mutually agree upon which, if any, of the eight held samples will be released for analysis.

Following receipt of final data reports from the lab, the analytical data will be validated, and final data tables and sample location maps will be prepared for submittal to the USEPA.

Schedule

The field work will be conducted in late November or early December, pending USEPA approval of this Work Plan and availability of the survey and sampling crews. The field activities are anticipated to require approximately three days to complete. The web meeting/conference call with USEPA to review and discuss the preliminary results of the eight initially analyzed samples is anticipated to be held within approximately three days following receipt of the preliminary results from the lab. Because laboratory results may be expected during a holiday period, Beazer will provide as much notice as possible of the target date for scheduling the web meeting/conference call. It will be important to hold the meeting in a timely manner and determine which of the held samples will be analyzed so that the laboratory can complete the work within the method-specified holding times. To account for the data validation timeframe, final data summary tables and sample location maps will be submitted to the USEPA within approximately six weeks following receipt of all associated laboratory analytical data.

TABLE 1
SAMPLE LOCATION DESCRIPTIONS AND ANALYTICAL APPROACH


Beazer East, Inc.
Former Koppers Wood-Treating Site
Carbondale, Illinois

Sample ID	Location Description	Analyze or Hold ¹
A1-64	Right-of-way on east side of N Wall St, south of intersection with E Knight St	Hold
A1-65	Right-of-way on east side of N Wall St	Hold
A1-66	Right-of-way on east side of N Pierce St	Hold
A1-67	Right-of-way on east side of N Robert A Stalls Ave	Hold
A1-68	Right-of-way on east side of N Allman St	Analyze
A1-69	Right-of-way on east side of N Robert A Stalls Ave	Analyze
A1-70	Right-of-way on east side of N Pierce St	Analyze
A1-71	Right-of-way on east side of N Wall St, south of intersection with E Jenkins St	Analyze
A1-72	Right-of-way on east side of N Wall St	Analyze
A1-73	Right-of-way on east side of N Pierce St	Analyze
A1-74	Right-of-way on east side of N Robert A Stalls Ave	Analyze
A1-75	Right-of-way on east side of N Allman St	Analyze
A1-76	Right-of-way on east side of N Allman St, north of intersection with E Burke St	Hold
A1-77	Right-of-way on east side of N Robert A Stalls Ave, north of intersection with E Burke St	Hold
A1-78	Right-of-way on east side of N Pierce St, north of intersection with E Burke St	Hold
A1-79	Right-of-way on east side of N Wall St, north of intersection with E Burke St	Hold

Notes:

1. Eight samples will be held at the lab pending the results of the eight initially analyzed samples, and discussions between Beazer and USEPA.
2. Samples designated for analysis will be analyzed for PCDDs/PCDFs via USEPA Method 8290.

CITY: CARBONDALE, ILLINOIS; PROJECT: BEAZER EAST, INC. FORMER KOPPER'S WOOD TREATING SITE; LOCATION: CARBONDALE, ILLINOIS; DATE: 11/15/2012; DRAWN BY: LYDIA FORAMER, LYDIA FORAMER; CHECKED BY: LYDIA FORAMER; SCALE: AS SHOWN; SHEET: 1 OF 1; PROJECT: BEAZER EAST, INC. FORMER KOPPER'S WOOD TREATING SITE; LOCATION: CARBONDALE, ILLINOIS; DATE: 11/15/2012; DRAWN BY: LYDIA FORAMER, LYDIA FORAMER; CHECKED BY: LYDIA FORAMER; SCALE: AS SHOWN; SHEET: 1 OF 1.



- LEGEND:**
- EDGE OF WATER
 - DRAINAGE DITCH AND DIRECTION OF FLOW
 - PROPERTY BOUNDARY (SEE NOTE 2)
 - PARCEL BOUNDARY
 - FENCELINE
 - EXISTING CONTOUR LINE
 - FORMER PROCESS AREA SURFACE COVER
 - SOIL REMOVAL AREA (SOIL/DEBRIS PILES AND SURFICIAL ASPHALT-LIKE MATERIALS)
 - PORTIONS OF SOUTHERN DRAINAGE DITCHES THAT HAVE BEEN FILLED IN PRIOR TO OR DURING SURFACE COVER CONSTRUCTION OR REMOVAL OF SOIL AND DEBRIS PILES.
 - 2008 RESIDENTIAL SAMPLE LOCATIONS (USEPA)
 - 2005-2010 SAMPLE LOCATIONS (BEAZER)
 - 2008 RESIDENTIAL SAMPLE LOCATIONS (CITY OF CARBONDALE)
 - AUGUST 2012 GRAB SAMPLE LOCATION
 - AUGUST 2012 COMPOSITE SAMPLE LOCATION
 - TSSD-TSS CONCENTRATION (ppt) AND SAMPLE DEPTH INTERVAL
 - PROPOSED COMPOSITE SAMPLE LOCATION (ANALYZE)
 - PROPOSED COMPOSITE SAMPLE LOCATION (HOLD)

- NOTES:**
1. SITE FEATURES AND TOPOGRAPHY OBTAINED FROM PHOTOGRAMMETRIC MAPPING PROVIDED BY LOCKWOOD MAPPING COMPANY IN SEPTEMBER 2001 AND SURVEY DATA PROVIDED BY ENGINEERING DESIGN SOURCE, INC. IN JANUARY 2004, AND BASED ON AERIAL PHOTOGRAPHY PROVIDED BY LOCKWOOD MAPPING, INC. TAKEN ON NOVEMBER 22, 1998 AT AN APPROXIMATE SCALE OF 1"=300'. TOPOGRAPHY IN THE EASTERN SOUTHERN DRAINAGE DITCHES AREA BASED ON TOPOGRAPHIC FIELD SURVEY CONDUCTED IN AUGUST 2007.
 2. PROPERTY BOUNDARY IS APPROXIMATE; OBTAINED FROM A COMBINATION OF SITE SURVEY DATA, HISTORICAL MAPS AND TAX MAPS.
 3. THE 2008 RESIDENTIAL SAMPLE LOCATIONS ARE APPROXIMATE.
 4. AERIAL IMAGE OBTAINED FROM GOOGLE EARTH AND DATED APRIL 2, 2012.



BEAZER EAST, INC.
FORMER KOPPER'S WOOD TREATING SITE
CARBONDALE, ILLINOIS

PROPOSED SAMPLE LOCATIONS

FIGURE
1

Beazer

BEAZER EAST, INC. C/O THREE RIVERS MANAGEMENT, INC.
MANOR OAK ONE, SUITE 200, 1910 COCHRAN ROAD, PITTSBURGH, PA 15220

February 19, 2013

Ms. Carolyn Bury
U.S. Environmental Protection Agency, Region V
77 West Jackson Boulevard
Mail Code DE-9J
Chicago, IL 60604-3590

Re: Former Koppers Wood-Treating Site – Carbondale, Illinois
November 2012 Dioxin Sampling Final/Validated Data Submittal

Dear Ms. Bury:

In accordance with the November 19, 2012 *Work Plan for Additional Soil Sampling and PCDD/PCDF Analysis* (Work Plan), which was approved by the USEPA on November 20, 2012, Beazer conducted sampling in the residential area south of the Former Koppers Wood-Treating Site in Carbondale, Illinois on November 27 and 28, 2012. The purpose of this letter is to transmit the final/validated laboratory analytical data associated with the November 2012 sampling to the USEPA. The following are attached to this letter:

- Attachment 1 – Validated Analytical Data Summary Table
- Attachment 2 – Sample Location Maps
- Attachment 3 – Data Validation Reports (includes validated laboratory analytical data sheets)

As discussed in the Work Plan, a total of 16 samples were collected – eight of the 16 were initially analyzed for PCDDs/PCDFs, and the other eight were held at the laboratory. Based on discussions with USEPA during a December 18, 2012 conference call, four of the initially held samples were released for PCDD/PCDF analysis. The results for all 12 of the analyzed samples are reported herein.

Please feel contact me at 412-208-8867 if you have any questions or comments regarding this submittal.

Sincerely,



Michael Slenska, P.E.
Senior Environmental Manager

Enclosure

cc: James Moore, IEPA
Jeffrey Holden, ARCADIS
Paul Anderson, ARCADIS
David Bessingpas, ARCADIS

Writer's Direct Dial: 412/208-8867

Attachment 1

Validated Analytical Data
Summary Table

TABLE 1
VALIDATED ANALYTICAL DATA SUMMARY - NOV. 2012 SAMPLES

FORMER KOPPERS WOOD-TREATING SITE
CARBONDALE, ILLINOIS

Sample ID: Depth (ft bgs): Sample Date:	Units	A1-64 0 - 0.5 11/27/12	A1-65 0 - 0.5 11/27/12	A1-66 0 - 0.5 11/28/12	A1-67 0 - 0.5 11/28/12	A1-68 0 - 0.5 11/27/12	A1-69 0 - 0.5 11/27/12	A1-70 0 - 0.5 11/27/12	A1-71 0 - 0.5 11/27/12	A1-72 0 - 0.5 11/27/12	A1-73 0 - 0.5 11/27/12	A1-74 0 - 0.5 11/27/12	A1-75 0 - 0.5 11/27/12
PCDDs/PCDFs													
1,2,3,4,6,7,8-HpCDD	pg/g	344	358	1,530	5,010 EJ	296 [317]	205	897	653	269	773 [1,160]	316	817
1,2,3,4,6,7,8-HpCDF	pg/g	25.8	41.3	189 J	468	24.1 [26.5]	19.7	254	82.8	19.4	130 [186]	30.6	62.4
1,2,3,4,7,8,9-HpCDF	pg/g	1.88 J	3.13	13.1	29.3	1.88 J [1.84 J]	1.42 J	26.5	5.77	1.39 J	9.45 [14.6]	2.21 J	4.42
1,2,3,4,7,8-HxCDD	pg/g	2.88	3.52	11.5	31.4	3.31 [3.34]	2.15 J	8.26	7.01	2.77 J	9.72 [12.4]	3.19	9.48
1,2,3,4,7,8-HxCDF	pg/g	1.48 J	1.93 J	7.81	7.87	1.51 J [1.46 J]	1.16 J	11.7	3.85	0.844 J	5.26 [6.94]	1.98 J	2.32 J
1,2,3,6,7,8-HxCDD	pg/g	7.22	10.1	44.5	95.0	8.83 [10.7]	5.83	29.7	17.9	6.08	24.1 [30.8]	7.64	20.8
1,2,3,6,7,8-HxCDF	pg/g	1.09 J	1.42 J	5.86	5.54	1.26 J [1.12 UX]	0.808 UX	7.16	3.19	0.685 UX	5.98 [7.50]	1.65 J	2.12 J
1,2,3,7,8,9-HxCDD	pg/g	6.96	8.17	27.1	79.3	8.04 [9.54]	5.35	21.0	16.4	6.66	23.7 [29.5]	6.97	33.7
1,2,3,7,8,9-HxCDF	pg/g	0.139 J	0.193 J	0.745 J	0.737 J	0.483 U [0.505 U]	0.390 U	1.63 J	0.275 J	0.316 U	0.984 U [1.59 J]	0.375 U	0.277 U
1,2,3,7,8-PeCDD	pg/g	1.64 J	2.04 J	4.85	10.5	2.06 J [2.56 J]	1.53 J	4.04	4.16	1.22 UX	6.58 [6.47]	2.03 J	8.18
1,2,3,7,8-PeCDF	pg/g	0.419 J	0.336 J	2.29 J	0.807 J	0.453 J [0.395 J]	0.429 J	0.721 J	1.03 J	0.235 U	1.14 J [1.11 J]	0.709 J	0.682 J
2,3,4,6,7,8-HxCDF	pg/g	1.76 J	2.32 J	9.08	11.1	2.12 J [2.21 J]	1.24 J	14.3	5.05	1.18 J	8.06 [10.7]	2.17 J	3.58
2,3,4,7,8-PeCDF	pg/g	0.524 J	0.778 J	3.86 J	1.58 J	1.04 J [1.03 J]	0.654 J	0.609 J	2.48 J	0.190 UX	1.38 J [1.54 J]	1.00 J	0.568 J
2,3,7,8-TCDD	pg/g	0.301 J	0.269 UX	0.870	0.782	0.364 J [0.372 J]	0.316 UX	0.329 UX	0.561 J	0.185 UX	0.667 [0.579]	0.259 J	1.25
2,3,7,8-TCDF	pg/g	0.652	0.408 J	1.65	0.479 J	0.331 J [0.287 J]	0.555 J	0.336 J	1.22	0.157 J	0.627 [0.769]	0.821	0.760
OCDD	pg/g	17,700 EJ	12,700 EJ	30,900 EJ	170,000 DEJ	10,900 EJ [11,200 EJ]	9,870 EJ	19,900 EJ	24,000 EJ	20,000 EJ	21,500 EJ [26,800 EJ]	12,400 EJ	21,000 EJ
OCDF	pg/g	112	169	718	3,970 J	82.3 [88.8]	60.9	576	319	78.7	450 [871]	107	340
Total HpCDD	pg/g	759	832	2,610	8,240	583 [656]	439	1,450	1,570	588	1,480 [2,150]	709	1,730
Total HpCDF	pg/g	88.7	138	639	2,250	82.7 [80.6]	58.5	849	273	62.4	397 [633]	97.7	227
Total HxCDD	pg/g	75.2	89.8	257	601	73.5 [84.3]	61.3	157	162	57.5	208 [274]	81.9	204
Total HxCDF	pg/g	31.5	47.4	170	327	38.1 [37.9]	19.3	281	91.3	20.4	139 [205]	36.4	64.4
Total PeCDD	pg/g	18.4	17.9	36.3	52.5	13.6 [16.5]	15.9	21.9	34.2	9.91	36.2 [47.1]	16.4	37.4
Total PeCDF	pg/g	13.3	14.8	52.9	34.4	22.3 [19.6]	9.72	25.7	38.2	4.96	40.7 [58.5]	19.7	40.6
Total TCDD	pg/g	9.13	5.82	7.00	4.51	2.11 [2.33]	3.73	1.46	12.2	1.25	7.27 [9.10]	1.87	7.82
Total TCDF	pg/g	9.56	8.38	30.5	9.56	9.05 [6.87]	7.12	2.86	27.0	1.78	16.9 [20.7]	16.1	16.3
2,3,7,8-TCDD TEQ	pg/g	13.4	13.0	44.6	142	11.8 [12.8]	8.61	31.6	25.7	10.7	31.1 [39.5]	12.3	32.1

Notes:

1. All 12 samples were composites of five discrete soil sample locations.

Definitions:

PCDDs/PCDFs = polychlorinated dibenzo-p-dioxins/polychlorinated dibenzofurans

pg/g = picograms per gram, or parts per trillion (ppt)

ft bgs = feet below ground surface

TEQ = Toxicity Equivalent, calculated using 2005 World Health Organization (WHO) Toxicity Equivalent Factors (TEFs)

[] = analytical result for duplicate sample

Data Qualifiers:

D = result based on analysis of diluted sample

E = the amount detected is above the High Calibration Limit

J = the amount detected is below the Low Calibration Limit; or estimated value based on data validation

U = compound not detected; reported value is the sample specific estimated detection limit


UX = non-detect; reported value is the estimated maximum possible concentration

Attachment 2

Sample Location Maps

CITY: BRYANBURG DRAWING: ENVIRONMENTAL SERVICES ENGINEERING ARCHITECTURE PLLC HOLDEN THE J HOLDEN LYNX DWG OFF-PROJ GENREV: 04/03/2013 12:04:52 DATE: 04/03/2013 11:14 AM ACADIVER: 15, 19, 20 LAYOUT: 2 DATE: 04/03/2013 11:14 AM CADUSER: 15, 19, 20 PLOTTER: 04/03/2013 11:14 AM BY: FORAKER, LYDIA

000-00-14 (500' DIAGONAL OF 000-00-10) 1.67 @ - 0.07 - 2013
 000-00-15 (500' DIAGONAL OF 000-00-10) 1.67 @ - 0.07 - 2013
 000-00-16 (500' DIAGONAL OF 000-00-10) 1.67 @ - 0.07 - 2013
 000-00-17 (500' DIAGONAL OF 000-00-10) 1.67 @ - 0.07 - 2013
 000-00-18 (500' DIAGONAL OF 000-00-10) 1.67 @ - 0.07 - 2013



- LEGEND:
- EDGE OF WATER
 - DRAINAGE DITCH AND DIRECTION OF FLOW
 - APPROXIMATE SOUTHERN DRAINAGE DITCH FLOW PATH DOWNSTREAM OF DEFINED CHANNEL
 - - - - - PROPERTY BOUNDARY (SEE NOTE 2)
 - - - - - RESIDENTIAL PROPERTY BOUNDARY
 - x - x - FENCELINE
 - - - - - EXISTING CONTOUR LINE
 - FORMER PROCESS AREA SURFACE COVER
 - SOIL REMOVAL AREA (SOIL, DEBRIS PILES AND SURFICIAL ASPHALT-LIKE MATERIALS)
 - PORTIONS OF SOUTHERN DRAINAGE DITCHES THAT HAVE BEEN FILLED IN PRIOR TO OR DURING SURFACE COVER CONSTRUCTION OR REMOVAL OF SOIL AND DEBRIS PILES.
 - MARCH 2008 SED. SAMPLE LOCATION
 - FLOODPLAIN SOIL SAMPLE LOCATION
 - DECEMBER 2009 SAMPLE LOCATION
 - MARCH 2010 SAMPLE LOCATION
 - SEDIMENT SAMPLING LOCATION
 - SCWF SEDIMENT SAMPLE LOCATION
 - ▲ AUGUST 2012 GRAB SAMPLE LOCATION
 - AUGUST 2012 COMPOSITE SAMPLE LOCATION
 - NOVEMBER 2012 COMPOSITE SAMPLE LOCATION
 - TDD-TEQ CONCENTRATION (ppb) AND SAMPLE DEPTH INTERVAL

- NOTES:
1. SITE FEATURES AND TOPOGRAPHY OBTAINED FROM PHOTOGRAMMETRIC MAPPING PROVIDED BY LOCKWOOD MAPPING COMPANY IN SEPTEMBER 2001 AND SURVEY DATA PROVIDED BY ENGINEERING DESIGN SOURCE, INC. IN JANUARY 2004, AND BASED ON AERIAL PHOTOGRAPHY PROVIDED BY LOCKWOOD MAPPING, INC. TAKEN ON NOVEMBER 22, 1996 AT AN APPROXIMATE SCALE OF 1"=300'. TOPOGRAPHY IN THE EASTERN SOUTHERN DRAINAGE DITCHES AREA BASED ON TOPOGRAPHIC FIELD SURVEY CONDUCTED IN AUGUST 2007.
 2. PROPERTY BOUNDARY IS APPROXIMATE, OBTAINED FROM A COMBINATION OF SITE SURVEY DATA, HISTORICAL MAPS AND TAX MAPS.
 3. THIS FIGURE SHOWS ALL SAMPLE LOCATIONS WHERE DIURONS/PURANS HAVE BEEN ANALYZED, INCLUDING SOME LOCATIONS THAT HAVE SINCE BEEN REMOVED OR COVERED AS PART OF REMEDIATION ACTIVITIES.

BEAZER EAST, INC.
 FORMER KOPPERS WOOD TREATING SITE
 CARBONDALE, ILLINOIS

SUMMARY OF TDD-TEQ CONCENTRATIONS




FIGURE 2

Attachment 3

Data Validation Reports
(includes validated laboratory
data sheets)

Beazer East Inc.

Former Koppers Wood-Treating Site

Data Review

CARBONDALE, ILLINOIS

Polychlorinated Dibenzo-Dioxins and Polychlorinated
Dibenzo-Furans (PCDDs/PCDFs) Analyses

SDG #: 2110011

Analyses Performed By:
Vista Analytical Laboratory
El Dorado Hills, California

Report #: 18268R
Review Level: Tier III
Project: B0039275.0000.00003

SUMMARY

This data quality assessment summarizes the review of Sample Delivery Group (SDG) # 2110011 for samples collected in association with the Beazer East Inc. Former Koppers Wood-Treating site. The review was conducted as a Tier III evaluation and included review of data package completeness. Only analytical data associated with constituents of concern were reviewed for this validation. Field documentation was not included in this review. Included with this assessment are the validation annotated sample result sheets, and chain of custody. Analyses were performed on the following samples:

Sample ID	Lab ID	Matrix	Sample Collection Date	Parent Sample	Analysis				
					VOC	SVOC	PCDDs/ PCDFs	MET	MISC
A1-68 (0-0.5')	2110011-01	Soil	11/27/2012				X		
DUP-1	2110011-02	Soil	11/27/2012	A1-68 (0-0.5')			X		
A1-75 (0-0.5')	2110011-03	Soil	11/27/2012				X		
A1-69 (0-0.5')	2110011-04	Soil	11/27/2012				X		
A1-74 (0-0.5')	2110011-05	Soil	11/27/2012				X		
A1-70 (0-0.5')	2110011-06	Soil	11/27/2012				X		
A1-73 (0-0.5')	2110011-07	Soil	11/27/2012				X		
A1-71 (0-0.5')	2110011-08	Soil	11/27/2012				X		
A1-72 (0-0.5')	2110011-09	Soil	11/27/2012				X		
EB 112712	2110011-10	Water	11/27/2012				X		

Note: Soil sample results were reported on a dry weight basis.

Sample location A1-73 (0-0.5') is the parent sample of field duplicate sample DUP 2 which is included in SDG 2110012 (data validation report 19269R); the field duplicate sample results were evaluated within this data validation report.

ANALYTICAL DATA PACKAGE DOCUMENTATION

The table below is the evaluation of the data package completeness.

Items Reviewed	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample receipt condition		X		X	
2. Requested analyses and sample results		X		X	
3. Master tracking list		X		X	
4. Methods of analysis		X		X	
5. Reporting limits		X		X	
6. Sample collection date		X		X	
7. Laboratory sample received date		X		X	
8. Sample preservation verification (as applicable)		X		X	
9. Sample preparation/extraction/analysis dates		X		X	
10. Fully executed Chain-of-Custody (COC) form		X		X	
11. Narrative summary of QA or sample problems provided		X		X	
12. Data Package Completeness and Compliance		X		X	

QA - Quality Assurance

ORGANIC ANALYSIS INTRODUCTION

Analyses were performed according to United States Environmental Protection Agency (USEPA) SW-846 Method 8290 as referenced in NYSDEC-ASP. Data were reviewed in accordance with USEPA National Functional Guidelines of October 1999 and USEPA Region II SOP associated with USEPA SW-846 Method 8290 Validating Polychlorinated Dibenzo-Dioxins and Polychlorinated Dibenzo-Furans by High Resolution GC/MS (SOP HW-19 Revision 1, October 2006).

The data review process is an evaluation of data on a technical basis rather than a determination of contract compliance. As such, the standards against which the data are being weighed may differ from those specified in the analytical method. It is assumed that the data package represents the best efforts of the laboratory and had already been subjected to adequate and sufficient quality review prior to submission.

During the review process, laboratory qualified and unqualified data are verified against the supporting documentation. Based on this evaluation, qualifier codes may be added, deleted, or modified by the data reviewer. Results are qualified with the following codes in accordance with USEPA National Functional Guidelines:

- Concentration (C) Qualifiers
 - U The compound was analyzed for but not detected. The associated value is the compound quantitation limit.
 - B The compound has been found in the sample as well as its associated blank, its presence in the sample may be suspect.
- Quantitation (Q) Qualifiers
 - E The compound was quantitated above the calibration range.
 - D Concentration is based on a diluted sample analysis.
- Validation Qualifiers
 - J The compound was positively identified; however, the associated numerical value is an estimated concentration only.
 - UJ The compound was not detected above the reported sample quantitation limit. However, the reported limit is approximate and may or may not represent the actual limit of quantitation.
 - JN The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification. The associated numerical value is an estimated concentration only.
 - UB Compound considered non-detect at the listed value due to associated blank contamination.
 - N The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification.
 - R The sample results are rejected as unusable. The compound may or may not be present in the sample.

Two facts should be noted by all data users. First, the "R" flag means that the associated value is unusable. In other words, due to significant quality control (QC) problems, the analysis is invalid and

provides no information as to whether the compound is present or not. "R" values should not appear on data tables because they cannot be relied upon, even as a last resort. The second fact to keep in mind is that no compound concentration, even if it has passed all QC tests, is guaranteed to be accurate. Strict QC serves to increase confidence in data but any value potentially contains error.

POLYCHLORINATED DIBENZODIOXINS AND POLYCHLORINATED DIBENZOFURANS (PCDD/PCDF) ANALYSES

1. Holding Times

The specified holding times for the following methods are presented in the following table.

Method	Matrix	Holding Time	Preservation
SW-846 8290	Water	30 days from collection to extraction and 45 days from extraction to analysis	Cool to 4±2 °C
	Soil	30 days from collection to extraction and 45 days from extraction to analysis	Cool to 4±2 °C

All samples were extracted and analyzed within the specified holding time criteria.

2. Blank Contamination

Quality assurance (QA) blanks (i.e. laboratory method blanks and equipment rinse blanks) are prepared to identify any contamination which may have been introduced into the samples during sample preparation or field activity. Method blanks measure laboratory contamination. Rinse blanks measure contamination of samples during field operations.

A blank action level (BAL) of five times the concentration of a detected compound in an associated blank is calculated for QA blanks containing concentrations greater than the method detection limit (MDL). The BAL is compared to the associated sample results to determine the appropriate qualification of the sample results, if needed.

Target compounds were not detected above the MDL in the associated laboratory method blank; therefore detected sample results were not associated with blank contamination.

3. Mass Spectrometer Tuning

Mass spectrometer performance including instrument sensitivity and mass resolution were acceptable.

Overall system performance and gas chromatographic column resolution were acceptable.

4. Calibration

Satisfactory instrument calibration is established to insure that the instrument is capable of producing acceptable quantitative data. An initial calibration demonstrates that the instrument is capable of acceptable performance at the beginning of an experimental sequence. The continuing calibration verifies that the instrument daily performance is satisfactory.

4.1 Initial Calibration

All compounds associated with the initial calibration standards must exhibit signal-to-noise ratios (S/N) of at least 2.5, isotopic ratios within the limits listed in table eight of the method, and percent relative standard deviations (%RSDs) of the relative response factors (RRFs) less than 20% for the labeled standards and less than 30% for the target compounds.

4.2 Continuing Calibration

Instrument performance must be verified at 12 hour periods after successful tune verifications. All compounds associated with the continuing calibration standard must exhibit S/N of at least 2.5, isotopic ratios within the limits listed in table eight of the method, and percent differences (%D) of the RRFs less than 30% for the labeled standards and less than 20% for the target compounds..

All initial and continuing calibration criteria were within the control limits.

5. Injection Internal Standard Performance

Injection internal standards are added to all extracts prior to instrumental analysis. The injection internal standard performance criteria insure that the GC/MS sensitivity and response are stable during every sample analysis. The criteria require the injection internal standard compounds exhibit a signal-to-noise (S/N) ratio of at least 10 and elute within \pm fifteen seconds of the retention times (RTs) established during calibration. The acceptance criteria also specify that each injection internal standard exhibit a ratio of the two identifying masses (m/z) within the method specified limits.

All injection internal standard S/N, RT, and m/z ratios were within established limits.

6. Surrogate Internal Standard Compounds

All field samples, blanks, LCS, and MS/MSD are spiked with surrogate internal standard compounds prior to sample preparation to evaluate overall laboratory performance and efficiency of the analytical technique. The acceptance criteria require that the surrogate internal standard compounds exhibit a signal-to-noise (S/N) ratio of at least 10 and elute within \pm fifteen seconds of the retention times (RTs) established during calibration. The acceptance criteria also specify that each surrogate internal standard exhibit a calculated recovery and a ratio of the two identifying masses (m/z) within the method specified limits.

All samples exhibited surrogate internal standard acceptance criteria within the control limits.

7. Clean-up Recovery Surrogate Performance

All field samples, blanks, LCS, and MS/MSD are spiked with recovery surrogates prior to extract clean-up. Recovery surrogate acceptance criteria require that their calculated recoveries, S/N, m/z ratios, and relative retention times (RRTs) be within the method-specified acceptance limits.

All recovery surrogate recoveries S/N, m/z ratios, and RRTs were within the control limits.

8. Matrix Spike/Matrix Spike Duplicate (MS/MSD) Analysis

MS/MSD data are used to assess the precision and accuracy of the analytical method. The compounds used to perform the (optional) MS/MSD analysis should exhibit recoveries within the method-specified acceptance limits of 80-120%. The relative percent difference (RPD) between the MS and MSD results should be within the laboratory-established acceptance limits.

Note: The MS/MSD recovery control limits do not apply for MS/MSD performed on sample locations where the compound concentration detected in the parent sample exceeds the MS/MSD concentration by a factor of four or greater. Sample results associated with MS/MSD exceedances where the parent samples are not site-specific are not qualified.

Sample location A1-69(0-0.5') was used for the MS/MSD analysis. All compounds associated with the MS/MSD analyses exhibited acceptable recoveries and RPDs between the MS and MSD results.

9. Ongoing Precision and Recovery (OPR) Sample Analysis

The OPR analysis is used to assess the precision and accuracy of the analytical method independent of matrix interferences. The compounds associated with the OPR analysis must exhibit a percent recovery within the method-specified acceptance limits.

All compounds associated with the OPR analysis exhibited recoveries within the control limits.

10. Field Duplicate Sample Analysis

Field duplicate sample analysis is used to assess the precision of the field sampling procedures and analytical method. A control limit of 50% for water matrices and 100% for soil matrices is applied to the RPD between the parent sample and the field duplicate. In the instance when the parent and/or duplicate sample concentrations are less than or equal to five times the RL, a control limit of two times the RL is applied for water matrices or three times the RL is applied for soil matrices.

Results (in pg/g) for the field duplicate samples are summarized in the following table.

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
A1-68 (0-0.5') / DUP-1	2,3,7,8-TCDD	0.364 J	0.372 J	2.2 %
	1,2,3,7,8-PeCDD	2.06 J	2.56 J	21.6 %
	1,2,3,4,7,8-HxCDD	3.31	3.34	0.9 %
	1,2,3,6,7,8-HxCDD	8.83	10.7	19.2 %
	1,2,3,7,8,9-HxCDD	8.04	9.54	17.1 %
	1,2,3,4,6,7,8-HpCDD	296	317	6.9 %
	OCDD	10900 E	11200 E	2.7 %
	2,3,7,8-TCDF	0.331 J	0.287 J	14.2 %
	1,2,3,7,8-PeCDF	0.453 J	0.395 J	13.7 %
	2,3,4,7,8-PeCDF	1.04 J	1.03 J	1.0 %
	1,2,3,4,7,8-HxCDF	1.51 J	1.46 J	3.4 %
	1,2,3,6,7,8-HxCDF	1.26 J	1.12 U	AC
	2,3,4,6,7,8-HxCDF	2.12 J	2.21 J	4.2 %
	1,2,3,4,6,7,8-HpCDF	24.1	26.5	9.5 %
	1,2,3,4,7,8,9-HpCDF	1.88 J	1.84 J	2.2 %
	OCDF	82.3	88.8	7.6 %
	Total TCDD	2.11	2.33	9.9 %
	Total PeCDD	13.6	16.5	19.3 %
	Total HxCDD	73.5	84.3	13.7 %
	Total HpCDD	583	656	11.8 %
Total TCDF	9.05	6.87	27.4 %	

Sample ID/Duplicate ID	Compound	Sample Result	Duplicate Result	RPD
A1-68 (0-0.5') / DUP-1	Total PeCDF	22.3	19.6	12.9 %
	Total HxCDF	38.1	37.9	0.5 %
	Total HpCDF	82.7	80.6	2.6 %
	TEQ	11.8	12.8	8.1 %
A1-73 (0-0.5') / DUP 2	2,3,7,8-TCDD	0.667	0.579	14.1 %
	1,2,3,7,8-PeCDD	6.58	6.47	1.7 %
	1,2,3,4,7,8-HxCDD	9.72	12.4	24.2 %
	1,2,3,6,7,8-HxCDD	24.1	30.8	24.4 %
	1,2,3,7,8,9-HxCDD	23.7	29.5	21.8 %
	1,2,3,4,6,7,8-HpCDD	773	1160	40.0 %
	OCDD	21500 E	26800 E	21.9 %
	2,3,7,8-TCDF	0.627	0.769	20.3 %
	1,2,3,7,8-PeCDF	1.14 J	1.11 J	2.7 %
	2,3,4,7,8-PeCDF	1.38 J	1.54 J	11.0 %
	1,2,3,4,7,8-HxCDF	5.26	6.94	27.5 %
	1,2,3,6,7,8-HxCDF	5.98	7.50	22.6 %
	2,3,4,6,7,8-HxCDF	8.06	10.7	28.1 %
	1,2,3,7,8,9-HxCDF	0.984 U	1.59 J	AC
	1,2,3,4,6,7,8-HpCDF	130	186	35.4 %
	1,2,3,4,7,8,9-HpCDF	9.45	14.6	42.8 %
	OCDF	450	871	63.7 %
	Total TCDD	7.27	9.10	22.4 %
	Total PeCDD	36.2	47.1	26.2 %
	Total HxCDD	208	274	27.4 %
	Total HpCDD	1480	2150	36.9 %
	Total TCDF	16.9	20.7	20.2 %
	Total PeCDF	40.7	58.5	35.9 %
	Total HxCDF	139	205	38.4 %
Total HpCDF	397	633	45.8 %	
TEQ	31.1	39.5	23.8 %	

AC Acceptable
J Estimated (result is < RL)
U Not detected

The field duplicate sample results are acceptable.

11. Compound Identification

PCDD/PCDF compounds are identified by using the compound's ion abundance ratios, signal-to-noise

values, and relative retention times.

An estimated maximum possible concentration (EMPC) designation is given to compounds which have signals eluting within the established retention time window which would, if positively identified, be greater than the detection limit. The signals do not, however, meet the ion abundance ratio criteria and therefore cannot be identified as the compound of interest. The EMPC value is the estimated concentration of the interferant quantitated "as the compound of interest". This value should be considered an elevated detection limit based on potential compound identification and quantitation interference. The "UX" qualifier has been added to the following sample results (in pg/g) to indicate the elevated detection limit as EMPC.

Sample ID	Compound	Laboratory Result	Reported Result
DUP-1	1,2,3,6,7,8-HxCDF	1.12 EMPC	1.12 UX
A1-69 (0-0.5')	2,3,7,8-TCDD	0.316 EMPC	0.316 UX
	1,2,3,6,7,8-HxCDF	0.808 EMPC	0.808 UX
A1-70 (0-0.5')	2,3,7,8-TCDD	0.329 EMPC	0.329 UX
A1-72 (0-0.5')	2,3,7,8-TCDD	0.185 EMPC	0.185 UX
	1,2,3,7,8-PeCDD	1.22 EMPC	1.22 UX
	2,3,4,7,8-PeCDF	0.190 EMPC	0.190 UX
	1,2,3,6,7,8-HxCDF	0.685 EMPC	0.685 UX

Sample results associated with compound that exhibited a concentration greater than the linear range of the instrument calibration are summarized in the following table.

Sample ID	Compound	Original Analysis	Diluted Analysis	Reported Analysis
A1-68 (0-0.5')	OCDD	10900 E	---	10900 EJ
DUP-1	OCDD	11200 E	---	11200 EJ
A1-75 (0-0.5')	OCDD	21000 E	---	21000 EJ
A1-69 (0-0.5')	OCDD	9870 E	---	9870 EJ
A1-74 (0-0.5')	OCDD	12400 E	---	12400 EJ
A1-70 (0-0.5')	OCDD	19900 E	---	19900 EJ
A1-73 (0-0.5')	OCDD	21500 E	---	21500 EJ
A1-71 (0-0.5')	OCDD	24000 E	---	24000 EJ
A1-72 (0-0.5')	OCDD	20000 E	---	20000 EJ

Note: In the instance where both the original analysis and the diluted analysis sample results exhibited a concentration greater than and/or less than the calibration linear range of the instrument; the sample result exhibiting the greatest concentration will be reported as the final result.

Sample results associated with compounds exhibiting concentration greater than the linear range qualified as documented in the table below when reported as the final reported sample result.

Reported Sample Results	Qualification
Diluted sample result within the calibration range	D
Diluted sample result < the calibration range	DJ
Diluted sample result > the calibration range	EDJ
Original sample result > the calibration range	EJ

The analyzing laboratory noted that the compounds in the following table exhibited interference by a co-eluting furan isomer and may have concentrations that are biased high. Therefore, the following results were qualified as estimated.

Sample Location	Analyte
A1-68 (0-0.5') DUP-1 A1-75 (0-0.5') A1-69 (0-0.5') A1-74 (0-0.5') A1-73 (0-0.5')	2,3,4,7,8-PeCDF
A1-70 (0-0.5') A1-71 (0-0.5')	2,3,4,7,8-PeCDF 1,2,3,7,8,9-HxCDF

12. System Performance and Overall Assessment

Overall system performance was acceptable. Other than for those deviations specifically mentioned in this review, the overall data quality is within the guidelines specified in the method.

DATA VALIDATION CHECKLIST FOR PCDD/PCDF

PCDDs/PCDFs; SW-846 8290	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS)					
Tier II Validation					
Holding times		X		X	
Reporting limits (units)		X		X	
Blanks					
A. Method blanks		X		X	
B. Equipment blanks		X		X	
Ongoing Precision and Accuracy (OPR) Accuracy (%R)		X		X	
Matrix Spike (MS) %R		X		X	
Matrix Spike Duplicate (MSD) %R		X		X	
MS/MSD RPD		X		X	
Field/Laboratory Duplicate Sample RPD		X		X	
Surrogate Internal Standard Spike %R		X		X	
Recovery Surrogate Standard Spike %R		X		X	
Dilution Factor		X		X	
Moisture Content		X		X	
Tier III Validation					
System performance and column resolution		X		X	
Initial calibration %RSD		X		X	
Continuing calibration %D		X		X	
Instrument tune and performance check		X		X	
Ion abundance criteria for each instrument used		X		X	
Signal-to-noise ratio		X		X	
Injection Internal Standard performance		X		X	
Recovery standard performance		X		X	
Compound identification and quantitation					
A. Reconstructed ion chromatograms		X		X	
B. Quantitation Reports		X		X	
C. RT of sample compounds within the established RT windows		X		X	
D. Transcription/calculation errors present		X		X	
E. Reporting limits adjusted for sample dilutions		X		X	
F. Compound quantification		X	X		

RSD – relative standard deviation
 %R - percent recovery
 RPD - relative percent difference
 %D – difference

SAMPLE COMPLIANCE REPORT

Sample Delivery Group (SDG)	Sampling Date	Protocol	Sample ID	Matrix	Compliance ¹					Noncompliance
					VOC	SVOC	PCDDs/PCDFs	MET	MISC	
2110011	11/27/2012	SW846	A1-68 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance
	11/27/2012	SW846	DUP-1	Soil	---	---	No	---	---	Calibration range exceedance; EMPC
	11/27/2012	SW846	A1-75 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance
	11/27/2012	SW846	A1-69 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance; EMPC
	11/27/2012	SW846	A1-74 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance
	11/27/2012	SW846	A1-70 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance; EMPC
	11/27/2012	SW846	A1-73 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance
	11/27/2012	SW846	A1-71 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance
	11/27/2012	SW846	A1-72 (0-0.5')	Soil	---	---	No	---	---	Calibration range exceedance; EMPC
	11/27/2012	SW846	EB 112712	Water	---	---	Yes	---	---	

1 Samples which are compliant with no added validation qualifiers are listed as "yes". Samples which are non-compliant or which have added qualifiers are listed as "no". A "no" designation does not necessarily indicate that the data have been rejected or are otherwise unusable

Validation Performed By: Dennis Dyke

Signature: 

Date: January 18, 2013

Peer Review: Dennis Capria

Date: January 24, 2013

**CHAIN OF CUSTODY /
LABORATORY QUALIFIERS /
CORRECTED SAMPLE ANALYSIS DATA SHEETS**



CHAIN OF CUSTODY

1 OF 3

FOR LABORATORY USE ONLY Storage Secured No

Laboratory Project ID: 2110011 Yes No

Storage ID: WR-2 Temp 0.8 °C

Project I.D.: _____ P.O.# B0039275.0000.00002 Sampler: I. STEWART & R. STEVENSON
 (Name)

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGPAS Company ARCADIS Address 6602 EXCELSIOR RD. City BAXTER State MN Zip 56425 Ph# 218-829-4607 Fax# _____

Relinquished by: (Signature and Printed Name) DAVID BESSINGPAS Date: 11/28/12 Time: 1445 Received by: (Signature and Printed Name) Bethma Benedict Date: 11/29/12 Time: 1039

Relinquished by: (Signature and Printed Name) RAY STEVENSON Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

ATTN: _____

Add Analysis(es) Requested		Container(s)															
Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29

Sample ID	Date	Time	Location/Sample Description	Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	
A1-68 (0-0.5')	11/27/12	0855		1	G	So								X								
DUP-1	11/27/12	—		1	G	So								X								
A1-75 (0-0.5')	11/27/12	0940		1	G	So								X								
A1-69 (0-0.5')	11/27/12	1010		1	G	So								X								
A1-69 (0-0.5') MS	11/27/12	1010		1	G	So								X								
A1-69 (0-0.5') MSD	11/27/12	1010		1	G	So								X								
A1-74 (0-0.5')	11/27/12	1100		1	G	So								X								
A1-70 (0-0.5')	11/27/12	1135		1	G	So								X								
A1-73 (0-0.5')	11/27/12	1210		1	G	So								X								
* DUP-2	11/27/12	—		1	G	So								X								* HOLD *

Special Instructions/Comments:
* Sample logged in to WorkOrder 2110012

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGPAS
 Company: ARCADIS
 Address: 6602 EXCELSIOR RD.
 City: BAXTER State: MN Zip: 56425
 Phone: 218-829-4607 Fax: _____
 Email: DAVID.BESSINGPAS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other _____

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MMS Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
 O = Other _____

WHITE - ORIGINAL

YELLOW - ARCHIVE

PINK - COPY



CHAIN OF CUSTODY

2 of 3

FOR LABORATORY USE ONLY Storage Secured No

Laboratory Project ID: 2110011 Yes No

Storage ID: WR-2 Temp 0.8 °C

Project I.D.: _____ P.O.# B0039275.0000.00002 Sampler: I. STEWART / R. STEVENSON
(Name)

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGBAS Company ARCADIS Address 6602 EXCELSIOR RD. City BAXTER State MN Zip 56425 Ph# 218-829-4607 Fax# _____

Relinquished by: (Signature and Printed Name) RAY STEVENSON Date: 11/28/12 Time: 1445 Received by: (Signature and Printed Name) Benedict J. Benedict Date: 11/29/12 Time: 1040

Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____
Tracking No.: _____

ATTN: _____

Quantity	Type	Matrix	Add Analysis(es) Requested																				
			2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29						

Sample ID	Date	Time	Location/Sample Description
A1-71 (0-0.5')	11/27/12	1330	
A1-72 (0-0.5')	11/27/12	1400	
* A1-65 (0-0.5')	11/27/12	1430	
* A1-64 (0-0.5')	11/27/12	1500	
ETB 112712	11/27/12	1540	
* A1-79 (0-0.5')	11/28/12	0900	
* A1-78 (0-0.5')	11/28/12	0925	
* A1-77 (0-0.5')	11/28/12	0950	
* A1-76 (0-0.5')	11/28/12	1020	
* A1-67 (0-0.5')	11/28/12	1115	

Special Instructions/Comments: _____

* Samples logged in to WorkOrder 2110012

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGBAS
 Company: ARCADIS
 Address: 6602 EXCELSIOR RD.
 City: BAXTER State: MN Zip: 56425
 Phone: 218-829-4607 Fax: _____
 Email: DAVID.BESSINGBAS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other _____

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MM5 Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
 O = Other _____



CHAIN OF CUSTODY

3 OF 3

FOR LABORATORY USE ONLY Storage Secured

Laboratory Project ID: 2110011 Yes No

Storage ID: WR-2 Temp 0.8 °C

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Project I.D.: _____ P.O.# B0039275.0000.00002 Sampler: I. STEWART / R. STEVENSON
 (Name)

Invoice to: Name DAVID BESSINGGATS Company ARCADIS Address 6602 EXCELSIOR RD. City BAXTER State MN Zip 56425 Ph# 218-829-4607 Fax# _____

Relinquished by: (Signature and Printed Name) [Signature] Date: 11/28/12 Time: 1445 Received by: (Signature and Printed Name) B. Benedict Date: 11/29/12 Time: 1040

Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

ATTN: _____

Quantity	Type	Matrix	Add Analysis(es) Requested																
			2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29		
1	G	So																	
2	A	AQ																	

Sample ID	Date	Time	Location/Sample Description
* A1-66 (0-0.5')	11/28/12	1150	
* EB 112812	11/28/12	1400	

* HOLD *

Special Instructions/Comments: _____

* Sample logged into work order 2110012

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGGATS
 Company: ARCADIS
 Address: 6602 EXCELSIOR RD.
 City: BAXTER State: MN Zip: 56425
 Phone: 218-829-4607 Fax: _____
 Email: DAVID.BESSINGGATS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other _____

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MMS Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
 O = Other _____

DATA QUALIFIERS & ABBREVIATIONS

B	This compound was also detected in the method blank.
D	Dilution
E	The amount detected is above the High Calibration Limit.
P	The amount reported is the maximum possible concentration due to possible chlorinated diphenylether interference.
H	Recovery was outside laboratory acceptance limits.
I	Chemical Interference
J	The amount detected is below the Low Calibration Limit.
*	See Cover Letter
Conc.	Concentration
DL	Sample-specific estimated detection limit
MDL	The minimum concentration of a substance that can be measured and reported with 99% confidence that the analyte concentration is greater than zero in the matrix tested.
EMPC	Estimated Maximum Possible Concentration
NA	Not applicable
RL	Reporting Limit – concentrations that correspond to low calibration point
ND	Not Detected
TEQ	Toxic Equivalency

Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.

Sample ID: A1-68 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-01	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.5 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 8:55	% Solids:	77.3	Date Analyzed :	06-Dec-12 18:11	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.364			J	IS 13C-2,3,7,8-TCDD	90.4	40 - 135	
1,2,3,7,8-PeCDD	2.06			J	13C-1,2,3,7,8-PeCDD	66.1	40 - 135	
1,2,3,4,7,8-HxCDD	3.31				13C-1,2,3,4,7,8-HxCDD	82.3	40 - 135	
1,2,3,6,7,8-HxCDD	8.83				13C-1,2,3,6,7,8-HxCDD	77.5	40 - 135	
1,2,3,7,8,9-HxCDD	8.04				13C-1,2,3,7,8,9-HxCDD	80.6	40 - 135	
1,2,3,4,6,7,8-HpCDD	296				13C-1,2,3,4,6,7,8-HpCDD	77.9	40 - 135	
OCDD	10900			E J	13C-OCDD	96.5	40 - 135	
2,3,7,8-TCDF	0.331			J	13C-2,3,7,8-TCDF	83.2	40 - 135	
1,2,3,7,8-PeCDF	0.453			J	13C-1,2,3,7,8-PeCDF	77.1	40 - 135	
2,3,4,7,8-PeCDF	1.04			J	13C-2,3,4,7,8-PeCDF	81.2	40 - 135	
1,2,3,4,7,8-HxCDF	1.51			J	13C-1,2,3,4,7,8-HxCDF	80.9	40 - 135	
1,2,3,6,7,8-HxCDF	1.26			J	13C-1,2,3,6,7,8-HxCDF	78.2	40 - 135	
2,3,4,6,7,8-HxCDF	2.12			J	13C-2,3,4,6,7,8-HxCDF	75.5	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.483			13C-1,2,3,7,8,9-HxCDF	77.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	24.1				13C-1,2,3,4,6,7,8-HpCDF	81.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.88			J	13C-1,2,3,4,7,8,9-HpCDF	78.9	40 - 135	
OCDF	82.3				13C-OCDF	83.8	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	87.1	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 11.8

TOTALS		
Total TCDD	2.11	3.15
Total PeCDD	13.6	14.3
Total HxCDD	73.5	
Total HpCDD	583	
Total TCDF	9.05	9.16
Total PeCDF	22.3	
Total HxCDF	38.1	
Total HpCDF	82.7	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: DUP-1

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-02	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.3 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 0:00	% Solids:	78.3	Date Analyzed :	06-Dec-12 18:59	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.372			J	IS 13C-2,3,7,8-TCDD	86.4	40 - 135	
1,2,3,7,8-PeCDD	2.56			J	13C-1,2,3,7,8-PeCDD	74.4	40 - 135	
1,2,3,4,7,8-HxCDD	3.34				13C-1,2,3,4,7,8-HxCDD	85.4	40 - 135	
1,2,3,6,7,8-HxCDD	10.7				13C-1,2,3,6,7,8-HxCDD	79.2	40 - 135	
1,2,3,7,8,9-HxCDD	9.54				13C-1,2,3,7,8,9-HxCDD	84.4	40 - 135	
1,2,3,4,6,7,8-HpCDD	317				13C-1,2,3,4,6,7,8-HpCDD	78.6	40 - 135	
OCDD	11200			E J	13C-OCDD	99.1	40 - 135	
2,3,7,8-TCDF	0.287			J	13C-2,3,7,8-TCDF	65.4	40 - 135	
1,2,3,7,8-PeCDF	0.395			J	13C-1,2,3,7,8-PeCDF	78.2	40 - 135	
2,3,4,7,8-PeCDF	1.03			J	13C-2,3,4,7,8-PeCDF	78.7	40 - 135	
1,2,3,4,7,8-HxCDF	1.46			J	13C-1,2,3,4,7,8-HxCDF	84.4	40 - 135	
1,2,3,6,7,8-HxCDF	ND		1.12	UX	13C-1,2,3,6,7,8-HxCDF	79.5	40 - 135	
2,3,4,6,7,8-HxCDF	2.21			J	13C-2,3,4,6,7,8-HxCDF	78.0	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.505			13C-1,2,3,7,8,9-HxCDF	85.6	40 - 135	
1,2,3,4,6,7,8-HpCDF	26.5				13C-1,2,3,4,6,7,8-HpCDF	82.4	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.84			J	13C-1,2,3,4,7,8,9-HpCDF	89.6	40 - 135	
OCDF	88.8				13C-OCDF	86.9	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	82.5	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 12.8

TOTALS			
Total TCDD	2.33		2.83
Total PeCDD	16.5		17.4
Total HxCDD	84.3		
Total HpCDD	656		
Total TCDF	6.87		8.15
Total PeCDF	19.6		19.7
Total HxCDF	37.9		39.0
Total HpCDF	80.6		81.4

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-75 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-03	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.7 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 9:40	% Solids:	74.9	Date Analyzed :	06-Dec-12 19:47	Column:	ZB-5 Analyst: MAS
					07-Dec-12 11:50	Column:	DB-225 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	1.25				IS 13C-2,3,7,8-TCDD	96.1	40 - 135	
1,2,3,7,8-PeCDD	8.18				13C-1,2,3,7,8-PeCDD	77.3	40 - 135	
1,2,3,4,7,8-HxCDD	9.48				13C-1,2,3,4,7,8-HxCDD	84.4	40 - 135	
1,2,3,6,7,8-HxCDD	20.8				13C-1,2,3,6,7,8-HxCDD	78.3	40 - 135	
1,2,3,7,8,9-HxCDD	33.7				13C-1,2,3,7,8,9-HxCDD	80.5	40 - 135	
1,2,3,4,6,7,8-HpCDD	817				13C-1,2,3,4,6,7,8-HpCDD	78.1	40 - 135	
OCDD	21000			E J	13C-OCDD	116	40 - 135	
2,3,7,8-TCDF	0.760				13C-2,3,7,8-TCDF	83.0	40 - 135	
1,2,3,7,8-PeCDF	0.682			J	13C-1,2,3,7,8-PeCDF	87.7	40 - 135	
2,3,4,7,8-PeCDF	0.568			J	13C-2,3,4,7,8-PeCDF	88.4	40 - 135	
1,2,3,4,7,8-HxCDF	2.32			J	13C-1,2,3,4,7,8-HxCDF	83.0	40 - 135	
1,2,3,6,7,8-HxCDF	2.12			J	13C-1,2,3,6,7,8-HxCDF	79.2	40 - 135	
2,3,4,6,7,8-HxCDF	3.58				13C-2,3,4,6,7,8-HxCDF	81.0	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.277			13C-1,2,3,7,8,9-HxCDF	83.5	40 - 135	
1,2,3,4,6,7,8-HpCDF	62.4				13C-1,2,3,4,6,7,8-HpCDF	83.0	40 - 135	
1,2,3,4,7,8,9-HpCDF	4.42				13C-1,2,3,4,7,8,9-HpCDF	89.7	40 - 135	
OCDF	340				13C-OCDF	94.1	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	91.7	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	32.1

TOTALS		
Total TCDD	7.82	8.06
Total PeCDD	37.4	
Total HxCDD	204	
Total HpCDD	1730	
Total TCDF	16.3	17.7
Total PeCDF	40.6	
Total HxCDF	64.4	
Total HpCDF	227	

DL - Sample specific estimated detection limit
 EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit
 The results are reported in dry weight.
 The sample size is reported in wet weight.

Sample ID: A1-69 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-04	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.1 g	QC Batch:	B2L0009	Date Extracted:	04-Dec-2012 15:00
Date Collected:	27-Nov-2012 10:10	% Solids:	79.5	Date Analyzed :	07-Dec-12 00:35	Column:	ZB-5 Analyst: MAS
					07-Dec-12 13:59	Column:	DB-225 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND		0.316	UX	IS 13C-2,3,7,8-TCDD	97.0	40 - 135	
1,2,3,7,8-PeCDD	1.53			J	13C-1,2,3,7,8-PeCDD	83.2	40 - 135	
1,2,3,4,7,8-HxCDD	2.15			J	13C-1,2,3,4,7,8-HxCDD	84.5	40 - 135	
1,2,3,6,7,8-HxCDD	5.83				13C-1,2,3,6,7,8-HxCDD	78.3	40 - 135	
1,2,3,7,8,9-HxCDD	5.35				13C-1,2,3,7,8,9-HxCDD	80.0	40 - 135	
1,2,3,4,6,7,8-HpCDD	205				13C-1,2,3,4,6,7,8-HpCDD	79.3	40 - 135	
OCDD	9870			E J	13C-OCDD	108	40 - 135	
2,3,7,8-TCDF	0.555			J	13C-2,3,7,8-TCDF	90.1	40 - 135	
1,2,3,7,8-PeCDF	0.429			J	13C-1,2,3,7,8-PeCDF	86.2	40 - 135	
2,3,4,7,8-PeCDF	0.654			J	13C-2,3,4,7,8-PeCDF	94.3	40 - 135	
1,2,3,4,7,8-HxCDF	1.16			J	13C-1,2,3,4,7,8-HxCDF	80.8	40 - 135	
1,2,3,6,7,8-HxCDF	ND		0.808	UX	13C-1,2,3,6,7,8-HxCDF	76.0	40 - 135	
2,3,4,6,7,8-HxCDF	1.24			J	13C-2,3,4,6,7,8-HxCDF	75.7	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.390			13C-1,2,3,7,8,9-HxCDF	83.4	40 - 135	
1,2,3,4,6,7,8-HpCDF	19.7				13C-1,2,3,4,6,7,8-HpCDF	79.3	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.42			J	13C-1,2,3,4,7,8,9-HpCDF	89.1	40 - 135	
OCDF	60.9				13C-OCDF	92.0	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	91.7	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 8.61

TOTALS								
Total TCDD	3.73		5.11					
Total PeCDD	15.9							
Total HxCDD	61.3							
Total HpCDD	439							
Total TCDF	7.12		9.14					
Total PeCDF	9.72							
Total HxCDF	19.3		20.1					
Total HpCDF	58.5							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-74 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-05	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.5 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 11:00	% Solids:	77.2	Date Analyzed :	06-Dec-12 20:35	Column:	ZB-5 Analyst: MAS
					07-Dec-12 12:22	Column:	DB-225 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.259			J	IS 13C-2,3,7,8-TCDD	86.7	40 - 135	
1,2,3,7,8-PeCDD	2.03			J	13C-1,2,3,7,8-PeCDD	76.1	40 - 135	
1,2,3,4,7,8-HxCDD	3.19				13C-1,2,3,4,7,8-HxCDD	76.2	40 - 135	
1,2,3,6,7,8-HxCDD	7.64				13C-1,2,3,6,7,8-HxCDD	72.9	40 - 135	
1,2,3,7,8,9-HxCDD	6.97				13C-1,2,3,7,8,9-HxCDD	73.8	40 - 135	
1,2,3,4,6,7,8-HpCDD	316				13C-1,2,3,4,6,7,8-HpCDD	74.4	40 - 135	
OCDD	12400			E J	13C-OCDD	97.0	40 - 135	
2,3,7,8-TCDF	0.821				13C-2,3,7,8-TCDF	78.1	40 - 135	
1,2,3,7,8-PeCDF	0.709			J	13C-1,2,3,7,8-PeCDF	81.4	40 - 135	
2,3,4,7,8-PeCDF	1.00			J	13C-2,3,4,7,8-PeCDF	85.2	40 - 135	
1,2,3,4,7,8-HxCDF	1.98			J	13C-1,2,3,4,7,8-HxCDF	76.4	40 - 135	
1,2,3,6,7,8-HxCDF	1.65			J	13C-1,2,3,6,7,8-HxCDF	71.5	40 - 135	
2,3,4,6,7,8-HxCDF	2.17			J	13C-2,3,4,6,7,8-HxCDF	72.3	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.375			13C-1,2,3,7,8,9-HxCDF	76.3	40 - 135	
1,2,3,4,6,7,8-HpCDF	30.6				13C-1,2,3,4,6,7,8-HpCDF	74.5	40 - 135	
1,2,3,4,7,8,9-HpCDF	2.21			J	13C-1,2,3,4,7,8,9-HpCDF	82.8	40 - 135	
OCDF	107				13C-OCDF	86.0	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	83.7	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 12.3

TOTALS		
Total TCDD	1.87	5.43
Total PeCDD	16.4	18.2
Total HxCDD	81.9	84.0
Total HpCDD	709	
Total TCDF	16.1	17.1
Total PeCDF	19.7	
Total HxCDF	36.4	
Total HpCDF	97.7	98.6

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-70 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-06	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.4 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 11:35	% Solids:	77.4	Date Analyzed :	06-Dec-12 21:23	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND		0.329	UX	IS 13C-2,3,7,8-TCDD	78.5	40 - 135	
1,2,3,7,8-PeCDD	4.04				13C-1,2,3,7,8-PeCDD	68.6	40 - 135	
1,2,3,4,7,8-HxCDD	8.26				13C-1,2,3,4,7,8-HxCDD	75.7	40 - 135	
1,2,3,6,7,8-HxCDD	29.7				13C-1,2,3,6,7,8-HxCDD	72.6	40 - 135	
1,2,3,7,8,9-HxCDD	21.0				13C-1,2,3,7,8,9-HxCDD	74.1	40 - 135	
1,2,3,4,6,7,8-HpCDD	897				13C-1,2,3,4,6,7,8-HpCDD	77.9	40 - 135	
OCDD	19900			E J	13C-OCDD	108	40 - 135	
2,3,7,8-TCDF	0.336			J	13C-2,3,7,8-TCDF	71.5	40 - 135	
1,2,3,7,8-PeCDF	0.721			J	13C-1,2,3,7,8-PeCDF	73.8	40 - 135	
2,3,4,7,8-PeCDF	0.609			J	13C-2,3,4,7,8-PeCDF	82.3	40 - 135	
1,2,3,4,7,8-HxCDF	11.7				13C-1,2,3,4,7,8-HxCDF	75.3	40 - 135	
1,2,3,6,7,8-HxCDF	7.16				13C-1,2,3,6,7,8-HxCDF	73.2	40 - 135	
2,3,4,6,7,8-HxCDF	14.3				13C-2,3,4,6,7,8-HxCDF	73.8	40 - 135	
1,2,3,7,8,9-HxCDF	1.63			J	13C-1,2,3,7,8,9-HxCDF	77.3	40 - 135	
1,2,3,4,6,7,8-HpCDF	254				13C-1,2,3,4,6,7,8-HpCDF	79.6	40 - 135	
1,2,3,4,7,8,9-HpCDF	26.5				13C-1,2,3,4,7,8,9-HpCDF	85.8	40 - 135	
OCDF	576				13C-OCDF	92.2	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	79.1	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	31.6

TOTALS		
Total TCDD	1.46	3.03
Total PeCDD	21.9	22.6
Total HxCDD	157	
Total HpCDD	1450	
Total TCDF	2.86	5.74
Total PeCDF	25.7	
Total HxCDF	281	281
Total HpCDF	849	

DL - Sample specific estimated detection limit
 EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit
 The results are reported in dry weight.
 The sample size is reported in wet weight.

Sample ID: A1-73 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-07	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.2 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 12:10	% Solids:	78.6	Date Analyzed :	06-Dec-12 22:11	Column:	ZB-5 Analyst: MAS
					07-Dec-12 12:54	Column:	DB-225 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.667				IS 13C-2,3,7,8-TCDD	70.5	40 - 135	
1,2,3,7,8-PeCDD	6.58				13C-1,2,3,7,8-PeCDD	62.7	40 - 135	
1,2,3,4,7,8-HxCDD	9.72				13C-1,2,3,4,7,8-HxCDD	63.1	40 - 135	
1,2,3,6,7,8-HxCDD	24.1				13C-1,2,3,6,7,8-HxCDD	61.3	40 - 135	
1,2,3,7,8,9-HxCDD	23.7				13C-1,2,3,7,8,9-HxCDD	61.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	773				13C-1,2,3,4,6,7,8-HpCDD	68.0	40 - 135	
OCDD	21500			E J	13C-OCDD	84.9	40 - 135	
2,3,7,8-TCDF	0.627				13C-2,3,7,8-TCDF	66.3	40 - 135	
1,2,3,7,8-PeCDF	1.14			J	13C-1,2,3,7,8-PeCDF	66.4	40 - 135	
2,3,4,7,8-PeCDF	1.38			J	13C-2,3,4,7,8-PeCDF	71.6	40 - 135	
1,2,3,4,7,8-HxCDF	5.26				13C-1,2,3,4,7,8-HxCDF	61.4	40 - 135	
1,2,3,6,7,8-HxCDF	5.98				13C-1,2,3,6,7,8-HxCDF	58.9	40 - 135	
2,3,4,6,7,8-HxCDF	8.06				13C-2,3,4,6,7,8-HxCDF	60.1	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.984			13C-1,2,3,7,8,9-HxCDF	65.5	40 - 135	
1,2,3,4,6,7,8-HpCDF	130				13C-1,2,3,4,6,7,8-HpCDF	64.2	40 - 135	
1,2,3,4,7,8,9-HpCDF	9.45				13C-1,2,3,4,7,8,9-HpCDF	73.7	40 - 135	
OCDF	450				13C-OCDF	69.7	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	70.1	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 31.1

TOTALS		
Total TCDD	7.27	8.45
Total PeCDD	36.2	39.7
Total HxCDD	208	
Total HpCDD	1480	
Total TCDF	16.9	17.8
Total PeCDF	40.7	42.2
Total HxCDF	139	140
Total HpCDF	397	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-71 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-08	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.3 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 13:30	% Solids:	77.5	Date Analyzed :	06-Dec-12 22:59	Column:	ZB-5 Analyst: MAS
					07-Dec-12 13:27	Column:	DB-225 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.561			J	IS 13C-2,3,7,8-TCDD	87.1	40 - 135	
1,2,3,7,8-PeCDD	4.16				13C-1,2,3,7,8-PeCDD	77.4	40 - 135	
1,2,3,4,7,8-HxCDD	7.01				13C-1,2,3,4,7,8-HxCDD	81.8	40 - 135	
1,2,3,6,7,8-HxCDD	17.9				13C-1,2,3,6,7,8-HxCDD	79.0	40 - 135	
1,2,3,7,8,9-HxCDD	16.4				13C-1,2,3,7,8,9-HxCDD	78.9	40 - 135	
1,2,3,4,6,7,8-HpCDD	653				13C-1,2,3,4,6,7,8-HpCDD	86.1	40 - 135	
OCDD	24000			E J	13C-OCDD	116	40 - 135	
2,3,7,8-TCDF	1.22				13C-2,3,7,8-TCDF	81.0	40 - 135	
1,2,3,7,8-PeCDF	1.03			J	13C-1,2,3,7,8-PeCDF	83.7	40 - 135	
2,3,4,7,8-PeCDF	2.48			J	13C-2,3,4,7,8-PeCDF	91.1	40 - 135	
1,2,3,4,7,8-HxCDF	3.85				13C-1,2,3,4,7,8-HxCDF	80.4	40 - 135	
1,2,3,6,7,8-HxCDF	3.19				13C-1,2,3,6,7,8-HxCDF	78.4	40 - 135	
2,3,4,6,7,8-HxCDF	5.05				13C-2,3,4,6,7,8-HxCDF	77.3	40 - 135	
1,2,3,7,8,9-HxCDF	0.275			J	13C-1,2,3,7,8,9-HxCDF	82.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	82.8				13C-1,2,3,4,6,7,8-HpCDF	86.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	5.77				13C-1,2,3,4,7,8,9-HpCDF	94.6	40 - 135	
OCDF	319				13C-OCDF	94.8	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	84.2	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	25.7

TOTALS		
Total TCDD	12.2	13.3
Total PeCDD	34.2	
Total HxCDD	162	
Total HpCDD	1570	
Total TCDF	27.0	27.5
Total PeCDF	38.2	
Total HxCDF	91.3	91.9
Total HpCDF	273	

DL - Sample specific estimated detection limit
 EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit
 The results are reported in dry weight.
 The sample size is reported in wet weight.

Sample ID: A1-72 (0-0.5')

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110011-09	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	10.4 g	QC Batch:	B2L0001	Date Extracted:	03-Dec-2012 8:36
Date Collected:	27-Nov-2012 14:00	% Solids:	77.7	Date Analyzed :	06-Dec-12 23:47	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND		0.185	UX	IS 13C-2,3,7,8-TCDD	90.6	40 - 135	
1,2,3,7,8-PeCDD	ND		1.22	UX	13C-1,2,3,7,8-PeCDD	77.5	40 - 135	
1,2,3,4,7,8-HxCDD	2.77			J	13C-1,2,3,4,7,8-HxCDD	79.0	40 - 135	
1,2,3,6,7,8-HxCDD	6.08				13C-1,2,3,6,7,8-HxCDD	74.7	40 - 135	
1,2,3,7,8,9-HxCDD	6.66				13C-1,2,3,7,8,9-HxCDD	75.7	40 - 135	
1,2,3,4,6,7,8-HpCDD	269				13C-1,2,3,4,6,7,8-HpCDD	84.0	40 - 135	
OCDD	20000			E J	13C-OCDD	108	40 - 135	
2,3,7,8-TCDF	0.157			J	13C-2,3,7,8-TCDF	83.4	40 - 135	
1,2,3,7,8-PeCDF	ND	0.235			13C-1,2,3,7,8-PeCDF	87.7	40 - 135	
2,3,4,7,8-PeCDF	ND		0.190	UX	13C-2,3,4,7,8-PeCDF	88.3	40 - 135	
1,2,3,4,7,8-HxCDF	0.844			J	13C-1,2,3,4,7,8-HxCDF	77.7	40 - 135	
1,2,3,6,7,8-HxCDF	ND		0.685	UX	13C-1,2,3,6,7,8-HxCDF	73.3	40 - 135	
2,3,4,6,7,8-HxCDF	1.18			J	13C-2,3,4,6,7,8-HxCDF	73.2	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.316			13C-1,2,3,7,8,9-HxCDF	78.2	40 - 135	
1,2,3,4,6,7,8-HpCDF	19.4				13C-1,2,3,4,6,7,8-HpCDF	83.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.39			J	13C-1,2,3,4,7,8,9-HpCDF	93.0	40 - 135	
OCDF	78.7				13C-OCDF	84.0	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	87.9	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 10.7

TOTALS		
Total TCDD	1.25	2.11
Total PeCDD	9.91	11.7
Total HxCDD	57.5	
Total HpCDD	588	
Total TCDF	1.78	2.49
Total PeCDF	4.96	5.35
Total HxCDF	20.4	21.1
Total HpCDF	62.4	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: EB 112712

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Aqueous	Lab Sample:	2110011-10	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	1.01 L	QC Batch:	B2L0033	Date Extracted:	12-Dec-2012 10:12
Date Collected:	27-Nov-2012 15:40			Date Analyzed :	13-Dec-12 20:39	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND	0.755			IS 13C-2,3,7,8-TCDD	81.5	40 - 135	
1,2,3,7,8-PeCDD	ND	1.01			13C-1,2,3,7,8-PeCDD	67.4	40 - 135	
1,2,3,4,7,8-HxCDD	ND	1.15			13C-1,2,3,4,7,8-HxCDD	67.1	40 - 135	
1,2,3,6,7,8-HxCDD	ND	1.35			13C-1,2,3,6,7,8-HxCDD	71.7	40 - 135	
1,2,3,7,8,9-HxCDD	ND	1.56			13C-1,2,3,7,8,9-HxCDD	63.4	32 - 141	
1,2,3,4,6,7,8-HpCDD	ND	1.97			13C-1,2,3,4,6,7,8-HpCDD	60.0	40 - 135	
OCDD	ND	1.78			13C-OCDD	53.0	40 - 135	
2,3,7,8-TCDF	ND	0.858			13C-2,3,7,8-TCDF	85.3	40 - 135	
1,2,3,7,8-PeCDF	ND	0.728			13C-1,2,3,7,8-PeCDF	62.9	40 - 135	
2,3,4,7,8-PeCDF	ND	0.684			13C-2,3,4,7,8-PeCDF	73.8	40 - 135	
1,2,3,4,7,8-HxCDF	ND	0.537			13C-1,2,3,4,7,8-HxCDF	69.0	40 - 135	
1,2,3,6,7,8-HxCDF	ND	0.532			13C-1,2,3,6,7,8-HxCDF	71.2	40 - 135	
2,3,4,6,7,8-HxCDF	ND	0.559			13C-2,3,4,6,7,8-HxCDF	74.7	40 - 135	
1,2,3,7,8,9-HxCDF	ND	0.817			13C-1,2,3,7,8,9-HxCDF	66.2	40 - 135	
1,2,3,4,6,7,8-HpCDF	ND	0.639			13C-1,2,3,4,6,7,8-HpCDF	61.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	ND	0.929			13C-1,2,3,4,7,8,9-HpCDF	59.4	40 - 135	
OCDF	ND	2.34			13C-OCDF	55.4	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	96.6	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 0.00

TOTALS		
Total TCDD	ND	0.755
Total PeCDD	ND	1.01
Total HxCDD	ND	1.56
Total HpCDD	ND	1.97
Total TCDF	ND	0.858
Total PeCDF	ND	0.728
Total HxCDF	ND	0.817
Total HpCDF	ND	0.929

DL - Sample specific estimated detection limit

LCL-UCL- Lower control limit - upper control limit

EMPC - Estimated maximum possible concentration

Beazer East Inc.

Former Koppers Wood-Treating Site

Data Review

CARBONDALE, ILLINOIS

Polychlorinated Dibenzo-Dioxins and Polychlorinated
Dibenzo-Furans (PCDDs/PCDFs) Analyses

SDG #: 2110012

Analyses Performed By:
Vista Analytical Laboratory
El Dorado Hills, California

Report #: 18269R
Review Level: Tier III
Project: B0039275.0000.00003

SUMMARY

This data quality assessment summarizes the review of Sample Delivery Group (SDG) # 2110012 for samples collected in association with the Beazer East Inc. Former Koppers Wood-Treating site. The review was conducted as a Tier III evaluation and included review of data package completeness. Only analytical data associated with constituents of concern were reviewed for this validation. Field documentation was not included in this review. Included with this assessment are the validation annotated sample result sheets, and chain of custody. Analyses were performed on the following samples:

Sample ID	Lab ID	Matrix	Sample Collection Date	Parent Sample	Analysis				
					VOC	SVOC	PCDDs/ PCDFs	MET	MISC
DUP 2	2110012-01	Soil	11/27/2012	A1-73 (0-0.5')			X		
A1-65 (0-0.5)	2110012-02	Soil	11/27/2012				X		
A1-64 (0-0.5)	2110012-03	Soil	11/27/2012				X		
A1-67 (0-0.5)	2110012-08	Soil	11/28/2012				X		
A1-66 (0-0.5)	2110012-09	Soil	11/28/2012				X		
EB 112812	2110012-10	Water	11/28/2012				X		

Note: Soil sample results were reported on a dry weight basis.

The parent sample of field duplicate sample DUP 2 (sample location A1-73 (0-0.5')) is from SDG 2110011; the field duplicate sample results were evaluated with SDG 2110011 in data validation report 18268R.

ANALYTICAL DATA PACKAGE DOCUMENTATION

The table below is the evaluation of the data package completeness.

Items Reviewed	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample receipt condition		X		X	
2. Requested analyses and sample results		X		X	
3. Master tracking list		X		X	
4. Methods of analysis		X		X	
5. Reporting limits		X		X	
6. Sample collection date		X		X	
7. Laboratory sample received date		X		X	
8. Sample preservation verification (as applicable)		X		X	
9. Sample preparation/extraction/analysis dates		X		X	
10. Fully executed Chain-of-Custody (COC) form		X		X	
11. Narrative summary of QA or sample problems provided		X		X	
12. Data Package Completeness and Compliance		X		X	

QA - Quality Assurance

ORGANIC ANALYSIS INTRODUCTION

Analyses were performed according to United States Environmental Protection Agency (USEPA) SW-846 Method 8290 as referenced in NYSDEC-ASP. Data were reviewed in accordance with USEPA National Functional Guidelines of October 1999 and USEPA Region II SOP associated with USEPA SW-846 Method 8290 Validating Polychlorinated Dibenzo-Dioxins and Polychlorinated Dibenzo-Furans by High Resolution GC/MS (SOP HW-19 Revision 1, October 2006).

The data review process is an evaluation of data on a technical basis rather than a determination of contract compliance. As such, the standards against which the data are being weighed may differ from those specified in the analytical method. It is assumed that the data package represents the best efforts of the laboratory and had already been subjected to adequate and sufficient quality review prior to submission.

During the review process, laboratory qualified and unqualified data are verified against the supporting documentation. Based on this evaluation, qualifier codes may be added, deleted, or modified by the data reviewer. Results are qualified with the following codes in accordance with USEPA National Functional Guidelines:

- Concentration (C) Qualifiers
 - U The compound was analyzed for but not detected. The associated value is the compound quantitation limit.
 - B The compound has been found in the sample as well as its associated blank, its presence in the sample may be suspect.
- Quantitation (Q) Qualifiers
 - E The compound was quantitated above the calibration range.
 - D Concentration is based on a diluted sample analysis.
- Validation Qualifiers
 - J The compound was positively identified; however, the associated numerical value is an estimated concentration only.
 - UJ The compound was not detected above the reported sample quantitation limit. However, the reported limit is approximate and may or may not represent the actual limit of quantitation.
 - JN The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification. The associated numerical value is an estimated concentration only.
 - UB Compound considered non-detect at the listed value due to associated blank contamination.
 - N The analysis indicates the presence of a compound for which there is presumptive evidence to make a tentative identification.
 - R The sample results are rejected as unusable. The compound may or may not be present in the sample.

Two facts should be noted by all data users. First, the "R" flag means that the associated value is unusable. In other words, due to significant quality control (QC) problems, the analysis is invalid and

provides no information as to whether the compound is present or not. "R" values should not appear on data tables because they cannot be relied upon, even as a last resort. The second fact to keep in mind is that no compound concentration, even if it has passed all QC tests, is guaranteed to be accurate. Strict QC serves to increase confidence in data but any value potentially contains error.

POLYCHLORINATED DIBENZODIOXINS AND POLYCHLORINATED DIBENZOFURANS (PCDD/PCDF) ANALYSES

1. Holding Times

The specified holding times for the following methods are presented in the following table.

Method	Matrix	Holding Time	Preservation
SW-846 8290	Water	30 days from collection to extraction and 45 days from extraction to analysis	Cool to 4±2 °C
	Soil	30 days from collection to extraction and 45 days from extraction to analysis	Cool to 4±2 °C

All samples were extracted and analyzed within the specified holding time criteria.

2. Blank Contamination

Quality assurance (QA) blanks (i.e. laboratory method blanks and equipment rinse blanks) are prepared to identify any contamination which may have been introduced into the samples during sample preparation or field activity. Method blanks measure laboratory contamination. Rinse blanks measure contamination of samples during field operations.

A blank action level (BAL) of five times the concentration of a detected compound in an associated blank is calculated for QA blanks containing concentrations greater than the method detection limit (MDL). The BAL is compared to the associated sample results to determine the appropriate qualification of the sample results, if needed.

Target compounds were detected in the associated QA blanks; however, the associated sample results were greater than the BA. Therefore, sample results greater than the BAL resulted in the removal of the laboratory qualifier (B). No other qualification of the sample results was required.

3. Mass Spectrometer Tuning

Mass spectrometer performance including instrument sensitivity and mass resolution were acceptable.

Overall system performance and gas chromatographic column resolution were acceptable.

4. Calibration

Satisfactory instrument calibration is established to insure that the instrument is capable of producing acceptable quantitative data. An initial calibration demonstrates that the instrument is capable of acceptable performance at the beginning of an experimental sequence. The continuing calibration verifies that the instrument daily performance is satisfactory.

4.1 Initial Calibration

All compounds associated with the initial calibration standards must exhibit signal-to-noise ratios (S/N) of at least 2.5, isotopic ratios within the limits listed in table eight of the method, and percent relative

standard deviations (%RSDs) of the relative response factors (RRFs) less than 20% for the labeled standards and less than 30% for the target compounds.

4.2 Continuing Calibration

Instrument performance must be verified at 12 hour periods after successful tune verifications. All compounds associated with the continuing calibration standard must exhibit S/N of at least 2.5, isotopic ratios within the limits listed in table eight of the method, and percent differences (%D) of the RRFs less than 30% for the labeled standards and less than 20% for the target compounds..

All initial and continuing calibration criteria were within the control limits.

5. Injection Internal Standard Performance

Injection internal standards are added to all extracts prior to instrumental analysis. The injection internal standard performance criteria insure that the GC/MS sensitivity and response are stable during every sample analysis. The criteria require the injection internal standard compounds exhibit a signal-to-noise (S/N) ratio of at least 10 and elute within \pm fifteen seconds of the retention times (RTs) established during calibration. The acceptance criteria also specify that each injection internal standard exhibit a ratio of the two identifying masses (m/z) within the method specified limits.

All injection internal standard S/N, RT, and m/z ratios were within established limits.

6. Surrogate Internal Standard Compounds

All field samples, blanks, LCS, and MS/MSD are spiked with surrogate internal standard compounds prior to sample preparation to evaluate overall laboratory performance and efficiency of the analytical technique. The acceptance criteria require that the surrogate internal standard compounds exhibit a signal-to-noise (S/N) ratio of at least 10 and elute within \pm fifteen seconds of the retention times (RTs) established during calibration. The acceptance criteria also specify that each surrogate internal standard exhibit a calculated recovery and a ratio of the two identifying masses (m/z) within the method specified limits.

Sample locations associated with surrogate internal standard compounds exhibiting recoveries outside of the control limits presented in the following table.

Sample Location	Surrogate	Recovery
DUP 2 A1-65 (0-0.5) A1-64 (0-0.5) A1-66 (0-0.5)	13C-OCDD	> UL
A1-67 (0-0.5)	13C-OCDD 13C-OCDF	> UL

UL Upper control limit

The criteria used to evaluate the surrogate recoveries are presented in the following table. In the case of any surrogate internal standard compound deviations, the sample results are qualified as documented in the table below.

Control Limit	Sample Result	Qualification
> UL	Non-detect	No Action
	Detect	J
< LL but > 10%	Non-detect	UJ
	Detect	J
< 10%	Non-detect	R
	Detect	J

7. Clean-up Recovery Surrogate Performance

All field samples, blanks, LCS, and MS/MSD are spiked with recovery surrogates prior to extract clean-up. Recovery surrogate acceptance criteria require that their calculated recoveries, S/N, m/z ratios, and relative retention times (RRTs) be within the method-specified acceptance limits.

All recovery surrogate recoveries S/N, m/z ratios, and RRTs were within the control limits.

8. Matrix Spike/Matrix Spike Duplicate (MS/MSD) Analysis

MS/MSD data are used to assess the precision and accuracy of the analytical method. The compounds used to perform the (optional) MS/MSD analysis should exhibit recoveries within the method-specified acceptance limits of 80-120%. The relative percent difference (RPD) between the MS and MSD results should be within the laboratory-established acceptance limits.

Note: The MS/MSD recovery control limits do not apply for MS/MSD performed on sample locations where the compound concentration detected in the parent sample exceeds the MS/MSD concentration by a factor of four or greater. Sample results associated with MS/MSD exceedances where the parent samples are not site-specific are not qualified.

Sample location A1-67(0-0.5) was used for the MS/MSD analysis. All compounds associated with the MS/MSD analyses exhibited acceptable recoveries and RPDs between the MS and MSD results.

9. Ongoing Precision and Recovery (OPR) Sample Analysis

The OPR analysis is used to assess the precision and accuracy of the analytical method independent of matrix interferences. The compounds associated with the OPR analysis must exhibit a percent recovery within the method-specified acceptance limits.

All compounds associated with the OPR analysis exhibited recoveries within the control limits.

10. Field Duplicate Sample Analysis

Field duplicate sample analysis is used to assess the precision of the field sampling procedures and analytical method. A control limit of 50% for water matrices and 100% for soil matrices is applied to the RPD between the parent sample and the field duplicate. In the instance when the parent and/or duplicate sample concentrations are less than or equal to five times the RL, a control limit of two times the RL is applied for water matrices or three times the RL is applied for soil matrices.

The field duplicate sample results were evaluated with SDG 2110011 in Data Validation Report 18268R.

11. Compound Identification

PCDD/PCDF compounds are identified by using the compound's ion abundance ratios, signal-to-noise values, and relative retention times.

An estimated maximum possible concentration (EMPC) designation is given to compounds which have signals eluting within the established retention time window which would, if positively identified, be greater than the detection limit. The signals do not, however, meet the ion abundance ratio criteria and therefore cannot be identified as the compound of interest. The EMPC value is the estimated concentration of the interferant quantitated "as the compound of interest". This value should be considered an elevated detection limit based on potential compound identification and quantitation interference. The "UX" qualifier has been added to the following sample results (in pg/g) to indicate the elevated detection limit as EMPC.

Sample ID	Compound	Laboratory Result	Reported Result
A1-65 (0-0.5)	2,3,7,8-TCDD	0.269 EMPC	0.269 UX

Sample results associated with compound that exhibited a concentration greater than the linear range of the instrument calibration are summarized in the following table.

Sample ID	Compound	Original Analysis	Diluted Analysis	Reported Analysis
DUP 2	OCDD	26800 E	---	26800 EJ
A1-65 (0-0.5)	OCDD	12700 E	---	12700 EJ
A1-64 (0-0.5)	OCDD	17700 E	---	17700 EJ
A1-67 (0-0.5)	1,2,3,4,6,7,8-HpCDD	5010 E	---	5010 EJ
	OCDD	170000 DE	---	170000 DEJ
A1-66 (0-0.5)	OCDD	30900 E	---	30900 EJ

Note: In the instance where both the original analysis and the diluted analysis sample results exhibited a concentration greater than and/or less than the calibration linear range of the instrument; the sample result exhibiting the greatest concentration will be reported as the final result.

Sample results associated with compounds exhibiting concentration greater than the linear range qualified as documented in the table below when reported as the final reported sample result.

Reported Sample Results	Qualification
Diluted sample result within the calibration range	D
Diluted sample result < the calibration range	DJ
Diluted sample result > the calibration range	EDJ
Original sample result > the calibration range	EJ

The analyzing laboratory noted that the compounds in the following table exhibited interference by a co-eluting furan isomer and may have concentrations that are biased high. Therefore, the following results were qualified as estimated.

Sample Location	Analyte
DUP 2 A1-65 (0-0.5)	2,3,4,7,8-PeCDF
A1-64 (0-0.5) A1-67 (0-0.5) A1-66 (0-0.5)	2,3,4,7,8-PeCDF 1,2,3,7,8,9-HxCDF

12. System Performance and Overall Assessment

Overall system performance was acceptable. Other than for those deviations specifically mentioned in this review, the overall data quality is within the guidelines specified in the method.

DATA VALIDATION CHECKLIST FOR PCDD/PCDF

PCDDs/PCDFs; SW-846 8290	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS)					
Tier II Validation					
Holding times		X		X	
Reporting limits (units)		X		X	
Blanks					
A. Method blanks		X		X	
B. Equipment blanks		X		X	
Ongoing Precision and Accuracy (OPR) Accuracy (%R)		X		X	
Matrix Spike (MS) %R		X		X	
Matrix Spike Duplicate (MSD) %R		X		X	
MS/MSD RPD		X		X	
Field/Laboratory Duplicate Sample RPD		X		X	
Surrogate Internal Standard Spike %R		X	X		
Recovery Surrogate Standard Spike %R		X		X	
Dilution Factor		X		X	
Moisture Content		X		X	
Tier III Validation					
System performance and column resolution		X		X	
Initial calibration %RSD		X		X	
Continuing calibration %D		X		X	
Instrument tune and performance check		X		X	
Ion abundance criteria for each instrument used		X		X	
Signal-to-noise ratio		X		X	
Injection Internal Standard performance		X		X	
Recovery standard performance		X		X	
Compound identification and quantitation					
A. Reconstructed ion chromatograms		X		X	
B. Quantitation Reports		X		X	
C. RT of sample compounds within the established RT windows		X		X	
D. Transcription/calculation errors present		X		X	
E. Reporting limits adjusted for sample dilutions		X		X	
F. Compound quantification		X	X		

RSD – relative standard deviation
 %R - percent recovery
 RPD - relative percent difference
 %D – difference

SAMPLE COMPLIANCE REPORT

Sample Delivery Group (SDG)	Sampling Date	Protocol	Sample ID	Matrix	Compliance ¹					Noncompliance
					VOC	SVOC	PCDDs/PCDFs	MET	MISC	
2110012	11/27/2012	SW846	DUP 2	Soil	---	---	No	---	---	Surrogate Internal Standard %R; Calibration range exceedance
	11/27/2012	SW846	A1-65 (0-0.5)	Soil	---	---	No	---	---	Surrogate Internal Standard %R; Calibration range exceedance; EMPC
	11/27/2012	SW846	A1-64 (0-0.5)	Soil	---	---	No	---	---	Surrogate Internal Standard %R; Calibration range exceedance
	11/28/2012	SW846	A1-67 (0-0.5)	Soil	---	---	No	---	---	Surrogate Internal Standard %R; Calibration range exceedance
	11/28/2012	SW846	A1-66 (0-0.5)	Soil	---	---	No	---	---	Surrogate Internal Standard %R; Calibration range exceedance; Analyte interference
	11/28/2012	SW846	EB 112812	Water	---	---	Yes	---	---	

1 Samples which are compliant with no added validation qualifiers are listed as "yes". Samples which are non-compliant or which have added qualifiers are listed as "no". A "no" designation does not necessarily indicate that the data have been rejected or are otherwise unusable

Validation Performed By: Dennis Dyke

Signature: 

Date: January 18, 2013

Peer Review: Dennis Capria

Date: January 24, 2013

**CHAIN OF CUSTODY /
LABORATORY QUALIFIERS /
CORRECTED SAMPLE ANALYSIS DATA SHEETS**



CHAIN OF CUSTODY

FOR LABORATORY USE ONLY

Storage Secured

Laboratory Project ID: 2110012

Yes No

Storage ID: WR-2

Temp: 0.8 °C

1 OF 3

TAT: (Check One):

Standard: 21 Days

Rush (surcharge may apply):

14 days 7 days Specify: _____

Project I.D.: _____ P.O.# B0039275.0000.00002 Sampler: I. STEWART & R. STEVENSON
(Name)

Invoice to: Name DAVID BESSINGOAS Company ARCADIS Address 6602 EXCELSIOR RD City BAKTER State MN Zip 56425 Ph# 218-829-4607 Fax# _____
Relinquished by: (Signature and Printed Name) DAVID BESSINGOAS Date: 11/28/12 Time: 1445 Received by: (Signature and Printed Name) B. Benedict Date: 11/29/12 Time: 1039
Relinquished by: (Signature and Printed Name) RAY STEVENSON Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Add Analysis(es) Requested

ATTN: _____

Tracking No.: _____

Container(s)

Sample ID	Date	Time	Location/Sample Description	Add Analysis(es) Requested																			
				Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB'S	209 CONGENERS	PBDE	PAH	WHO-29		
* A1-68 (0-0.5')	11/27/12	0855		1	G	So							X										
* DUP-1	11/27/12	—		1	G	So							X										
* A1-75 (0-0.5')	11/23/12	0940		1	G	So							X										
* A1-69 (0-0.5')	11/27/12	1010		1	G	So							X										
* A1-69 (0-0.5') MS	11/27/12	1010		1	G	So							X										
* A1-69 (0-0.5') MSD	11/27/12	1010		1	G	So							X										
* A1-74 (0-0.5')	11/27/12	1100		1	G	So							X										
* A1-70 (0-0.5')	11/27/12	1135		1	G	So							X										
* A1-73 (0-0.5')	11/27/12	1210		1	G	So							X										
DUP-2	11/27/12	—		1	G	So							X										*HOLD*

Special Instructions/Comments:

* Samples logged into Workorder 2110011

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGOAS
Company: ARCADIS
Address: 6602 EXCELSIOR RD
City: BAKTER State: MN Zip: 56425
Phone: 218-829-4607 Fax: _____

Container Types: A = 1 Liter Amber, G = Glass Jar

P = PUF, T = MM5 Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,

O = Other _____

Email: DAVID.BESSINGOAS@ARCADIS-US.COM

Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,

SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum

AQ = Aqueous, O = Other _____

WHITE - ORIGINAL

YELLOW - ARCHIVE

PINK - COPY



CHAIN OF CUSTODY

2 of 3

FOR LABORATORY USE ONLY

Storage Secured

Laboratory Project ID: 2110012

Yes No

Storage ID: WR-2

Temp: 0.8 °C

TAT: (Check One):

Standard: 21 Days

Rush (surcharge may apply):

14 days 7 days Specify: _____

Project I.D.: _____ P.O.# B0039275.0000.0002 Sampler: I. STEWART / R. STEVENSON
(Name)

Invoice to: Name	Company	Address	City	State	Zip	Ph#	Fax#
DAVID BESSINGRAS	ARCADIS	6602 EXCELSIOR RD.	BAXTER	MN	56425	218-829-4607	
Relinquished by: (Signature and Printed Name)	Date:	Time:	Received by: (Signature and Printed Name)	Date:	Time:		
<u>R. STEVENSON</u>	<u>11/28/12</u>	<u>1445</u>	<u>R. STEVENSON</u>	<u>11/29/12</u>	<u>1040</u>		
Relinquished by: (Signature and Printed Name)	Date:	Time:	Received by: (Signature and Printed Name)	Date:	Time:		

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
1104 Windfield Way
El Dorado Hills, CA 95762
(916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

ATTN: _____

Add Analysis(es) Requested			Container(s)																	
			EPA1613																	
			EPA8290																	
			EPA8280																	
			EPA1668																	
			EPA1614																	
			CARB429																	
			COPLANAR PCB's																	
			209 CONGENERS																	
			PBDE																	
			PAH																	
			WHO-29																	
			Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29

Sample ID	Date	Time	Location/Sample Description	Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29	
* A1-71 (0-0.5')	11/27/12	1330		1	G	So																
* A1-72 (0-0.5')	11/27/12	1400		1	G	So																
A1-65 (0-0.5')	11/27/12	1430		1	G	So																* HOLD *
A1-64 (0-0.5')	11/27/12	1500		1	G	So																* HOLD *
* EB 112712	11/27/12	1540		2	A	Aq																
A1-79 (0-0.5')	11/28/12	0900		1	G	So																* HOLD *
A1-78 (0-0.5')	11/28/12	0925		1	G	So																* HOLD *
A1-77 (0-0.5')	11/28/12	0950		1	G	So																* HOLD *
A1-76 (0-0.5')	11/28/12	1020		1	G	So																* HOLD *
A1-67 (0-0.5')	11/28/12	1115		1	G	So																* HOLD *

Special Instructions/Comments: * Sample logged in to work order 2110011

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGRAS
 Company: ARCADIS
 Address: 6602 EXCELSIOR RD.
 City: BAXTER State: MN Zip: 56425
 Phone: 218-829-4607 Fax: _____
 Email: DAVID.BESSINGRAS@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MMS Train, O = Other

*Bottle Preservative Type: T = Thiosulfate,
 O = Other



CHAIN OF CUSTODY

3 of 3

FOR LABORATORY USE ONLY Storage Secured

Laboratory Project ID: 2110012 Yes No

Storage ID: WR-2 Temp: 0.8 °C

Project I.D.: _____ P.O.# B0039275.0000.00002 Sampler: I. STEWART / R. STEVENSON
 (Name)

TAT: (Check One):
 Standard: 21 Days
 Rush (surcharge may apply):
 14 days 7 days Specify: _____

Invoice to: Name DAVID BESSINGRAT Company ARCADIS Address 6602 EXCELSIOR RD City BAXTER State MIN Zip 56425 Ph# 218-829-4607 Fax# _____

Relinquished by: (Signature and Printed Name) [Signature] Date: 11/28/12 Time: 1445 Received by: (Signature and Printed Name) [Signature] Date: 11/29/12 Time: 1040

Relinquished by: (Signature and Printed Name) _____ Date: _____ Time: _____ Received by: (Signature and Printed Name) _____ Date: _____ Time: _____

See "Sample Log-in Checklist" for additional sample information

SHIP TO: Vista Analytical Laboratory
 1104 Windfield Way
 El Dorado Hills, CA 95762
 (916) 673-1520 • Fax (916) 673-0106

Method of Shipment: _____

Tracking No.: _____

ATTN: _____

Container(s)		Add Analysis(es) Requested															
Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29

Sample ID	Date	Time	Location/Sample Description	Quantity	Type	Matrix	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	2378-TCDD	2378-TCDD/TCDF	PCDD/PCDF	TOTALS	COPLANAR PCB's	209 CONGENERS	PBDE	PAH	WHO-29			
<u>A1-66 (0-0.5')</u>	<u>11/28/12</u>	<u>1150</u>		<u>1</u>	<u>G</u>	<u>So</u>																		
<u>* EB 112812</u>	<u>11/28/12</u>	<u>1400</u>		<u>2</u>	<u>A</u>	<u>Aq</u>																		<u>* HOLD *</u>

Special Instructions/Comments:
* Sample logged in to \$WorkOrder 2110011
11/30/12 moved 'EB112812' to 2110012 as per Bill

SEND DOCUMENTATION AND RESULTS TO:

Name: DAVID BESSINGRAT
 Company: ARCADIS
 Address: 6602 EXCELSIOR RD.
 City: BAXTER State: MIN Zip: 56425
 Phone: 218-829-4607 Fax: _____
 Email: DAVID.BESSINGRAT@ARCADIS-US.COM
 Matrix Types: DW = Drinking Water, EF = Effluent, PP = Pulp/Paper,
 SD = Sediment, SL = Sludge, SO = Soil, WW = Wastewater, B = Blood/Serum
 AQ = Aqueous, O = Other

Container Types: A = 1 Liter Amber, G = Glass Jar
 P = PUF, T = MM5 Train, O = Other _____

*Bottle Preservative Type: T = Thiosulfate,
 O = Other _____

DATA QUALIFIERS & ABBREVIATIONS

B	This compound was also detected in the method blank.
D	Dilution
E	The amount detected is above the High Calibration Limit.
P	The amount reported is the maximum possible concentration due to possible chlorinated diphenylether interference.
H	Recovery was outside laboratory acceptance limits.
I	Chemical Interference
J	The amount detected is below the Low Calibration Limit.
*	See Cover Letter
Conc.	Concentration
DL	Sample-specific estimated detection limit
MDL	The minimum concentration of a substance that can be measured and reported with 99% confidence that the analyte concentration is greater than zero in the matrix tested.
EMPC	Estimated Maximum Possible Concentration
NA	Not applicable
RL	Reporting Limit – concentrations that correspond to low calibration point
ND	Not Detected
TEQ	Toxic Equivalency

Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.

Sample ID: DUP 2

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110012-01	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	13.3 g	QC Batch:	B2L0072	Date Extracted:	19-Dec-2012 14:30
Date Collected:	27-Nov-2012 0:00	% Solids:	76.6	Date Analyzed :	02-Jan-13 17:57	Column:	DB-225 Analyst: MAS
				29-Dec-12 17:26 Column: ZB-5 Analyst: MAS			

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.579				IS 13C-2,3,7,8-TCDD	82.3	40 - 135	
1,2,3,7,8-PeCDD	6.47				13C-1,2,3,7,8-PeCDD	81.7	40 - 135	
1,2,3,4,7,8-HxCDD	12.4				13C-1,2,3,4,7,8-HxCDD	80.3	40 - 135	
1,2,3,6,7,8-HxCDD	30.8				13C-1,2,3,6,7,8-HxCDD	79.9	40 - 135	
1,2,3,7,8,9-HxCDD	29.5				13C-1,2,3,7,8,9-HxCDD	79.2	40 - 135	
1,2,3,4,6,7,8-HpCDD	1160				13C-1,2,3,4,6,7,8-HpCDD	84.3	40 - 135	
OCDD	26800			B , E J	13C-OCDD	209	40 - 135	H
2,3,7,8-TCDF	0.769				13C-2,3,7,8-TCDF	79.2	40 - 135	
1,2,3,7,8-PeCDF	1.11			J	13C-1,2,3,7,8-PeCDF	79.0	40 - 135	
2,3,4,7,8-PeCDF	1.54			J	13C-2,3,4,7,8-PeCDF	85.0	40 - 135	
1,2,3,4,7,8-HxCDF	6.94				13C-1,2,3,4,7,8-HxCDF	89.1	40 - 135	
1,2,3,6,7,8-HxCDF	7.50				13C-1,2,3,6,7,8-HxCDF	82.3	40 - 135	
2,3,4,6,7,8-HxCDF	10.7				13C-2,3,4,6,7,8-HxCDF	78.6	40 - 135	
1,2,3,7,8,9-HxCDF	1.59			J	13C-1,2,3,7,8,9-HxCDF	80.3	40 - 135	
1,2,3,4,6,7,8-HpCDF	186				13C-1,2,3,4,6,7,8-HpCDF	81.9	40 - 135	
1,2,3,4,7,8,9-HpCDF	14.6				13C-1,2,3,4,7,8,9-HpCDF	92.4	40 - 135	
OCDF	871				13C-OCDF	107	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	72.3	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	39.5

TOTALS		
Total TCDD	9.10	10.2
Total PeCDD	47.1	
Total HxCDD	274	
Total HpCDD	2150	
Total TCDF	20.7	23.7
Total PeCDF	58.5	
Total HxCDF	205	
Total HpCDF	633	

DL - Sample specific estimated detection limit
 EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit
 The results are reported in dry weight.
 The sample size is reported in wet weight.

Sample ID: A1-65 (0-0.5)

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110012-02	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	12.9 g	QC Batch:	B2L0072	Date Extracted:	19-Dec-2012 14:30
Date Collected:	27-Nov-2012 14:30	% Solids:	78.4	Date Analyzed :	29-Dec-12 18:14	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND		0.269	UX	IS 13C-2,3,7,8-TCDD	86.8	40 - 135	
1,2,3,7,8-PeCDD	2.04			J	13C-1,2,3,7,8-PeCDD	85.9	40 - 135	
1,2,3,4,7,8-HxCDD	3.52				13C-1,2,3,4,7,8-HxCDD	79.2	40 - 135	
1,2,3,6,7,8-HxCDD	10.1				13C-1,2,3,6,7,8-HxCDD	73.6	40 - 135	
1,2,3,7,8,9-HxCDD	8.17				13C-1,2,3,7,8,9-HxCDD	74.5	40 - 135	
1,2,3,4,6,7,8-HpCDD	358				13C-1,2,3,4,6,7,8-HpCDD	77.2	40 - 135	
OCDD	12700			B , E J	13C-OCDD	176	40 - 135	H
2,3,7,8-TCDF	0.408			J	13C-2,3,7,8-TCDF	79.1	40 - 135	
1,2,3,7,8-PeCDF	0.336			J	13C-1,2,3,7,8-PeCDF	80.4	40 - 135	
2,3,4,7,8-PeCDF	0.778			J	13C-2,3,4,7,8-PeCDF	82.9	40 - 135	
1,2,3,4,7,8-HxCDF	1.93			J	13C-1,2,3,4,7,8-HxCDF	88.1	40 - 135	
1,2,3,6,7,8-HxCDF	1.42			J	13C-1,2,3,6,7,8-HxCDF	81.7	40 - 135	
2,3,4,6,7,8-HxCDF	2.32			J	13C-2,3,4,6,7,8-HxCDF	79.8	40 - 135	
1,2,3,7,8,9-HxCDF	0.193			J	13C-1,2,3,7,8,9-HxCDF	83.2	40 - 135	
1,2,3,4,6,7,8-HpCDF	41.3				13C-1,2,3,4,6,7,8-HpCDF	83.7	40 - 135	
1,2,3,4,7,8,9-HpCDF	3.13				13C-1,2,3,4,7,8,9-HpCDF	90.5	40 - 135	
OCDF	169				13C-OCDF	97.7	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	85.0	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 13.0

TOTALS		
Total TCDD	5.82	6.85
Total PeCDD	17.9	
Total HxCDD	89.8	
Total HpCDD	832	
Total TCDF	8.38	9.37
Total PeCDF	14.8	
Total HxCDF	47.4	
Total HpCDF	138	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-64 (0-0.5)

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110012-03	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	12.7 g	QC Batch:	B2L0072	Date Extracted:	19-Dec-2012 14:30
Date Collected:	27-Nov-2012 15:00	% Solids:	79.4	Date Analyzed :	02-Jan-13 18:29	Column:	DB-225 Analyst: MAS
					29-Dec-12 19:03	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.301			J	IS 13C-2,3,7,8-TCDD	79.5	40 - 135	
1,2,3,7,8-PeCDD	1.64			J	13C-1,2,3,7,8-PeCDD	83.1	40 - 135	
1,2,3,4,7,8-HxCDD	2.88				13C-1,2,3,4,7,8-HxCDD	87.0	40 - 135	
1,2,3,6,7,8-HxCDD	7.22				13C-1,2,3,6,7,8-HxCDD	80.9	40 - 135	
1,2,3,7,8,9-HxCDD	6.96				13C-1,2,3,7,8,9-HxCDD	80.4	40 - 135	
1,2,3,4,6,7,8-HpCDD	344				13C-1,2,3,4,6,7,8-HpCDD	81.6	40 - 135	
OCDD	17700			B, E J	13C-OCDD	201	40 - 135	H
2,3,7,8-TCDF	0.652				13C-2,3,7,8-TCDF	75.6	40 - 135	
1,2,3,7,8-PeCDF	0.419			J	13C-1,2,3,7,8-PeCDF	81.6	40 - 135	
2,3,4,7,8-PeCDF	0.524			J	13C-2,3,4,7,8-PeCDF	86.5	40 - 135	
1,2,3,4,7,8-HxCDF	1.48			J	13C-1,2,3,4,7,8-HxCDF	90.7	40 - 135	
1,2,3,6,7,8-HxCDF	1.09			J	13C-1,2,3,6,7,8-HxCDF	80.5	40 - 135	
2,3,4,6,7,8-HxCDF	1.76			J	13C-2,3,4,6,7,8-HxCDF	79.9	40 - 135	
1,2,3,7,8,9-HxCDF	0.139			J	13C-1,2,3,7,8,9-HxCDF	82.6	40 - 135	
1,2,3,4,6,7,8-HpCDF	25.8				13C-1,2,3,4,6,7,8-HpCDF	84.0	40 - 135	
1,2,3,4,7,8,9-HpCDF	1.88			J	13C-1,2,3,4,7,8,9-HpCDF	96.4	40 - 135	
OCDF	112				13C-OCDF	105	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	69.4	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	13.4

TOTALS		
Total TCDD	9.13	10.5
Total PeCDD	18.4	
Total HxCDD	75.2	
Total HpCDD	759	
Total TCDF	9.56	11.8
Total PeCDF	13.3	
Total HxCDF	31.5	
Total HpCDF	88.7	

DL - Sample specific estimated detection limit
 EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit
 The results are reported in dry weight.
 The sample size is reported in wet weight.

Sample ID: A1-67 (0-0.5)

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110012-08	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	12.3 g	QC Batch:	B2L0072	Date Extracted:	19-Dec-2012 14:30
Date Collected:	28-Nov-2012 11:15	% Solids:	81.7	Date Analyzed :	29-Dec-12 20:39	Column:	ZB-5 Analyst: MAS
					29-Dec-12 21:27	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.782				IS 13C-2,3,7,8-TCDD	85.5	40 - 135	
1,2,3,7,8-PeCDD	10.5				13C-1,2,3,7,8-PeCDD	93.8	40 - 135	
1,2,3,4,7,8-HxCDD	31.4				13C-1,2,3,4,7,8-HxCDD	84.2	40 - 135	
1,2,3,6,7,8-HxCDD	95.0				13C-1,2,3,6,7,8-HxCDD	80.3	40 - 135	
1,2,3,7,8,9-HxCDD	79.3				13C-1,2,3,7,8,9-HxCDD	81.7	40 - 135	
1,2,3,4,6,7,8-HpCDD	5010			E J	13C-1,2,3,4,6,7,8-HpCDD	123	40 - 135	
OCDD	170000			D, B, E J	13C-OCDD	302	40 - 135	D, H
2,3,7,8-TCDF	0.479			J	13C-2,3,7,8-TCDF	72.4	40 - 135	
1,2,3,7,8-PeCDF	0.807			J	13C-1,2,3,7,8-PeCDF	84.4	40 - 135	
2,3,4,7,8-PeCDF	1.58			J	13C-2,3,4,7,8-PeCDF	83.9	40 - 135	
1,2,3,4,7,8-HxCDF	7.87				13C-1,2,3,4,7,8-HxCDF	98.5	40 - 135	
1,2,3,6,7,8-HxCDF	5.54				13C-1,2,3,6,7,8-HxCDF	89.1	40 - 135	
2,3,4,6,7,8-HxCDF	11.1				13C-2,3,4,6,7,8-HxCDF	87.3	40 - 135	
1,2,3,7,8,9-HxCDF	0.737			J	13C-1,2,3,7,8,9-HxCDF	90.9	40 - 135	
1,2,3,4,6,7,8-HpCDF	468				13C-1,2,3,4,6,7,8-HpCDF	93.6	40 - 135	
1,2,3,4,7,8,9-HpCDF	29.3				13C-1,2,3,4,7,8,9-HpCDF	98.6	40 - 135	
OCDF	3970			J	13C-OCDF	170	40 - 135	H
					CRS 37Cl-2,3,7,8-TCDD	79.1	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 142

TOTALS		
Total TCDD	4.51	5.46
Total PeCDD	52.5	
Total HxCDD	601	
Total HpCDD	8240	
Total TCDF	9.56	10.2
Total PeCDF	34.4	38.6
Total HxCDF	327	
Total HpCDF	2250	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: A1-66 (0-0.5)

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Soil	Lab Sample:	2110012-09	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	13.1 g	QC Batch:	B2L0072	Date Extracted:	19-Dec-2012 14:30
Date Collected:	28-Nov-2012 11:50	% Solids:	77.5	Date Analyzed :	02-Jan-13 19:01	Column:	DB-225 Analyst: MAS
					29-Dec-12 19:51	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/g)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	0.870				IS 13C-2,3,7,8-TCDD	75.2	40 - 135	
1,2,3,7,8-PeCDD	4.85				13C-1,2,3,7,8-PeCDD	85.6	40 - 135	
1,2,3,4,7,8-HxCDD	11.5				13C-1,2,3,4,7,8-HxCDD	67.6	40 - 135	
1,2,3,6,7,8-HxCDD	44.5				13C-1,2,3,6,7,8-HxCDD	64.3	40 - 135	
1,2,3,7,8,9-HxCDD	27.1				13C-1,2,3,7,8,9-HxCDD	64.8	40 - 135	
1,2,3,4,6,7,8-HpCDD	1530				13C-1,2,3,4,6,7,8-HpCDD	72.8	40 - 135	
OCDD	30900			B , E J	13C-OCDD	198	40 - 135	H
2,3,7,8-TCDF	1.65				13C-2,3,7,8-TCDF	66.3	40 - 135	
1,2,3,7,8-PeCDF	2.29			J	13C-1,2,3,7,8-PeCDF	76.8	40 - 135	
2,3,4,7,8-PeCDF	3.86			J	13C-2,3,4,7,8-PeCDF	79.7	40 - 135	
1,2,3,4,7,8-HxCDF	7.81				13C-1,2,3,4,7,8-HxCDF	82.5	40 - 135	
1,2,3,6,7,8-HxCDF	5.86				13C-1,2,3,6,7,8-HxCDF	74.1	40 - 135	
2,3,4,6,7,8-HxCDF	9.08				13C-2,3,4,6,7,8-HxCDF	71.6	40 - 135	
1,2,3,7,8,9-HxCDF	0.745			J	13C-1,2,3,7,8,9-HxCDF	74.6	40 - 135	
1,2,3,4,6,7,8-HpCDF	189			J	13C-1,2,3,4,6,7,8-HpCDF	75.5	40 - 135	
1,2,3,4,7,8,9-HpCDF	13.1				13C-1,2,3,4,7,8,9-HpCDF	80.0	40 - 135	
OCDF	718				13C-OCDF	95.0	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	76.1	40 - 135	

Toxic Equivalent Quotient (TEQ) Data

TEQMinWHO2005Dioxin 44.6

TOTALS

Total TCDD	7.00		7.30	
Total PeCDD	36.3			
Total HxCDD	257			
Total HpCDD	2610			
Total TCDF	30.5			
Total PeCDF	52.9			
Total HxCDF	170			
Total HpCDF	639			

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL- Lower control limit - upper control limit

The results are reported in dry weight.

The sample size is reported in wet weight.

Sample ID: EB 112812

EPA Method 8290

Client Data		Sample Data		Laboratory Data			
Name:	ARCADIS	Matrix:	Aqueous	Lab Sample:	2110012-10	Date Received:	29-Nov-2012 10:23
Project:	Carbondale	Sample Size:	0.996 L	QC Batch:	B2L0077	Date Extracted:	20-Dec-2012 8:01
Date Collected:	28-Nov-2012 14:00			Date Analyzed :	27-Dec-12 14:05	Column:	ZB-5 Analyst: MAS

Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
2,3,7,8-TCDD	ND	1.70			IS 13C-2,3,7,8-TCDD	88.2	40 - 135	
1,2,3,7,8-PeCDD	ND	1.41			13C-1,2,3,7,8-PeCDD	105	40 - 135	
1,2,3,4,7,8-HxCDD	ND	2.03			13C-1,2,3,4,7,8-HxCDD	81.5	40 - 135	
1,2,3,6,7,8-HxCDD	ND	2.39			13C-1,2,3,6,7,8-HxCDD	81.4	40 - 135	
1,2,3,7,8,9-HxCDD	ND	2.37			13C-1,2,3,7,8,9-HxCDD	80.6	32 - 141	
1,2,3,4,6,7,8-HpCDD	ND	2.18			13C-1,2,3,4,6,7,8-HpCDD	80.0	40 - 135	
OCDD	ND	3.11			13C-OCDD	99.5	40 - 135	
2,3,7,8-TCDF	ND	0.616			13C-2,3,7,8-TCDF	86.2	40 - 135	
1,2,3,7,8-PeCDF	ND	1.41			13C-1,2,3,7,8-PeCDF	86.0	40 - 135	
2,3,4,7,8-PeCDF	ND	1.39			13C-2,3,4,7,8-PeCDF	86.6	40 - 135	
1,2,3,4,7,8-HxCDF	ND	1.20			13C-1,2,3,4,7,8-HxCDF	87.7	40 - 135	
1,2,3,6,7,8-HxCDF	ND	1.33			13C-1,2,3,6,7,8-HxCDF	82.4	40 - 135	
2,3,4,6,7,8-HxCDF	ND	1.52			13C-2,3,4,6,7,8-HxCDF	84.2	40 - 135	
1,2,3,7,8,9-HxCDF	ND	1.83			13C-1,2,3,7,8,9-HxCDF	89.7	40 - 135	
1,2,3,4,6,7,8-HpCDF	ND	1.26			13C-1,2,3,4,6,7,8-HpCDF	77.5	40 - 135	
1,2,3,4,7,8,9-HpCDF	ND	1.47			13C-1,2,3,4,7,8,9-HpCDF	90.5	40 - 135	
OCDF	ND	2.89			13C-OCDF	92.7	40 - 135	
					CRS 37Cl-2,3,7,8-TCDD	86.3	40 - 135	

Toxic Equivalent Quotient (TEQ) Data	
TEQMinWHO2005Dioxin	0.00

TOTALS		
Total TCDD	ND	3.01
Total PeCDD	ND	1.41
Total HxCDD	ND	3.23
Total HpCDD	ND	2.18
Total TCDF	ND	0.616
Total PeCDF	ND	1.77
Total HxCDF	ND	2.60
Total HpCDF	ND	1.12

DL - Sample specific estimated detection limit

LCL-UCL- Lower control limit - upper control limit

EMPC - Estimated maximum possible concentration



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 5
77 WEST JACKSON BOULEVARD
CHICAGO, IL 60604-3590

March 14, 2014

REPLY TO THE ATTENTION OF:
LU-9J

Certified Mail 7001 0320 0006 0192 7132
Return Receipt Requested and via Email

Mike Slenska
Three Rivers Management for
Beazer East, Inc.
Manor Oak One, Suite 200
1910 Cochran Rd.
Pittsburgh, PA 15220

Re: Response to Human Health Risk
Assessment Inquiry
Former Koppers Company Wood-
Treating Site, Carbondale, IL
U.S. EPA ID No. ILD 000 819 946

Dear Mr. Slenska:

Beazer recently asked EPA how to address the Northeast Carbondale neighborhood in the forthcoming Human Health Risk Assessment. Owing to the neighborhood's proximity to the Former Koppers Company Wood-Treating Site, EPA and IEPA (jointly), Beazer, and the City of Carbondale have at various times investigated the surface soil there for contamination. The evaluations proceeded due to the potential migration of site-related chemicals through surface run-off and airborne dispersion into the neighborhood.

The EPA's analysis of the soil analytical data and other evidence assembled to date indicate that the neighborhood south of the facility is not contaminated with wood-treating chemicals. The detected chemical concentrations in the neighborhood were generally in the range of urban area background concentrations. Therefore, consistent with EPA risk assessment protocol, the neighborhood south of the property does not need to be included in the risk analysis. Nonetheless, the risk assessment document should contain a description of the contaminant characterization that Beazer completed in the neighborhood, including a description of the sampling design (e.g., the rationale for sample locations) and data collection activities. The risk assessment document should include Beazer's sampling results and this letter in an appendix or attachment. In addition, the risk assessment document should make reference to the sampling results from 2005 (EPA and IEPA with Beazer's splits) and 2006 (City of Carbondale).

The following surface soil sampling events in the neighborhood supported EPA's analysis:

- 1) a soil sampling event that USEPA and IEPA completed in 2005
- 2) a soil sampling event that the City of Carbondale completed in 2006, and


3) soil sampling events completed by Beazer East, Inc. in 2012.

EPA also considered these other available lines of evidence:

- 1) the concentrations and distribution of analytes in the soil did not indicate airborne migration under current conditions
- 2) physical barriers present in the land surface between the Site and the neighborhood would likely prevent overland flow of chemical migration from the Koppers Site to the neighborhood during precipitation events (berm and drainage ditches)
- 3) the contaminant concentrations north of the property line (on the Koppers side) were orders of magnitude higher than the concentrations found in the neighborhood to the south (supporting the conclusion that physical barriers prevent overland flow/surface migration to the south)
- 4) the detected chemical concentrations in the neighborhood were generally in the range of urban area background concentrations, and
- 5) the containment remedies and their maintenance within the facility prevent chemicals being released off-site in the future.

Please call me at 312-886-3020 if you have any questions about this letter.

Sincerely,



Carolyn Bury
Project Manager

cc: Jim Moore, IEPA
Jeff Holden, Arcadis (electronic)



Appendix C

ProUCL Outputs

**APPENDIX C
PRO-UCL RESULTS FOR SOIL NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:11:31 PM
 From File Book1.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (arsenic)

General Statistics

Total Number of Observations	11	Number of Distinct Observations	11
		Number of Missing Observations	0
Minimum	6900	Mean	10000
Maximum	13000	Median	10400
SD	2109	Std. Error of Mean	635.9
Coefficient of Variation	0.211	Skewness	0.0997

Normal GOF Test

Shapiro Wilk Test Statistic	0.924	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.85	Data appear Normal at 5% Significance Level
Lilliefors Test Statistic	0.216	Lilliefors GOF Test
5% Lilliefors Critical Value	0.267	Data appear Normal at 5% Significance Level

Data appear Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL	95% UCLs (Adjusted for Skewness)
95% Student's-t UCL 11153	95% Adjusted-CLT UCL (Chen-1995) 11066
	95% Modified-t UCL (Johnson-1978) 11156

Gamma GOF Test

A-D Test Statistic	0.422	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.729	Detected data appear Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.216	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.255	Detected data appear Gamma Distributed at 5% Significance Level

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	24.36	k star (bias corrected MLE)	17.78
Theta hat (MLE)	410.5	Theta star (bias corrected MLE)	562.5
nu hat (MLE)	535.9	nu star (bias corrected)	391.1
MLE Mean (bias corrected)	10000	MLE Sd (bias corrected)	2372
		Approximate Chi Square Value (0.05)	346.3
Adjusted Level of Significance	0.0278	Adjusted Chi Square Value	339.4

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	11295	95% Adjusted Gamma UCL (use when n<50)	11524
--	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.927	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.85	Data appear Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.2	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.267	Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	8.839	Mean of logged Data	9.19
Maximum of Logged Data	9.473	SD of logged Data	0.214

Assuming Lognormal Distribution

95% H-UCL	11380	90% Chebyshev (MVUE) UCL	11951
95% Chebyshev (MVUE) UCL	12834	97.5% Chebyshev (MVUE) UCL	14059
99% Chebyshev (MVUE) UCL	16466		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	11046	95% Jackknife UCL	11153
95% Standard Bootstrap UCL	11006	95% Bootstrap-t UCL	11153
95% Hall's Bootstrap UCL	10954	95% Percentile Bootstrap UCL	11009
95% BCA Bootstrap UCL	10991		
90% Chebyshev(Mean, Sd) UCL	11908	95% Chebyshev(Mean, Sd) UCL	12772
97.5% Chebyshev(Mean, Sd) UCL	13971	99% Chebyshev(Mean, Sd) UCL	16327

Suggested UCL to Use

95% Student's-t UCL 11153

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SOIL NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:11:31 PM
 From File Book1.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (bap te (nds = 1/2 dl))

General Statistics

Total Number of Observations	11	Number of Distinct Observations	11
		Number of Missing Observations	0
Minimum	8.38	Mean	367.5
Maximum	1730	Median	138
SD	592.9	Std. Error of Mean	178.8
Coefficient of Variation	1.613	Skewness	1.887

Normal GOF Test

Shapiro Wilk Test Statistic	0.651	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.85	Data Not Normal at 5% Significance Level
Lilliefors Test Statistic	0.338	Lilliefors GOF Test
5% Lilliefors Critical Value	0.267	Data Not Normal at 5% Significance Level

Data Not Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	691.6	95% Adjusted-CLT UCL (Chen-1995)	770.3
		95% Modified-t UCL (Johnson-1978)	708.5

Gamma GOF Test

A-D Test Statistic	0.517	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.786	Detected data appear Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.178	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.27	Detected data appear Gamma Distributed at 5% Significance Level

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	0.477	k star (bias corrected MLE)	0.407
Theta hat (MLE)	771.3	Theta star (bias corrected MLE)	902.7
nu hat (MLE)	10.48	nu star (bias corrected)	8.958
MLE Mean (bias corrected)	367.5	MLE Sd (bias corrected)	576
		Approximate Chi Square Value (0.05)	3.301
Adjusted Level of Significance	0.0278	Adjusted Chi Square Value	2.766

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	997.2	95% Adjusted Gamma UCL (use when n<50)	1190
--	-------	--	------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.936	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.85	Data appear Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.134	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.267	Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	2.126	Mean of logged Data	4.564
Maximum of Logged Data	7.456	SD of logged Data	1.864

Assuming Lognormal Distribution

95% H-UCL	9484	90% Chebyshev (MVUE) UCL	1107
95% Chebyshev (MVUE) UCL	1430	97.5% Chebyshev (MVUE) UCL	1877
99% Chebyshev (MVUE) UCL	2756		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	661.6	95% Jackknife UCL	691.6
95% Standard Bootstrap UCL	652.7	95% Bootstrap-t UCL	1871
95% Hall's Bootstrap UCL	2395	95% Percentile Bootstrap UCL	674.9
95% BCA Bootstrap UCL	758.2		
90% Chebyshev(Mean, Sd) UCL	903.8	95% Chebyshev(Mean, Sd) UCL	1147
97.5% Chebyshev(Mean, Sd) UCL	1484	99% Chebyshev(Mean, Sd) UCL	2146

Suggested UCL to Use

95% Adjusted Gamma UCL 1190

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SOIL NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:11:31 PM
 From File Book1.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (chromium)

General Statistics

Total Number of Observations	11	Number of Distinct Observations	10
		Number of Missing Observations	0
Minimum	14700	Mean	19305
Maximum	28200	Median	19000
SD	4124	Std. Error of Mean	1243
Coefficient of Variation	0.214	Skewness	0.932

Normal GOF Test

Shapiro Wilk Test Statistic	0.916	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.85	Data appear Normal at 5% Significance Level
Lilliefors Test Statistic	0.159	Lilliefors GOF Test
5% Lilliefors Critical Value	0.267	Data appear Normal at 5% Significance Level

Data appear Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL	95% UCLs (Adjusted for Skewness)
95% Student's-t UCL 21558	95% Adjusted-CLT UCL (Chen-1995) 21723
	95% Modified-t UCL (Johnson-1978) 21616

Gamma GOF Test

A-D Test Statistic	0.299	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.729	Detected data appear Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.15	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.255	Detected data appear Gamma Distributed at 5% Significance Level

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	25.75	k star (bias corrected MLE)	18.79
Theta hat (MLE)	749.7	Theta star (bias corrected MLE)	1027
nu hat (MLE)	566.5	nu star (bias corrected)	413.3
MLE Mean (bias corrected)	19305	MLE Sd (bias corrected)	4454
		Approximate Chi Square Value (0.05)	367.2
Adjusted Level of Significance	0.0278	Adjusted Chi Square Value	360.1

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	21730	95% Adjusted Gamma UCL (use when n<50)	22158
--	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.942	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.85	Data appear Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.145	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.267	Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	9.596	Mean of logged Data	9.849
Maximum of Logged Data	10.25	SD of logged Data	0.205

Assuming Lognormal Distribution

95% H-UCL	21812	90% Chebyshev (MVUE) UCL	22882
95% Chebyshev (MVUE) UCL	24507	97.5% Chebyshev (MVUE) UCL	26763
99% Chebyshev (MVUE) UCL	31193		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	21350	95% Jackknife UCL	21558
95% Standard Bootstrap UCL	21279	95% Bootstrap-t UCL	22227
95% Hall's Bootstrap UCL	22717	95% Percentile Bootstrap UCL	21355
95% BCA Bootstrap UCL	21555		
90% Chebyshev(Mean, Sd) UCL	23035	95% Chebyshev(Mean, Sd) UCL	24725
97.5% Chebyshev(Mean, Sd) UCL	27070	99% Chebyshev(Mean, Sd) UCL	31677

Suggested UCL to Use

95% Student's-t UCL 21558

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
Date/Time of Computation 10/25/2014 11:10:21 PM
From File Book1_a.xls
Full Precision OFF
Confidence Coefficient 95%
Number of Bootstrap Operations 2000

Result (arsenic)

General Statistics

Total Number of Observations	8	Number of Distinct Observations	8
		Number of Missing Observations	0
Minimum	6300	Mean	7531
Maximum	9400	Median	7550
SD	986.7	Std. Error of Mean	348.8
Coefficient of Variation	0.131	Skewness	0.678

Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.

For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).

Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.0

Normal GOF Test

Shapiro Wilk Test Statistic	0.934	Shapiro Wilk GOF Test	
5% Shapiro Wilk Critical Value	0.818	Data appear Normal at 5% Significance Level	
Lilliefors Test Statistic	0.182	Lilliefors GOF Test	
5% Lilliefors Critical Value	0.313	Data appear Normal at 5% Significance Level	

Data appear Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	8192	95% Adjusted-CLT UCL (Chen-1995)	8194
		95% Modified-t UCL (Johnson-1978)	8206

Gamma GOF Test

A-D Test Statistic	0.292	Anderson-Darling Gamma GOF Test	
5% A-D Critical Value	0.715	Detected data appear Gamma Distributed at 5% Significance Level	
K-S Test Statistic	0.161	Kolmogrov-Smirnov Gamma GOF Test	
5% K-S Critical Value	0.293	Detected data appear Gamma Distributed at 5% Significance Level	

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	68.47	k star (bias corrected MLE)	42.88
Theta hat (MLE)	110	Theta star (bias corrected MLE)	175.6
nu hat (MLE)	1096	nu star (bias corrected)	686.1
MLE Mean (bias corrected)	7531	MLE Sd (bias corrected)	1150
		Approximate Chi Square Value (0.05)	626.3
Adjusted Level of Significance	0.0195	Adjusted Chi Square Value	611.8

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50))	8250	95% Adjusted Gamma UCL (use when n<50)	8446
---	------	--	------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.946	Shapiro Wilk Lognormal GOF Test	
5% Shapiro Wilk Critical Value	0.818	Data appear Lognormal at 5% Significance Level	
Lilliefors Test Statistic	0.159	Lilliefors Lognormal GOF Test	
5% Lilliefors Critical Value	0.313	Data appear Lognormal at 5% Significance Level	

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	8.748	Mean of logged Data	8.919
Maximum of Logged Data	9.148	SD of logged Data	0.129

Assuming Lognormal Distribution

95% H-UCL	8258	90% Chebyshev (MVUE) UCL	8559
95% Chebyshev (MVUE) UCL	9025	97.5% Chebyshev (MVUE) UCL	9672
99% Chebyshev (MVUE) UCL	10942		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	8105	95% Jackknife UCL	8192
95% Standard Bootstrap UCL	8070	95% Bootstrap-t UCL	8291
95% Hall's Bootstrap UCL	8541	95% Percentile Bootstrap UCL	8100
95% BCA Bootstrap UCL	8125		
90% Chebyshev (Mean, Sd) UCL	8578	95% Chebyshev (Mean, Sd) UCL	9052
97.5% Chebyshev (Mean, Sd) UCL	9710	99% Chebyshev (Mean, Sd) UCL	11002

Suggested UCL to Use

95% Student's-t UCL 8192

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.

These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets.

For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
Date/Time of Computation 10/25/2014 11:10:21 PM
From File Book1_a.xls
Full Precision OFF
Confidence Coefficient 95%
Number of Bootstrap Operations 2000

Result (bap te (nds = 1/2 dl))

General Statistics

Total Number of Observations	8	Number of Distinct Observations	8
		Number of Missing Observations	0
Minimum	65.6	Mean	165.7
Maximum	236	Median	190
SD	67.04	Std. Error of Mean	23.7
Coefficient of Variation	0.405	Skewness	-0.651

Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.

For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).

Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.0

Normal GOF Test

Shapiro Wilk Test Statistic	0.876	Shapiro Wilk GOF Test	
5% Shapiro Wilk Critical Value	0.818	Data appear Normal at 5% Significance Level	
Lilliefors Test Statistic	0.25	Lilliefors GOF Test	
5% Lilliefors Critical Value	0.313	Data appear Normal at 5% Significance Level	

Data appear Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	210.6	95% Adjusted-CLT UCL (Chen-1995)	198.9
		95% Modified-t UCL (Johnson-1978)	209.7

Gamma GOF Test

A-D Test Statistic	0.633	Anderson-Darling Gamma GOF Test	
5% A-D Critical Value	0.719	Detected data appear Gamma Distributed at 5% Significance Level	
K-S Test Statistic	0.291	Kolmogrov-Smirnov Gamma GOF Test	
5% K-S Critical Value	0.295	Detected data appear Gamma Distributed at 5% Significance Level	

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	5.397	k star (bias corrected MLE)	3.456
Theta hat (MLE)	30.7	Theta star (bias corrected MLE)	47.94
nu hat (MLE)	86.35	nu star (bias corrected)	55.3
MLE Mean (bias corrected)	165.7	MLE Sd (bias corrected)	89.13
		Approximate Chi Square Value (0.05)	39.21
Adjusted Level of Significance	0.0195	Adjusted Chi Square Value	35.81

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50))	233.7	95% Adjusted Gamma UCL (use when n<50)	255.9
---	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.828	Shapiro Wilk Lognormal GOF Test	
5% Shapiro Wilk Critical Value	0.818	Data appear Lognormal at 5% Significance Level	
Lilliefors Test Statistic	0.292	Lilliefors Lognormal GOF Test	
5% Lilliefors Critical Value	0.313	Data appear Lognormal at 5% Significance Level	

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	4.184	Mean of logged Data	5.015
Maximum of Logged Data	5.464	SD of logged Data	0.502

Assuming Lognormal Distribution

95% H-UCL	267.2	90% Chebyshev (MVUE) UCL	258.3
95% Chebyshev (MVUE) UCL	299.2	97.5% Chebyshev (MVUE) UCL	356
99% Chebyshev (MVUE) UCL	467.5		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	204.7	95% Jackknife UCL	210.6
95% Standard Bootstrap UCL	201.8	95% Bootstrap-t UCL	204.8
95% Hall's Bootstrap UCL	195.5	95% Percentile Bootstrap UCL	199.8
95% BCA Bootstrap UCL	198.1		
90% Chebyshev(Mean, Sd) UCL	236.8	95% Chebyshev(Mean, Sd) UCL	269
97.5% Chebyshev(Mean, Sd) UCL	313.7	99% Chebyshev(Mean, Sd) UCL	401.5

Suggested UCL to Use

95% Student's-t UCL 210.6

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.

These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets.

For additional insight the user may want to consult a statistician.

Note: For highly negatively-skewed data, confidence limits (e.g., Chen, Johnson, Lognormal, and Gamma) may not be reliable. Chen's and Johnson's methods provide adjustments for positively skewed data sets.

**APPENDIX C
PRO-UCL RESULTS FOR SOIL EAST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:10:21 PM
 From File Book1_a.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (chromium)

General Statistics

Total Number of Observations	8	Number of Distinct Observations	8
		Number of Missing Observations	0
Minimum	15800	Mean	19950
Maximum	27400	Median	19650
SD	3887	Std. Error of Mean	1374
Coefficient of Variation	0.195	Skewness	0.91

Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.

For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).

Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.0

Normal GOF Test

Shapiro Wilk Test Statistic	0.914	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.818	Data appear Normal at 5% Significance Level
Lilliefors Test Statistic	0.181	Lilliefors GOF Test
5% Lilliefors Critical Value	0.313	Data appear Normal at 5% Significance Level

Data appear Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL	95% UCLs (Adjusted for Skewness)
95% Student's-t UCL 22553	95% Adjusted-CLT UCL (Chen-1995) 22683
	95% Modified-t UCL (Johnson-1978) 22627

Gamma GOF Test

A-D Test Statistic	0.307	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.716	Detected data appear Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.203	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.294	Detected data appear Gamma Distributed at 5% Significance Level

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	31.93	k star (bias corrected MLE)	20.04
Theta hat (MLE)	624.8	Theta star (bias corrected MLE)	995.5
nu hat (MLE)	510.9	nu star (bias corrected)	320.6
MLE Mean (bias corrected)	19950	MLE Sd (bias corrected)	4456
		Approximate Chi Square Value (0.05)	280.2
Adjusted Level of Significance	0.0195	Adjusted Chi Square Value	270.6

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	22833	95% Adjusted Gamma UCL (use when n<50)	23644
--	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.935	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.818	Data appear Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.19	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.313	Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	9.668	Mean of logged Data	9.885
Maximum of Logged Data	10.22	SD of logged Data	0.187

Assuming Lognormal Distribution

95% H-UCL	22914	90% Chebyshev (MVUE) UCL	23912
95% Chebyshev (MVUE) UCL	25711	97.5% Chebyshev (MVUE) UCL	28207
99% Chebyshev (MVUE) UCL	33110		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	22210	95% Jackknife UCL	22553
95% Standard Bootstrap UCL	22050	95% Bootstrap-t UCL	23312
95% Hall's Bootstrap UCL	22965	95% Percentile Bootstrap UCL	22213
95% BCA Bootstrap UCL	22388		
90% Chebyshev(Mean, Sd) UCL	24072	95% Chebyshev(Mean, Sd) UCL	25940
97.5% Chebyshev(Mean, Sd) UCL	28531	99% Chebyshev(Mean, Sd) UCL	33622

Suggested UCL to Use

95% Student's-t UCL 22553

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.

These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets.

For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SEDIMENT NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:09:10 PM
 From File Book1_b.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (arsenic)

General Statistics

Total Number of Observations	14	Number of Distinct Observations	13
		Number of Missing Observations	0
Minimum	6700	Mean	11893
Maximum	29200	Median	9400
SD	6440	Std. Error of Mean	1721
Coefficient of Variation	0.542	Skewness	1.89

Normal GOF Test

Shapiro Wilk Test Statistic	0.762	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.874	Data Not Normal at 5% Significance Level
Lilliefors Test Statistic	0.285	Lilliefors GOF Test
5% Lilliefors Critical Value	0.237	Data Not Normal at 5% Significance Level

Data Not Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	14941	95% Adjusted-CLT UCL (Chen-1995)	15653
		95% Modified-t UCL (Johnson-1978)	15086

Gamma GOF Test

A-D Test Statistic	0.847	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.738	Data Not Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.226	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.229	Detected data appear Gamma Distributed at 5% Significance Level

Detected data follow Appr. Gamma Distribution at 5% Significance Level

Gamma Statistics

k hat (MLE)	5.053	k star (bias corrected MLE)	4.018
Theta hat (MLE)	2354	Theta star (bias corrected MLE)	2960
nu hat (MLE)	141.5	nu star (bias corrected)	112.5
MLE Mean (bias corrected)	11893	MLE Sd (bias corrected)	5933
		Approximate Chi Square Value (0.05)	89.01
Adjusted Level of Significance	0.0312	Adjusted Chi Square Value	86.24

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	15031	95% Adjusted Gamma UCL (use when n<50)	15513
--	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.883	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.874	Data appear Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.193	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.237	Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	8.81	Mean of logged Data	9.281
Maximum of Logged Data	10.28	SD of logged Data	0.439

Assuming Lognormal Distribution

95% H-UCL	15088	90% Chebyshev (MVUE) UCL	15961
95% Chebyshev (MVUE) UCL	17874	97.5% Chebyshev (MVUE) UCL	20530
99% Chebyshev (MVUE) UCL	25747		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	14724	95% Jackknife UCL	14941
95% Standard Bootstrap UCL	14634	95% Bootstrap-t UCL	18076
95% Hall's Bootstrap UCL	26175	95% Percentile Bootstrap UCL	14686
95% BCA Bootstrap UCL	15757		
90% Chebyshev(Mean, Sd) UCL	17056	95% Chebyshev(Mean, Sd) UCL	19395
97.5% Chebyshev(Mean, Sd) UCL	22642	99% Chebyshev(Mean, Sd) UCL	29018

Suggested UCL to Use

95% Adjusted Gamma UCL 15513

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.

These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets.

For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SEDIMENT NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:09:10 PM
 From File Book1_b.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (bap te (nds = 1/2 dl))

General Statistics			
Total Number of Observations	14	Number of Distinct Observations	14
		Number of Missing Observations	0
Minimum	74.2	Mean	726.6
Maximum	2600	Median	592.5
SD	648	Std. Error of Mean	173.2
Coefficient of Variation	0.892	Skewness	1.995

Normal GOF Test		Shapiro Wilk GOF Test	
Shapiro Wilk Test Statistic	0.806	Data Not Normal at 5% Significance Level	
5% Shapiro Wilk Critical Value	0.874		
Lilliefors Test Statistic	0.218	Lilliefors GOF Test	
5% Lilliefors Critical Value	0.237	Data appear Normal at 5% Significance Level	

Data appear Approximate Normal at 5% Significance Level

Assuming Normal Distribution			
95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	1033	95% Adjusted-CLT UCL (Chen-1995)	1110
		95% Modified-t UCL (Johnson-1978)	1049

Gamma GOF Test		Anderson-Darling Gamma GOF Test	
A-D Test Statistic	0.204	Detected data appear Gamma Distributed at 5% Significance Level	
5% A-D Critical Value	0.75		
K-S Test Statistic	0.123	Kolmogrov-Smirnov Gamma GOF Test	
5% K-S Critical Value	0.233	Detected data appear Gamma Distributed at 5% Significance Level	

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics			
k hat (MLE)	1.573	k star (bias corrected MLE)	1.284
Theta hat (MLE)	461.8	Theta star (bias corrected MLE)	566
nu hat (MLE)	44.05	nu star (bias corrected)	35.95
MLE Mean (bias corrected)	726.6	MLE Sd (bias corrected)	641.3
		Approximate Chi Square Value (0.05)	23.23
Adjusted Level of Significance	0.0312	Adjusted Chi Square Value	21.88

Assuming Gamma Distribution			
95% Approximate Gamma UCL (use when n>=50)	1125	95% Adjusted Gamma UCL (use when n<50)	1194

Lognormal GOF Test		Shapiro Wilk Lognormal GOF Test	
Shapiro Wilk Test Statistic	0.978	Data appear Lognormal at 5% Significance Level	
5% Shapiro Wilk Critical Value	0.874		
Lilliefors Test Statistic	0.145	Lilliefors Lognormal GOF Test	
5% Lilliefors Critical Value	0.237	Data appear Lognormal at 5% Significance Level	

Data appear Lognormal at 5% Significance Level

Lognormal Statistics			
Minimum of Logged Data	4.307	Mean of logged Data	6.238
Maximum of Logged Data	7.863	SD of logged Data	0.92

Assuming Lognormal Distribution			
95% H-UCL	1540	90% Chebyshev (MVUE) UCL	1346
95% Chebyshev (MVUE) UCL	1616	97.5% Chebyshev (MVUE) UCL	1991
99% Chebyshev (MVUE) UCL	2727		

Nonparametric Distribution Free UCL Statistics
Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs			
95% CLT UCL	1011	95% Jackknife UCL	1033
95% Standard Bootstrap UCL	1004	95% Bootstrap-t UCL	1230
95% Hall's Bootstrap UCL	2427	95% Percentile Bootstrap UCL	1025
95% BCA Bootstrap UCL	1099		
90% Chebyshev(Mean, Sd) UCL	1246	95% Chebyshev(Mean, Sd) UCL	1482
97.5% Chebyshev(Mean, Sd) UCL	1808	99% Chebyshev(Mean, Sd) UCL	2450

Suggested UCL to Use
 95% Student's-t UCL 1033

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR SEDIMENT NORTH WEST OF THE SITE
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:09:10 PM
 From File Book1_b.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (chromium)

General Statistics

Total Number of Observations	14	Number of Distinct Observations	14
		Number of Missing Observations	0
Minimum	14600	Mean	22057
Maximum	60500	Median	19550
SD	11693	Std. Error of Mean	3125
Coefficient of Variation	0.53	Skewness	3.098

Normal GOF Test

Shapiro Wilk Test Statistic	0.589	Shapiro Wilk GOF Test
5% Shapiro Wilk Critical Value	0.874	Data Not Normal at 5% Significance Level
Lilliefors Test Statistic	0.297	Lilliefors GOF Test
5% Lilliefors Critical Value	0.237	Data Not Normal at 5% Significance Level

Data Not Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL		95% UCLs (Adjusted for Skewness)	
95% Student's-t UCL	27592	95% Adjusted-CLT UCL (Chen-1995)	29963
		95% Modified-t UCL (Johnson-1978)	28023

Gamma GOF Test

A-D Test Statistic	1.324	Anderson-Darling Gamma GOF Test
5% A-D Critical Value	0.737	Data Not Gamma Distributed at 5% Significance Level
K-S Test Statistic	0.23	Kolmogrov-Smirnov Gamma GOF Test
5% K-S Critical Value	0.229	Data Not Gamma Distributed at 5% Significance Level

Data Not Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	6.475	k star (bias corrected MLE)	5.135
Theta hat (MLE)	3406	Theta star (bias corrected MLE)	4295
nu hat (MLE)	181.3	nu star (bias corrected)	143.8
MLE Mean (bias corrected)	22057	MLE Sd (bias corrected)	9733
		Approximate Chi Square Value (0.05)	117.1
Adjusted Level of Significance	0.0312	Adjusted Chi Square Value	113.9

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50)	27089	95% Adjusted Gamma UCL (use when n<50)	27849
--	-------	--	-------

Lognormal GOF Test

Shapiro Wilk Test Statistic	0.774	Shapiro Wilk Lognormal GOF Test
5% Shapiro Wilk Critical Value	0.874	Data Not Lognormal at 5% Significance Level
Lilliefors Test Statistic	0.203	Lilliefors Lognormal GOF Test
5% Lilliefors Critical Value	0.237	Data appear Lognormal at 5% Significance Level

Data appear Approximate Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	9.589	Mean of logged Data	9.922
Maximum of Logged Data	11.01	SD of logged Data	0.368

Assuming Lognormal Distribution

95% H-UCL	26618	90% Chebyshev (MVUE) UCL	28198
95% Chebyshev (MVUE) UCL	31144	97.5% Chebyshev (MVUE) UCL	35233
99% Chebyshev (MVUE) UCL	43264		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	27198	95% Jackknife UCL	27592
95% Standard Bootstrap UCL	27069	95% Bootstrap-t UCL	36523
95% Hall's Bootstrap UCL	46812	95% Percentile Bootstrap UCL	27871
95% BCA Bootstrap UCL	30450		
90% Chebyshev(Mean, Sd) UCL	31433	95% Chebyshev(Mean, Sd) UCL	35679
97.5% Chebyshev(Mean, Sd) UCL	41574	99% Chebyshev(Mean, Sd) UCL	53152

Suggested UCL to Use

95% Student's-t UCL 27592 or 95% Modified-t UCL 28023

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR PILES FORK CRAB ORCHARD CREEK SEDIMENT
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:07:46 PM
 From File Book1_c.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (arsenic)

General Statistics

Total Number of Observations	19	Number of Distinct Observations	19
		Number of Missing Observations	0
Minimum	5950	Mean	8900
Maximum	16600	Median	8100
SD	3068	Std. Error of Mean	703.8
Coefficient of Variation	0.345	Skewness	1.439

Normal GOF Test

Shapiro Wilk Test Statistic 0.834
 5% Shapiro Wilk Critical Value 0.901
 Lilliefors Test Statistic 0.191
 5% Lilliefors Critical Value 0.203

Shapiro Wilk GOF Test

Data Not Normal at 5% Significance Level

Lilliefors GOF Test

Data appear Normal at 5% Significance Level

Data appear Approximate Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL

95% Student's-t UCL 10120

95% UCLs (Adjusted for Skewness)

95% Adjusted-CLT UCL (Chen-1995) 10306
 95% Modified-t UCL (Johnson-1978) 10159

Gamma GOF Test

A-D Test Statistic 0.74
 5% A-D Critical Value 0.741
 K-S Test Statistic 0.151
 5% K-S Critical Value 0.199

Anderson-Darling Gamma GOF Test

Detected data appear Gamma Distributed at 5% Significance Level

Kolmogrov-Smirnoff Gamma GOF Test

Detected data appear Gamma Distributed at 5% Significance Level

Detected data appear Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	10.69	k star (bias corrected MLE)	9.039
Theta hat (MLE)	832.4	Theta star (bias corrected MLE)	984.6
nu hat (MLE)	406.3	nu star (bias corrected)	343.5
MLE Mean (bias corrected)	8900	MLE Sd (bias corrected)	2960
		Approximate Chi Square Value (0.05)	301.5
Adjusted Level of Significance	0.0369	Adjusted Chi Square Value	298.1

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50) 10138

95% Adjusted Gamma UCL (use when n<50) 10255

Lognormal GOF Test

Shapiro Wilk Test Statistic 0.91
 5% Shapiro Wilk Critical Value 0.901
 Lilliefors Test Statistic 0.134
 5% Lilliefors Critical Value 0.203

Shapiro Wilk Lognormal GOF Test

Data appear Lognormal at 5% Significance Level

Lilliefors Lognormal GOF Test

Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	8.691	Mean of logged Data	9.046
Maximum of Logged Data	9.717	SD of logged Data	0.305

Assuming Lognormal Distribution

95% H-UCL	10151	90% Chebyshev (MVUE) UCL	10752
95% Chebyshev (MVUE) UCL	11605	97.5% Chebyshev (MVUE) UCL	12790
99% Chebyshev (MVUE) UCL	15117		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	10058	95% Jackknife UCL	10120
95% Standard Bootstrap UCL	10024	95% Bootstrap-t UCL	10612
95% Hall's Bootstrap UCL	10671	95% Percentile Bootstrap UCL	10058
95% BCA Bootstrap UCL	10274		
90% Chebyshev(Mean, Sd) UCL	11011	95% Chebyshev(Mean, Sd) UCL	11968
97.5% Chebyshev(Mean, Sd) UCL	13295	99% Chebyshev(Mean, Sd) UCL	15903

Suggested UCL to Use

95% Student's-t UCL 10120

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.

These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets.

For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR PILES FORK CRAB ORCHARD CREEK SEDIMENT
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:07:46 PM
 From File Book1_c.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (bap te (nds = 1/2 dl))

General Statistics

Total Number of Observations	13	Number of Distinct Observations	13
		Number of Missing Observations	0
Minimum	30.4	Mean	4055
Maximum	37300	Median	969
SD	10035	Std. Error of Mean	2783
Coefficient of Variation	2.475	Skewness	3.548

Normal GOF Test

Shapiro Wilk Test Statistic 0.394
 5% Shapiro Wilk Critical Value 0.866
 Lilliefors Test Statistic 0.459
 5% Lilliefors Critical Value 0.246

Shapiro Wilk GOF Test

Data Not Normal at 5% Significance Level

Lilliefors GOF Test

Data Not Normal at 5% Significance Level

Data Not Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL

95% Student's-t UCL 9015

95% UCLs (Adjusted for Skewness)

95% Adjusted-CLT UCL (Chen-1995) 11559
 95% Modified-t UCL (Johnson-1978) 9472

Gamma GOF Test

A-D Test Statistic 1.42
 5% A-D Critical Value 0.791
 K-S Test Statistic 0.3
 5% K-S Critical Value 0.25

Anderson-Darling Gamma GOF Test

Data Not Gamma Distributed at 5% Significance Level

Kolmogrov-Smirnov Gamma GOF Test

Data Not Gamma Distributed at 5% Significance Level

Data Not Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	0.495	k star (bias corrected MLE)	0.432
Theta hat (MLE)	8190	Theta star (bias corrected MLE)	9384
nu hat (MLE)	12.87	nu star (bias corrected)	11.24
MLE Mean (bias corrected)	4055	MLE Sd (bias corrected)	6169
		Approximate Chi Square Value (0.05)	4.728
Adjusted Level of Significance	0.0301	Adjusted Chi Square Value	4.142

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50) 9637

95% Adjusted Gamma UCL (use when n<50) 10998

Lognormal GOF Test

Shapiro Wilk Test Statistic 0.898
 5% Shapiro Wilk Critical Value 0.866
 Lilliefors Test Statistic 0.192
 5% Lilliefors Critical Value 0.246

Shapiro Wilk Lognormal GOF Test

Data appear Lognormal at 5% Significance Level

Lilliefors Lognormal GOF Test

Data appear Lognormal at 5% Significance Level

Data appear Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	3.414	Mean of logged Data	7.023
Maximum of Logged Data	10.53	SD of logged Data	1.578

Assuming Lognormal Distribution

95% H-UCL	23344	90% Chebyshev (MVUE) UCL	8056
95% Chebyshev (MVUE) UCL	10224	97.5% Chebyshev (MVUE) UCL	13232
99% Chebyshev (MVUE) UCL	19142		

Nonparametric Distribution Free UCL Statistics

Data appear to follow a Discernible Distribution at 5% Significance Level

Nonparametric Distribution Free UCLs

95% CLT UCL	8633	95% Jackknife UCL	9015
95% Standard Bootstrap UCL	8444	95% Bootstrap-t UCL	43629
95% Hall's Bootstrap UCL	28794	95% Percentile Bootstrap UCL	9513
95% BCA Bootstrap UCL	12437		
90% Chebyshev(Mean, Sd) UCL	12404	95% Chebyshev(Mean, Sd) UCL	16186
97.5% Chebyshev(Mean, Sd) UCL	21436	99% Chebyshev(Mean, Sd) UCL	31747

Suggested UCL to Use

99% Chebyshev (Mean, Sd) UCL 31747

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.

**APPENDIX C
PRO-UCL RESULTS FOR PILES FORK CRAB ORCHARD CREEK SEDIMENT
FORMER KOPPERS WOOD-TREATING SITE, CARBONDALE, ILLINOIS**

UCL Statistics for Data Sets with Non-Detects

User Selected Options
 Date/Time of Computation 10/25/2014 11:07:46 PM
 From File Book1_c.xls
 Full Precision OFF
 Confidence Coefficient 95%
 Number of Bootstrap Operations 2000

Result (chromium)

General Statistics

Total Number of Observations	19	Number of Distinct Observations	15
		Number of Missing Observations	0
Minimum	12600	Mean	15734
Maximum	22500	Median	14650
SD	2920	Std. Error of Mean	669.9
Coefficient of Variation	0.186	Skewness	1.435

Normal GOF Test

Shapiro Wilk Test Statistic 0.817
 5% Shapiro Wilk Critical Value 0.901
 Lilliefors Test Statistic 0.231
 5% Lilliefors Critical Value 0.203

Shapiro Wilk GOF Test

Data Not Normal at 5% Significance Level

Lilliefors GOF Test

Data Not Normal at 5% Significance Level

Data Not Normal at 5% Significance Level

Assuming Normal Distribution

95% Normal UCL

95% Student's-t UCL 16896

95% UCLs (Adjusted for Skewness)

95% Adjusted-CLT UCL (Chen-1995) 17072
 95% Modified-t UCL (Johnson-1978) 16933

Gamma GOF Test

A-D Test Statistic 1.132
 5% A-D Critical Value 0.74
 K-S Test Statistic 0.22
 5% K-S Critical Value 0.198

Anderson-Darling Gamma GOF Test

Data Not Gamma Distributed at 5% Significance Level

Kolmogrov-Smirnov Gamma GOF Test

Data Not Gamma Distributed at 5% Significance Level

Data Not Gamma Distributed at 5% Significance Level

Gamma Statistics

k hat (MLE)	34.67	k star (bias corrected MLE)	29.23
Theta hat (MLE)	453.8	Theta star (bias corrected MLE)	538.2
nu hat (MLE)	1318	nu star (bias corrected)	1111
MLE Mean (bias corrected)	15734	MLE Sd (bias corrected)	2910
		Approximate Chi Square Value (0.05)	1035
Adjusted Level of Significance	0.0369	Adjusted Chi Square Value	1028

Assuming Gamma Distribution

95% Approximate Gamma UCL (use when n>=50) 16896

95% Adjusted Gamma UCL (use when n<50) 17002

Lognormal GOF Test

Shapiro Wilk Test Statistic 0.865
 5% Shapiro Wilk Critical Value 0.901
 Lilliefors Test Statistic 0.209
 5% Lilliefors Critical Value 0.203

Shapiro Wilk Lognormal GOF Test

Data Not Lognormal at 5% Significance Level

Lilliefors Lognormal GOF Test

Data Not Lognormal at 5% Significance Level

Data Not Lognormal at 5% Significance Level

Lognormal Statistics

Minimum of Logged Data	9.441	Mean of logged Data	9.649
Maximum of Logged Data	10.02	SD of logged Data	0.17

Assuming Lognormal Distribution

95% H-UCL	16886	90% Chebyshev (MVUE) UCL	17569
95% Chebyshev (MVUE) UCL	18405	97.5% Chebyshev (MVUE) UCL	19567
99% Chebyshev (MVUE) UCL	21848		

Nonparametric Distribution Free UCL Statistics

Data do not follow a Discernible Distribution (0.05)

Nonparametric Distribution Free UCLs

95% CLT UCL	16836	95% Jackknife UCL	16896
95% Standard Bootstrap UCL	16806	95% Bootstrap-t UCL	17304
95% Hall's Bootstrap UCL	17308	95% Percentile Bootstrap UCL	16879
95% BCA Bootstrap UCL	17137		
90% Chebyshev(Mean, Sd) UCL	17744	95% Chebyshev(Mean, Sd) UCL	18654
97.5% Chebyshev(Mean, Sd) UCL	19918	99% Chebyshev(Mean, Sd) UCL	22400

Suggested UCL to Use

95% Student's-t UCL 16896

or 95% Modified-t UCL 16933

Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL. These recommendations are based upon the results of the simulation studies summarized in Singh, Singh, and Iaci (2002) and Singh and Singh (2003). However, simulation results will not cover all Real World data sets. For additional insight the user may want to consult a statistician.