

**CORRECTIVE ACTION MONITORING REPORT  
2010 FIRST SEMIANNUAL EVENT**

**FORMER HOUSTON WOOD PRESERVING WORKS  
4910 LIBERTY ROAD  
HOUSTON, TEXAS**

July 19, 2010

*Prepared for:*


Mr. Geoffrey Reeder, P.G.  
**UNION PACIFIC RAILROAD COMPANY**

24125 Aldine Westfield Road  
Spring, Texas 77373

*Prepared by:*

**PASTOR, BEHLING & WHEELER, LLC**

2201 Double Creek Drive, Suite 4004  
Round Rock, Texas 78664  
(512) 671-3434



PBW Project No. 1358

**TABLE OF CONTENTS**

	<u>Page</u>
LIST OF TABLES .....	ii
LIST OF FIGURES .....	ii
LIST OF APPENDICES .....	ii
1.0 EXECUTIVE SUMMARY .....	1
2.0 INTRODUCTION .....	2
3.0 2010 FIRST SEMI-ANNUAL GROUNDWATER MONITORING EVENT .....	4
3.1 Narrative Summary of Second Semi-annual Monitoring Activities .....	4
3.1.1 Corrective Action Program .....	4
3.1.2 Groundwater Monitoring .....	5
3.2 Purge Water Management .....	5
3.3 Monitoring and Corrective Action System Wells .....	6
3.4 Analytical Results .....	6
3.5 Well Measurements .....	6
3.6 Potentiometric Surface Maps .....	7
3.7 Non-Aqueous Phase Liquids .....	7
3.8 Recovered Groundwater and NAPL .....	7
3.9 Contaminant Mass Recovered .....	8
3.10 Analytical Data Evaluation .....	8
3.11 Reported Concentration Maps .....	9
3.12 Extent of NAPL .....	9
3.13 Updated Compliance Schedule .....	9
3.14 Summary of Changes Made to Corrective Action Program .....	9
3.15 Modifications and Amendments to Compliance Plan .....	10
3.16 Corrective Measures Implementation (CMI) Report .....	10
3.17 Well Casing Elevations .....	10
3.18 Recommendation for Changes .....	10
3.19 Well Installation and/or Abandonment .....	10
3.20 Activity Within Area Subject to Institutional Control .....	10
3.21 Other Requested Items .....	10

## LIST OF TABLES

<u>Table</u>	<u>Title</u>
1	Summary of Analytical Results for the A-Transmissive Zone (A-TZ)
2	Summary of Analytical Results for the B-Transmissive Zone (B-TZ)
3	Summary of Analytical Results for Quality Assurance/Quality Control Samples
4	Water Level Measurements
5	Compliance Status of Wells and Piezometers

## LIST OF FIGURES

<u>Figure</u>	<u>Title</u>
1	Site Location Map
2	Corrective Action Monitoring Well Network
3	A-TZ Potentiometric Surface Contour Map – January 21-22, 2010
4	B-TZ Potentiometric Surface Contour Map – January 21-22, 2010
5	A-TZ Reported Concentrations – 2010 1 <sup>st</sup> Semi Annual Monitoring Event
6	B-TZ Reported Concentrations – 2010 1 <sup>st</sup> Semi Annual Monitoring Event

## LIST OF APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Compliance Plan Tables
B	Field Parameters
C	Laboratory and Analytical Reports and Data Usability Summaries
D	Waste Manifest
E	POC Concentrations vs. Time Graphs
F	Updated Compliance Schedule

## 1.0 EXECUTIVE SUMMARY

This semi-annual report presents a summary and evaluation of the Corrective Action Groundwater Monitoring for the Closed Surface Impoundment (Solid Waste Management Unit (SWMU) No. 1) at the former Wood Preserving Works facility (the Site) located in Houston, Texas. The groundwater monitoring activities for this period were performed by Pastor, Behling & Wheeler, LLC (PBW) on behalf of Union Pacific Railroad (UPRR) in January 2010.

The two uppermost groundwater bearing units, the A-Transmissive Zone (A-TZ) and the B-Transmissive Zone (B-TZ), were monitored during this period. Groundwater elevation data collected during the January 2010 sampling event show a radial groundwater flow in the A-TZ with flow to the northwest in the western portion of SWMU No. 1 and to the southeast in the eastern portion of SWMU No. 1. The hydraulic gradient in the A-TZ was estimated to be approximately 0.002 ft/ft (to the west). This groundwater flow was similar to the 2009 second semi-annual monitoring event.

Groundwater elevation data collected in the B-TZ show groundwater flow to the west with a hydraulic gradient of 0.014 ft/ft. Groundwater flow during the previous event (2009 second semi-annual monitoring event) was to the northwest.

Analytical results from the January 2010 sampling event were compared to Texas Commission on Environmental Quality Texas Risk Reduction Program Protective Concentration Limits, as designated in Section IV.D of the Compliance Plan, dated June 10, 2005. Constituent concentrations were below their respective PCLs for the ninth consecutive semi-annual monitoring event. Monitoring wells in both the A-TZ and B-TZ are considered to be compliant for this monitoring period.

## 2.0 INTRODUCTION

This semi-annual report presents a summary and evaluation of groundwater monitoring data collected during the 2010 first semi-annual monitoring period (January through June) at the Union Pacific Railroad (UPRR) former Houston Wood Preserving Works facility (the Site) located at 4910 Liberty Road in Houston, Texas (Figure 1). Semi-annual groundwater monitoring is required for the Site as a condition of the Texas Commission on Environmental Quality (TCEQ) Hazardous Waste Permit No. 50343 and associated Compliance Plan (CP) No. 50343, both renewed and issued on June 10, 2005. Groundwater monitoring at the Site is performed to monitor groundwater quality beneath the Closed Surface Impoundment Unit No. 001 (Solid Waste Management Unit (SWMU) No. 1).

On behalf of UPRR, Pastor, Behling & Wheeler, LLC. (PBW) conducted groundwater monitoring activities at the Site on January 21-22, 2010. Groundwater monitoring activities included sampling and gauging the background and point of compliance (POC) wells and piezometers associated with SWMU No. 1. The sampling event, analytical data, and data evaluation provided in this report fulfill the semi-annual corrective action reporting requirements for the first half of 2010 as described in the CP, Section VII.C.2. This section requires the following reporting elements:

<b>Semi-Annual Corrective Action Report Requirements</b>	<b>Report Section, Table(s) and/or Figure(s)</b>
A narrative summary of the evaluations made in accordance with CP Sections V, VI, and VII for the preceding six-month period. These periods shall be January 1 through June 30 and July 1 through December 31 (VII.C.2.a.)	3.0
Summary of Methods utilized for management of recovered/purged water (VII.C.2.b.)	3.2
An updated table and map of the monitoring and corrective action system wells (VII.C.2.c.)	Section 3.1.1 and Figure 2
The results of the chemical analyses, submitted in a tabulated format in a form acceptable to the Executive Director, which clearly indicates each parameter that exceeds the Groundwater Protection Standard (GWPS). Copies of the original laboratory report for chemical analyses showing detection limits and quality control and quality assurance data shall be provided if requested by the Executive Director (VII.C.2.d.)	Tables 1 & 2 Appendix C
Tabulation of the water level elevations (relative to mean sea level), depth to water measurements, and total depth of well measurements collected since the data that was submitted in the previous semiannual report (VII.C.2.e.)	Table 4
Potentiometric surface maps showing the elevation of the water table at the time of sampling and direction of groundwater flow gradients (VII.C.2.f.)	Figures 3 & 4
A notation of the presence or absence of non-aqueous phase liquids (NAPLs), both light and dense phases, in each well during each sampling event since the last event covered in the previous semiannual report and tabulation of depth and thickness of NAPLs, if detected (VII.C.2.g.)	Table 4

<b>Semi-Annual Corrective Action Report Requirements (cont'd)</b>	<b>Report Section, Table(s) and/or Figure(s)</b>
Quarterly tabulations of quantities of recovered groundwater and NAPLs, and graphs of monthly recorded flow rates versus time for the recovery wells during each period. A narrative summary describing and evaluating the NAPL recovery program shall also be included (VII.C.2.h.)	Not Applicable
Tabulation of the total contaminant mass recovered from each recovery system for each reporting period, if such a system is installed (VII.C.2.i.)	Not Applicable
Tabulation of the data evaluation results pursuant to Section VI.D and status of each well listed on CP Table V with regard to compliance with the corrective action objectives and compliance with the GWPSs (VII.C.2.j.)	Table 5
Maps of the contaminated area depicting concentrations of constituents listed in Table IV and any newly detected Table III constituents as isopleths contours or discrete concentrations if isopleths contours cannot be inferred (VII.C.2.k.)	Not Applicable
Maps indicating the extent and thickness of the LNAPLs and DNAPLs, if detected (VII.C.2.l.)	Not Detected
An updated schedule summary as required by Section X (VII.C.2.m.)	Appendix D
Summary of any changes made to the monitoring/corrective action program and a summary of recovery well inspections, repairs, and any operational difficulties (VII.C.2.n.)	None
A table of the modifications and amendments made to this Compliance Plan with their corresponding approval dates by the executive director or the Commission and a brief description of each action (VII.C.2.o.)	None
Corrective Measures Implementation (CMI) Report to be submitted in accordance with Section VIII.F, if necessary (VII.C.2.p.)	Not Applicable
Tabulation of well casing elevations in accordance with Attachment B No. 16 (VII.C.2.q.)	Table 4
Recommendation for any changes (VII.C.2.r.)	None
Certification and well installation diagram for any new well installation or replacement and certification for any well plugging and abandonment (VII.C.2.s.)	Not Applicable
A summary of any activity within an area subject to institutional control (VII.C.2.t.)	None
Any other items requested by the Executive Director (VII.C.2.u.)	None

As of June 2010, a recovery system had not been installed at this facility. Therefore, Provisions 8, 9, and 10 that relate to recovery wells or recovery system, are not applicable to this reporting period.

Responses to each of the semi-annual report provisions required by CP Section VII.C.2 are provided in Section 3.0. Conclusions and recommendations are provided in Section 4.0.

### **3.0 2010 FIRST SEMI-ANNUAL GROUNDWATER MONITORING EVENT**

A discussion of each of the semi-annual report provisions required by CP Section VII.C.2 is presented below by reference number to the list of provisions in Section 2.0.

#### **3.1 Narrative Summary of First Semi-annual Monitoring Activities**

The CP requires an evaluation of the Corrective Action Program (Section V) and Groundwater Monitoring Program summarizing the overall effectiveness of the Corrective Action Program (Section VI). This narrative summary includes provisions for response and reporting requirements as detailed in the CP Section VII, as discussed below.

##### **3.1.1 Corrective Action Program**

Groundwater samples were collected from the Background and POC wells (as detailed in CP Table V, which is provided in Appendix A) to assess potentially affected groundwater quality in the A-Transmissive Zone (A-TZ) and the B-Transmissive Zone (B-TZ). These water-bearing zones are defined as:

- A-TZ refers to the first sand unit encountered at approximately 13 feet below ground surface (bgs) and averages 7 feet in thickness; and
- B-TZ refers to the second sand unit encountered at approximately 30 feet bgs and averages 9 feet in thickness.

The definitions of the A-TZ and B-TZ are consistent with the Uppermost Transmissive Zone (UTZ) and Second Transmissive Zone (STZ), respectively, as defined in CP Provision I.A.

The following monitoring wells were sampled during this event (Figure 2):

- A-TZ POC wells: MW-01A, MW-02, MW-07, MW-10A, and MW-11A;
- A-TZ Background well: MW-08;
- B-TZ POC wells: MW-10B, MW-11B, and P-10; and
- B-TZ background well: P-12.

### 3.1.2 Groundwater Monitoring

PBW performed quarterly inspections of SWMU No. 1 in January and April 2010 and conducted semi-annual groundwater sampling activities on January 21-22, 2010. Groundwater sampling was performed using procedures outlined in a U.S. Environmental Protection Agency (EPA) document titled *Low-Flow (Minimal Drawdown) Ground-Water Sampling Procedures* (EPA/540/S-95/504) published in April 1996 and approved in the CP application. Groundwater samples were analyzed for the Detected Hazardous and Solid Waste Constituents listed in the CP, Table III (Appendix A).

Monitoring wells are equipped with dedicated polytetrafluoroethylene (PTFE) tubing for groundwater sampling. A Master-Flex<sup>®</sup> peristaltic pump was used to collect the groundwater samples. An approximate one-foot section of disposable silicon tubing was placed around the pump head and attached to the PTFE tubing for proper operation of the pump. Groundwater was pumped from the screened interval of each well at a flow rate of less than 0.5 L/min using a flow-through cell, field parameters including temperature, pH, specific conductivity, dissolved oxygen, and turbidity were measured during purging and sampling activities. When field parameters had stabilized to the EPA-specified criteria, a sample was then collected for analysis. The samples were also collected at a flow rate of less than 0.5 L/min. Recorded field parameters are summarized in Appendix B.

For each well, sample bottles were filled directly from the pumping apparatus described above, and were sealed and packed in coolers with sufficient ice to maintain a sample temperature of approximately 4°C. The sample coolers were delivered to ALS Laboratory, in Houston, Texas for analysis. Chain-of-Custody (COC) forms were completed and kept with their respective samples. Copies of the analytical data and COCs are included in Appendix C. Groundwater samples were then analyzed for the Detected Hazardous and Solid Waste Constituents listed in the CP, Table III (Appendix A).

### 3.2 Purge Water Management

Approximately 3 gallons of purge water was generated during the January 2010 low-flow groundwater sampling event. The purge water was containerized in a Department of Transportation (DOT) certified, 55-gallon steel drum and temporarily stored on site in a fenced and locked container storage area (NOR 006). Since the groundwater sampled and analyzed during this event did not contain hazardous constituents above the applicable health-based levels (i.e. PCLs discussed in Section 3.10), the purge water generated was not considered hazardous in accordance with the EPA “contained-in determination”



detailed in the 1986 EPA memorandum “RCRA Regulatory Status of Contaminated Groundwater”. However, wastes generated during the 2010 first semi-annual monitoring event were picked up from the Site by USA Environment, LP and transported to the U.S. Ecology Texas, LP facility, located in Robstown, Texas for disposal on April 16, 2010 under EPA waste codes F034 and K001, and TCEQ Notice of Registration (NOR) waste codes 0909101H (purge water) and 0917406H (PPE debris). Waste manifests are provided in Appendix D.

### **3.3 Monitoring and Corrective Action System Wells**

A summary of the current monitoring and corrective action groundwater wells is discussed in Section 3.1.1. Configuration of the current monitoring and corrective action well network is presented on Figure 2.

### **3.4 Analytical Results**

The 2010 first semi-annual groundwater analytical results from the A-TZ and B-TZ are summarized in Tables 1 and 2, respectively and the laboratory analytical report is provided in Appendix C. The analytical results were compared to the Detected Hazardous and Solid Waste Constituent limits, which are taken from the TCEQ Texas Risk Reduction Program (TRRP) Tier 1 Protective Concentration Levels (PCLs). TRRP PCLs serve as the Groundwater Protection Standard (GWPS), as detailed in Section IV.D and Table III of the CP. If any concentrations exceeded the concentration limits of this report, the concentration is bolded within the table.

Quality assurance/quality control (QA/QC) samples (field blank, matrix spike and matrix spike duplicate results) are summarized in Table 3.

### **3.5 Well Measurements**

During the sampling event, the following information was recorded at each monitoring well:

#### *Before Sampling*

- The presence of light NAPLs was evaluated; and
- Depth to groundwater below the top of casing was measured to the nearest 0.01 foot.

### *After Sampling*

- The presence of dense non-aqueous phase liquids (DNAPLs) were evaluated using visual observations and an oil-water interface probe; and
- Total well depths of the wells were measured.

Table 4 provides a summary of these measurements. None of the compliance wells had measurable amounts or any indication of LNAPL or DNAPL.

### **3.6 Potentiometric Surface Maps**

Groundwater elevation data recorded during the 2010 first semi-annual monitoring event were used to create potentiometric surface maps of the A-TZ and B-TZ, presented on Figures 3 and 4, respectively.

Groundwater elevation data collected during the January 2010 sampling event show a radial groundwater flow pattern in the A-TZ at SWMU No. 1. Groundwater flow was generally to the northwest in the western portion of SWMU No. 1 and to the southeast in the eastern portion of SWMU No. 1 with a hydraulic gradient of approximately 0.002 ft/ft to the west. This groundwater flow was similar to the 2009 second semi-annual monitoring event.

Groundwater elevation data collected in the B-TZ also indicates a radial flow pattern with groundwater flow to the west on the west side of SWMU No. 1 with a hydraulic gradient of 0.014 ft/ft (Figure 4). Groundwater flow during the 2009 second semi-annual monitoring event was generally to the northwest.

### **3.7 Non-Aqueous Phase Liquids**

Measurable amounts of LNAPL and/or DNAPL were not observed in any of the compliance wells.

### **3.8 Recovered Groundwater and NAPL**

To date, a recovery system has not been installed at the SWMU No. 1; therefore, this provision is not applicable.

### 3.9 Contaminant Mass Recovered

With the groundwater analytical data for the POC wells in compliance and no groundwater recovery system installed, or necessary, this provision is not applicable for the Site.

### 3.10 Analytical Data Evaluation

Section VI.D of the CP describes two methods which may be used to determine the compliance status of a given well:

- 1) Analytical results may be either directly compared with PCLs (CP Table III; included in Appendix A), or
- 2) Analytical results can be statistically compared PCLs using the Confidence Interval Procedure for the mean concentration based on normal, log-normal, or non-parametric distribution, which the 95% confidence coefficient of the t-distribution will be used in construction of the confidence interval.

Direct comparison to PCLs was used to evaluate the analytical data. Tables 1 (A-TZ) and 2 (B-TZ) show the results of a direct comparison of data for this sampling event to the respective PCLs. Wells and piezometers are in compliance if each of the constituents listed in the CP Table III was reported at a concentration less than or equal to the PCL. Based on the analytical results from the January 2010 monitoring event the compliance wells completed in both transmissive zones are compliant with groundwater results below their respective PCLs; therefore the monitoring wells are considered to be compliant for this monitoring period. Compliance status for each of the monitoring wells is provided in Table 5.

Monitoring wells in A-TZ and B-TZ have not exceeded the established CP PCLs since July 2005, at which time dibenzofuran exceeded its respective PCL of 0.098 mg/L in MW-01A (0.11 mg/L). Including the 2010 first semi-annual analytical data, the SMWU No. 1 monitoring wells have been compliant for nine consecutive semi-annual monitoring events (4.5 years). Concentration versus time graphs for COCs in the A-TZ (2-methylnaphthalene (Figure E-1), dibenzofuran (Figure E-2), and naphthalene (Figure E-3)) and the B-TZ (dibenzofuran (Figure E-4) and naphthalene (Figure E-5)) are provided in Appendix E. The graphs demonstrate that COC concentrations in the A-TZ and B-TZ POC wells have shown a steady

decrease over time, and are currently compliant with the TCEQ Remedy Standard A requirements for groundwater protection.

A QA/QC review and Data Usability Summary (DUS) were prepared for the January 2010 analytical data by Conestoga-Rovers & Associates (CRA) (Appendix C). The laboratory qualified analytes with concentrations above the sample detection limits (SDLs) but below the method quantitation limits (MQLs) are estimated on the analytical tables (Tables 1 and 2). None of the data required further qualification by CRA based on the established QC criteria. Based on the QA/QC data review, the analytical data are usable for the intended use.

### **3.11 Reported Concentration Maps**

Reported concentrations of each constituent analyzed for the 2010 First Semi-Annual Groundwater Monitoring Event are presented on Figures 5 and 6 for the A-TZ and B-TZ compliance wells, respectively. In the event a constituent exceeded their respective PCL, the value would be highlighted on the figures. There were no exceedances of PCLs for any of the required constituents.

### **3.12 Extent of NAPL**

Measurable amounts of LNAPL or DNAPL were not detected in any of the compliance wells.

### **3.13 Updated Compliance Schedule**

Section X of the CP requires that the Permittee submit a schedule summarizing the activities required by the Compliance Plan issued on June 10, 2005, which was originally submitted to the TCEQ on August 4, 2004. An updated compliance schedule is included as Appendix F of this report.

### **3.14 Summary of Changes Made to Corrective Action Program**

No changes have been made to the corrective action program.

### **3.15 Modifications and Amendments to Compliance Plan**

A compliance plan renewal application was submitted to TCEQ on December 23, 2003 consistent with the renewal requirements for the RCRA permit at the site. The RCRA permit and CP were issued June 10, 2005. There have been no modifications or amendments to the Compliance Plan since the last permit issued.

### **3.16 Corrective Measures Implementation (CMI) Report**

A Response Action Plan (RAP) has not been submitted; therefore, this provision does not apply.

### **3.17 Well Casing Elevations**

Top-of-casing elevations referenced to feet above Mean Sea Level (MSL) for each compliance monitoring well are summarized in Table 4.

### **3.18 Recommendation for Changes**

There are no recommendations for changes to the monitoring program or to the Corrective Action Program.

### **3.19 Well Installation and/or Abandonment**

No monitoring wells were installed or abandoned as part of the monitoring program or the Corrective Action Program during the reporting period.

### **3.20 Activity Within Area Subject to Institutional Control**

No areas are under institutional control; therefore, this provision does not apply.

### **3.21 Other Requested Items**

No other items have been requested by the executive director.

## **TABLES**

**Table 1**  
**Summary of Analytical Results for the A-Transmissive Zone (A-TZ)**  
**Semiannual Monitoring Report: 2010 First Semiannual Event**

**Houston Wood Preserving Works**  
**Houston, Texas**

Analyte	PCL (mg/L)	Monitoring Well IDs (Concentrations mg/L)																				
		MW-01A			DUP-01			MW-02			MW-07			MW-08			MW-10A			MW-11A		
		1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ
Acenaphthene	1.5	0.04			0.039			0.0073			<0.0009	U		<0.0009	U		<0.0009	U		<0.0009	U	
Acenaphthylene	1.5	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	
Anthracene	7.3	<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U	
bis(2-ethylhexyl)phthalate	0.006	<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U	
Dibenzofuran	0.098	0.0016	J		0.0014	J		<0.0007	U		<0.0007	U		<0.0007	U		<0.0007	U		<0.0007	U	
Fluoranthene	0.98	0.0017	J		0.0015	J		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	
Fluorene	0.98	0.022			0.019			0.0037	J		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U	
2-Methylnaphthalene	0.098	0.0019	J		0.0018	J		<0.0009	U		<0.0009	U		<0.0009	U		<0.0009	U		<0.0009	U	
Naphthalene	0.49	0.0043	J		0.0036	J		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U	
Phenanthrene	0.73	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	
Pyrene	0.73	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	

Notes:

PCL = Protective Concentration Level

The Compliance Plan Section IV.D defines the Groundwater Protection Standard (GWPS) as the PCL

DUP-01= Duplicate sample collected at MW-01A

LQ - Lab Qualifier

J = Estimated value between the SDL and the MQL

U = Value not detected greater than the MQL

VQ - Validation Qualifier

**Table 2**  
**Summary of Analytical Results for the B-Transmissive Zone (B-TZ)**  
**Semiannual Monitoring Report: 2010 First Semiannual Event**

**Houston Wood Preserving Works**  
**Houston, Texas**

Analyte	PCL (mg/L)	Monitoring Well IDs (Concentrations mg/L)														
		MW-10B			MW-11B			P-10			DUP-02			P-12		
		1/21/2010	LQ	VQ	1/21/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ	1/22/2010	LQ	VQ
Acenaphthene	1.5	0.052			0.048			<0.0009	U		<0.0009	U		<0.0009	U	
Acenaphthylene	1.5	<0.0005	U		0.0013	J		<0.0005	U		<0.0005	U		<0.0005	U	
Anthracene	7.3	0.0025	J		0.0011	J		<0.0006	U		<0.0006	U		<0.0006	U	
bis(2-ethylhexyl)phthalate	0.006	<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U		<0.0033	U	
Dibenzofuran	0.098	0.018			0.012			<0.0007	U		<0.0007	U		<0.0007	U	
Di-n-butyl phthalate	2.4	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	
Fluoranthene	0.98	0.0017	J		0.013			<0.0005	U		<0.0005	U		<0.0005	U	
Fluorene	0.98	0.031			<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U	
Naphthalene	0.49	0.0037	J		<0.0006	U		<0.0006	U		<0.0006	U		<0.0006	U	
Phenol	7.3	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	
Pyrene	0.73	<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U		<0.0005	U	

Notes:

PCL = Protective Concentration Level

The Compliance Plan Section IV.D defines the Groundwater Protection Standard (GWPS) as the PCL

DUP-02 = Duplicate sample collected at P-10

LQ - Lab Qualifier

J = Estimated value between the SDL and the MDQ

U = Value not detected greater than the MQL

VQ - Validation Qualifier



**Table 3**  
**Summary of Analytical Results for Quality Assurance/Quality Control Samples**  
**Semiannual Monitoring Report: 2010 First Semiannual Event**

**Houston Wood Preserving Works**  
**Houston, Texas**

Analyte	PCL (mg/L)	Sample IDs (Concentrations mg/L)		
		FB-01	P-12(MS) <sup>(1)</sup>	P-12(MSD) <sup>(1)</sup>
		Field Blank	Matrix Spike	Matrix Spike Duplicate
		1/22/2010	1/22/2010	1/22/2010
Acenaphthene	1.5	<0.0009 U	0.03342	0.03396
Acenaphthylene	1.5	<0.0005 U	0.03427	0.03601
Anthracene	7.3	<0.0006 U	0.03367	0.03379
bis(2-ethylhexyl)phthalate	0.006	<0.0033 U	0.0329	0.03468
Dibenzofuran	0.098	<0.0007 U	0.0346	0.03485
Di-n-butyl phthalate	2.4	<0.0005 U	0.03589	0.03599
Fluoranthene	0.98	<0.0005 U	0.03442	0.03541
Fluorene	0.98	<0.0006 U	0.03352	0.03458
2-Methylnaphthalene	0.098	<0.0009 U	0.03232	0.03509
Naphthalene	0.49	<0.0006 U	0.03381	0.03487
Phenanthrene	0.73	<0.0005 U	0.03488	0.03415
Phenol	7.3	<0.0005 U	0.06662	0.06181
Pyrene	0.73	<0.0005 U	0.03525	0.03723

**Notes:**

PCL = Protective Concentration Level

(1) = P-12(MS) and P-12(MSD) are matrix spike and matrix spike duplicate samples collected at P-12, respectively.

U = Value not detected greater than the MQL

Table 4

Water Level Measurements  
Semiannual Monitoring Report: 2010 First Semiannual Event

Houston Wood Preserving Works  
Houston, Texas

Well ID	Top of Casing Elevation (TOC) (ft MSL)	Date Measured	Water Depth (ft. BTOC)	Depth to NAPL (ft. BTOC)	Total Well Depth as Completed (ft. BTOC)	Total Well Depth (ft. BTOC)	Potentiometric Elevation (ft. MSL)
<b>A-TZ Monitoring Locations</b>							
MW-01A	47.92	1/22/2010	3.07	ND	20.2	19.90	44.85
MW-02	47.97	1/22/2010	3.91	ND	20.3	20.15	44.06
MW-07	48.86	1/22/2010	4.02	ND	NA	24.80	44.84
MW-08	49.33	1/22/2010	4.17	ND	26.8	25.15	45.16
MW-10A	49.86	1/21/2010	4.64	ND	25.9	25.60	45.22
MW-11A	50.05	1/21/2010	4.97	ND	24.4	24.10	45.08
<b>B-TZ Monitoring Locations</b>							
MW-10B	49.94	1/21/2010	4.91	ND	48.8	46.50	45.03
MW-11B	50.18	1/21/2010	5.15	ND	46.8	46.75	45.03
P-10	47.69	1/22/2010	4.06	ND	40.0	42.80	43.63
P-12	48.78	1/22/2010	4.13	ND	40.0	42.90	44.65

Notes

BTOC = feet below the top of the well casing

ft. MSL = feet above Mean Sea Level

NA = Information not available


ND = Not Detected

**Table 5**  
**Compliance Status of Wells and Piezometers**  
**Semiannual Monitoring Report: 2010 First Semiannual Event**

**Houston Wood Preserving Works**  
**Houston, Texas**

Zone	Monitoring Well Location	Well Designation	Compliance Status
A-TZ Monitoring Location	MW-01A	Point of Compliance	Compliant
	MW-02	Point of Compliance	Compliant
	MW-07	Point of Compliance	Compliant
	MW-08	Background Well	Compliant
	MW-10A	Point of Compliance	Compliant
	MW-11A	Point of Compliance	Compliant
B-TZ Monitoring Location	MW-10B	Point of Compliance	Compliant
	MW-11B	Point of Compliance	Compliant
	P-10	Point of Compliance	Compliant
	P-12	Background Well	Compliant

## **FIGURES**



QUADRANGLE LOCATION



Scale in Feet



**UNION PACIFIC RAILROAD CO.**

**HOUSTON WOOD PRESERVING WORKS**

Figure 1

**SITE LOCATION MAP**

PROJECT: 1358

BY: ZGK


REVISIONS

DATE: JULY, 2010

CHECKED: ECM

**PASTOR, BEHLING & WHEELER, LLC**  
CONSULTING ENGINEERS AND SCIENTISTS

Source:  
U.S.G.S. 7.5 minute quadrangle, Settegast, Texas, 1982.



**UNION PACIFIC RAILROAD CO.**  
**HOUSTON WOOD PRESERVING WORKS**

**CORRECTIVE ACTION MONITORING WELL NETWORK**  
**TCEQ PERMIT UNIT NO. 1**

PROJECT: 1388 BY: ZGK REVISIONS  
 DATE: JULY, 2010 CHECKED: ECM

**PASTOR, BEHLING & WHEELER, LLC**  
 CONSULTING ENGINEERS AND SCIENTISTS

**Figure 2**

**EXPLANATION**


- Road, Parking Lot, Sidewalk
- Fence
- Railroad
- A-TZ Monitoring Well Location
- B-TZ Monitoring Well Location

Note:  
 \* Background well.

Approx. Scale in Feet  
 0 60 120


Source:  
 Base map from ERM-Southwest, Inc  
 0014419s310.dwg, 6/19/2006.

STATE OF TEXAS  
 ERIC C. MATZNER  
 GEOLOGY  
 LIC. # 795  
 LICENSED PROFESSIONAL GEOLOGIST



UNION PACIFIC RAILROAD CO.	
HOUSTON WOOD PRESERVING WORKS	
Figure 3	
<b>A-TZ POTENTIOMETRIC SURFACE CONTOUR MAP JANUARY 21-22, 2010</b>	
PROJECT: 1358	BY: ZGK
DATE: JULY, 2010	CHECKED: ECM
REVISIONS	
<b>PASTOR, BEHLING &amp; WHEELER, LLC</b> CONSULTING ENGINEERS AND SCIENTISTS	

<b>EXPLANATION</b>	
	Road, Parking Lot, Sidewalk
	Fence
	Railroad
	A-TZ Monitoring Well Location (* - Compliance Well)
	Groundwater Elevation (Ft, MSL) (** - Data Not Used to Develop Potentiometric Contour)
	Groundwater Elevation Contour (Ft, MSL) C.I. = 1 Ft
	General Groundwater Flow Direction
<b>ESTIMATED GRADIENT</b>	
	$A_i \rightarrow A_i = \frac{0.25ft}{150ft} = 0.002 \text{ ft/ft}$
Source: Base map from ERM-Southwest, Inc 0014419a310.dwg, 6/19/2006.	




 **UNION PACIFIC RAILROAD CO.**







**HOUSTON WOOD PRESERVING WORKS**

Figure 4  
**B-TZ POTENTIOMETRIC SURFACE  
 CONTOUR MAP  
 JANUARY 21-22, 2010**



PROJECT: 1358	BY: ZGK	REVISIONS
DATE: JULY, 2010	CHECKED: ECM	

**PASTOR, BEHLING & WHEELER, LLC**  
 CONSULTING ENGINEERS AND SCIENTISTS



	Road, Parking Lot, Sidewalk
	Fence
	Railroad
	B-TZ Monitoring Well Location (* - Compliance Well)
	Groundwater Elevation Contour (Ft, MSL) C.I. = 1 Ft (dashed where inferred)
	General Groundwater Flow Direction


	<b>Bi</b> →	$B_i = \frac{2h}{L} = 0.014 \text{ ft/ft}$
	ESTIMATED GRADIENT	

Source:  
 Base map from ERM-Southwest, Inc  
 0014419a310.dwg, 6/19/2006.




Constituent	Conc. (mg/L)
Acenaphthene	0.0073
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Fluoranthene	<0.0005U
Fluorene	0.0037J
2-Methylnaphthalene	<0.0009U
Naphthalene	<0.0006U
Phenathrene	<0.0005U
Pyrene	<0.0005U

Constituent	Conc. (mg/L)	Conc.* (mg/L)
Acenaphthene	0.04	0.039
Acenaphthylene	<0.0005U	<0.0005U
Anthracene	<0.0006U	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U	<0.0033U
Dibenzofuran	0.0016J	0.0014J
Fluoranthene	0.0017J	0.0015J
Fluorene	0.022	0.019
2-Methylnaphthalene	0.0019J	0.0018J
Naphthalene	0.0043J	0.0036J
Phenathrene	<0.0005U	<0.0005U
Pyrene	<0.0005U	<0.0005U



Constituent	Conc. (mg/L)
Acenaphthene	<0.0009U
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Fluoranthene	<0.0005U
Fluorene	<0.0006U
2-Methylnaphthalene	<0.0009U
Naphthalene	<0.0006U
Phenathrene	<0.0005U
Pyrene	<0.0005U



Constituent	Conc. (mg/L)
Acenaphthene	<0.0009U
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Fluoranthene	<0.0005U
Fluorene	<0.0006U
2-Methylnaphthalene	<0.0009U
Naphthalene	<0.0006U
Phenathrene	<0.0005U
Pyrene	<0.0005U

Constituent	Conc. (mg/L)
Acenaphthene	<0.0009U
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Fluoranthene	<0.0005U
Fluorene	<0.0006U
2-Methylnaphthalene	<0.0009U
Naphthalene	<0.0006U
Phenathrene	<0.0005U
Pyrene	<0.0005U


Constituent	Conc. (mg/L)
Acenaphthene	<0.0009U
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Fluoranthene	<0.0005U
Fluorene	<0.0006U
2-Methylnaphthalene	<0.0009U
Naphthalene	<0.0006U
Phenathrene	<0.0005U
Pyrene	<0.0005U

Indicator Parameters	
Constituent	PCL (mg/L)
Acenaphthene	1.5
Acenaphthylene	1.5
Anthracene	7.3
bis(2-ethylhexyl)phthalate	0.006
Dibenzofuran	0.098
Fluoranthene	0.98
Fluorene	0.98
2-Methylnaphthalene	0.098
Naphthalene	0.49
Phenathrene	0.73
Pyrene	0.73

**EXPLANATION**

- Fence
- Railroad
- A-TZ Monitoring Well Location

- Notes:
1. \* Duplicates sample taken at MW-1A.
  2. Sample collected on January 22, 2010.
  3. J= Estimated value between SQL and MDL.
  4. U= Value not detected greater than the MDL.



**UNION PACIFIC RAILROAD CO.**

**HOUSTON WOOD PRESERVING WORKS**


Figure 5  
**A-TZ REPORTED CONCENTRATIONS  
 2010 1<sup>st</sup> SEMI ANNUAL  
 MONITORING EVENT**

PROJECT: 1358	BY: ZGK	REVISIONS
DATE: JULY, 2010	CHECKED: ECM	

**PASTOR, BEHLING & WHEELER, LLC**  
 CONSULTING ENGINEERS AND SCIENTISTS



Approx. Scale in Feet



Source:  
Base map from ERM-Southwest, Inc  
0014419a310.dwg, 6/19/2006.

Constituent	Conc. (mg/L)
Acenaphthene	0.052
Acenaphthylene	<0.0005U
Anthracene	0.0025J
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	0.018
Di-n-butyl Phthalate	<0.0005U
Fluoranthene	0.0017J
Fluorene	0.031
Naphthalene	0.0037J
Phenol	<0.0005U
Pyrene	<0.0005U

MW-10B

SWMU 1

Constituent	Conc. (mg/L)
Acenaphthene	0.048
Acenaphthylene	0.0013J
Anthracene	0.0011J
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	0.012
Di-n-butyl Phthalate	<0.0005U
Fluoranthene	0.013
Fluorene	<0.0006U
Naphthalene	<0.0006U
Phenol	<0.0005U
Pyrene	<0.0005U

MW-11B

P-10

Constituent	Conc. (mg/L)	Conc.* (mg/L)
Acenaphthene	<0.0009U	<0.0009U
Acenaphthylene	<0.0005U	<0.0005U
Anthracene	<0.0006U	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U	<0.0033U
Dibenzofuran	<0.0007U	<0.0007U
Di-n-butyl Phthalate	<0.0005U	<0.0005U
Fluoranthene	<0.0005U	<0.0005U
Fluorene	<0.0006U	<0.0006U
Naphthalene	<0.0006U	<0.0006U
Phenol	<0.0005U	<0.0005U
Pyrene	<0.0005U	<0.0005U

Constituent	Conc. (mg/L)
Acenaphthene	<0.0009U
Acenaphthylene	<0.0005U
Anthracene	<0.0006U
bis(2-ethylhexyl)phthalate	<0.0033U
Dibenzofuran	<0.0007U
Di-n-butyl Phthalate	<0.0005U
Fluoranthene	<0.0005U
Fluorene	<0.0006U
Naphthalene	<0.0006U
Phenol	<0.0005U
Pyrene	<0.0005U

P-12


Indicator Parameters

Constituent	PCL (mg/L)
Acenaphthene	1.5
Acenaphthylene	1.5
Anthracene	7.3
bis(2-ethylhexyl)phthalate	0.006
Dibenzofuran	0.098
Di-n-butyl Phthalate	2.4
Fluoranthene	0.98
Fluorene	0.98
Naphthalene	0.49
Phenol	7.3
Pyrene	0.73

**EXPLANATION**

- Fence
- Railroad
- B-TZ Monitoring Well Location
- Piezometer Location

- Notes:
1. \* Duplicate sample taken at P-10.
  2. Sample collected on January 21-22, 2010.
  3. J= Estimated value between SQL and MDL.
  4. U= Value not detected greater than the MDL.



**UNION PACIFIC RAILROAD CO.**

**HOUSTON WOOD PRESERVING WORKS**

Figure 6

**B-TZ REPORTED CONCENTRATIONS  
2010 1<sup>st</sup> SEMI ANNUAL  
MONITORING EVENT**

PROJECT: 1358	BY: ZGK	REVISIONS
DATE: JULY, 2010	CHECKED: ECM	

**PASTOR, BEHLING & WHEELER, LLC**  
CONSULTING ENGINEERS AND SCIENTISTS

**APPENDIX A**  
**COMPLIANCE PLAN TABLES**

TABLE III - CORRECTIVE ACTION PROGRAM  
 Table of Detected Hazardous and Solid Waste Constituents and  
 Concentration Limits for the Ground-Water Protection Standard

**Closed Surface Impoundment (NOR Unit No. 001, SWMU No. 01)**

<u>A-Transmissive Zone</u>		<u>B-Transmissive Zone</u>	
COLUMN A Hazardous Constituents	COLUMN B Concentration Limits (mg/l)	COLUMN A Hazardous Constituents	COLUMN B Concentration Limits (mg/l)
Acenaphthene	1.5 <sup>PCL</sup>	Acenaphthene	1.5 <sup>PCL</sup>
Acenaphthylene	1.5 <sup>PCL</sup>	Acenaphthylene	1.5 <sup>PCL</sup>
Anthracene	7.3 <sup>PCL</sup>	Anthracene	7.3 <sup>PCL</sup>
Dibenzofuran	0.098 <sup>PCL</sup>	Dibenzofuran	0.098 <sup>PCL</sup>
Bis(2-ethylhexyl)phthalate	0.006 <sup>PCL</sup>	Bis(2-ethylhexyl)phthalate	0.006 <sup>PCL</sup>
Fluoranthene	0.98 <sup>PCL</sup>	Fluoranthene	0.98 <sup>PCL</sup>
Fluorene	0.98 <sup>PCL</sup>	Fluorene	0.98 <sup>PCL</sup>
2-Methylnaphthalene	0.098 <sup>PCL</sup>	Di-n-butyl phthalate	2.4 <sup>PCL</sup>
Naphthalene	0.49 <sup>PCL</sup>	Naphthalene	0.49 <sup>PCL</sup>
Phenanthrene	0.73 <sup>PCL</sup>	Phenol	7.3 <sup>PCL</sup>
Pyrene	0.73 <sup>PCL</sup>	Pyrene	0.73 <sup>PCL</sup>

PCL Alternate Concentration Limit pursuant to 30 TAC §335.160(b) based upon the Protective Concentration Level determined under 30 TAC Chapter 350 for Residential Land Use. The PCL value, Column B, will change as updates to the rule are promulgated. Changes to the rule automatically change the concentration value established in Column B in this table.

**APPENDIX B**  
**FIELD PARAMETERS**

**Table B-1**  
**Groundwater Sampling Field Parameters**  
**Semiannual Monitoring Report: 2010 First Semiannual Event**

**Houston Wood Preserving Works**  
**Houston, Texas**

Field Parameter	Monitoring Well IDs									
	A-Transmissive Zone						B-Transmissive Zone			
	MW-01A	MW-02	MW-07	MW-08	MW-10A	MW-11A	MW-10B	MW-11B	P-10	P-12
	1/22/2010	1/22/2010	1/22/2010	1/22/2010	1/21/2010	1/21/2010	1/21/2010	1/21/2010	1/22/2010	1/22/2010
Time Sampled (hrs CST)	8:20	7:20	10:30	9:20	16:50	15:30	16:15	14:50	12:40	11:20
Temperature (°C)	22.4	22.7	22.4	22.40	22.70	23.60	22.7	23.2	23.4	22.80
pH (Standard Units)	6.94	6.62	6.85	7.24	7.15	6.92	6.88	6.85	6.92	7.14
Specific Conductivity (µS)	1,150	830	870	780	1,060	1,220	1,130	1,320	1,190	1,260
Dissolved Oxygen (mg/L)	0.61	0.43	0.62	0.43	0.62	0.62	0.54	0.20	0.82	0.67
Turbidity (NTU)	12.00	5.70	12.00	6.90	7.20	7.30	8.10	7.60	3.90	7.20

**APPENDIX C**  
**LABORATORY ANALYTICAL REPORTS and DATA USABILITY SUMMARIES**



**Environmental Division**

01-Mar-2010

Eric Matzner  
Pastor, Behling & Wheeler, LLC  
2201 Double Creek Drive  
Suite 4004  
Round Rock, TX 78664

Tel: (512) 671-3434  
Fax: (512) 671-3446

Re: UPRR HWPW SWMU 1

Work Order: **1001524**

Dear Eric,

ALS Laboratory Group received 13 samples on 22-Jan-2010 04:00 PM for the analyses presented in the following report.

The analytical data provided relates directly to the samples received by ALS Laboratory Group and for only the analyses requested. Results are expressed as "as received" unless otherwise noted.

QC sample results for this data met EPA or laboratory specifications except as noted in the Case Narrative or as noted with qualifiers in the QC batch information. Should this laboratory report need to be reproduced, it should be reproduced in full unless written approval has been obtained by ALS Laboratory Group. Samples will be disposed in 30 days unless storage arrangements are made.

The total number of pages in this report is 28.

If you have any questions regarding this report, please feel free to call me.

Sincerely,

Electronically approved by: Glenda H. Ramos

Lora Terrill  
VP Lab Operations



Certificate No: TX: T104704231-09-1



**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Work Order:** 1001524

**TRRP Laboratory Data  
Package Cover Page**

This data package consists of all or some of the following as applicable:

This signature page, the laboratory review checklist, and the following reportable data:

- R1 Field chain-of-custody documentation:
- R2 Sample identification cross-reference
- R3 Test reports (analytical data sheets) for each environmental sample that includes:
  - a) Items consistent with NELAC 5.13 or ISO/IEC 17025 Section 5.10
  - b) dilution factors,
  - c) preparation methods,
  - d) cleanup methods, and
  - e) if required for the project, tentatively identified compounds (TICs).
- R4 Surrogate recovery data including:
  - a) Calculated recovery (%R), and
  - b) The laboratory's surrogate QC limits.
- R5 Test reports/summary forms for blank samples;
- R6 Test reports/summary forms for laboratory control samples (LCSs) including:
  - a) LCS spiking amounts,
  - b) Calculated %R for each analyte, and
  - c) The laboratory's LCS QC limits.
- R7 Test reports for project matrix spike/matrix spike duplicates (MS/MSDs) including:
  - a) Samples associated with the MS/MSD clearly identified,
  - b) MS/MSD spiking amounts,
  - c) Concentration of each MS/MSD analyte measured in the parent and spiked samples,
  - d) Calculated %Rs and relative percent differences (RPDs), and
  - e) The laboratory's MS/MSD QC limits
- R8 Laboratory analytical duplicate (if applicable) recovery and precision:
  - a) the amount of analyte measured in the duplicate,
  - b) the calculated RPD, and
  - c) the laboratory's QC limits for analytical duplicates.
- R9 List of method quantitation limits (MQLs) for each analyte for each method and matrix;?
- R10 Other problems or anomalies.

Release Statement: I am responsible for the release of this laboratory data package. This data package has been reviewed by the laboratory and is complete and technically compliant with the requirements of the methods used, except where noted by the labor in the attached exception reports. By my signature below, I affirm to the best of my knowledge, all problems/anomalies, observed the laboratory as having the potential to affect the quality of the data, have been identified by the laboratory in the Laboratory Review Checklist, and no information or data have been knowingly withheld that would affect the quality of the data.

Check, if applicable: [NA] This laboratory is an in-house laboratory controlled by the person responding to rule. The official sign the cover page of the rule-required report (for example, the APAR) in which these data are used is responsible for releasing this c package and is by signature affirming the above release statement is true.



Lora Terrill

VP Lab Operations

## Laboratory Review Checklist: Reportable Data

Laboratory Name: ALS Laboratory Group			LRC Date: 03/01/2010				
Project Name: UPRR HWPW SWMU 1			Laboratory Job Number: 1001524				
Reviewer Name: Lora Terrill			Prep Batch Number(s) : 40719				
# <sup>1</sup>	A <sup>2</sup>	Description	Yes	No	NA <sup>3</sup>	NR <sup>4</sup>	ER# <sup>5</sup>
R1	OI	<b>CHAIN-OF-CUSTODY (C-O-C)</b>					
		1) Did samples meet the laboratory's standard conditions of sample acceptability upon receipt?	X				
		2) Were all departures from standard conditions described in an exception report?	X				
R2	OI	<b>SAMPLE AND QUALITY CONTROL (QC) IDENTIFICATION</b>					
		1) Are all field sample ID numbers cross-referenced to the laboratory ID numbers?	X				
		2) Are all laboratory ID numbers cross-referenced to the corresponding QC data?	X				
R3	OI	<b>TEST REPORTS</b>					
		1) Were all samples prepared and analyzed within holding times?	X				
		2) Other than those results < MQL, were all other raw values bracketed by calibration standards?	X				
		3) Were calculations checked by a peer or supervisor?	X				
		4) Were all analyte identifications checked by a peer or supervisor?	X				
		5) Were sample quantitation limits reported for all analytes not detected?	X				
		6) Were all results for soil and sediment samples reported on a dry weight basis?				X	
		7) Was % moisture (or solids) reported for all soil and sediment samples?				X	
		8) If required for the project, TICs reported?				X	
R4	O	<b>SURROGATE RECOVERY DATA</b>					
		1) Were surrogates added prior to extraction?	X				
		2) Were surrogate percent recoveries in all samples within the laboratory QC limits?	X				
R5	OI	<b>TEST REPORTS/SUMMARY FORMS FOR BLANK SAMPLES</b>					
		1) Were appropriate type(s) of blanks analyzed?	X				
		2) Were blanks analyzed at the appropriate frequency?	X				
		3) Were method blanks taken through the entire analytical process, including preparation and, if applicable, cleanup procedures?	X				
		4) Were blank concentrations < MQL?	X				
R6	OI	<b>LABORATORY CONTROL SAMPLES (LCS):</b>					
		1) Were all COCs included in the LCS?	X				
		2) Was each LCS taken through the entire analytical procedure, including prep and cleanup steps?	X				
		3) Were LCSs analyzed at the required frequency?	X				
		4) Were LCS (and LCSD, if applicable) %Rs within the laboratory QC limits?	X				
		5) Does the detectability data document the laboratory's capability to detect the COCs at the MDL used to calculate the SDLs?	X				
		6) Was the LCSD RPD within QC limits?	X				
R7	OI	<b>MATRIX SPIKE (MS) AND MATRIX SPIKE DUPLICATE (MSD) DATA</b>					
		1) Were the project/method specified analytes included in the MS and MSD?	X				
		2) Were MS/MSD analyzed at the appropriate frequency?	X				
		3) Were MS (and MSD, if applicable) %Rs within the laboratory QC limits?	X				
		4) Were MS/MSD RPDs within laboratory QC limits?	X				
R8	OI	<b>ANALYTICAL DUPLICATE DATA</b>					
		1) Were appropriate analytical duplicates analyzed for each matrix?			X		
		2) Were analytical duplicates analyzed at the appropriate frequency?			X		
		3) Were RPDs or relative standard deviations within the laboratory QC limits?			X		
R9	OI	<b>METHOD QUANTITATION LIMITS (MQLS):</b>					
		1) Are the MQLs for each method analyte listed and included in the laboratory data package?	X				
		2) Do the MQLs correspond to the concentration of the lowest non-zero calibration standard?	X				
		3) Are unadjusted MQLs included in the laboratory data package?	X				
R10	OI	<b>OTHER PROBLEMS/ANOMALIES</b>					
		1) Are all known problems/anomalies/special conditions noted in this LRC and ER?	X				
		2) Were all necessary corrective actions performed for the reported data?	X				
		3) If requested, is the justification for elevated SDLs documented?	X				3

1 Items identified by the letter "R" should be included in the laboratory data package submitted in o the TRRP-required report(s). Items identified by the letter "S" should be retained and made available upon request for the appropriate retention period.

2 O = organic analyses; I = inorganic analyses (and general chemistry, when applicable);

3 NA = Not applicable;

4 NR = Not Reviewed;

5 ER# = Exception Report identification number (an Exception Report should be completed for an item if "NR" or "No" is checked).

### Laboratory Review Checklist: Supporting Data

Laboratory Name: ALS Laboratory Group			LRC Date: 03/01/2010				
Project Name: UPRR HWPW SWMU 1			Laboratory Job Number: 1001524				
Reviewer Name: Lora Terrill			Prep Batch Number(s): : 40719				
# <sup>1</sup>	A <sup>2</sup>	Description	Yes	No	NA <sup>3</sup>	NR <sup>4</sup>	ER# <sup>5</sup>
<b>S1</b>	<b>OI</b>	<b>INITIAL CALIBRATION (ICAL)</b>					
		1) Were response factors (RFs) and/or relative response factors (RRFs) for each analyte within the QC limits?	X				
		2) Were percent RSDs or correlation coefficient criteria met?	X				
		3) Was the number of standards recommended in the method used for all analytes?	X				
		4) Were all points generated between the lowest and highest standard used to calculate the curve?	X				
		5) Are ICAL data available for all instruments used?	X				
		6) Has the initial calibration curve been verified using an appropriate second source standard?	X				
<b>S2</b>	<b>OI</b>	<b>INITIAL AND CONTINUING CALIBRATION VERIFICATION (ICCV AND CCV) AND</b>					
		1) Was the CCV analyzed at the method-required frequency?	X				
		2) Were percent differences for each analyte within the method-required QC limits?	X				
		3) Was the ICAL curve verified for each analyte?	X				
		4) Was the absolute value of the analyte concentration in the inorganic CCB < MDL?			X		
<b>S3</b>	<b>O</b>	<b>MASS SPECTRAL TUNING:</b>					
		1) Was the appropriate compound for the method used for tuning?	X				
		2) Were ion abundance data within the method-required QC limits?	X				
<b>S4</b>	<b>O</b>	<b>INTERNAL STANDARDS (IS):</b>					
		Were IS area counts and retention times within the method-required QC limits?	X				
<b>S5</b>	<b>OI</b>	<b>RAW DATA (NELAC SECTION 1 APPENDIX A GLOSSARY, AND SECTION 5.12 OR</b>					
		1) Were the raw data (e.g., chromatograms, spectral data) reviewed by an analyst?	X				
		2) Were data associated with manual integrations flagged on the raw data?	X				
<b>S6</b>	<b>O</b>	<b>DUAL COLUMN CONFIRMATION</b>					
		Did dual column confirmation results meet the method-required QC?			X		
<b>S7</b>	<b>O</b>	<b>TENTATIVELY IDENTIFIED COMPOUNDS (TICS):</b>					
		If TICS were requested, were the mass spectra and TIC data subject to appropriate checks?			X		
<b>S8</b>	<b>I</b>	<b>INTERFERENCE CHECK SAMPLE (ICS) RESULTS:</b>					
		Were percent recoveries within method QC limits?			X		
<b>S9</b>	<b>I</b>	<b>SERIAL DILUTIONS, POST DIGESTION SPIKES, AND METHOD OF STANDARD</b>					
		Were percent differences, recoveries, and the linearity within the QC limits specified in the method?			X		
<b>S10</b>	<b>OI</b>	<b>PROFICIENCY TEST REPORTS:</b>					
		Was the laboratory's performance acceptable on the applicable proficiency tests or evaluation studies?	X				
<b>S11</b>	<b>OI</b>	<b>METHOD DETECTION LIMIT (MDL) STUDIES</b>					
		1) Was a MDL study performed for each reported analyte?	X				
		2) Is the MDL either adjusted or supported by the analysis of DCSSs?	X				
<b>S12</b>	<b>OI</b>	<b>STANDARDS DOCUMENTATION</b>					
		Are all standards used in the analyses NIST-traceable or obtained from other appropriate sources?	X				
<b>S13</b>	<b>OI</b>	<b>COMPOUND/ANALYTE IDENTIFICATION PROCEDURES</b>					
		Are the procedures for compound/analyte identification documented?	X				
<b>S14</b>	<b>OI</b>	<b>DEMONSTRATION OF ANALYST COMPETENCY (DOC)</b>					
		1) Was DOC conducted consistent with NELAC 5C or ISO/IEC 4.2.2?	X				
		2) Is documentation of the analyst's competency up-to-date and on file?	X				
<b>S15</b>	<b>OI</b>	<b>VERIFICATION/VALIDATION DOCUMENTATION FOR METHODS</b>					
		Are all the methods used to generate the data documented, verified, and validated, where applicable, (NELAC 5.10.2 or ISO/IEC 17025 Section 5.4.5)?	X				
<b>S16</b>	<b>OI</b>	<b>LABORATORY STANDARD OPERATING PROCEDURES (SOPS):</b>					
		Are laboratory SOPs current and on file for each method performed?	X				

- 1 Items identified by the letter "R" should be included in the laboratory data package submitted to the TCEQ in the TRRP-required report(s). Items identified by the letter "S" should be retained and made available upon request for the appropriate retention period.
- 2 O = organic analyses; I = inorganic analyses (and general chemistry, when applicable).
- 3 NA = Not applicable.
- 4 NR = Not Reviewed.
- 5 ER# = Exception Report identification number (an Exception Report should be completed for an item if "NR" or "No" is checked).

<b>Laboratory Review Checklist: Exception Report</b>	
Laboratory Name: ALS Laboratory Group	LRC Date: 03/01/2010
Project Name: UPRR HWPW SWMU 1	Laboratory Job Number: 1001524
Reviewer Name: Lora Terrill	Prep Batch Number(s) : 40719
<b>ER #<sup>1</sup></b>	<b>DESCRIPTION</b>
	No Exceptions.

- 1 ER# = Exception Report identification number (an Exception Report should be completed for an item if “NR” or “No” is checked on the LRC)

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Work Order:** 1001524

**Work Order Sample Summary**

<u>Lab Samp ID</u>	<u>Client Sample ID</u>	<u>Matrix</u>	<u>Tag Number</u>	<u>Collection Date</u>	<u>Date Received</u>	<u>Hold</u>
1001524-01	WG-1620-MW02-012210	Water		1/22/2010 07:20	1/22/2010 16:00	<input type="checkbox"/>
1001524-02	WG-1620-MW01A-012210	Water		1/22/2010 08:20	1/22/2010 16:00	<input type="checkbox"/>
1001524-03	WG-1620-FD01-012210	Water		1/22/2010 08:20	1/22/2010 16:00	<input type="checkbox"/>
1001524-04	WG-1620-MW08-012210	Water		1/22/2010 09:20	1/22/2010 16:00	<input type="checkbox"/>
1001524-05	WG-1620-MW07-012210	Water		1/22/2010 10:30	1/22/2010 16:00	<input type="checkbox"/>
1001524-06	WG-1620-P12-012210	Water		1/22/2010 11:20	1/22/2010 16:00	<input type="checkbox"/>
1001524-07	WG-1620-P10-012210	Water		1/22/2010 12:40	1/22/2010 16:00	<input type="checkbox"/>
1001524-08	WG-1620-FD02-012210	Water		1/22/2010 12:40	1/22/2010 16:00	<input type="checkbox"/>
1001524-09	WG-1620-FB01-012210	Water		1/22/2010 13:00	1/22/2010 16:00	<input type="checkbox"/>
1001524-10	WG-1620-MW11B-012110	Water		1/21/2010 14:50	1/22/2010 16:00	<input type="checkbox"/>
1001524-11	WG-1620-MW11A-012110	Water		1/21/2010 15:30	1/22/2010 16:00	<input type="checkbox"/>
1001524-12	WG-1620-MW10B-012110	Water		1/21/2010 16:15	1/22/2010 16:00	<input type="checkbox"/>
1001524-13	WG-1620-MW10A-012110	Water		1/21/2010 16:50	1/22/2010 16:00	<input type="checkbox"/>

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW02-012210  
**Collection Date:** 1/22/2010 07:20 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-01  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>		Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>
2-Methylnaphthalene		U	0.90	5.0	µg/L	1	1/27/2010 17:52
<b>Acenaphthene</b>	<b>7.3</b>		<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 17:52
Acenaphthylene		U	0.50	5.0	µg/L	1	1/27/2010 17:52
Anthracene		U	0.60	5.0	µg/L	1	1/27/2010 17:52
Bis(2-ethylhexyl)phthalate		U	3.3	5.0	µg/L	1	1/27/2010 17:52
Dibenzofuran		U	0.70	5.0	µg/L	1	1/27/2010 17:52
Fluoranthene		U	0.50	5.0	µg/L	1	1/27/2010 17:52
<b>Fluorene</b>	<b>3.7</b>	J	<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 17:52
Naphthalene		U	0.60	5.0	µg/L	1	1/27/2010 17:52
Phenanthrene		U	0.50	5.0	µg/L	1	1/27/2010 17:52
Pyrene		U	0.50	5.0	µg/L	1	1/27/2010 17:52
Surr: 2,4,6-Tribromophenol	62.7			42-124	%REC	1	1/27/2010 17:52
Surr: 2-Fluorobiphenyl	60.7			48-120	%REC	1	1/27/2010 17:52
Surr: 2-Fluorophenol	50.4			20-120	%REC	1	1/27/2010 17:52
Surr: 4-Terphenyl-d14	56.2			51-135	%REC	1	1/27/2010 17:52
Surr: Nitrobenzene-d5	56.0			41-120	%REC	1	1/27/2010 17:52
Surr: Phenol-d6	52.9			20-120	%REC	1	1/27/2010 17:52

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW01A-012210  
**Collection Date:** 1/22/2010 08:20 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-02  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
<b>2-Methylnaphthalene</b>	<b>1.9</b>	J	<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
<b>Acenaphthene</b>	<b>40</b>		<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 18:15
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 18:15
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 18:15
<b>Dibenzofuran</b>	<b>1.6</b>	J	<b>0.70</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
<b>Fluoranthene</b>	<b>1.7</b>	J	<b>0.50</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
<b>Fluorene</b>	<b>22</b>		<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
<b>Naphthalene</b>	<b>4.3</b>	J	<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:15
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 18:15
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 18:15
Surr: 2,4,6-Tribromophenol	70.5			42-124	%REC	1	1/27/2010 18:15
Surr: 2-Fluorobiphenyl	60.1			48-120	%REC	1	1/27/2010 18:15
Surr: 2-Fluorophenol	54.6			20-120	%REC	1	1/27/2010 18:15
Surr: 4-Terphenyl-d14	57.1			51-135	%REC	1	1/27/2010 18:15
Surr: Nitrobenzene-d5	59.1			41-120	%REC	1	1/27/2010 18:15
Surr: Phenol-d6	59.8			20-120	%REC	1	1/27/2010 18:15

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-FD01-012210  
**Collection Date:** 1/22/2010 08:20 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-03  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
<b>2-Methylnaphthalene</b>	<b>1.8</b>	J	<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
<b>Acenaphthene</b>	<b>39</b>		<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 18:38
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 18:38
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 18:38
<b>Dibenzofuran</b>	<b>1.4</b>	J	<b>0.70</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
<b>Fluoranthene</b>	<b>1.5</b>	J	<b>0.50</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
<b>Fluorene</b>	<b>19</b>		<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
<b>Naphthalene</b>	<b>3.6</b>	J	<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 18:38
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 18:38
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 18:38
Surr: 2,4,6-Tribromophenol	71.5			42-124	%REC	1	1/27/2010 18:38
Surr: 2-Fluorobiphenyl	63.1			48-120	%REC	1	1/27/2010 18:38
Surr: 2-Fluorophenol	53.5			20-120	%REC	1	1/27/2010 18:38
Surr: 4-Terphenyl-d14	56.2			51-135	%REC	1	1/27/2010 18:38
Surr: Nitrobenzene-d5	59.1			41-120	%REC	1	1/27/2010 18:38
Surr: Phenol-d6	57.5			20-120	%REC	1	1/27/2010 18:38

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.



# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW08-012210  
**Collection Date:** 1/22/2010 09:20 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-04  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
2-Methylnaphthalene	U		0.90	5.0	µg/L	1	1/27/2010 19:02
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 19:02
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 19:02
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 19:02
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 19:02
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 19:02
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 19:02
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 19:02
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 19:02
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 19:02
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 19:02
Surr: 2,4,6-Tribromophenol	66.5			42-124	%REC	1	1/27/2010 19:02
Surr: 2-Fluorobiphenyl	58.7			48-120	%REC	1	1/27/2010 19:02
Surr: 2-Fluorophenol	49.8			20-120	%REC	1	1/27/2010 19:02
Surr: 4-Terphenyl-d14	58.0			51-135	%REC	1	1/27/2010 19:02
Surr: Nitrobenzene-d5	57.2			41-120	%REC	1	1/27/2010 19:02
Surr: Phenol-d6	57.3			20-120	%REC	1	1/27/2010 19:02

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW07-012210  
**Collection Date:** 1/22/2010 10:30 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-05  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>		Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>
2-Methylnaphthalene	U		0.90	5.0	µg/L	1	1/27/2010 19:25
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 19:25
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 19:25
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 19:25
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 19:25
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 19:25
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 19:25
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 19:25
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 19:25
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 19:25
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 19:25
Surr: 2,4,6-Tribromophenol	58.3			42-124	%REC	1	1/27/2010 19:25
Surr: 2-Fluorobiphenyl	55.6			48-120	%REC	1	1/27/2010 19:25
Surr: 2-Fluorophenol	46.9			20-120	%REC	1	1/27/2010 19:25
Surr: 4-Terphenyl-d14	56.7			51-135	%REC	1	1/27/2010 19:25
Surr: Nitrobenzene-d5	55.8			41-120	%REC	1	1/27/2010 19:25
Surr: Phenol-d6	53.1			20-120	%REC	1	1/27/2010 19:25

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-P12-012210  
**Collection Date:** 1/22/2010 11:20 AM

**Work Order:** 1001524  
**Lab ID:** 1001524-06  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>		Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 15:56
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 15:56
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 15:56
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 15:56
Di-n-butyl phthalate	U		0.50	5.0	µg/L	1	1/27/2010 15:56
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 15:56
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 15:56
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 15:56
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 15:56
Phenol	U		0.50	5.0	µg/L	1	1/27/2010 15:56
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 15:56
Surr: 2,4,6-Tribromophenol	57.7			42-124	%REC	1	1/27/2010 15:56
Surr: 2-Fluorobiphenyl	56.7			48-120	%REC	1	1/27/2010 15:56
Surr: 2-Fluorophenol	49.0			20-120	%REC	1	1/27/2010 15:56
Surr: 4-Terphenyl-d14	57.4			51-135	%REC	1	1/27/2010 15:56
Surr: Nitrobenzene-d5	56.4			41-120	%REC	1	1/27/2010 15:56
Surr: Phenol-d6	56.8			20-120	%REC	1	1/27/2010 15:56

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-P10-012210  
**Collection Date:** 1/22/2010 12:40 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-07  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 19:48
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 19:48
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 19:48
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 19:48
Di-n-butyl phthalate	U		0.50	5.0	µg/L	1	1/27/2010 19:48
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 19:48
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 19:48
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 19:48
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 19:48
Phenol	U		0.50	5.0	µg/L	1	1/27/2010 19:48
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 19:48
Surr: 2,4,6-Tribromophenol	71.8			42-124	%REC	1	1/27/2010 19:48
Surr: 2-Fluorobiphenyl	58.3			48-120	%REC	1	1/27/2010 19:48
Surr: 2-Fluorophenol	50.5			20-120	%REC	1	1/27/2010 19:48
Surr: 4-Terphenyl-d14	55.8			51-135	%REC	1	1/27/2010 19:48
Surr: Nitrobenzene-d5	56.9			41-120	%REC	1	1/27/2010 19:48
Surr: Phenol-d6	55.8			20-120	%REC	1	1/27/2010 19:48

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-FD02-012210  
**Collection Date:** 1/22/2010 12:40 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-08  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 20:11
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 20:11
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 20:11
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 20:11
Di-n-butyl phthalate	U		0.50	5.0	µg/L	1	1/27/2010 20:11
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 20:11
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 20:11
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 20:11
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 20:11
Phenol	U		0.50	5.0	µg/L	1	1/27/2010 20:11
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 20:11
Surr: 2,4,6-Tribromophenol	65.1			42-124	%REC	1	1/27/2010 20:11
Surr: 2-Fluorobiphenyl	57.8			48-120	%REC	1	1/27/2010 20:11
Surr: 2-Fluorophenol	52.5			20-120	%REC	1	1/27/2010 20:11
Surr: 4-Terphenyl-d14	58.0			51-135	%REC	1	1/27/2010 20:11
Surr: Nitrobenzene-d5	58.8			41-120	%REC	1	1/27/2010 20:11
Surr: Phenol-d6	61.2			20-120	%REC	1	1/27/2010 20:11

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-FB01-012210  
**Collection Date:** 1/22/2010 01:00 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-09  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
2-Methylnaphthalene	U		0.90	5.0	µg/L	1	1/27/2010 20:35
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 20:35
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 20:35
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 20:35
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 20:35
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 20:35
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 20:35
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 20:35
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 20:35
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 20:35
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 20:35
Surr: 2,4,6-Tribromophenol	59.5			42-124	%REC	1	1/27/2010 20:35
Surr: 2-Fluorobiphenyl	55.6			48-120	%REC	1	1/27/2010 20:35
Surr: 2-Fluorophenol	48.9			20-120	%REC	1	1/27/2010 20:35
Surr: 4-Terphenyl-d14	52.8			51-135	%REC	1	1/27/2010 20:35
Surr: Nitrobenzene-d5	52.9			41-120	%REC	1	1/27/2010 20:35
Surr: Phenol-d6	52.9			20-120	%REC	1	1/27/2010 20:35

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW11B-012110  
**Collection Date:** 1/21/2010 02:50 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-10  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
Acenaphthene	48		0.90	5.0	µg/L	1	1/27/2010 20:58
Acenaphthylene	1.3	J	0.50	5.0	µg/L	1	1/27/2010 20:58
Anthracene	1.1	J	0.60	5.0	µg/L	1	1/27/2010 20:58
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 20:58
Di-n-butyl phthalate	U		0.50	5.0	µg/L	1	1/27/2010 20:58
Dibenzofuran	12		0.70	5.0	µg/L	1	1/27/2010 20:58
Fluoranthene	1.4	J	0.50	5.0	µg/L	1	1/27/2010 20:58
Fluorene	13		0.60	5.0	µg/L	1	1/27/2010 20:58
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 20:58
Phenol	U		0.50	5.0	µg/L	1	1/27/2010 20:58
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 20:58
Surr: 2,4,6-Tribromophenol	65.4			42-124	%REC	1	1/27/2010 20:58
Surr: 2-Fluorobiphenyl	58.8			48-120	%REC	1	1/27/2010 20:58
Surr: 2-Fluorophenol	48.9			20-120	%REC	1	1/27/2010 20:58
Surr: 4-Terphenyl-d14	55.0			51-135	%REC	1	1/27/2010 20:58
Surr: Nitrobenzene-d5	54.5			41-120	%REC	1	1/27/2010 20:58
Surr: Phenol-d6	58.0			20-120	%REC	1	1/27/2010 20:58

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW11A-012110  
**Collection Date:** 1/21/2010 03:30 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-11  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
2-Methylnaphthalene	U		0.90	5.0	µg/L	1	1/27/2010 21:21
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 21:21
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 21:21
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 21:21
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 21:21
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 21:21
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 21:21
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 21:21
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 21:21
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 21:21
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 21:21
Surr: 2,4,6-Tribromophenol	66.8			42-124	%REC	1	1/27/2010 21:21
Surr: 2-Fluorobiphenyl	58.7			48-120	%REC	1	1/27/2010 21:21
Surr: 2-Fluorophenol	50.5			20-120	%REC	1	1/27/2010 21:21
Surr: 4-Terphenyl-d14	55.4			51-135	%REC	1	1/27/2010 21:21
Surr: Nitrobenzene-d5	55.5			41-120	%REC	1	1/27/2010 21:21
Surr: Phenol-d6	54.0			20-120	%REC	1	1/27/2010 21:21

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.



# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW10B-012110  
**Collection Date:** 1/21/2010 04:15 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-12  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
<b>Acenaphthene</b>	<b>52</b>		<b>0.90</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 21:44
<b>Anthracene</b>	<b>2.5</b>	J	<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 21:44
Di-n-butyl phthalate	U		0.50	5.0	µg/L	1	1/27/2010 21:44
<b>Dibenzofuran</b>	<b>18</b>		<b>0.70</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
<b>Fluoranthene</b>	<b>1.7</b>	J	<b>0.50</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
<b>Fluorene</b>	<b>31</b>		<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
<b>Naphthalene</b>	<b>3.7</b>	J	<b>0.60</b>	<b>5.0</b>	<b>µg/L</b>	1	1/27/2010 21:44
Phenol	U		0.50	5.0	µg/L	1	1/27/2010 21:44
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 21:44
Surr: 2,4,6-Tribromophenol	67.9			42-124	%REC	1	1/27/2010 21:44
Surr: 2-Fluorobiphenyl	51.8			48-120	%REC	1	1/27/2010 21:44
Surr: 2-Fluorophenol	50.0			20-120	%REC	1	1/27/2010 21:44
Surr: 4-Terphenyl-d14	53.4			51-135	%REC	1	1/27/2010 21:44
Surr: Nitrobenzene-d5	54.5			41-120	%REC	1	1/27/2010 21:44
Surr: Phenol-d6	55.2			20-120	%REC	1	1/27/2010 21:44

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

# ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**Sample ID:** WG-1620-MW10A-012110  
**Collection Date:** 1/21/2010 04:50 PM

**Work Order:** 1001524  
**Lab ID:** 1001524-13  
**Matrix:** WATER

Analyses	Result	Qual	SDL	MLL	Units	Dilution Factor	Date Analyzed
<b>SEMIVOLATILES</b>			Method: <b>SW8270</b>	Prep: SW3510 / 1/27/10		Analyst: <b>ACN</b>	
2-Methylnaphthalene	U		0.90	5.0	µg/L	1	1/27/2010 22:07
Acenaphthene	U		0.90	5.0	µg/L	1	1/27/2010 22:07
Acenaphthylene	U		0.50	5.0	µg/L	1	1/27/2010 22:07
Anthracene	U		0.60	5.0	µg/L	1	1/27/2010 22:07
Bis(2-ethylhexyl)phthalate	U		3.3	5.0	µg/L	1	1/27/2010 22:07
Dibenzofuran	U		0.70	5.0	µg/L	1	1/27/2010 22:07
Fluoranthene	U		0.50	5.0	µg/L	1	1/27/2010 22:07
Fluorene	U		0.60	5.0	µg/L	1	1/27/2010 22:07
Naphthalene	U		0.60	5.0	µg/L	1	1/27/2010 22:07
Phenanthrene	U		0.50	5.0	µg/L	1	1/27/2010 22:07
Pyrene	U		0.50	5.0	µg/L	1	1/27/2010 22:07
Surr: 2,4,6-Tribromophenol	91.4			42-124	%REC	1	1/27/2010 22:07
Surr: 2-Fluorobiphenyl	70.2			48-120	%REC	1	1/27/2010 22:07
Surr: 2-Fluorophenol	54.5			20-120	%REC	1	1/27/2010 22:07
Surr: 4-Terphenyl-d14	71.9			51-135	%REC	1	1/27/2010 22:07
Surr: Nitrobenzene-d5	66.2			41-120	%REC	1	1/27/2010 22:07
Surr: Phenol-d6	67.8			20-120	%REC	1	1/27/2010 22:07

**Note:** See Qualifiers Page for a list of qualifiers and their explanation.

**WorkOrder:** 1001524  
**Test Code:** 8270\_TCL\_W  
**Test Number:** SW8270  
**Test Name:** Semivolatiles

**METHOD DETECTION /  
 REPORTING LIMITS**

**Matrix:** Aqueous      **Units:** µg/L

Type	Analyte	CAS	MDL	Unadjusted MQL
A	2-Methylnaphthalene	91-57-6	0.9	5
A	Acenaphthene	83-32-9	0.9	5
A	Acenaphthylene	208-96-8	0.5	5
A	Anthracene	120-12-7	0.6	5
A	Bis(2-ethylhexyl)phthalate	117-81-7	3.3	5
A	Di-n-butyl phthalate	84-74-2	0.5	5
A	Dibenzofuran	132-64-9	0.7	5
A	Fluoranthene	206-44-0	0.5	5
A	Fluorene	86-73-7	0.6	5
A	Naphthalene	91-20-3	0.6	5
A	Phenanthrene	85-01-8	0.5	5
A	Phenol	108-95-2	0.5	5
A	Pyrene	129-00-0	0.5	5
S	Surr: 2,4,6-Tribromophenol	118-79-6	0	5
S	Surr: 2-Fluorobiphenyl	321-60-8	0	5
S	Surr: 2-Fluorophenol	367-12-4	0	5
S	Surr: 4-Terphenyl-d14	1718-51-0	0	5
S	Surr: Nitrobenzene-d5	4165-60-0	0	5
S	Surr: Phenol-d6	13127-88-3	0	5

ALS Laboratory Group

Date: 01-Mar-10

**Client:** Pastor, Behling & Wheeler, LLC  
**Work Order:** 1001524  
**Project:** UPRR HWPW SWMU 1

**QC BATCH REPORT**

Batch ID: **40719** Instrument ID **SV-3** Method: **SW8270**

**MBLK** Sample ID: **SBLKW1-100127-40719** Units: **µg/L** Analysis Date: **1/27/2010 02:46 PM**

Client ID: Run ID: **SV-3\_100127A** SeqNo: **1865439** Prep Date: **1/27/2010** DF: **1**

Analyte	Result	MQL	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
2-Methylnaphthalene	U	5.0								
Acenaphthene	U	5.0								
Acenaphthylene	U	5.0								
Anthracene	U	5.0								
Bis(2-ethylhexyl)phthalate	U	5.0								
Di-n-butyl phthalate	U	5.0								
Dibenzofuran	U	5.0								
Fluoranthene	U	5.0								
Fluorene	U	5.0								
Naphthalene	U	5.0								
Phenanthrene	U	5.0								
Phenol	U	5.0								
Pyrene	U	5.0								
<i>Surr: 2,4,6-Tribromophenol</i>	<i>70.78</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>70.8</i>	<i>42-124</i>	<i>0</i>			
<i>Surr: 2-Fluorobiphenyl</i>	<i>62.39</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>62.4</i>	<i>48-120</i>	<i>0</i>			
<i>Surr: 2-Fluorophenol</i>	<i>54.23</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>54.2</i>	<i>20-120</i>	<i>0</i>			
<i>Surr: 4-Terphenyl-d14</i>	<i>60.94</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>60.9</i>	<i>51-135</i>	<i>0</i>			
<i>Surr: Nitrobenzene-d5</i>	<i>62.85</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>62.9</i>	<i>41-120</i>	<i>0</i>			
<i>Surr: Phenol-d6</i>	<i>61.47</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>61.5</i>	<i>20-120</i>	<i>0</i>			

**Note:** See Qualifiers Page for a list of Qualifiers and their explanation.

**Client:** Pastor, Behling & Wheeler, LLC  
**Work Order:** 1001524  
**Project:** UPRR HWPW SWMU 1

# QC BATCH REPORT

Batch ID: **40719**      Instrument ID **SV-3**      Method: **SW8270**

LCS		Sample ID: <b>SLCSW1-100127-40719</b>			Units: <b>µg/L</b>		Analysis Date: <b>1/27/2010 03:09 PM</b>			
Client ID:		Run ID: <b>SV-3_100127A</b>			SeqNo: <b>1865440</b>		Prep Date: <b>1/27/2010</b>		DF: <b>1</b>	
Analyte	Result	ML	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
2-Methylnaphthalene	35.33	5.0	50	0	70.7	55-120	0			
Acenaphthene	36.07	5.0	50	0	72.1	55-120	0			
Acenaphthylene	36.9	5.0	50	0	73.8	55-120	0			
Anthracene	36.8	5.0	50	0	73.6	55-120	0			
Bis(2-ethylhexyl)phthalate	37.64	5.0	50	0	75.3	50-125	0			
Di-n-butyl phthalate	38.81	5.0	50	0	77.6	55-120	0			
Dibenzofuran	36.22	5.0	50	0	72.4	55-120	0			
Fluoranthene	36.29	5.0	50	0	72.6	55-120	0			
Fluorene	36.75	5.0	50	0	73.5	55-120	0			
Naphthalene	36.26	5.0	50	0	72.5	55-120	0			
Phenanthrene	36.88	5.0	50	0	73.8	55-120	0			
Phenol	66.06	5.0	100	0	66.1	50-120	0			
Pyrene	38.97	5.0	50	0	77.9	55-120	0			
<i>Surr: 2,4,6-Tribromophenol</i>	<i>70.1</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>70.1</i>	<i>42-124</i>	<i>0</i>			
<i>Surr: 2-Fluorobiphenyl</i>	<i>67.68</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>67.7</i>	<i>48-120</i>	<i>0</i>			
<i>Surr: 2-Fluorophenol</i>	<i>65.94</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>65.9</i>	<i>20-120</i>	<i>0</i>			
<i>Surr: 4-Terphenyl-d14</i>	<i>67.35</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>67.3</i>	<i>51-135</i>	<i>0</i>			
<i>Surr: Nitrobenzene-d5</i>	<i>66.52</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>66.5</i>	<i>41-120</i>	<i>0</i>			
<i>Surr: Phenol-d6</i>	<i>68.68</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>68.7</i>	<i>20-120</i>	<i>0</i>			

**Note:** See Qualifiers Page for a list of Qualifiers and their explanation.

**Client:** Pastor, Behling & Wheeler, LLC  
**Work Order:** 1001524  
**Project:** UPRR HWPW SWMU 1

## QC BATCH REPORT

Batch ID: **40719**      Instrument ID **SV-3**      Method: **SW8270**

MS		Sample ID: <b>1001524-06AMS</b>			Units: <b>µg/L</b>			Analysis Date: <b>1/27/2010 04:19 PM</b>		
Client ID: <b>WG-1620-P12-012210</b>		Run ID: <b>SV-3_100127A</b>			SeqNo: <b>1865442</b>			Prep Date: <b>1/27/2010</b>		DF: <b>1</b>
Analyte	Result	ML	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
2-Methylnaphthalene	32.32	5.0	50	0	64.6	55-120	0			
Acenaphthene	33.42	5.0	50	0	66.8	55-120	0			
Acenaphthylene	34.27	5.0	50	0	68.5	55-120	0			
Anthracene	33.67	5.0	50	0	67.3	55-120	0			
Bis(2-ethylhexyl)phthalate	32.9	5.0	50	0	65.8	50-125	0			
Di-n-butyl phthalate	35.89	5.0	50	0	71.8	55-120	0			
Dibenzofuran	34.6	5.0	50	0	69.2	55-120	0			
Fluoranthene	34.42	5.0	50	0	68.8	55-120	0			
Fluorene	33.52	5.0	50	0	67	55-120	0			
Naphthalene	33.81	5.0	50	0	67.6	55-120	0			
Phenanthrene	34.88	5.0	50	0	69.8	55-120	0			
Phenol	66.62	5.0	100	0	66.6	50-120	0			
Pyrene	35.25	5.0	50	0	70.5	55-120	0			
<i>Surr: 2,4,6-Tribromophenol</i>	59.55	5.0	100	0	59.6	42-124	0			
<i>Surr: 2-Fluorobiphenyl</i>	57.08	5.0	100	0	57.1	48-120	0			
<i>Surr: 2-Fluorophenol</i>	60.88	5.0	100	0	60.9	20-120	0			
<i>Surr: 4-Terphenyl-d14</i>	56.32	5.0	100	0	56.3	51-135	0			
<i>Surr: Nitrobenzene-d5</i>	60.55	5.0	100	0	60.6	41-120	0			
<i>Surr: Phenol-d6</i>	60.92	5.0	100	0	60.9	20-120	0			

**Note:** See Qualifiers Page for a list of Qualifiers and their explanation.

Client: Pastor, Behling & Wheeler, LLC  
 Work Order: 1001524  
 Project: UPRR HWPW SWMU 1

# QC BATCH REPORT

Batch ID: **40719** Instrument ID **SV-3** Method: **SW8270**

MSD		Sample ID: <b>1001524-06AMSD</b>			Units: <b>µg/L</b>			Analysis Date: <b>1/27/2010 04:43 PM</b>		
Client ID: <b>WG-1620-P12-012210</b>		Run ID: <b>SV-3_100127A</b>			SeqNo: <b>1865443</b>		Prep Date: <b>1/27/2010</b>		DF: <b>1</b>	
Analyte	Result	MLL	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
2-Methylnaphthalene	35.09	5.0	50	0	70.2	55-120	32.32	8.22	20	
Acenaphthene	33.96	5.0	50	0	67.9	55-120	33.42	1.61	20	
Acenaphthylene	36.01	5.0	50	0	72	55-120	34.27	4.95	20	
Anthracene	33.79	5.0	50	0	67.6	55-120	33.67	0.349	20	
Bis(2-ethylhexyl)phthalate	34.68	5.0	50	0	69.4	50-125	32.9	5.28	20	
Di-n-butyl phthalate	35.99	5.0	50	0	72	55-120	35.89	0.272	20	
Dibenzofuran	34.85	5.0	50	0	69.7	55-120	34.6	0.704	20	
Fluoranthene	35.41	5.0	50	0	70.8	55-120	34.42	2.82	20	
Fluorene	34.58	5.0	50	0	69.2	55-120	33.52	3.1	20	
Naphthalene	34.87	5.0	50	0	69.7	55-120	33.81	3.07	20	
Phenanthrene	34.15	5.0	50	0	68.3	55-120	34.88	2.12	20	
Phenol	61.81	5.0	100	0	61.8	50-120	66.62	7.49	20	
Pyrene	37.23	5.0	50	0	74.5	55-120	35.25	5.46	20	
<i>Surr: 2,4,6-Tribromophenol</i>	<i>67.84</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>67.8</i>	<i>42-124</i>	<i>59.55</i>	<i>13</i>	<i>20</i>	
<i>Surr: 2-Fluorobiphenyl</i>	<i>64.13</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>64.1</i>	<i>48-120</i>	<i>57.08</i>	<i>11.6</i>	<i>20</i>	
<i>Surr: 2-Fluorophenol</i>	<i>62.91</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>62.9</i>	<i>20-120</i>	<i>60.88</i>	<i>3.28</i>	<i>20</i>	
<i>Surr: 4-Terphenyl-d14</i>	<i>61.87</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>61.9</i>	<i>51-135</i>	<i>56.32</i>	<i>9.4</i>	<i>20</i>	
<i>Surr: Nitrobenzene-d5</i>	<i>64.9</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>64.9</i>	<i>41-120</i>	<i>60.55</i>	<i>6.93</i>	<i>20</i>	
<i>Surr: Phenol-d6</i>	<i>60.65</i>	<i>5.0</i>	<i>100</i>	<i>0</i>	<i>60.7</i>	<i>20-120</i>	<i>60.92</i>	<i>0.442</i>	<i>20</i>	

The following samples were analyzed in this batch:

1001524-01A	1001524-02A	1001524-03A
1001524-04A	1001524-05A	1001524-06A
1001524-07A	1001524-08A	1001524-09A
1001524-10A	1001524-11A	1001524-12A
1001524-13A		

Note: See Qualifiers Page for a list of Qualifiers and their explanation.

**Client:** Pastor, Behling & Wheeler, LLC  
**Project:** UPRR HWPW SWMU 1  
**WorkOrder:** 1001524


**QUALIFIERS,  
ACRONYMS, UNITS**

<u>Qualifier</u>	<u>Description</u>
*	Value exceeds Regulatory Limit
a	Not accredited
B	Analyte detected in the associated Method Blank above the Reporting Limit
E	Value above quantitation range
H	Analyzed outside of Holding Time
J	Analyte detected below quantitation limit
M	Manually integrated, see raw data for justification
n	Not offered for accreditation
ND	Not Detected at the Reporting Limit
O	Sample amount is > 4 times amount spiked
P	Dual Column results percent difference > 40%
R	RPD above laboratory control limit
S	Spike Recovery outside laboratory control limits
U	Analyzed but not detected above the MDL

<u>Acronym</u>	<u>Description</u>
DUP	Method Duplicate
LCS	Laboratory Control Sample
LCSD	Laboratory Control Sample Duplicate
MBLK	Method Blank
MDL	Method Detection Limit
MQL	Method Quantitation Limit
MS	Matrix Spike
MSD	Matrix Spike Duplicate
PDS	Post Digestion Spike
PQL	Practical Quantitation Limit
SD	Serial Dilution
SDL	Sample Detection Limit
TRRP	Texas Risk Reduction Program

<u>Units Reported</u>	<u>Description</u>
µg/L	Micrograms per Liter





**ALS Laboratory Group**  
 10450 Standcliff Rd., Suite 210  
 Houston, Texas 77099  
 Tel. +1 281 530 5656  
 Fax. +1 281 530 5887

**Chain of Custody Form**

Page 1 of 2

**ALS Laboratory Group**  
 3352 128th Ave.  
 Holland, MI 49424-9263  
 Tel: +1 616 399 6070  
 Fax: +1 616 399 6185

Customer Information			Project Information			ALS Project Manager: <u>10527</u>												
Purchase Order #	Project Name	HWPW SWMU 1	Parameter/Method Request for Analysis	LOW SVOC (8270) Select														
Work Order #	Project Number	1620		ATZ LIST														
Company Name	Bill To Company	Union Pacific Railroad		BTE LIST														
Send Report To	Invoice Attn																	
Address	Address	1400 Douglas Street																
City/State/Zip	City/State/Zip	Stop 0750																
Phone	Phone	Omaha, NE 681790750																
Fax	Fax																	
e-Mail Address	e-Mail Address																	
No.	Sample Description	Date	Time	Matrix	Pres.	# Bottles	A	B	C	D	E	F	G	H	I	J	Hold	
1	WG-1620-MW02-012210	1-22-10	0720	W		2	X	X										
2	WG-1620-MW04-012210	1-22-10	0820	W		2	X	X										
3	WG-1620-FD01-012210	1-22-10	0820	W		2	X	X										
4	WG-1620-MW08-012210	1-22-10	0920	W		2	X	X										
5	WG-1620-MW07-012210	1-22-10	1030	W		2	X	X										
6	WG-1620-PI2-012210	1-22-10	1120	W		2	X	X										
7	WG-1620-PI2MS-012210	1-22-10	1120	W		2	X	X										
8	WG-1620-PI2MSD-012210	1-22-10	1120	W		2	X	X										
9	WG-1620-PI0-012210	1-22-10	1240	W		2	X	X										
10	WG-1620-FD02-012210	1-22-10	1240	W		2	X	X										
Sampler(s) Please Print & Sign		Shipment Method		Required Turnaround Time: (Check Box)		Results Due Date												
JOHN BREANNIN <i>John Breannin</i>		HAND DELIVERED		<input checked="" type="checkbox"/> Std 10 WK Days <input type="checkbox"/> 5 WK Days <input type="checkbox"/> 2 WK Days <input type="checkbox"/> Other														
Relinquished by <i>John Breannin</i>		Received by <i>John Breannin</i>		Date: 1-22-10		Time: 10:25		Notes: 1-22-10 Work Days TAT.										
Requisitioned by <i>John Breannin</i>		Date: 1-22-10		Time: 10:25		Cooler ID: 1303		QC Package: (Check One Box Below) <input checked="" type="checkbox"/> Level II Std QC <input type="checkbox"/> Level III Std QC <input type="checkbox"/> Level IV SW046/CLP <input type="checkbox"/> Other										
Logged by (Laboratory): <i>John Breannin</i>		Date: 1-23-10		Time: 10:25		Cooler ID: 3297		TRRP Checklist <input checked="" type="checkbox"/> TRRP Level I <input type="checkbox"/> TRRP Level II <input type="checkbox"/> TRRP Level III <input type="checkbox"/> TRRP Level IV <input type="checkbox"/>										
Preservative Key: 1-HCl 2-HNO <sub>3</sub> 3-H <sub>2</sub> SO <sub>4</sub> 4-NaOH 5-Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> 6-NaHSO <sub>3</sub> 7-Other 8-4°C 9-5035																		

Note: 1. Any changes must be made in writing once samples and COC Form have been submitted to ALS Laboratory Group.  
 2. Unless otherwise agreed in a formal contract, services provided by ALS Laboratory Group are expressly limited to the terms and conditions stated on the reverse.  
 3. The Chain of Custody is a legal document. All information must be completed accurately.

Copyright 2008 by ALS Laboratory Group.

Page 2 of 2

Customer Information				Project Information				ALS Work Order # <u>00127</u> Parameter/Method Request for Analysis											
Project Name HWPW SWMU 1				Project Number 1620				Select											
Bill To Company Pastor, Behling & Wheeler, LLC				Invoice Ath.															
Eric Matzner				Address 2201 Double Creek Drive Suite 4004															
City/State/Zip Round Rock, TX 78664				Phone (512) 671-3434															
e-Mail Address				Fax (512) 671-3446															
No.	Sample Description	Date	Time	Matrix	Pres	# Bottles	A	B	C	D	E	F	G	H	I	J	Hold		
1	WG-1620-FB01-012210	1-22-10	1300	W		2	X												
2	WG-1620-MW11B-012210	1-21-10	1450	W		2	X		X										
3	WG-1620-MW11A-012110	1-21-10	1530	W		2	X		X										
4	WG-1620-MW10B-012110	1-21-10	1615	W		2	X		X										
5	WG-1620-MW10A-012110	1-21-10	1650	W		2	X		X										
6																			
7																			
8																			
9																			
10																			

**Sampler(s) Please Print & Sign**  
 JOHN BRAYNON  
 Date: 1-22-10  
 Time: 1600

**Ship Method**  
 HAND DELIVERED  
 Required Turnaround Time: (Check Box)  
 5 WK Days  
 2 WK Days  
 24 Hour

**Received by:**  
 [Signature]  
 Date: 1-23-10  
 Time: 1625

**Checked by Laboratory:**  
 [Signature]  
 Date: 1-23-10  
 Time: 1625

**Notes:**  
 10 Work Days TAT.

**QC Package:** (Check One Box Below)  
 Level II Std QC  
 Level III Std QC  
 Level IV SW846/CLP  
 TRRP Checklist

**Preservative Key:**  
 1-HCl  
 2-HNO<sub>3</sub>  
 3-H<sub>2</sub>SO<sub>4</sub>  
 4-NaOH  
 5-Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub>  
 6-NaHSO<sub>3</sub>  
 7-Other

Note: 1. Any changes must be made in writing once samples and COC Form have been submitted to ALS Laboratory Group.  
 2. Unless otherwise agreed in a formal contract, services provided by ALS Laboratory Group are expressly limited to the terms and conditions stated on the reverse.  
 3. The Chain of Custody is a legal document. All information must be completed accurately.

Copyright 2008 by ALS Laboratory Group.

Sample Receipt Checklist

Client Name: **PBW**

Date/Time Received: **22-Jan-10 16:00**

Work Order: **1001524**

Received by: **PS**

Checklist completed by Richard Sanchez 25-Jan-10  
eSignature Date

Reviewed by: Lera Ferrill 26-Jan-10  
eSignature Date

Matrices: water  
Carrier name: ALS.HS

Shipping container/cooler in good condition? Yes  No  Not Present

Custody seals intact on shipping container/cooler? Yes  No  Not Present

Custody seals intact on sample bottles? Yes  No  Not Present

Chain of custody present? Yes  No

Chain of custody signed when relinquished and received? Yes  No

Chain of custody agrees with sample labels? Yes  No

Samples in proper container/bottle? Yes  No

Sample containers intact? Yes  No

Sufficient sample volume for indicated test? Yes  No

All samples received within holding time? Yes  No

Container/Temp Blank temperature in compliance? Yes  No

Temperature(s)/Thermometer(s):

Cooler(s)/Kit(s):

Water - VOA vials have zero headspace? Yes  No  No VOA vials submitted

Water - pH acceptable upon receipt? Yes  No  N/A

pH adjusted? Yes  No  N/A

pH adjusted by:

Login Notes:

Client Contacted:

Date Contacted:

Person Contacted:

Contacted By:

Regarding:

Comments:

CorrectiveAction:



**CONESTOGA-ROVERS  
& ASSOCIATES**

E-Mail Date: March 18, 2010  
E-Mail To: Eric Matzner/ Pastor, Behling & Wheeler, LLC  
c.c.: Patricia Lynch  
E-Mail and Hard Copy if Requested

**DATA USABILITY SUMMARY  
UNION PACIFIC RAILROAD (UPRR)  
HOUSTON WOOD PRESERVING WORKS  
SEMI-ANNUAL COMPLIANCE MONITORING  
HOUSTON, TEXAS  
JANUARY 2010**

**PREPARED BY:**  
**CONESTOGA-ROVERS & ASSOCIATES**  
6320 Rothway, Suite 100  
Houston, Texas 77040  
Telephone: 713-734-3090 Fax: 713-734-3391  
Contact: Patricia L. Lynch [bjw] *PL Lynch*  
Date: March 18, 2010  
[www.CRAworld.com](http://www.CRAworld.com)

## Data Usability Summary

<b>Reviewer:</b>	Patricia L. Lynch - Conestoga-Rovers & Associates, Inc.
<b>Contract Laboratory:</b>	ALS Laboratory Group – Houston, Texas
<b>Project/Area of Interest:</b>	UPRR Houston Wood Preserving Works - Houston, Texas
<b>Description of Data Packages Reviewed:</b>	Groundwater sample results for SWMU No. 1 in data package 1001524
<b>Sample Collection Date(s):</b>	January 21 - 22, 2010
<b>Intended Use of Data:</b>	To monitor the COCs in groundwater at the site and to evaluate whether migration of COCs could result in risk to human or ecological health.

### 1.0 Scope of Data Usability Summary

Data were reviewed and validated in accordance with Title 30 of the Texas Administrative Code Section 350.54 (30 TAC 350.54) as described in *Review and Reporting of COC Concentration Data*, (RG-366/TRRP-13) and the results of the review/validation are discussed in this Data Usability Summary (DUS). The review included examination of the reported data, the laboratory review checklist (LRC), and field/laboratory quality assurance/quality control (QA/QC) samples collected at the Site. Tables summarizing data qualifications discussed in this DUS can be found in Appendix A.

Ten (10) groundwater samples plus two field duplicates and one field blank were analyzed for semi-volatile organic compounds (SVOCs) by SW-846 Method 8270C<sup>1</sup>

A sampling and analysis summary is presented in Table 1. This summary includes a cross-reference of field sample identification numbers and laboratory sample numbers. Each sample was assigned a unique field identification number. The lists of SVOC target compounds are presented in Table 2.

### 2.0 Laboratory Qualifications

Analytical services were provided by ALS Laboratory Group (ALS) located in Houston, Texas. The laboratory's quality assurance program is consistent with the quality standards outlined in the National Environmental Laboratory Accreditation Program (NELAP). The laboratory was accredited under Texas Certification Number T104704231-09-1-TX at the time the analyses were performed.

---

<sup>1</sup> "Test Methods for Evaluating Solid Waste Physical/Chemical Methods", SW-846, 3rd Edition, September 1986 (with subsequent revisions).

### **3.0 Project Objectives**

#### **3.1 Levels of Required Performance (LORP)**

Prior to sampling, the LORP for each COC was established for the investigation. A standard available analytical method was selected and minimal detection limits that are at or below the Texas Risk Reduction Tier 1 Residential Protective Concentration Levels (PCLs), <sup>GW</sup> GW<sub>ING</sub> for groundwater were sought.

#### **3.2 Sampling/ Analytical QA/QC Objectives**

Pastor, Behling & Wheeler, LLC designed the QA/QC program to identify contamination resulting from sample collection, sample transport and the analytical process.

- Method blanks of a similar matrix to that of the associated samples are prepared by the laboratory and analyzed to determine if laboratory contaminants are affecting the analytical results. Method blanks are prepared and analyzed with each batch.
- A field blank was collected and analyzed to determine if the chemicals of concern would be detected based on the ambient field conditions. The field blank was kept in the same environment in which the other field samples were collected.

Similarly, the QA/QC program was designed to evaluate the quality of the resulting data with respect to bias and precision. First, a laboratory control sample (LCS) was prepared and analyzed with each batch. The recovery ranges established by the laboratory are adopted as the acceptance criteria for the project. Second, a matrix spike/matrix spike duplicate (MS/MSD) was prepared and analyzed with each batch. The recovery ranges and RPDs established by the laboratory are adopted as the acceptance criteria for the project. Third, field duplicates were collected and submitted for analysis. The RPD acceptance criterion for the water field duplicates is 30 percent. This RPD criterion is only used when sample concentrations are above the estimated regions of detection.

### **4.0 Data Review/Validation Results**

#### **4.1 Analytical Results**

The laboratory qualified analytes with concentrations above the Sample Detection Limits (SDLs) but below the Method Quantitation Limits (MQL) as estimated on the analytical tables per the TRRP-13 document. None of the data required further qualification based on the established QC criteria.

#### **4.2 LORP**

All SDLs and unadjusted MQLs met the LORP for this investigation.

#### 4.3 Preservation and Holding Times

Samples were properly preserved in the field and cooled to 4°C ( $\pm 2^\circ\text{C}$ ). Samples were delivered on ice with chains of custody, and the paperwork was filled out properly. All samples were prepared and analyzed within the applicable holding times.

#### 4.4 Sample Containers

Sample containers were certified pre-cleaned glass provided by the laboratory. These containers meet or exceed analyte specifications established in the USEPA *Specifications and Guidance for Contaminant-free Sample Containers*.

#### 4.5 Calibrations

According to the LRCs, initial calibration and continuing calibration data met the criteria for the selected methods.

#### 4.6 Blanks

Method Blank: As this was not discrete samples handled in the field, the method blank is not listed on the sample identification cross-reference list found in Table 1. Results are reported in the data package on a laboratory batch basis. All of the laboratory blank results were reported as ND (not detected).

Field Blank: A field blank was collected and analyzed for semi-volatiles and is listed on the sample summary table. All target SVOC compounds were non-detect in the field blank.

#### 4.7 Internal Standard and Surrogate Recoveries

Recoveries of internal standards and surrogates for SVOCs are addressed in the LRCs of the laboratory data packages. All surrogate recoveries and internal standard areas and retention times were within the acceptance limits.

#### 4.8 Laboratory Control Samples (LCS)

LCS data for all COCs were reported for the batch, and the LCS spike recoveries for all COCs were within the project objectives.

#### 4.9 Matrix Spikes

Sample WG-1620-P12-012210 was selected for matrix spike/matrix spike duplicate analyses for SVOCs, and the results are reported in the data packages. All recoveries and RPDs were within the laboratory established control limits.

#### 4.10 Field Duplicate

Field duplicates of samples listed below were collected and analyzed.

- WG-1620-FD01-012210 is a duplicate of WG-1620-MW01A-012210.
- WG-1620-FD02-012210 is a duplicate of WG-1620-P10-012210.

All results showed good precision above the estimated regions of detection (see Table 3). Some results were non-detect, and the RPDs could not be calculated. Only detected results are found on Table 3.

#### 4.11 Field Procedures

Pastor, Behling & Wheeler, LLC collected soil groundwater samples in accordance with their Standard Operating Procedures (SOP) for sample collection.

#### 4.12 Summary

The analytical data in this report are usable to assess the impact of COCs in groundwater at the site without qualification.



APPENDIX A

TABLES

TABLE 1

**SAMPLE AND ANALYSIS SUMMARY**  
**SEMI-ANNUAL COMPLIANCE MONITORING**  
**SWMU NO. 1**  
**UNION PACIFIC RAILROAD (UPRR)**  
**HOUSTON WOOD PRESERVING WORKS**  
**HOUSTON, TEXAS**  
**JANUARY 2010**

<i>Sample I.D.</i>	<i>Location I.D.</i>	<i>Matrix</i>	<i>Date (mm/dd/yy)</i>	<i>Time (hr:min)</i>	<i>Analysis/Parameters [1 parameter]</i>	<i>Comment</i>
WG-1620-MW02-012210	MW-02	Water	01/22/10	7:20:00 AM	SVOCs	
WG-1620-MW01A-012210	MW-01A	Water	01/22/10	8:20:00 AM	SVOCs	
WG-1620-FD01-012210	MW-01A	Water	01/22/10	8:20:00 AM	SVOCs	Field duplicate of WG-1620-MW01A-012210
WG-1620-MW08-012210	MW-08	Water	01/22/10	9:20:00 AM	SVOCs	
WG-1620-MW07-012210	MW-07	Water	01/22/10	10:30:00 AM	SVOCs	
WG-1620-P12-012210	P-12	Water	01/22/10	11:20:00 AM	SVOCs	
WG-1620-P10-012210	P-10	Water	01/22/10	12:40:00 PM	SVOCs	
WG-1620-FD02-012210	P-10	Water	01/22/10	12:40:00 PM	SVOCs	Field duplicate of WG-1620-P10-012210
WG-1620-FB01-012210	Field Blank	Water	01/22/10	1:00:00 PM	SVOCs	Field Blank
WG-1620-MW11B-012110	MW-11B	Water	01/21/10	2:50:00 PM	SVOCs	
WG-1620-MW11A-012110	MW-11A	Water	01/21/10	3:30:00 PM	SVOCs	
WG-1620-MW10B-012110	MW-10B	Water	01/21/10	4:15:00 PM	SVOCs	
WG-1620-MW10A-012110	MW-10A	Water	01/21/10	4:50:00 PM	SVOCs	

## Notes:

SVOCs Semi-Volatile Organic Compounds.

TABLE 2

**TARGET COMPOUND SUMMARY  
SEMI-ANNUAL COMPLIANCE MONITORING  
SWMU NO. 1  
UNION PACIFIC RAILROAD (UPRR)  
HOUSTON WOOD PRESERVING WORKS  
HOUSTON, TEXAS  
JANUARY 2010**

SVOCs (ATZ)	SVOCs (BTZ)
Acenaphthene	Acenaphthene
Acenaphthylene	Acenaphthylene
Anthracene	Anthracene
bis(2-ethylhexyl)phthalate	bis(2-ethylhexyl)phthalate
Dibenzofuran	Dibenzofuran
Fluoranthene	Fluoranthene
Fluorene	Fluorene
Naphthalene	Naphthalene
Phenanthrene	Pyrene
Pyrene	Phenol
2-Methylnaphthalene	Di-n-butyl phthalate

## Notes:

SVOCs - Semi-Volatile Organic Compounds.

TABLE 3

FIELD DUPLICATE SUMMARY  
SEMI-ANNUAL COMPLIANCE MONITORING  
SWMU NO. 1  
UNION PACIFIC RAILROAD (UPRR)  
HOUSTON WOOD PRESERVING WORKS  
HOUSTON, TEXAS  
JANUARY 2010

	<i>Sample Location:</i>				<i>MW01A</i>	
	<i>Orig</i>		<i>Duplicate</i>		<i>RPD</i>	<i>Units</i>
<i>Semi-Volatile Organics</i>						
Dibenzofuran	1.6	J	1.4	J	13.0	µg/L
Fluoranthene	1.7	J	1.5	J	12.0	µg/L
Acenaphthene	40		39		2.5	µg/L
Fluorene	22		19		15.0	µg/L
Naphthalene	4.3	J	3.6	J	18.0	µg/L
2-Methylnaphthalene	1.9	J	1.8	J	5.4	µg/L

## Notes:

J - Estimated concentration

RPD - Relative Percent Difference.

**APPENDIX D**  
**WASTE MANIFEST**

1,157#

UoH 3357

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator ID Number TXD000820266	2. Page 1 of 1	3. Emergency Response Phone 866-780-3116	4. Manifest Tracking Number 001139387 GBF	
5. Generator's Name and Mailing Address PO Box 87687 UNION Pacific Rail Road HOUSTON TX 77287				Generator's Site Address (if different than mailing address) 4910 Liberty Rd HOUSTON TX 77026		
Generator's Phone:						
6. Transporter 1 Company Name USA Environment LP		U.S. EPA ID Number TXR0005457				
7. Transporter 2 Company Name		U.S. EPA ID Number				
8. Designated Facility Name and Site Address 800-242-3209 US Ecology TEXAS LP 3.5 miles S. on Petronila Rd ROBSTOWN TX 78380		U.S. EPA ID Number TXD069452340				
9a. HM	9b. U.S. DOT Description (including Proper Shipping Name, Hazard Class, ID Number, and Packing Group (if any))	10. Containers		11. Total Quantity	12. Unit Wt./Vol.	13. Waste Codes
		No.	Type			
1.	RCRA, Hazardous Waste Solid, n.d.s (PPE & Debris/solid) 9, UA 307 PG III	1	Dm	25		F034 09153014 0917406H
2.						
3.						
4.						
14. Special Handling Instructions and Additional Information approval # 090056383-0 USA 100 # 2469-TD H156						
15. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations. If export shipment and I am the Primary Exporter, I certify that the contents of this consignment conform to the terms of the attached EPA Acknowledgment of Consent. I certify that the waste minimization statement identified in 40 CFR 262.27(a) (if I am a large quantity generator) or (b) (if I am a small quantity generator) is true.						
Generator's/Offeror's Printed/Typed Name GEOFFREY REEDER		Signature Geoffrey Reeder			Month Day Year 14   1   10	
16. International Shipments <input type="checkbox"/> Import to U.S. <input type="checkbox"/> Export from U.S. Port of entry/exit: _____ Date leaving U.S.: _____						
17. Transporter Acknowledgment of Receipt of Materials						
Transporter 1 Printed/Typed Name Arturo Garcia		Signature Arturo Garcia			Month Day Year 14   1   10	
Transporter 2 Printed/Typed Name		Signature			Month Day Year	
18. Discrepancy						
18a. Discrepancy Indication Space <input type="checkbox"/> Quantity <input type="checkbox"/> Type <input type="checkbox"/> Residue <input type="checkbox"/> Partial Rejection <input type="checkbox"/> Full Rejection						
Manifest Reference Number:						
18b. Alternate Facility (or Generator) Corrected waste code per customer 7/13/10 (88)					U.S. EPA ID Number	
Facility's Phone:						
18c. Signature of Alternate Facility (or Generator)					Month Day Year	
19. Hazardous Waste Report Management Method Codes (i.e., codes for hazardous waste treatment, disposal, and recycling systems)						
1.	H132	2.		3.		4.
20. Designated Facility Owner or Operator: Certification of receipt of hazardous materials covered by the manifest except as noted in item 18a						
Printed/Typed Name Javi Andrade		Signature Javi Andrade			Month Day Year 14   1   10	

GENERATOR  
TRANSPORTER INT'L  
DESIGNATED FACILITY

1. 4/16 #

W.O.# 3357

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator ID Number TXD000820266	2. Page 1 of 1	3. Emergency Response Phone 800-780-3116	4. Manifest Tracking Number 001139386 GBF				
5. Generator's Name and Mailing Address PO Box 87687 UNION Pacific Rail Road HOUSTON TX 77287 Generator's Phone: 713 425 6900				Generator's Site Address (if different than mailing address) 4910 Liberty Rd HOUSTON TX 77026					
6. Transporter 1 Company Name USA Environment, LP				U.S. EPA ID Number TXR00005437					
7. Transporter 2 Company Name				U.S. EPA ID Number					
8. Designated Facility Name and Site Address US Ecology TEXAS LP 800-242-3209 3.5 miles S Petronilla Rd Robstown TX 78380 Facility's Phone:				U.S. EPA ID Number TXD069452340					
GENERATOR	9a. HM	9b. U.S. DOT Description (including Proper Shipping Name, Hazard Class, ID Number, and Packing Group (if any))		10. Containers		11. Total Quantity	12. Unit Wt./Vol.	13. Waste Codes	
	1.	RCRA, Hazardous liquid nos (purge water) 9, NA 3077 PG III		1	Dr	350		FO34 <del>0909101H</del>	
	2.							0914101H	
	3.								
	4.								
14. Special Handling Instructions and Additional Information approval # 0900 56384-0 USA 100 # 2469-TD-HLS6									
15. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations. If export shipment and I am the Primary Exporter, I certify that the contents of this consignment conform to the terms of the attached EPA Acknowledgment of Consent. I certify that the waste minimization statement identified in 40 CFR 262.27(a) (if I am a large quantity generator) or (b) (if I am a small quantity generator) is true.									
Generator's/Offoror's Printed/Typed Name GEOFFREY REEDER				Signature GEOFFREY REEDER		Month Day Year 4 1 10			
16. International Shipments <input type="checkbox"/> Import to U.S. <input type="checkbox"/> Export from U.S. Port of entry/exit: _____ Date leaving U.S.: _____									
17. Transporter Acknowledgment of Receipt of Materials									
Transporter 1 Printed/Typed Name Arturo Flores				Signature Arturo Flores		Month Day Year 4 1 10			
Transporter 2 Printed/Typed Name				Signature		Month Day Year			
18. Discrepancy									
18a. Discrepancy Indication Space <input type="checkbox"/> Quantity <input type="checkbox"/> Type <input type="checkbox"/> Residue <input type="checkbox"/> Partial Rejection <input type="checkbox"/> Full Rejection									
Manifest Reference Number:									
18b. Alternate Facility (or Generator) Corrected waste code per customer 7/13/10 85						U.S. EPA ID Number			
Facility's Phone:									
18c. Signature of Alternate Facility (or Generator)						Month Day Year			
19. Hazardous Waste Report Management Method Codes (i.e., codes for hazardous waste treatment, disposal, and recycling systems)									
1. H132		2.		3.		4.			
20. Designated Facility Owner or Operator. Certification of receipt of hazardous materials covered by the manifest except as noted in Form 18a									
Printed/Typed Name Javi Andrade				Signature Javi Andrade		Month Day Year 4 16 10			

DESIGNATED FACILITY TO DESTINATION STATE (IF REQUIRED)

**APPENDIX E**  
**POC CONCENTRATIONS VS. TIME GRAPHS**



Figure E-1  
2-Methylnaphthalene Concentrations vs Time - A-TZ Unit  
UPRR HWPW Facility - RCRA SWMU No. 1




Figure E-2  
Dibenzofuran Concentrations vs Time - A-TZ Unit  
UPRR HWPW Facility - RCRA SWMU No. 1




Figure E-3  
Naphthalene Concentrations vs Time - A-TZ Unit  
UPRR HWPW Facility - RCRA SWMU No. 1




Figure E-4  
Dibenzofuran Concentrations vs Time - B-TZ Unit  
UPRR HWPW Facility - RCRA SWMU No. 1





Figure E-5  
Naphthalene Concentrations vs Time - B-TZ Unit  
UPRR HWPW Facility - RCRA SWMU No. 1



**APPENDIX F**  
**UPDATED COMPLIANCE SCHEDULE**

ID	Task Name/Permit or CP Section No.	2010												2011											
		1st Quarter			2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter			3rd Quarter			4th Quarter		
		J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	
1	<b>Facility Management</b>																								
2	General Inspection Requirements (quarterly) [Permit Section III.D; Table III.D]																								
26	<b>Addendum to the Affected Property Assessment Report (APAR) [Permit Section IX.A; CP Section VIII.D]</b>	▬																							
27	Field Investigation Activities																								
28	Addition Delineation Field Investigation (Groundwater/Soil)																								
29	Prepare and Submit Addendum to the APAR																								
30	Respond to TCEQ Comments on the APAR Addendum	▬																							
31	Addition Delineation Field Investigation (Groundwater/Soil)	▬																							
32	Prepare and Submit Final APAR Addendum																								
33	<b>Corrective Measures Implementation (CMI)/Response Action Plan (RAP) [CP Section VIII.F]</b>	▬																							
34	Prepare and Submit Response Action Plan (RAP)	▬																							
35	<b>Ground-Water Monitoring Program [Permit Section VI.A.; CP Section VI.]</b>																								
36	Water Level Measurements (Semiannually) [CP Section VI.C.4.a]1																								
49	Monitoring Well Inspections (Semiannually) [CP Section VI.C.4.a]1																								
72	Ground Water Sampling and Data Evaluation (2nd Semiannual) [CP Section VI.C.2]																								
73	Ground Water Sampling and Data Evaluation (1st Semiannual) [CP Section VI.C.2]	▬																							
74	Ground Water Sampling and Data Evaluation (2nd Semiannual) [CP Section VI.C.2]	▬																							
75	Ground Water Sampling and Data Evaluation (1st Semiannual) [CP Section VI.C.2]	▬																							
76	Ground Water Sampling and Data Evaluation (2nd Semiannual) [CP Section VI.C.2]	▬																							
77	<b>Response and Reporting [Permit Section II.B.7; CP Section VII.]</b>																								
78	First Semi-Annual GW Monitoring Report - July 21 [CP Section VII.C.2]	↓																							
85	Second Semi-Annual GW Monitoring Report - January 21 [CP Section VII.C.2]	↓																							

Compliance Schedule UPRR Houston Wood Preserving Works Site Houston, Texas	Task		Rolled Up Task		External Tasks	
	Progress		Rolled Up Milestone		Project Summary	
	Milestone		Rolled Up Progress		External Milestone	
	Summary		Split		Deadline	